SUSPECTED ASBESTOS MATERIAL LOCATION SUMMARY (SEE SPECIFICATIONS FOR ACM REPORT)				
ROOM NAME		ASBESTOS MATERIAL (ACM)	RESULTS	AFFECTED BY THE PROJECT
BASE BUILDING				
AF STORAGE, EAST WALL	6" BEIGE BASE BOARD	TAN MASTIC	TEM - SAMPLE NOT ANALYZED	NO
AF STORAGE	12"X12" PEACH VINYL FLOOR TILE	TAN MASTIC	TEM - SAMPLE NOT ANALYZED	NO
CONFERENCE ROOM	12"X12" WHITE VINYL FLOOR TILE	YELLOW MASTIC	NEGATIVE	NO 1
TELCO	4" BROWN VINYL BASEBOARD	TAN MASTIC	TEM - SAMPLE NOT ANALYZED	NO
EQUIPMENT ROOM	12"X 12"WHITE VINYL FLOOR TILE WITH SPOTS AND BLACK MASTIC	BLACK MASTIC	YES	NO
		OFF WHITE FLOOR TILE	TEM - SAMPLE NOT ANALYZED	NO
TELCO	12"X 12"WHITE VINYL FLOOR TILE WITH SPOTS AND BLACK MASTIC	BLACK MASTIC	YES	NO 1
ATCT				
10TH FLOOR (JUNCTION LEVEL), EQUIPM ROOM	2" BLACK VINYL BASE BOARD	YELLOW MASTIC	TEM - SAMPLE NOT ANALYZED	NO
10TH FLOOR (JUNCTION LEVEL), CORRIDOR	INTERIOR PERIMETER DRYWALL WITH JOINT COMPOUND	WHITE JOINT COMPOUND	YES	NO 1
	12"X 12" WHITE VINYL FLOOR TILE GREY SPOTS	YELLOW MASTIC	NEGATIVE	NO
10TH FLOOR (JUNCTION LEVEL), STAIRS	BLACK VINYL FLOOR TILE WITH STRIKES AND MASTIC	YELLOW MASTIC	NEGATIVE	NO

HAZMAT NOTES

1. BUILDING CONTAINS HAZARDOUS MATERIAL (HAZMAT). THE TABLE ON THIS DRAWING IS A SUMMARY OF ASBESTOS CONTAINING MATERIAL (ACM) AND IT'S LOCATION AS SHOWN IN THE REPORT PREPARED BY RESEARCH MANAGEMENT CONSULTANTS, INC. A SUMMARY OF THIS REPORT IS INCLUDED AS AN APPENDIX TO THE SPECIFICATIONS. THE COMPLETE REPORT IS ON FILE WITH THE FAA. PROVIDE TEST WHERE ASSUMED ACM IS LISTED.
2. 1 IT IS THE INTENT OF THIS DRAWING TO REMOVE THE ASBESTOS CONTAINING MATERIAL THAT ARE BEING DISTRURBED BY THIS PROJECT. REFER TO APPROPRIATE SECTIONS OF FAA STANDARD SPECIFICATIONS.
3. PAINTED AREAS SUCH AS THE STAIR HANDRAILS ARE ASSUMED TO CONTAIN LEAD-BASED PAINT. REFER TO FAA STANDARD SPECIFICATIONS.
4. THE CONTRACTOR SHALL ENSURE THAT ALL DEMOLITION GENERATED SOLID WASTES, INCLUDING THOSE THAT CONSIST OF ASBESTOS, LEAD, OR OTHER HAZARDOUS CONSTITUENTS, WASTES, SUBSTANCES, OR MATERIALS, ARE MANAGED TO AVOID CONTAMINATION OF ENVIRONMENTAL MEDIA AND HANDLED AND DISPOSED OF CONSISTENT WITH ALL APPLICABLE LAWS AND REQUIREMENTS.

SCALES SHOWN FOR 22" X 34" SHEET. ADJUST SCALES FOR OTHER SIZES.

PAGE OF

REV	APPROVED DATE	DESCRIPTION	JCN	REDLINE DATE	APVD
1	08/05/2020	ISSUE FOR CONSTRUCTION			

DEPARTMENT OF TRANSPORTATION
FEDERAL AVIATION ADMINISTRATION

FORT LAUDERDALE AIRPORT TRAFFIC CONTROL TOWER
MAJOR IMPROVEMENTS
GENERAL
HAZARDOUS MATERIALS

FT LAUDERDALE (INTERNATIONAL) FL

Wiley|Wilson
5901 Peachtree Dunwoody Rd.
Bldg. C, Ste 515
Atlanta, Georgia 30328-6055
678.320.1888
wileywilson.com

WW JOB NUMBER: 219075.00

REVIEWED BY | SUBMITTED BY | APPROVED BY

SUBMITTER'S TITLE - CIVIL ENGINEER | APPROVER'S TITLE - MANAGER

DESIGNED GMR | DRAWN GMR | CHECKED RAB

ISSUED BY: ATLANTA TERMINAL ENGINEERING CENTER

DATE JAN 31, 2020 | JCN 1508912

DRAWING NO FLL-D-TOWB-H001 REV 1