LIMITED ASBESTOS SURVEY REPORT

Fort Lauderdale/Hollywood International Airport Air Traffic Control Tower & Base Building 4150 Southwest 12th Terrace Fort Lauderdale, Florida 33315

GLE Project No.: 18000-19284

Prepared for:

Federal Aviation Administration 1701 Columbia Avenue College Park, Georgia 30337

April 2018

Prepared by:



1000 NW 65th Street, Suite 300-D Ft. Lauderdale, Florida 33309 754-223-2697 • Fax 754-223-2937



May 2, 2018

Ms. Sushma Patel Federal Aviation Administration 1701 Columbia Avenue College Park, Georgia 30337

RE: Limited Asbestos Survey Report FLL Air Traffic Control Tower & Base Building 4150 Southwest 12th Terrace Fort Lauderdale, Florida 33315

GLE Project No.: 18000-19284

Dear Ms. Patel:

GLE Associates, Inc. (GLE) performed a Limited survey for Asbestos-Containing Materials (ACMs) on April 17, 2018, at the FLL Air Traffic Control Tower & Base Building located at 4150 Southwest 12th Terrace, in Fort Lauderdale, Florida. The survey was performed by Mr. Brandon Christensen with GLE. This report outlines the sampling and testing procedures, and presents the results along with our conclusions and recommendations.

GLE appreciates the opportunity to serve as your consultant on this project. If you should have any questions, or if we can be of further service, please do not hesitate to call.

Sincerely, GLE Associates, Inc.

Brandon Christensen Project Manager

Robert B. Greene, PE, PG, CIH, LEED AP President Florida LAC # EA 0000009

BSC/MBC/RBG/el

H:\Work\ASB\18000\19284 FAA - FLL ATCT & Base Bldg. ACM, LCP & Silica\Report\Asb\Asbestos Report 18000-19284.doc

GLE Associates, Inc.

TABLE OF CONTENTS

| 1.0 | INT | RODUCTION | |
|-----|-------|--|---|
| | 1.1 | | |
| | 1.2 | Facility Description | 1 |
| 2.0 | RES | ULTS | 1 |
| | 2.1 | Asbestos Survey Procedures | 1 |
| | 2.2 | Identified Suspect Asbestos-Containing Materials | 2 |
| | | Table 2.2-1: Summary of Homogeneous Sampling Areas | 3 |
| 3.0 | CON | CLUSIONS AND RECOMMENDATIONS | 4 |
| | 3.1 | General | |
| 4.0 | LIM | ITATIONS AND CONDITIONS | 4 |
| APP | ENDIC | CES | |

Appendix A – Analytical Results and Chain of Custody Appendix B – Personnel and Laboratory Certifications

1.0 INTRODUCTION

1.1 INTRODUCTION

The purpose of this limited survey was to identify accessible ACMs and their general locations within the FLL Air Traffic Control Tower (ATCT) and base building, located at 4150 southwest 12th terrace, located in Fort Lauderdale, Florida. The survey was limited to the building materials that could be impacted during the ATCT roof and catwalk renovations. The survey was conducted pursuant to National Emission Standards for Hazardous Air Pollutants (NESHAP, 40 CFR 61) requirements, associated with the scheduled renovation plans. The survey was performed on April 17, 2017, by Mr. Brandon Christensen, an Environmental Protection Agency/Asbestos Hazard Emergency Response Act (EPA/AHERA) accredited inspector. The scope of this survey did not include demolition of any building components, evaluation of architectural plans, or the quantification of materials for abatement purposes, or removal cost estimating.

1.2 FACILITY DESCRIPTION

| Facility Type: | Government | | |
|---------------------|---|--|--|
| Construction Date: | Unknown | | |
| Number of Floors: | 10 | | |
| Structural | | | |
| Foundation: | Concrete Slab | | |
| Wall Support: | Concrete Masonry Unit | | |
| Exterior Finish: | Stucco, Paint | | |
| Roof Support: | Metal Truss, | | |
| Roof System Type: | Built up Roof, PVC, Rolled Asphalt Roof | | |
| Mechanical/Plumbing | Not in Scope | | |
| Interior | Not in Scope | | |
| | | | |

A summary of the facility investigated is outlined in the table below.

2.0 **RESULTS**

2.1 ASBESTOS SURVEY PROCEDURES

The survey was performed by visually observing accessible areas of the subject area. EPA/AHERA accredited inspectors performed the visual observations (refer to Appendix B for personnel qualifications).

After the overall visual survey was completed, representative sampling areas were determined. The surveyors delineated homogeneous areas of suspect materials and samples of each material were obtained, in general accordance with regulations as established by the Occupational Safety and Health Administration (OSHA) and NESHAP. The field surveyors determined sample locations based on previous experience. Both friable and non-friable materials were sampled. A

friable material is one that can be crushed when dry by normal hand pressure. This survey did not include the demolition of building components to access suspect material.

After completion of the fieldwork, the samples were delivered to GLE's National Voluntary Laboratory Accreditation Program (NVLAP) accredited laboratory for analysis. The samples were analyzed by Polarized Light Microscopy (PLM) coupled with dispersion staining, in general accordance with EPA-600/R-93/116. Utilizing this procedure, the various asbestos minerals (chrysotile, amosite, crocidolite, actinolite, tremolite, and anthophyllite) can be determined. The percentages of asbestos minerals in the samples were visually determined by the microscopist. Please note that the EPA designates all materials containing greater than 1% asbestos as an "asbestos-containing material" (ACM).

Regulated Asbestos-Containing Material (RACM) is defined as (a) Friable asbestos materials, (b) Category I non-friable ACM that has become friable, (c) Category I non-friable ACM that will be or has been subjected to sanding, grinding, cutting, or abrading, or (d) Category II non-friable ACM that has a high probability of becoming or has become crumbled, pulverized, or reduced to powder by the forces expected to act on the material in the course of demolition or renovation operations regulated by this subpart.

Category I and Category II non-friable ACM, as defined by the EPA:

- Category I non-friable ACM means asbestos containing packings, gaskets, resilient floor covering, asphalt roofing products, and pliable sealants and mastics that are in good condition and not friable, containing more than 1% asbestos, as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763, Section 1, PLM.
- Category II non-friable ACM means any material, excluding Category I non-friable ACM, containing more than 1% asbestos as determined using the methods specified in Appendix E, Subpart E, 40 CFR Part 763 Section 1, PLM that, when dry, cannot be crumbled, pulverized, or reduced to powder by hand pressure.

2.2 IDENTIFIED SUSPECT ASBESTOS-CONTAINING MATERIALS

A total of thirty-three samples of suspect building materials were collected from the subject area during the survey, representing eleven different homogeneous areas. The results of the laboratory analyses are included in Appendix A.

A summary of the homogenous sampling areas of suspect ACM determined to be present is outlined in the following table.

| TABLE 2.2-1: SUMMARY OF HOMOGENEOUS SAMPLING AREAS FLL ATCT AND BASE BUILDING 4150 Southwest 12 th Terrace Fort Lauderdale, Florida 33315 | | | | | | | |
|--|---|----------------------------------|----------------------|-------------|---------------------------|-------------------------|-----------------|
| HA # | Homogeneous Material Description | Homogeneous Material Location | FRIABILITY (F/NF) | % ASBESTOS* | # OF SAMPLES COLLECTED | Approximate Quantity | ACM CATEGORY |
| M-01 | White Coating w/ Black Pitch Pan Flashing | ATCT Roof | NF | ND | 3 | NIS | NA |
| M-02 | White Caulking at Antenna | ATCT Roof Parapet Wall | NF | ND | 3 | NIS | NA |
| M-03 | White PVC Roof Membrane w/ Yellow Adhesive | ASDE Penthouse Roof | NF | ND | 3 | NIS | NA |
| M-04 | White Roof Caulking | ASDE Penthouse Roof | NF | ND | 3 | NIS | NA |
| M-05 | Black Caulking at Catwalk Parapet Wall | Catwalk Parapet Wall | NF | ND | 3 | NIS | NA |
| M-06 | Gray w/ Black Pitch Pan Flashing | ATCT Roof | NF | ND | 3 | NIS | NA |
| R-01 | Black Rolled Roof Curb | ATCT Roof | NF | ND | 3 | NIS | NA |
| R-02 | Black Rolled Roof | Base Building Roof | NF | ND | 3 | NIS | NA |
| RBU-01 | White Coating over Built Up Roof | ATCT Roof | NF | ND | 3 | NIS | NA |
| RF-01 | Black Roof Edge Flashing | Base Building Roof | NF | ND | 3 | NIS | NA |
| RF-02 | Black Roof Vent Flashing | Base Building Roof | NF | ND | 3 | NIS | NA |

| ASBESTOS CONTENT * = The facility owner has the option of point-counting by polarized light microscopy (PLM) those RACM whose asbestos content is less in order to more accurately determine the asbestos content therein. Expressed as percent PC = Results based on Point-Count analysis | | | | | s content is less than 10% | |
|--|-----------------------|------------------------------------|-------------|--------------------------------------|----------------------------|-----------------------|
| FRIABILITY | F = Friable Material | NF = Non-Friable Material | | | | |
| ACM CATEGORY | RACM = Regulated ACM | CAT I = Category I non-friable ACM | | CAT II = Category II non-friable ACM | | |
| ABBREVIATIONS: | NA = Not Applicable | ND = None Detected | NIS = Not i | n Scope | C = Chrysotile | A = Amosite |
| | HA = Homogeneous Area | SF = Square Feet | LF = Linear | Feet | CF = Cubic Feet | AP = Assumed Positive |

3.0 CONCLUSIONS AND RECOMMENDATIONS

3.1 GENERAL

No asbestos-containing materials were identified in the scope of this survey.

4.0 LIMITATIONS AND CONDITIONS

As a result of previous renovations, there may be hidden materials, such as floor tile, sheet vinyl flooring, insulation, etc. These materials may be found in various areas hidden under existing flooring materials or in wall cavities. Any materials found during construction activities, either not addressed in this survey report, or similar to the ACM identified in this survey report should be assumed to be ACM until sampling and analysis documents otherwise.

Because of the hidden nature of many building components (i.e. within mechanical chases), it may be impossible to determine if all of the suspect building materials have been located and subsequently tested. Destructive testing in some instances is not a viable option. We cannot, therefore, guarantee that all potential ACM has been located. For the same reasons, estimates of quantities and/or conditions are subject to readily apparent situations, and our findings reflect this condition. We do warrant, however, that the investigations and methodology reflect our best efforts based upon the prevailing standard of care in the environmental industry.

The information contained in this report was prepared based upon specific parameters and regulations in force at the time of this report. The information herein is only for the specific use of the client and GLE. GLE accepts no responsibility for the use, interpretation, or reliance by other parties on the information contained herein, unless prior written authorization has been obtained from GLE.

APPENDIX A Analytical Results and Chain of Custody

SUMMARY OF BULK SAMPLE ANALYSIS

FAA-Engineering Services; FLL ATCT & Base Building

18000-19284

| Sample | Sample Type | | Fiber Type |
|----------|---|------|--------------------------------------|
| M-01A | White Coating & Black Pitch Pan Flashing | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-01B | White Coating & Black Pitch Pan Flashing | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-01C-QC | White Coating & Black Pitch Pan Flashing | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-02A | White Caulk | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-02B | White Caulk | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-02C | White Caulk | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-03A | White PVC Roof Membrane & Yellow Adhesive | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-03B | White PVC Roof Membrane & Yellow Adhesive | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-03C | White PVC Roof Membrane & Yellow Adhesive | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-04A | White Roof Caulk | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-04B | White Roof Caulk | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-04C | White Roof Caulk | 100% | Polymer, Quartz, Calcite, Clay, Mica |

Analyst / Approved Signatory:

Darryl Neldner

* Polarized Light Microscopy coupled with dispersion is the technique used for identification in accordance with EPA 600/M4-82-020, EPA 600/R-93/116, and NIOSH Method 9002.

** The percentage of each component is visually estimated. The result of this analysis relate only to the material tested.

Analysis performed by GLE Associates, Inc. NVLAP Code 102003-0, CO AL-17485, TX 30-0337

Feedback regarding laboratory performance should be addressed to lab@gleassociates.com.

Report Date: 4/18/2018

The report shall not be used to claim product endorsement by NVLAP or any agency of the U.S. Government.

^{(&}gt;1% greater than one percent, <1% less than one percent) QC - Sample reanalyzed for QA/QC.

^{***} This report shall not be reproduced except in full, without the written approval of the laboratory. GLE Report # 22502

SUMMARY OF BULK SAMPLE ANALYSIS

FAA-Engineering Services; FLL ATCT & Base Building

18000-19284

| ample | Sample Type | | Fiber Type |
|----------|----------------------------------|------|--------------------------------------|
| M-05A-QC | Black Caulk | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-05B | Black Caulk | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-05C | Black Caulk | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| M-06A | Gray/Black Pitch Pan Flashing | 100% | Bitumen, Quartz, Calcite, Mica |
| M-06B | Gray/Black Pitch Pan Flashing | 100% | Bitumen, Quartz, Calcite, Mica |
| M-06C | Gray/Black Pitch Pan Flashing | 100% | Bitumen, Quartz, Calcite, Mica |
| R-01A | Black Rolled Roof Curb | 100% | Bitumen, Quartz, Calcite, Mica |
| R-01B | Black Rolled Roof Curb | 100% | Bitumen, Quartz, Calcite, Mica |
| R-01C | Black Rolled Roof Curb | 100% | Bitumen, Quartz, Calcite, Mica |
| R-02A | Black Rolled Roof | 100% | Bitumen, Quartz, Calcite, Mica |
| R-02B-QC | Black Rolled Roof | 100% | Bitumen, Quartz, Calcite, Mica |
| R-02C | Black Rolled Roof | 100% | Bitumen, Quartz, Calcite, Mica |
| RBU-01A | White Coating | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| RBU-01B | White Coating | 100% | Polymer, Quartz, Calcite, Clay, Mica |
| RBU-01C | White Coating | 100% | Polymer, Quartz, Calcite, Clay, Mica |

Analyst / Approved Signatory:

Darryl Neldner

* Polarized Light Microscopy coupled with dispersion is the technique used for identification in accordance with EPA 600/M4-82-020, EPA 600/R-93/116, and NIOSH Method 9002.

** The percentage of each component is visually estimated. The result of this analysis relate only to the material tested.

Analysis performed by GLE Associates, Inc. NVLAP Code 102003-0, CO AL-17485, TX 30-0337

Feedback regarding laboratory performance should be addressed to lab@gleassociates.com.

The report shall not be used to claim product endorsement by NVLAP or any agency of the U.S. Government.

^{(&}gt;1% greater than one percent, <1% less than one percent) QC - Sample reanalyzed for QA/QC.

^{***} This report shall not be reproduced except in full, without the written approval of the laboratory. GLE Report # 22502

SUMMARY OF BULK SAMPLE ANALYSIS

FAA-Engineering Services; FLL ATCT & Base Building

18000-19284

| Sample | Sample Type | | Fiber Type | |
|-----------|--------------------------|------|--------------------------------|--|
| RF-01A | Black Roof Edge Flashing | 100% | Bitumen, Quartz, Calcite, Mica | |
| RF-01B | Black Roof Edge Flashing | 100% | Bitumen, Quartz, Calcite, Mica | |
| RF-01C | Black Roof Edge Flashing | 100% | Bitumen, Quartz, Calcite, Mica | |
| RF-02A | Black Roof Vent Flashing | 100% | Bitumen, Quartz, Calcite, Mica | |
| RF-02B | Black Roof Vent Flashing | 100% | Bitumen, Quartz, Calcite, Mica | |
| RF-02C-QC | Black Roof Vent Flashing | 100% | Bitumen, Quartz, Calcite, Mica | |

Analyst / Approved Signatory:

Darryl Neldner

* Polarized Light Microscopy coupled with dispersion is the technique used for identification in accordance with EPA 600/M4-82-020, EPA 600/R-93/116, and NIOSH Method 9002.

** The percentage of each component is visually estimated. The result of this analysis relate only to the material tested.

Analysis performed by GLE Associates, Inc. NVLAP Code 102003-0, CO AL-17485, TX 30-0337

Feedback regarding laboratory performance should be addressed to lab@gleassociates.com.

Report Date: 4/18/2018

The report shall not be used to claim product endorsement by NVLAP or any agency of the U.S. Government. (>1% greater than one percent, <1% less than one percent) QC - Sample reanalyzed for QA/QC.

^{***} This report shall not be reproduced except in full, without the written approval of the laboratory. GLE Report # 22502

| | USTODY/SAMPLE TRANSMITTAL FOI GLE Associates, Inc. 1000 NW 65 th Street, Suite 300-D Ft. Lauderdale, FL 33309 PHONE: (954) 968-6414 FAX: (954) 968-6090 | PROJECT : PROJECT: LABORAT | | |
|---|---|---|--|--|
| | SAMPLEIN | FORMATION | 7/1//2010 | |
| | | | DESCRIPTION | |
| SAMPLE # M-01 ABC | DESCRIPTION White Coating w/ Black Pitch Pan Flashing | R-01 ABC | DESCRIPTION Black Rolled Roof Curb | |
| M-02 ABC | White Caulk at Antenna | R-02 ABC | Black Rolled Roof | |
| M-03 ABC | White PVC Roof Membrane w/ Yellow Adhesive | RBU-01 ABC | White Coating over Built Up Roof | |
| M-04 ABC | White Roof Caulking | RF-01 ABC | Black Roof Edge Flashing | |
| M-05 ABC | Black Caulking at Catwalk Parapet Wall | RF-02 ABC | Black Roof Vent Flashing | |
| M-06 ABC | Gray w/ Black Pitch Pan Flashing | | | |
| | | | | |
| IMPORTAN | <u>T</u> : TOTAL NUMBER OF SAMPLES | SUBMITTED | 33 | |
| | <u>T</u> : TOTAL NUMBER OF SAMPLES : <u>T</u> : POSITIVE STOP ANALYSIS | SUBMITTED | 33 Yes | |
| IMPORTAN | <u>T</u> : POSITIVE STOP ANALYSIS <u>T</u> : E-MAIL RESULTS TO | | | |
| IMPORTAN IMPORTAN | <u>T</u> : POSITIVE STOP ANALYSIS <u>T</u> : E-MAIL RESULTS TO No round time starts at receipt by lak | OTE: and does not i | Yes Jsimmons/elongo include weekend or holidays. | |
| IMPORTAN IMPORTAN Turnal Select Turna | <u>T</u> : POSITIVE STOP ANALYSIS <u>T</u> : E-MAIL RESULTS TO No round time starts at receipt by lak | OTE: and does not in the second secon | Yes Jsimmons/elongo include weekend or holidays. ur 3 Day X 4 Day | |
| IMPORTAN IMPORTAN Turna | T: POSITIVE STOP ANALYSIS T: E-MAIL RESULTS TO No round time starts at receipt by lak round Time r 6 Hour 24 Hour REPORT RESULTS TO | OTE: and does not in the second seco | Yes Jsimmons/elongo include weekend or holidays. ur 3 Day X 4 Day SS ABOVE HAIN OF CUSTODY: LAKOPA ORY | |
| IMPORTAN IMPORTAN Turnan Select Turna 3 hour CHAIN PACKAGED I | T: POSITIVE STOP ANALYSIS T: E-MAIL RESULTS TO No round time starts at receipt by lab round Time r 6 Hour 24 Hour REPORT RESULTS TO OF CUSTODY: GLE ASSOCIATES, INC. BY: Brandon Christensen | OTE: and does not in 48 Hou FO THE ADDRE C SAMPI | Yes Jsimmons/elongo include weekend or holidays. ur 3 Day X 4 Day SS ABOVE HAIN OF CUSTODY: LAKORY LES RECEIVED BY: | |
| IMPORTAN IMPORTAN IMPORTAN Select Turna Select Turna 3 hour CHAIN PACKAGED I DATE PACKA | T: POSITIVE STOP ANALYSIS T: E-MAIL RESULTS TO No round time starts at receipt by lake tround Time ar 6 Hour 24 Hour REPORT RESULTS TO OF CUSTODY: GLE ASSOCIATES, INC. BY: Brandon Christenson AGED: 4/17/2018 | OTE: and does not i 48 Hou FO THE ADDRE C SAMPI DATE: | Yes Jsimmons/elongo include weekend or holidays. ur 3 Day X 4 Day SS ABOVE HAIN OF CUSTODY: LAKORY LES RECEIVED BY: | |
| IMPORTAN IMPORTAN IMPORTAN Select Turna Select Turna 3 hour CHAIN PACKAGED I DATE PACKA METHOD OF | T: POSITIVE STOP ANALYSIS T: E-MAIL RESULTS TO No round time starts at receipt by lab round Time r 6 Hour 24 Hour REPORT RESULTS TO OF CUSTODY: GLE ASSOCIATES, INC. BY: Brandon Christensen | OTE: and does not if 48 Hou FO THE ADDRE C SAMPI DATE: TIME: | Yes Jsimmons/elongo include weekend or holidays. ur 3 Day X 4 Day SS ABOVE HAIN OF CUSTODY: LAKORY LES RECEIVED BY: | |
| IMPORTAN IMPORTAN IMPORTAN Select Turna Select Turna 3 hour CHAIN PACKAGED I DATE PACKA METHOD OF | T: POSITIVE STOP ANALYSIS T: E-MAIL RESULTS TO No round time starts at receipt by lake round Time r 6 Hour 24 Hour REPORT RESULTS TO OF CUSTODY: GLE ASSOCIATES, INC. BY: Brandon Christensen AGED: 4/17/2018 TRANSMITTAL: FEDEX | OTE: and does not if 48 Hou 48 Hou TO THE ADDRE C SAMPI DATE: TIME: COND | Yes Jsimmons/elongo include weekend or holidays. ur 3 Day X 4 Day SS ABOVE HAIN OF CUSTODY: LAURA ORY LES RECEIVED BY: | |
| IMPORTAN IMPORTAN IMPORTAN Select Turna Select Turna 3 hour CHAIN PACKAGED I DATE PACKA METHOD OF | T: POSITIVE STOP ANALYSIS T: E-MAIL RESULTS TO No round time starts at receipt by lak round Time r 6 Hour 24 Hour 24 Hour 24 Hour 24 Hour 24 Hour CEPORT RESULTS T OF CUSTODY: GLE ASSOCIATES, INC. BY: Brandon Christensen AGED: 4/17/2018 TRANSMITTAL: FEDEX ED BY: ELongo CHAIN OF CUSTODY: RETURN | OTE: and does not if 48 Hou 48 Hou TO THE ADDRE C SAMPI DATE: TIME: COND | Yes Jsimmons/elongo include weekend or holidays. ur 3 Day X 4 Day SS ABOVE HAIN OF CUSTODY: LAKONA ORY LES RECEIVED BY: | |
| IMPORTAN IMPORTAN IMPORTAN Select Turna Select Turna 3 hour CHAIN PACKAGED I DATE PACKA METHOD OF TRANSMITT | T: POSITIVE STOP ANALYSIS T: E-MAIL RESULTS TO No round time starts at receipt by lak round Time r 6 Hour 24 Hour 25 Hour 26 Hour 27 Hour 27 Hour 28 Hour 29 Hour 29 Hour 29 Hour 29 Hour 20 | OTE: and does not i 48 Hou TO THE ADDRE C SAMPI DATE: TIME: COND TED TO GLE ASSO | Yes Jsimmons/elongo include weekend or holidays. ur 3 Day X 4 Day SS ABOVE HAIN OF CUSTODY: LANDA ORY LES RECEIVED BY: ITION OF PACKAGED SAME CIATES, INC. E: E: | |

APPENDIX B Personnel and Laboratory Certifications **RICK SCOTT, GOVERNOR**

JONATHAN ZACHEM, SECRETARY





Do not alter this document in any form.

This is your license. It is unlawful for anyone other than the licensee to use this document.



STATE OF FLORIDA DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION


ASBESTOS LICENSING UNIT 2601 BLAIR STONE ROAD TALLAHASSEE FL 32399-0783 (850) 487-1395

GREENE, ROBERT BLAIR GLE ASSOCIATES INC 5405 CYPRESS CENTER DR SUITE 110 TAMPA FL 33609

Congratulations! With this license you become one of the nearly one million Floridians licensed by the Department of Business and Professional Regulation. Our professionals and businesses range from architects to yacht brokers, from boxers to barbeque restaurants, and they keep Florida's economy strong.

Every day we work to improve the way we do business in order to serve you better. For information about our services, please log onto www.myfloridalicense.com. There you can find more information about our divisions and the regulations that impact you, subscribe to department newsletters and learn more about the Department's initiatives.


Our mission at the Department is: License Efficiently, Regulate Fairly. We constantly strive to serve you better so that you can serve your customers. Thank you for doing business in Florida, and congratulations on your new license!



DETACH HERE

RICK SCOTT, GOVERNOR

KEN LAWSON, SECRETARY





United States Department of Commerce National Institute of Standards and Technology



Certificate of Accreditation to ISO/IEC 17025:2005

NVLAP LAB CODE: 102003-0

GLE Associates, Inc.

Tampa, FL

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

Asbestos Fiber Analysis

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005. This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2018-04-01 through 2019-03-31

Effective Dates



For the National Voluntary Laboratory Accreditation Program

NVLAP National Voluntary Laboratory Accreditation Program



SCOPE OF ACCREDITATION TO ISO/IEC 17025:2005

GLE Associates, Inc.

5405 Cypress Center Drive Suite 110 Tampa, FL 33609 Mr. Darryl S. Neldner Phone: 813-241-8350 x247 Fax: 813-241-8737 Email: dneldner@gleassociates.com http://www.gleassociates.com

ASBESTOS FIBER ANALYSIS

NVLAP LAB CODE 102003-0

Bulk Asbestos Analysis

| <u>Code</u> 18/A01 | Description EPA 40 CFR Appendix E to Subpart E of Part 763, Interim Method of the Determination of Asbestos in Bulk Insulation Samples |
|-----------------------|---|
| 18/A03 | EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials |

For the National Voluntary Laboratory Accreditation Program