US Army Corps
of Engineers
Sacramento District

RENOVATE 926 WG BUILDING 332

NELLIS AFB

NEVADA

PN: RKMF17-0065

Index of Drawings	
SHEET NUMBER	SHEET TITLE
G-001	COVER SHEET
G-101	PROJECT LOCATION AND HAUL PATH
C-101	DEMOLITION PLAN
C-102	SITE PLAN
AD101	FIRST FLOOR DEMOLITION PLAN
AD102	SECOND FLOOR DEMOLITION PLAN
AD103	THIRD FLOOR DEMOLITION PLAN
AD201	NORTH AND SOUTH ELEVATIONS - DEMOLITION
A-101	FIRST FLOOR PLAN
A-102	SECOND FLOOR PLAN
A-103	THIRD FLOOR PLAN
A-201	NORTH AND SOUTH ELEVATIONS
A-202	EAST AND WEST ELEVATIONS
A-620	DOOR SCHEDULE
I-610	FIRST FLOOR INTERIOR FINISH/COLOR SCHDULE
I-611	SECOND FLOOR INTERIOR FINISH/COLOR SCHDULE
I-612	THIRD FLOOR INTERIOR FINISH/COLOR SCHDULE
IF101	1ST FLOOR FURNITURE PLAN
IF102	2ND FLOOR FURNITURE PLAN
IF103	3RD FLOOR FURNITURE PLAN

DISTRIBUTION STATEMENT A
Approved for public release; distribution is unlimited.

US Army Corps of Engineers ®

THIS PROJECT WAS DESIGNED BY THE SACRAMENTO DISTRICT OF THE U.S. ARMY CORPS OF ENGINEERS. THE INITIALS OR SIGNATURES AND REGISTRATION DESIGNATIONS OF INDIVIDUALS APPEAR ON THESE PROJECT DOCUMENTS WITHIN THE SCOPE OF THEIR EMPLOYMENT AS REQUIRED BY ER 1110-1-8152

Approved: /s/ Ric Poespelman, P.E. — Chief, Design Branch — SEP 2018 Date
Prepared Under the Direction of: Colonel David G. Ray, P.E. — Commander, US Corps of Engineers — SEP 2018 Date

Drawn by: ORA
Designed by: ORA
Design File No. 229-25-0715
Spec No. 2164

Approved Functional Adequacy: /s/ Scott Tincher, P.E. — Chief, Design Branch — SEP 2018 Date
Prepared by: SACRAMENTO DISTRICT DESIGN BRANCH
/s/ Matthew Z. Valentine — Chief, Arch. Design Section — SEP 2018 Date

Drawing Code:

NELLIS AFB — PN: RKMF17-0065 — NEVADA
RENOVATE 926 WG BUILDING 332
COVER SHEET

SHEET IDENTIFICATION
G-001



STATE MAP
SCALE: NONE



LOCATION MAP
SCALE: NONE



PROJECT SITE MAP
SCALE: NONE

NOTES:

1. CONSTRUCTION CONTRACTORS MAY ACCESS THE BASE THROUGH THE MAIN GATE, SIMMONS GATE, RANGE ROAD GATE, AND AREA II GATE. HOWEVER, ALL COMMERCIAL VEHICLES AND VEHICLES LARGER THAN PICKUP TRUCKS WILL BE RE□UIRED TO ACCESS THE BASE THROUGH THE AREA II GATE ONLY□THE TURNOFF TO THE AREA II GATE IS ACROSS FROM THE RACETRACK ON N. LAS VEGAS BLVD APPROXIMATELY 3 MILES NORTH OF THE MAIN GATE.
2. THE HAUL PATH SHOWN FROM AREA II GATE IS APPROXIMATELY 6□ MILES.
3. UPON ARRIVAL AT A SECURITY GATE, ALL VEHICLE OCCUPANTS WILL BE RE□UIRED TO SHOW IDENTIFICATION BEFORE ENTERING THE BASE. A PICTURED IDENTIFICATION SUCH AS A DRIVER□S LICENSE WILL BE RE□UIRED.
4. SPEED LIMIT: UNLESS OTHERWISE POSTED, THE SPEED LIMIT ON BASE IS 25 MPH AND IN BASE HOUSING AREAS AND FLIGHTLINE IT IS 15 MPH.
5. ALL TRUCKS MUST HAVE COMPANY NAME LOGOS ON THE DOOR SIDES.
6. NO PRIVATELY OWNED VEHICLES □POV□ALLOWED WITHIN THE CONSTRUCTION SITE.
7. THE CONTRACTOR SHALL VERIFY THE WORKING HOURS WITH THE BASE SECURITY FOR APPROVAL. PERSONNEL CANNOT SHOW UP AT THE GATE WITHOUT PRIOR NOTIFICATION FOR ACCESS AND EXPECT TO GAIN ACCESS. VERBAL ACCESS CANNOT BE PROVIDED.
8. ADDITIONAL ACCESS INFORMATION IS INCLUDED UNDER THE APPENDICES - NELLIS RE□UIREMENTS/GUIDANCE
9. POINT OF CONTACTS:
   9.1. BASE OPERATOR - □702□652-1110
   9.2. GATE AREA II - □702□652-1801

US Army Corps of Engineers®

MARK	DESCRIPTION	DATE

DESIGNED BY: PC
DRAWN BY: PC
CHECKED BY: JSE
SUBMITTED BY: /s/ MARKUS BIDENTKER
SUPERVISOR: JSE
ANSI D 21x34

ISSUE DATE: SEP 2018
SOLICITATION NO.: XXXX
CONTRACT NO.: XXXX
FILE NO. 22825-0715
FILE NAME G-101XXX.dwg

U.S. ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT

IN-HOUSE DESIGN
1325 J STREET
SACRAMENTO, CA 95814-2922

NELLIS AFB, NV
BLDG 332 RENOVATION
RKMF 17-0065
XXXX

PROJECT LOCATION AND HAUL PATH

SHEET ID
G-101

C:\users\l2edd\jse\documents\pwwork\cespk\d0608124\G-101XXX.dwg

NOTES:

1. DEMOLISH ALL EXISTING CONCRETE SIDEWALKS, PAVERS, PRECAST CONCRETE EDGING, PLANTS, TREES, IRRIGATION, ROCK MULCH, ETC. WITHIN 30 FEET OF BUILDING 332.
2. DEMOLISH EXISTING CONCRETE CURB ALONG SOUTH SIDE OF PARKING LOT.

LEGEND

DEMOLISH E.CONCRETE SIDEWALK

DEMOLISH TREES

GRAPHIC SCALE

20 0 10 20 40 80

(IN FEET)
1 inch = 20 ft.

US Army Corps of Engineers®

MARK	DESCRIPTION	DATE

DESIGNED BY: PC
DRAWN BY: PC
CHECKED BY: JSE
SUBMITTED BY: /s/ MARKUS BOEDTKER
SIZE: ANSI D
FILE NAME: C-101XXX.dwg
ISSUE DATE: SEP 2018
SOLICITATION NO.: XXXX
CONTRACT NO.: XXXX
FILE NO.: 228-25-0715
SPEC NO.: 2164

U.S. ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT

IN-HOUSE DESIGN
1325 J STREET
SACRAMENTO, CA 95814-2922

NELLIS AFB, NV
BLDG 332 RENOVATION
RKMF 17-0065
XXXX

DEMOLITION PLAN

SHEET ID
C-101

C:\users\l2edd:se\documents\pwwork\cespk\d0608124\C-101XXX.dwg



NOTES:

1. PROVIDE NEW CONCRETE WALKWAYS TO ALL BUILDING DOORS AND STAIR WAYS. PROVIDE WALKWAY BETWEEN BLDG 334 AND HOLLOMAN AVE/ SOUTH PARKING LOT.

LEGEND

HARDSCAPE

LANDSCAPED AREA

GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

US Army Corps of Engineers®

MARK	DESCRIPTION	DATE

DESIGNED BY: PC
DRAWN BY: PC
CHECKED BY: JSE
SUBMITTED BY: /s/ MARKUS BOEDTKER
SIZE: 22x34 ANSI D
ISSUE DATE: SEP 2018
SOLICITATION NO.: XXXX
CONTRACT NO.: XXXX
FILE NO.: 228-25-0715
FILE NAME: C-101XXX.dwg
PROJECT NO.: 21164

U.S. ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT

IN-HOUSE DESIGN
1325 J STREET
SACRAMENTO, CA 95814-2922

NELLIS AFB, NV
BLDG 332 RENOVATION
RKMF 17-0065
XXXX

SITE PLAN

SHEET ID
C-102

C:\users\l2edd:se\documents\pwwork\cespk\d0608124\C-101XXX.dwg



1 AD101 FIRST FLOOR DEMOLITION PLAN

1/8" = 1'-0"



US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: ORA
DRAWN BY: ORA
CHECKED BY: MKB
SUBMITTED BY: Matthew Z. Valentine
SIZE: ANSI D
FILE NAME: Enter Revit File Name
ISSUE DATE: SEP 2018
PROJECT # Enter #
Specs 21164
FILE NUMBER: 229-25-0715

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

FIRST FLOOR DEMOLITION PLAN

SHEET ID

AD101



NOTE: BROCKEN LINES SHOWN INDICATES ITEMS TO BE REMOVED EXCEPT AS NOTED.

1 AD102

SECOND FLOOR DEMOLITION PLAN

1/8" = 1'-0"

PLAN NORTH

5' 0 5' 15' 25'

1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

ISSUE DATE: SEP 2018
PROJECT # Enter #
Specs 21564
FILE NUMBER: 229-25-0715

DESIGNED BY: ORA
DRAWN BY: ORA
CHECKED BY: MKB
SUBMITTED BY: Matthew Z. Valentine
SIZE: ANSI D
FILE NAME: Enter Revit File Name

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

SECOND FLOOR DEMOLITION PLAN

SHEET ID

AD102



NOTE: BROCKEN LINES SHOWN INDICATES ITEMS TO BE REMOVED EXCEPT AS NOTED.

1 AD103

THIRD FLOOR DEMOLITION PLAN

1/8" = 1'-0"

PLAN NORTH

5' 0 5' 15' 25'

1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

ISSUE DATE: SEP 2018
PROJECT # Enter #
Specs 21164
FILE NUMBER: 229-25-0715

DESIGNED BY: ORA
DRAWN BY: ORA
CHECKED BY: MKB
SUBMITTED BY: Matthew Z. Valentine
SIZE: ANSI 'D'
FILE NAME: Enter Revit File Name

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

THIRD FLOOR DEMOLITION PLAN

SHEET ID

AD103



1 AD201 NORTH ELEVATION - DEMOLITION

1/8" = 1'-0"

NOTE: BROCKEN LINES SHOWN INDICATES ITEMS TO BE REMOVED EXCEPT AS NOTED.



2 AD201 SOUTH ELEVATION - DEMOLITION

1/8" = 1'-0"

4' 0 4' 8'

SCALE: 1/4" = 1' - 0"

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: ORA
DRAWN BY: ORA
CHECKED BY: MKB
SUBMITTED BY: Matthew Z. Valentine
SIZE: ANSI D
ISSUE DATE: SEP 2018
PROJECT # Enter #
Specs 21164
FILE NUMBER: 229-25-0715
FILE NAME: Enter Proj# File Name

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

NORTH AND SOUTH ELEVATIONS - DEMOLITION

SHEET ID

AD201



1 A-101

FIRST FLOOR PLAN

1/8" = 1'-0"

NOTE:
1. METAL STUD SHALL BE 600S137-33 @ 16" O.C. ANCHOR TOP AND BOTTOM TRACK INTO EXISTING CONCRETE WITH 0.177" DIA. PAF @ 16" O.C. EMBED PAF 1-1/2" INTO EXISTING CONCRETE.
2. INSTALL NEW EXTERIOR BATT INSULATION, MINIMUM R-19.
3. FOR PREFERRED NEW INTERIOR PARTITION TYPE, SEE REMARK COLUMN OF APPENDIX - ROOM AREA COMPUTATION OF THE RFP.

PLAN NORTH

5' 0 5' 15' 25'

1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: ORA
DRAWN BY: ORA
CHECKED BY: MKB
SUBMITTED BY: Matthew Z. Valentine
SIZE: ANSI 'D'
FILE NAME: Enter Proof File Name
ISSUE DATE: SEP 2018
PROJECT # Enter # Specs 21564
FILE NUMBER: 229-25-0715

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

FIRST FLOOR PLAN

SHEET ID

A-101



1 A-102

SECOND FLOOR PLAN

1/8" = 1'-0"

NOTE:
1. METAL STUD SHALL BE 600S137-33 @ 16" O.C. ANCHOR TOP AND BOTTOM TRACK INTO EXISTING CONCRETE WITH 0.177" DIA. PAF @ 16" O.C. EMBED PAF 1-1/2" INTO EXISTING CONCRETE.
2. INSTALL NEW EXTERIOR BATT INSULATION, MINIMUM R-19.
3. FOR PREFERRED NEW INTERIOR PARTITION TYPE, SEE REMARK COLUMN OF APPENDIX - ROOM AREA COMPUTATION OF THE RFP.

PLAN NORTH

5' 0 5' 15' 25'
1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

ISSUE DATE: SEP 2018
PROJECT # Enter #
Specs 21564
FILE NUMBER: 229-25-0715

DESIGNED BY: ORA
DRAWN BY: ORA
CHECKED BY: MKB
SUBMITTED BY: Matthew Z. Valentine
FILE NAME: ANSI 'D' Enter Sheet File Name

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

SECOND FLOOR PLAN

SHEET ID

A-102



1 A-103

THIRD FLOOR PLAN

1/8" = 1'-0"

NOTE:
1. METAL STUD SHALL BE 600S137-33 @ 16" O.C. ANCHOR TOP AND BOTTOM TRACK INTO EXISTING CONCRETE WITH 0.177" DIA. PAF @ 16" O.C. EMBED PAF 1-1/2" INTO EXISTING CONCRETE.
2. INSTALL NEW EXTERIOR BATT INSULATION, MINIMUM R-19.
3. FOR PREFERRED NEW INTERIOR PARTITION TYPE, SEE REMARK COLUMN OF APPENDIX - ROOM AREA COMPUTATION OF THE RFP.

PLAN NORTH

5' 0 5' 15' 25'
1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

ISSUE DATE: SEP 2018
PROJECT # Enter #
Specs 2164
FILE NUMBER: 229-25-0715

DESIGNED BY: ORA
DRAWN BY: ORA
CHECKED BY: MK
SUBMITTED BY: Matthew Z. Valentine
FILE NAME: ANSI 'D' Enter Revit File Name

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065
THIRD FLOOR PLAN

SHEET ID
A-103

1
A-201

SOUTH ELEVATION

1/8" = 1'-0"



2
A-201

NORTH ELEVATION

1/8" = 1'-0"

NOTE:
1. METAL STUD SHALL BE 600S137-33 @ 16" O.C. ANCHOR TOP AND BOTTOM TRACK INTO EXISTING CONCRETE WITH 0.177" DIA. PAF @ 16" O.C. EMBED PAF 1-1/2" INTO EXISTING CONCRETE.
2. INSTALL NEW EXTERIOR BATT INSULATION, MINIMUM R-19.

5' 0 5' 15' 25'
1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: ORA	ISSUE DATE: SEP 2018
DRAWN BY: ORA	PROJECT # Enter #
CHECKED BY: MKB	Specs 21164
SUBMITTED BY: Matthew Z. Valentine	FILE NUMBER: 229-25-0715
SIZE: ANSI D'	FILE NAME: Enter/Revit File Name

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

NORTH AND SOUTH ELEVATIONS

SHEET ID

A-201



1
A-202

WEST ELEVATION

1/8" = 1'-0"



2
A-202

EAST ELEVATION

1/8" = 1'-0"

5' 0 5' 15' 25'

1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: ORA
DRAWN BY: ORA
CHECKED BY: MKB
SUBMITTED BY: Matthew Z. Valentine
SIZE: ANSI D
FILE NAME: Enter/Text/ File Name
ISSUE DATE: SEP 2018
PROJECT # Enter #
Specs 21164
FILE NUMBER: 229-25-0715

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

EAST AND WEST ELEVATIONS

SHEET ID

A-202

USACE_DOOR SCHEDULE - FIRST FLOOR

DOOR NO.	TYPE	DOOR SIZE WIDTH	DOOR SIZE HEIGHT	DOOR SIZE THICKNESS	DOOR MATERIAL	DOOR FINISH	FRAME MATERIAL	FRAME FINISH	COMMENTS:
100	FG1	6' - 0"	7' - 0"	2"	GLASS		ALUM.	ANOD.	MECHANICAL PUSH BUTTON LOCK
101	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
105	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
106	D	3' - 0"	6' - 8"	1 3/4"	WD	STN	HM	PNT	DUTCH DOOR
107	FF	6' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
107A	FF	8' - 0"	7' - 0"	1 3/4"	HM	PNT	HM	PNT	MECHANICAL PUSH BUTTON LOCK
110	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
111	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
112	F	3' - 0"	6' - 8"	1 3/4"	WD	STN	HM	PNT	
113	F	3' - 0"	7' - 0"	1 3/4"	HM	PNT	HM	PNT	MECHANICAL PUSH BUTTON LOCK
114	FF	6' - 0"	7' - 0"	1 3/4"	HM	PNT	HM	PNT	MECHANICAL PUSH BUTTON LOCK
115	FF	6' - 0"	7' - 0"	1 3/4"	HM	PNT	HM	PNT	MECHANICAL PUSH BUTTON LOCK
116	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
117	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
118	F	2' - 4"	6' - 8"	1 3/4"	WD	STN	HM	PNT	
119	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
125	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
127	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
128	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
129	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
132	N	3' - 0"	7' - 0"	1 3/4"	WD	PNT	HM	PNT	
134	F	3' - 0"	7' - 0"	1 3/4"	HM	PNT	HM	PNT	MECHANICAL PUSH BUTTON LOCK
137A	FF	6' - 0"	7' - 0"	1 3/4"	HM	PNT	HM	PNT	MECHANICAL PUSH BUTTON LOCK
137B	FG	3' - 0"	7' - 0"	2"	ALUM	ANOD	ALUM	ANOD	MECHANICAL PUSH BUTTON LOCK

USACE_DOOR SCHEDULE - SECOND FLOOR

DOOR NO.	TYPE	DOOR SIZE WIDTH	DOOR SIZE HEIGHT	DOOR SIZE THICKNESS	DOOR MATERIAL	DOOR FINISH	FRAME MATERIAL	FRAME FINISH	COMMENTS:
201	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
209	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
210A	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
210B	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
211A	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	NPT	
211B	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
212	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
213	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
214	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
215	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
217	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
218	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
219	F	2' - 6"	6' - 8"	1 3/4"	WD	STN	HM	PNT	
220	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
222	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
223	F	3' - 0"	7' - 0"	1 3/4"	HM	PNT	HM	PNT	
224	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
225	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
226	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
229	N	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
232A	FG	3' - 0"	7' - 0"	2"	ALUM	ANOD	ALUM	ANOD	MECHANICAL PUSH BUTTON LOCK
232B	G	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	WITH/ VISION LITE
233	FG	3' - 0"	7' - 0"	2"	ALUM	ANOD	ALUM	ANOD	MECHANICAL PUSH BUTTON LOCK

USACE_DOOR SCHEDULE - THIRD FLOOR

DOOR NO.	TYPE	DOOR SIZE WIDTH	DOOR SIZE HEIGHT	DOOR SIZE THICKNESS	DOOR MATERIAL	DOOR FINISH	FRAME MATERIAL	FRAME FINISH	COMMENTS:
302A	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
302B	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
303	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
304	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
305	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
306	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
307	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
310	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
312	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
313	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
314	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
315	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	MECHANICAL PUSH BUTTON LOCK
316	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
317	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
318	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
319	F	2' - 4"	6' - 8"	1 3/4"	WD	STN	HM	PNT	
320	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
322	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
323	F	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
327	N	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
330A	G	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
330B	G	3' - 0"	7' - 0"	1 3/4"	WD	STN	HM	PNT	
331	FG	3' - 0"	7' - 0"	2"	ALUM	ANOD	ALUM	ANOD	MECHANICAL PUSH BUTTON LOCK
332	FG	3' - 0"	7' - 0"	2"	ALUM	ANOD	ALUM	ANOD	MECHANICAL PUSH BUTTON LOCK



DOOR TYPES

1/4" = 1'-0"

NOTE: ALL EXTERIOR STEEL DOOR SHALL BE INSULATED.

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: ORA
DRAWN BY: ORA
CHECKED BY: MK
SUBMITTED BY: Matthew Z. Valentine
SIZE: ANSI D
FILE NAME: Enter/Revit File Name
ISSUE DATE: SEP 2018
PROJECT # Enter #
Specs 21564
FILE NUMBER: 229-25-0715

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

DOOR SCHEDULE

SHEET ID

A-620

FIRST FLOOR INTERIOR FINISH/COLOR SCHEDULE

RM. NO.	ROOM NAME	FLOOR	BASE	WAINSCOT MATERIAL	WAINSCOT HEIGHT	WALLS NORTH	COLOR	EAST	COLOR	SOUTH	COLOR	WEST	COLOR	CEILING MATERIAL	CEILING COLOR	CEILING HEIGHT	CABINETRY CABINETS	CABINETRY CNTRTOP	DOORS	TRIM	REMARKS
100	LOBBY/ENTRY	PPT1/G1	PPT1/G1	--		GWB	P1	GWB	P6	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	FF/P4	P4	--
101	FLT CHIEF	C1	RB1	--		DMT	P1	GWB	P1	DMT	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
102	CLIENT SVC CENTER	C1	RB1	--		GWB	P1	GWB	P1	DMT	P1	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
103	KNOWLEDGE OPS	C1	RB1	--		GWB	P1	DMT	P1	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
104	NETWORK SYS.	C1	RB1	--		GWB	P1	--	--	--	--	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
105	OFFICE STOR.	R1	RB1	--		GWB	P1	DMT	P1	DMT	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
106	COMP & EQUIPMENT STOR.	ESD1	RB1	--		GWB	P1	GWB	P1	GWB	P1	--	--	GWB	P3	8'-0"	--	--	P4	P4	NOTE 4, 9
107	MAIN STORAGE	CONC1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P3	8'-0"	--	--	P4	P4	--
108	LOG PLANS	C1	RB1	--		GWB	P1	--	--	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
109	MATL MGMN'T	C1	RB1	--		--	--	DMT	P1	GWB	P1	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
110	READINESS OFF.	C1	RB1	--		DMT	P1	DMT	P1	GWB	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
111	TRAINING SPACES	C1	RB1	--		DMT	P1	GWB	P1	GWB	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	CR, WS2
112	COMM RM	ESD1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P3	8'-6"	--	--	P4	P4	NOTES 3, 4
113	ELEC RM	CONC1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	EXP	P3	VARIES	--	--	P4	P4	--
114	MECH	CONC1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	EXP	P3	VARIES	--	--	P4	P4	--
115	MECH	CONC1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	EXP	P3	VARIES	--	--	P4	P4	--
116	BREAKROOM	R1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P6	ACT	ACT1	8'-0"	PLAM1	SSM1	S1	P4	--
117	MEN RR	PPT1/G1	PPT1/G1	CT1/CT2/G2	4' - 9"	GWB	P2	GWB	P2	GWB	P2	GWB	P2	GWB	P2	8'-0"	PLAM2	SSM2	S1	P4	TP1
118	JAN	PPT1/G1	PPT1/G1	CT1/G2	4' - 9"	GWB	P2	GWB	P2	GWB	P2	GWB	P2	GWB	P2	8'-0"	--	--	S1	P4	NOTE 1
119	WOMEN RR	PPT1/G1	PPT1/G1	CT1/CT2/G2	4' - 9"	GWB	P2	GWB	P2	GWB	P2	GWB	P2	GWB	P2	8'-0"	PLAM2	SSM2	S1	P4	TP1
120	RECEPTION	C1	RB1	--		--	--	GWB	P1	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
121	CHAP ASST	C1	RB1	--		--	--	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
122	SR CHAPLAIN	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
123	JR CHAP	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
124	COUNSELING	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
125	EEO OFFICE	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
126	EEO OFFICE	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
127	MEETING RM	C1	RB1	--		GWB	P1	GWB	P1	DMT	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	CR, WS2
128	SR JDG ADVOCATE	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
129	JR JDG ADVOCATE	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
130	PARALEGAL & STOR.	C1	RB1	--		GWB	P1	GWB	P1	--	--	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
131	RECEPTION	C1	RB1	--		--	--	--	--	--	--	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
132	STAIR	R2/R3	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P3	8'-0"	--	--	P4	P4	NOTE 2
133	ELEV.	CONC1	--	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	--	--	--	--	--	FF	P4	NOTE 7
134	ELEV. MECH	CONC1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	P4	P4	--
135	DISPLAY AREA	C1	RB1	--		GWB	P1	GWB	P1	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
136	CORRIDOR	C1	RB1	--		GWB	P1	GWB	P1	--	--	GWB	P1	ACT	ACT1	8'-0"	--	--	P4	P4	--
137	CORRIDOR	C1	RB1	--		DMT/GWB	P1	GWB	P1	DMT/GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	P4/S1	P4	--

SHEET NOTES:

1.) SHELVING IN JANITOR CLOSETS SHALL BE ADJUSTABLE.

2.) HANDRAILS IN STAIRWELLS SHALL BE PAINTED: P5

3.) BACKERBOARDS IN COMM ROOMS SHALL BE 3/4" FIRE-RETARDANT TREATED PLYWOOD (VOID-FREE) PER UFC 3-580-01.

4.) STATIC-CONTROL FLOOR SYSTEM SHALL BE CONNECTED TO BUILDING GROUND.

5.) CORNER WALL GUARDS SHALL BE INSTALLED AT ALL VULNERABLE OUTSIDE CORNERS.

6.) DEMOUNTABLE WALLS ARE CONTRACTOR FURNISHED/CONTRACTOR INSTALLED (CF/CI). ACCOMMODATE BUILDING INFRASTRUCTURE AS REQUIRED.

7.) ELEVATOR CAB FINISHES SHALL BE HIGH-IMPACT PLASTIC LAMINATE FOR WALLS, PORCELAIN PAVER TILES FOR FLOOR, AND FACTORY FINISH CEILING.

8.) ALL WINDOWS LOCATED AT EXTERIOR WALLS RECEIVE WINDOW COVERING: WS1, UNLESS OTHERWISE NOTED (UON).

9.) SEE ARCHITECTURAL SHEETS FOR CHAIN LINK FENCE.

10.) WALL COLUMNS IN FINISH SCHEDULES REPRESENT SUGGESTED WALL CONSTRUCTION MATERIAL.

11.) CEILING COLUMN IN FINISH SCHEDULES REPRESENT SUGGESTED CEILING HEIGHTS. ACCOMMODATE HVAC WORK AS REQUIRED.

GENERAL NOTES:

A. FOR WALLS WITH A WAINSCOT, THE WAINSCOT MATERIAL IS LISTED IN THE WAINSCOT COLUMN. THE MATERIAL LOCATED ABOVE THE WAINSCOT IS LISTED IN THE WALLS COLUMNS.

B. THE DOOR COLUMN DENOTES THE FINISH, NOT THE DOOR MATERIAL.

C. THE COLUMN LABELED AS TRIM IS USED FOR DOOR & WINDOW FRAMES.

FINISH LEGEND:

ACT: ACOUSTICAL CEILING TILES (2'X2', SEE NOTE 11)
ACT1: COLOR: FLAT WHITE

C: CARPET (24"X24" TILES)
C1: COLOR: MULTI-COLOR PATTERN, MEDIUM TONES
C2: C1 WITH CARPET PAD (COMMANDER'S OFFICE)

CG: CORNER GUARDS (SEE NOTE 5)
COLOR: COMPLEMENT WALL COLOR

CONC: CONCRETE
CONC1: SURFACE SEALED CONCRETE WITH HARDENER

CR: CHAIR RAIL (COORDINATE INSTALL HEIGHT WITH GF/GI SEATING)
COLOR: COMPLEMENT WALL COLOR

CT: CERAMIC TILE (WALLS)
CT1: FIELD TILE - COLOR: NEUTRAL, LIGHT TONES (MINIMUM 6"X6")
CT2: ACCENT BAND - COLOR: COORDINATE WITH CT1

DMT: DEMOUNTABLE WALL SYSTEM (SEE NOTES 6 & 10)

ESD: ELECTROSTATIC DISSIPATIVE (GROUNDED TO BUILDING)
ESD1: COLOR: SPECKLED PATTERN

EXP: EXPOSED TO STRUCTURE ABOVE (U.O.N., NO OTHER FINISH REQUIRED)

FF: FACTORY FINISH

G: GROUT (ANTI-BACTERIAL)
G1: COLOR: MEDIUM TO DARK TONES (FLOOR)
G2: COLOR: LIGHT TO MEDIUM TONES (WALL)

GWB: GYPSUM WALLBOARD, USE APPROPRIATE TYPE REQUIRED BY ROOM FUNCTION (SEE NOTES 10 & 11)

P: PAINT
P1: EGGSHELL SHEEN (FIELD COLOR)
P2: SEMI-GLOSS SHEEN (RESTROOMS)
P3: FLAT WHITE (CEILING)
P4: HIGH-GLOSS SHEEN (TRIM)
P5: ENAMEL (HANDRAILS)
P6: EGGSHELL SHEEN (ACCENT COLOR, LOBBIES & BREAKROOMS)

PLAM: PLASTIC LAMINATE (NEUTRAL COLOR)
PLAM1: CABINETS (BREAKROOM)
PLAM2: PLUMBING REVEAL (RESTROOMS)

PROJ: PROJECTOR SCREEN WITH PROJECTOR MOUNT

PPT: PORCELAIN PAVER TILES (FLOORS)
PPT1: COLOR: NEUTRAL, MEDIUM TONES (PREFERRED 12"X12")

R: RESILIENT FLOORING (NEUTRAL, MEDIUM TONE COLOR)
R1: HOMOGENEOUS VINYL (SHEET, HEAT-WELDED WITH SLIGHT PATTERN)
R2: RUBBER STAIR TREAD WITH INTEGRATED RISER (RAISED PROFILE TEXTURE AND CONTRASTING EDGE COLOR FOR VISUALLY IMPAIRED)
R3: RUBBER TILE (24"X24", STAIR LANDINGS)

RB: RESILIENT WALL BASE (4" HIGH)
RB1: COLOR: MEDIUM TONES (COORDINATE WITH CARPET AND RESILIENT FLOORING)

S: STAIN, WOOD
S1: COLOR: CLEAR (OAK)

SSM: SOLID SURFACE MATERIAL (NEUTRAL COLOR)
SSM1: COLOR: MEDIUM TONES WITH SLIGHT PATTERN (BREAKROOM COUNTERTOP)
SSM2: COLOR: LIGHT TONES (RESTROOMS COUNTERTOP)

TP: TOILET PARTITIONS & URINAL SCREENS (SOLID POLYETHYLENE)
TP1: COLOR: NEUTRAL, LIGHT TO MEDIUM TONES

WS: WINDOW SHADES (NEUTRAL COLOR, SEE NOTE 8)
WS1: SINGLE ROLLER - TRANSLUCENT (5 OPENNESS)
WS2: DUAL ROLLERS - TRANSLUCENT (5) AND BLACKOUT

This project was designed by the Sacramento District of the U. S. Army Corps of Engineers.The initials or signatures and registration designations of individuals appear on these project documents within the scope of their employment as required by ER 1110-1-8152

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: D OWEN
DRAWN BY: D OWEN
CHECKED BY: K STEPHENS
SUBMITTED BY: /s/ Matthew Z. Valentine
SIZE: ANSI D
FILE NUMBER: 229-25-0715
FILE NAME: B332 INTERIORS CENTRAL (SID)
ISSUE DATE: SEP 2018
PROJECT #: RKMF-17-0065
SPEC #.: 2164

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
U.S. DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 526 WG BUILDING 332
RKMF 17-0065

FIRST FLOOR INTERIOR FINISH/COLOR SCHEDULE

SHEET ID
I-610

SECOND FLOOR INTERIOR FINISH/COLOR SCHEDULE

				WAINSCOT		WALLS								CEILING			CABINETRY				
RM. NO.	ROOM NAME	FLOOR	BASE	MATERIAL	HEIGHT	NORTH	COLOR	EAST	COLOR	SOUTH	COLOR	WEST	COLOR	MATERIAL	COLOR	HEIGHT	CABINETS	CNTRTOP	DOORS	TRIM	REMARKS
200	LOBBY	C1	RB1	--		GWB	P1	GWB	P6	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	P4	P4	--
201	MED RECORD	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P3	8'-0"	--	--	S1	P4	--
202	NURSES	C1	RB1	--		GWB	P1	GWB	P1	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
203	PHYSICIANS	C1	RB1	--		GWB	P1	--	--	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
204	KNWLDG OPS	C1	RB1	--		GWB	P1	--	--	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
205	UNIT TRN MGR	C1	RB1	--		GWB	P1	--	--	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
206	OPTOMETRIST	C1	RB1	--		GWB	P1	--	--	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
207	LAB TECH	C1	RB1	--		GWB	P1	--	--	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
208	DENTAL ADMIN	C1	RB1	--		GWB	P1	--	--	--	--	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
209	STORAGE	R1	RB1	--		GWB	P1	DMT	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
210	TRAINING ROOM	C1	RB1	--		DMT/GWB	P1	DMT	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	CR, PROJ, WS2
211	SKILLS LAB	R1	RB1	--		DMT	P1	GWB	P1	GWB	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	WS2
212	COMM ROOM	ESD1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P3	8'-6"	--	--	P4	P4	NOTES 3, 4
213	ELECT. ROOM	CONC1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	EXP	P3	VARIES	--	--	P4	P4	--
214	MECH	CONC1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	EXP	P3	VARIES	--	--	P4	P4	--
215	EXAM RM	R1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	PLAM1	SSM1	S1	P4	--
216A	EXAM RM	R1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	PLAM1	SSM1	S1	P4	--
216B	EXAM RM	R1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	PLAM1	SSM1	S1	P4	--
217	MED TECH	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
218	MEN RR	PPT1/G1	PPT1/G1	CT1/CT2/G2	4' - 9"	GWB	P2	GWB	P2	GWB	P2	GWB	P2	GWB	P2	8'-0"	PLAM2	SSM2	S1	P4	TP1
219	JAN	PPT1/G1	PPT1/G1	CT1/G2	4' - 9"	GWB	P2	GWB	P2	GWB	P2	GWB	P2	GWB	P2	8'-0"	--	--	S1	P4	NOTE 1
220	WOMEN RR	PPT1/G1	PPT1/G1	CT1/CT2/G2	4' - 9"	GWB	P2	GWB	P2	GWB	P2	GWB	P2	GWB	P2	8'-0"	PLAM2	SSM2	S1	P4	TP1
221	CMDR SUPPORT STAFF	C2	RB1	--		DMT/GWB	P1	DMT	P1	GWB	P1	DMT/GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
222	OFF. STOR.	R1	RB1	--		DMT	P1	DMT	P1	DMT	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
223	CONF ROOM	C2	RB1	--		DMT/GWB	P1	GWB	P1	GWB	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	CR, WS2
224	CMDR OFFICE	C2	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
225	1SG OFFICE	C2	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
226	SUPERINTENDENT	C2	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
227	CMDR RECPN	C2	RB1	--		GWB	P1	--	--	--	--	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
228	MED TECH	C1	RB1	--		GWB	P1	GWB	P1	--	--	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
229	STAIR	R2/R3	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P3	8'-0"	--	--	P4	P4	NOTE 2
230	ELEV	--	--	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	--	--	--	--	--	FF	P4	NOTE 7
231	CORRIDOR	C1	RB1	--		--	--	GWB	P1	--	--	GWB	P1	ACT	ACT1	8'-0"	--	--	P4/S1	P4	--
232	CORRIDOR	C1	RB1	--		DMT/GWB	P1	GWB	P1	DMT/GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
233	CORRIDOR	C2	RB	--		GWB	P1	GWB	P1	DMT	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	P4/S1	P4	--

SHEET NOTES:

1.) SHELVING IN JANITOR CLOSETS SHALL BE ADJUSTABLE.

2.) HANDRAILS IN STAIRWELLS SHALL BE PAINTED: P5

3.) BACKERBOARDS IN COMM ROOMS SHALL BE 3/4" FIRE-RETARDANT TREATED PLYWOOD (VOID-FREE) PER UFC 3-580-01.

4.) STATIC-CONTROL FLOOR SYSTEM SHALL BE CONNECTED TO BUILDING GROUND.

5.) CORNER WALL GUARDS SHALL BE INSTALLED AT ALL VULNERABLE OUTSIDE CORNERS.

6.) DEMOUNTABLE WALLS ARE CONTRACTOR FURNISHED/CONTRACTOR INSTALLED (CF/CI). ACCOMMODATE BUILDING INFRASTRUCTURE AS REQUIRED.

7.) ELEVATOR CAB FINISHES SHALL BE HIGH-IMPACT PLASTIC LAMINATE FOR WALLS, PORCELAIN PAVER TILES FOR FLOOR, AND FACTORY FINISH CEILING.

8.) ALL WINDOWS LOCATED AT EXTERIOR WALLS RECEIVE WINDOW COVERING: WS1, UNLESS OTHERWISE NOTED (UON).

9.) SEE ARCHITECTURAL SHEETS FOR CHAIN LINK FENCE.

10.) WALL COLUMNS IN FINISH SCHEDULES REPRESENT SUGGESTED WALL CONSTRUCTION MATERIAL.

11.) CEILING COLUMN IN FINISH SCHEDULES REPRESENT SUGGESTED CEILING HEIGHTS. ACCOMMODATE HVAC WORK AS REQUIRED.

GENERAL NOTES:

A. FOR WALLS WITH A WAINSCOT, THE WAINSCOT MATERIAL IS LISTED IN THE WAINSCOT COLUMN. THE MATERIAL LOCATED ABOVE THE WAINSCOT IS LISTED IN THE WALLS COLUMNS.

B. THE DOOR COLUMN DENOTES THE FINISH, NOT THE DOOR MATERIAL.

C. THE COLUMN LABELED AS TRIM IS USED FOR DOOR & WINDOW FRAMES.

FINISH LEGEND:

ACT: ACOUSTICAL CEILING TILES (2'X2', SEE NOTE 11)
ACT1: COLOR: FLAT WHITE

C: CARPET (24"X24" TILES)
C1: COLOR: MULTI-COLOR PATTERN, MEDIUM TONES
C2: C1 WITH CARPET PAD (COMMANDER'S OFFICE)

CG: CORNER GUARDS (SEE NOTE 5)
COLOR: COMPLEMENT WALL COLOR

CONC: CONCRETE
CONC1: SURFACE SEALED CONCRETE WITH HARDENER

CR: CHAIR RAIL (COORDINATE INSTALL HEIGHT WITH GF/GI SEATING)
COLOR: COMPLEMENT WALL COLOR

CT: CERAMIC TILE (WALLS)
CT1: FIELD TILE - COLOR: NEUTRAL, LIGHT TONES (MINIMUM 6"X6")
CT2: ACCENT BAND - COLOR: COORDINATE WITH CT1

DMT: DEMOUNTABLE WALL SYSTEM (SEE NOTES 6 & 10)

ESD: ELECTROSTATIC DISSIPATIVE (GROUNDED TO BUILDING)
ESD1: COLOR: SPECKLED PATTERN

EXP: EXPOSED TO STRUCTURE ABOVE (U.O.N., NO OTHER FINISH REQUIRED)

FF: FACTORY FINISH

G: GROUT (ANTI-BACTERIAL)
G1: COLOR: MEDIUM TO DARK TONES (FLOOR)
G2: COLOR: LIGHT TO MEDIUM TONES (WALL)

GWB: GYPSUM WALLBOARD, USE APPROPRIATE TYPE REQUIRED BY ROOM FUNCTION (SEE NOTES 10 & 11)

P: PAINT
P1: EGGSHELL SHEEN (FIELD COLOR)
P2: SEMI-GLOSS SHEEN (RESTROOMS)
P3: FLAT WHITE (CEILING)
P4: HIGH-GLOSS SHEEN (TRIM)
P5: ENAMEL (HANDRAILS)
P6: EGGSHELL SHEEN (ACCENT COLOR, LOBBIES & BREAKROOMS)

PLAM: PLASTIC LAMINATE (NEUTRAL COLOR)
PLAM1: CABINETS (BREAKROOM)
PLAM2: PLUMBING REVEAL (RESTROOMS)

PROJ: PROJECTOR SCREEN WITH PROJECTOR MOUNT

PPT: PORCELAIN PAVER TILES (FLOORS)
PPT1: COLOR: NEUTRAL, MEDIUM TONES (PREFERRED 12"X12")

R: RESILIENT FLOORING (NEUTRAL, MEDIUM TONE COLOR)
R1: HOMOGENEOUS VINYL (SHEET, HEAT-WELDED WITH SLIGHT PATTERN)
R2: RUBBER STAIR TREAD WITH INTEGRATED RISER (RAISED PROFILE TEXTURE AND CONTRASTING EDGE COLOR FOR VISUALLY IMPAIRED)
R3: RUBBER TILE (24"X24", STAIR LANDINGS)

RB: RESILIENT WALL BASE (4" HIGH)
RB1: COLOR: MEDIUM TONES (COORDINATE WITH CARPET AND RESILIENT FLOORING)

S: STAIN, WOOD
S1: COLOR: CLEAR (OAK)

SSM: SOLID SURFACE MATERIAL (NEUTRAL COLOR)
SSM1: COLOR: MEDIUM TONES WITH SLIGHT PATTERN (BREAKROOM COUNTERTOP)
SSM2: COLOR: LIGHT TONES (RESTROOMS COUNTERTOP)

TP: TOILET PARTITIONS & URINAL SCREENS (SOLID POLYETHYLENE)
TP1: COLOR: NEUTRAL, LIGHT TO MEDIUM TONES

WS: WINDOW SHADES (NEUTRAL COLOR, SEE NOTE 8)
WS1: SINGLE ROLLER - TRANSLUCENT (5 OPENNESS)
WS2: DUAL ROLLERS - TRANSLUCENT (5) AND BLACKOUT

This project was designed by the Sacramento District of the U. S. Army Corps of Engineers.The initials or signatures and registration designations of individuals appear on these project documents within the scope of their employment as required by ER 1110-1-8152

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: D.OWEN
DRAWN BY: D.OWEN
CHECKED BY: K.STEPHENS
SUBMITTED BY: Matthew Z. Valentine
SIZE: E1 FILE NAME: B332 INTERIORS CENTRAL (SID)
ISSUE DATE: SEP 2018
PROJECT #: RKMF-17-0065
SPEC #: 2164
FILE NUMBER: 229-25-0715

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
U.S. DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 332 WG BUILDING 332
RKMF 17-0065

SECOND FLOOR INTERIOR FINISH/COLOR SCHEDULE

SHEET ID

I-611

THIRD FLOOR INTERIOR FINISH/COLOR SCHEDULE

				WAINSCOT		WALLS								CEILING			CABINETRY				
RM. NO.	ROOM NAME	FLOOR	BASE	MATERIAL	HEIGHT	NORTH	COLOR	EAST	COLOR	SOUTH	COLOR	WEST	COLOR	MATERIAL	COLOR	HEIGHT	CABINETS	CNTRTOP	DOORS	TRIM	REMARKS
300	LOBBY	C1	RB1	--		GWB	P1	GWB	P6	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	P4	P4	--
301	FLIGHT CHIEF	C1	RB1	--		GWB	P1	--	--	--	--	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
302	TRAINING ROOM	C1	RB1	--		GWB	P1	DMT	P1	DMT	P1	DMT	P1	GWB	P3	8'-0"	--	--	S1	P4	CR, PROJ, WS2
303	SUPT.	C2	RB1	--		GWB	P1	DMT	P1	DMT	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
304	CURRENT OPS.	C2	RB1	--		GWB	P1	DMT	P1	DMT	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
305	DEP. COMMANDER	C2	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
306	COMMANDER	C2	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
307	XO	C2	RB1	--		DMT	P1	DMT	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
308	CAREER ADV.	C2	RB1	--		GWB	P1	--	--	GWB	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
309	COMMAND SUPPORT STAFF	C2	RB1	--		--	--	DMT	P1	GWB	P1	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
310	CONF. ROOM	C2	RB1	--		DMT	P1	DMT	P1	GWB	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	CR, WS2
311	TRAINING MNGR	C1	RB1	--		--	--	--	--	DMT	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
312	STORAGE	R1	RB1	--		DMT	P1	DMT	P1	GWB	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
313	COMM RM	ESD1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P3	8'-6"	--	--	P4	P4	NOTES 3, 4
314	ELECT RM	CONC1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	EXP	P3	8'-0"	--	--	P4	P4	--
315	SIPR/INTEL	C1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	P4	P4	WS2
316	BREAK RM	R1	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P6	ACT	ACT1	8'-0"	S1	SSM1	S1	P4	--
317	MEN RR	PPT1/G1	PPT1/G1	CT1/CT2/G2	4' - 9"	GWB	P2	GWB	P2	GWB	P2	GWB	P2	GWB	P2	8'-0"	PLAM2	SSM2	S1	P4	TP1
318	WOMEN RR	PPT1/G1	PPT1/G1	CT1/CT2/G2	4' - 9"	GWB	P2	GWB	P2	GWB	P2	GWB	P2	GWB	P2	8'-0"	PLAM2	SSM2	S1	P4	TP1
319	JAN	PPT1/G1	PPT1/G1	CT1/G2	4' - 9"	GWB	P2	GWB	P2	GWB	P2	GWB	P2	GWB	P2	8'-0"	--	--	S1	P4	NOTE 1
320	MAINT OFFICER	C1	RB1	--		DMT	P1	DMT	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
321	COMMANDER SUPPORT STAFF	C2	RB1	--		GWB	P1	GWB	P1	GWB	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
322	COMMANDER	C2	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
323	1SG OFF	C2	RB1	--		GWB	P1	GWB	P1	GWB	P1	DMT	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
324	SUPERINTENDENT	C1	RB1	--		GWB	P1	DMT	P1	DMT	P1	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
325	COMPUTER WORK STATIONS	C1	RB1	--		GWB	P1	--	--	--	--	--	--	ACT	ACT1	8'-0"	--	--	S1	P4	--
326	SHOP CHIEF	C1	RB1	--		GWB	P1	--	--	--	--	GWB	P1	ACT	ACT1	8'-0"	--	--	S1	P4	--
327	STAIR	R2/R3	RB1	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P3	8'-0"	--	--	P4	P4	NOTE 2
328	ELEV	--	--	--		GWB	P1	GWB	P1	GWB	P1	GWB	P1	--	--	--	--	--	FF	P4	NOTE 7
329	CORRIDOR	C1	RB1	--		--	--	GWB	P1	--	--	--	--	ACT	ACT1	8'-0"	--	--	P4	P4	--
330	CORRIDOR	C1	RB1	--		DMT/GWB	P1	GWB	P1	DMT/GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	P4/S1	P4	--
331	CORRIDOR	C2	RB1	--		DMT/GWB	P1	GWB	P1	DMT/GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	P4/S1	P4	--
332	CORRIDOR	C2	RB1	--		DMT/GWB	P1	GWB	P1	DMT/GWB	P1	GWB	P1	ACT	ACT1	8'-0"	--	--	P4/S1	P4	--

SHEET NOTES:

1.) SHELVING IN JANITOR CLOSETS SHALL BE ADJUSTABLE.

2.) HANDRAILS IN STAIRWELLS SHALL BE PAINTED: P5

3.) BACKERBOARDS IN COMM ROOMS SHALL BE 3/4" FIRE-RETARDANT TREATED PLYWOOD (VOID-FREE) PER UFC 3-580-01.

4.) STATIC-CONTROL FLOOR SYSTEM SHALL BE CONNECTED TO BUILDING GROUND.

5.) CORNER WALL GUARDS SHALL BE INSTALLED AT ALL VULNERABLE OUTSIDE CORNERS.

6.) DEMOUNTABLE WALLS ARE CONTRACTOR FURNISHED/CONTRACTOR INSTALLED (CF/CI). ACCOMMODATE BUILDING INFRASTRUCTURE AS REQUIRED.

7.) ELEVATOR CAB FINISHES SHALL BE HIGH-IMPACT PLASTIC LAMINATE FOR WALLS, PORCELAIN PAVER TILES FOR FLOOR, AND FACTORY FINISH CEILING.

8.) ALL WINDOWS LOCATED AT EXTERIOR WALLS RECEIVE WINDOW COVERING: WS1, UNLESS OTHERWISE NOTED (UON).

9.) SEE ARCHITECTURAL SHEETS FOR CHAIN LINK FENCE.

10.) WALL COLUMNS IN FINISH SCHEDULES REPRESENT SUGGESTED WALL CONSTRUCTION MATERIAL.

11.) CEILING COLUMN IN FINISH SCHEDULES REPRESENT SUGGESTED CEILING HEIGHTS. ACCOMMODATE HVAC WORK AS REQUIRED.

GENERAL NOTES:

A. FOR WALLS WITH A WAINSCOT, THE WAINSCOT MATERIAL IS LISTED IN THE WAINSCOT COLUMN. THE MATERIAL LOCATED ABOVE THE WAINSCOT IS LISTED IN THE WALLS COLUMNS.

B. THE DOOR COLUMN DENOTES THE FINISH, NOT THE DOOR MATERIAL.

C. THE COLUMN LABELED AS TRIM IS USED FOR DOOR & WINDOW FRAMES.

FINISH LEGEND:

ACT: ACOUSTICAL CEILING TILES (2'X2', SEE NOTE 11)
ACT1: COLOR: FLAT WHITE

C: CARPET (24"X24" TILES)
C1: COLOR: MULTI-COLOR PATTERN, MEDIUM TONES
C2: C1 WITH CARPET PAD (COMMANDER'S OFFICE)

CG: CORNER GUARDS (SEE NOTE 5)
COLOR: COMPLEMENT WALL COLOR

CONC: CONCRETE
CONC1: SURFACE SEALED CONCRETE WITH HARDENER

CR: CHAIR RAIL (COORDINATE INSTALL HEIGHT WITH GF/GI SEATING)
COLOR: COMPLEMENT WALL COLOR

CT: CERAMIC TILE (WALLS)
CT1: FIELD TILE - COLOR: NEUTRAL, LIGHT TONES (MINIMUM 6"X6")
CT2: ACCENT BAND - COLOR: COORDINATE WITH CT1

DMT: DEMOUNTABLE WALL SYSTEM (SEE NOTES 6 & 10)

ESD: ELECTROSTATIC DISSIPATIVE (GROUNDED TO BUILDING)
ESD1: COLOR: SPECKLED PATTERN

EXP: EXPOSED TO STRUCTURE ABOVE (U.O.N., NO OTHER FINISH REQUIRED)

FF: FACTORY FINISH

G: GROUT (ANTI-BACTERIAL)
G1: COLOR: MEDIUM TO DARK TONES (FLOOR)
G2: COLOR: LIGHT TO MEDIUM TONES (WALL)

GWB: GYPSUM WALLBOARD, USE APPROPRIATE TYPE REQUIRED BY ROOM FUNCTION (SEE NOTES 10 & 11)

P: PAINT
P1: EGGSHELL SHEEN (FIELD COLOR)
P2: SEMI-GLOSS SHEEN (RESTROOMS)
P3: FLAT WHITE (CEILING)
P4: HIGH-GLOSS SHEEN (TRIM)
P5: ENAMEL (HANDRAILS)
P6: EGGSHELL SHEEN (ACCENT COLOR, LOBBIES & BREAKROOMS)

PLAM: PLASTIC LAMINATE (NEUTRAL COLOR)
PLAM1: CABINETS (BREAKROOM)
PLAM2: PLUMBING REVEAL (RESTROOMS)

PROJ: PROJECTOR SCREEN WITH PROJECTOR MOUNT

PPT: PORCELAIN PAVER TILES (FLOORS)
PPT1: COLOR: NEUTRAL, MEDIUM TONES (PREFERRED 12"X12")

R: RESILIENT FLOORING (NEUTRAL, MEDIUM TONE COLOR)
R1: HOMOGENEOUS VINYL (SHEET, HEAT-WELDED WITH SLIGHT PATTERN)
R2: RUBBER STAIR TREAD WITH INTEGRATED RISER (RAISED PROFILE TEXTURE AND CONTRASTING EDGE COLOR FOR VISUALLY IMPAIRED)
R3: RUBBER TILE (24"X24", STAIR LANDINGS)

RB: RESILIENT WALL BASE (4" HIGH)
RB1: COLOR: MEDIUM TONES (COORDINATE WITH CARPET AND RESILIENT FLOORING)

S: STAIN, WOOD
S1: COLOR: CLEAR (OAK)

SSM: SOLID SURFACE MATERIAL (NEUTRAL COLOR)
SSM1: COLOR: MEDIUM TONES WITH SLIGHT PATTERN (BREAKROOM COUNTERTOP)
SSM2: COLOR: LIGHT TONES (RESTROOMS COUNTERTOP)

TP: TOILET PARTITIONS & URINAL SCREENS (SOLID POLYETHYLENE)
TP1: COLOR: NEUTRAL, LIGHT TO MEDIUM TONES

WS: WINDOW SHADES (NEUTRAL COLOR, SEE NOTE 8)
WS1: SINGLE ROLLER - TRANSLUCENT (5 OPENNESS)
WS2: DUAL ROLLERS - TRANSLUCENT (5) AND BLACKOUT

This project was designed by the Sacramento District of the U. S. Army Corps of Engineers.The initials or signatures and registration designations of individuals appear on these project documents within the scope of their employment as required by ER 1110-1-8152

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: D OWEN
DRAWN BY: D OWEN
CHECKED BY: K STEPHENS
SUBMITTED BY: Matthew Z Valentine
SIZE: ANSI D
FILE NAME: B332 INTERIORS CENTRAL (SID)
ISSUE DATE: SEP 2018
PROJECT #: RKMF-17-0065
SPEC #: 2164
FILE NUMBER: 229-25-0715

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
U.S. DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE B326 WCI BUILDING 332
RKMF 17-0065

THIRD FLOOR INTERIOR FINISH/COLOR SCHEDULE

SHEET ID

I-612

FURNITURE LEGEND:

TABLE, DINING (36" X 36")

TABLE, CONFERENCE (48" X 48")

TABLE, CONFERENCE (36" DIA.) WITH UPHOLSTERED CONFERENCE CHAIRS

TABLE, CONFERENCE (48" X 96")

5' - 6" / 6' - 6"

DESK, FREESTANDING MODULAR
WITHOUT OVERHEAD HUTCH
WITH OVERHEAD HUTCH

7' - 0" / 8' - 0"

EXECUTIVE (WOOD) DESK WITH TASK CHAIR AND UPHOLSTERED WOOD GUEST CHAIRS

CHAIR, GUEST

CHAIR, CONFERENCE

CHAIR, TASK (DESK)



SHEET NOTES:

1.) REFER TO ARCHITECTURAL SHEETS FOR SUGGESTED WALL CONSTRUCTION TYPES.
2.) PROVIDE DESIGN OF FF&E IN ACCORDANCE WITH THE AIR FORCE RESERVE COMMAND COMPREHENSIVE INTERIOR DESIGN POLICY MANUAL.
3.) DEMOUNTABLE WALLS ARE CONTRACTOR FURNISHED/CONTRACTOR INSTALLED (CF/CI).

1 / IF101 — 1ST FLOOR FURNITURE PLAN

1/8" = 1'-0"

PLAN NORTH

5' 0 5' 15' 25'

1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

ISSUE DATE: SEP 2018
PROJECT # RKMF 17-0065
SPEC # 21564
FILE NUMBER: 229-25-0715
FILE NAME: B332 INTERIORS CENTRAL (FF&E)

DESIGNED BY: D OWEN
DRAWN BY: D OWEN
CHECKED BY: K STEPHENS
SUBMITTED BY: Sr Mechanical Engineer
SIZE: ANSI 'D'

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 326 WG BUILDING 332
RKMF 17-0065

1ST FLOOR FURNITURE PLAN

SHEET ID

IF101

FURNITURE LEGEND:

TABLE, DINING (36" X 36")

TABLE, CONFERENCE (48" X 48")

TABLE, CONFERENCE (36" DIA.) WITH UPHOLSTERED CONFERENCE CHAIRS

TABLE, CONFERENCE (48" X 96")

5' - 6"
6' - 6"
DESK, FREESTANDING MODULAR
WITHOUT OVERHEAD HUTCH
WITH OVERHEAD HUTCH

7' - 0"
8' - 0"
EXECUTIVE (WOOD) DESK WITH TASK CHAIR AND UPHOLSTERED WOOD GUEST CHAIRS

CHAIR, GUEST

CHAIR, CONFERENCE

CHAIR, TASK (DESK)



SHEET NOTES:

1.) REFER TO ARCHITECTURAL SHEETS FOR SUGGESTED WALL CONSTRUCTION TYPES.
2.) PROVIDE DESIGN OF FF&E IN ACCORDANCE WITH THE AIR FORCE RESERVE COMMAND COMPREHENSIVE INTERIOR DESIGN POLICY MANUAL.
3.) DEMOUNTABLE WALLS ARE CONTRACTOR FURNISHED/CONTRACTOR INSTALLED (CF/CI).

1 / IF102 2ND FLOOR FURNITURE PLAN

1/8" = 1'-0"

PLAN NORTH

5' 0 5' 15' 25'
1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

DESIGNED BY: D OWEN
DRAWN BY: D OWEN
CHECKED BY: K STEPHENS
SUBMITTED BY: /s/ Matthew Z Valentine
SIZE: 8 1/2 X 11 NAME: ANSI/ D/ B332 INTERIORS CENTRAL (FF&E)
ISSUE DATE: SEP 2018
PROJECT # RKMF 17-0065
SPEC # 21564
FILE NUMBER: 229-25-0715

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

2ND FLOOR FURNITURE PLAN

SHEET ID

IF102

FURNITURE LEGEND:

TABLE, DINING (36" X 36")

TABLE, CONFERENCE (48" X 48")

TABLE, CONFERENCE (36" DIA.) WITH UPHOLSTERED CONFERENCE CHAIRS

TABLE, CONFERENCE (48" X 96")

5' - 6" / 6' - 6"

DESK, FREESTANDING MODULAR
WITHOUT OVERHEAD HUTCH
WITH OVERHEAD HUTCH

7' - 0" / 8' - 0"

EXECUTIVE (WOOD) DESK WITH TASK CHAIR AND UPHOLSTERED WOOD GUEST CHAIRS

CHAIR, GUEST

CHAIR, CONFERENCE

CHAIR, TASK (DESK)



SHEET NOTES:

1.) REFER TO ARCHITECTURAL SHEETS FOR SUGGESTED WALL CONSTRUCTION TYPES.
2.) PROVIDE DESIGN OF FF&E IN ACCORDANCE WITH THE AIR FORCE RESERVE COMMAND COMPREHENSIVE INTERIOR DESIGN POLICY MANUAL.
3.) DEMOUNTABLE WALLS ARE CONTRACTOR FURNISHED/CONTRACTOR INSTALLED (CF/CI).

1 / IF103 — 3RD FLOOR FURNITURE PLAN

1/8" = 1'-0"

PLAN NORTH

5' 0 5' 15' 25'

1/8"=1'-0" GRAPHIC SCALE

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE

ISSUE DATE: SEP 2018
PROJECT # RKMF 17-0065
SPEC # 21564
FILE NUMBER: 229-25-0715
FILE NAME: B332_INTERIORS_CENTRAL (FF&E)

DESIGNED BY: D.OWEN
DRAWN BY: D.OWEN
CHECKED BY: K STEPHENS
SUBMITTED BY: /s/ Matthew J. Valentine
SIZE: ANSI 'D'

US ARMY CORPS OF ENGINEERS
SACRAMENTO DISTRICT
US DEPT OF ARMY

SACRAMENTO DISTRICT
1325 J STREET
SACRAMENTO, CA 95814

NELLIS AIR FORCE BASE, NEVADA
RENOVATE 926 WG BUILDING 332
RKMF 17-0065

3RD FLOOR FURNITURE PLAN

SHEET ID

IF103