

PROJECT MANUAL

**SHAW AIR FORCE BASE
CMSGT EMERSON E. WILLIAMS FACILITY
DFAC BUILDING 417.**

PREPARED FOR:

**UNITED STATES AIR FORCE
HQ AIR FORCE SERVICES CENTER**

04.29.25 Issue For Addendum A Submittal

TABLE OF CONTENTS Dining Facility

GENERAL

Cover Page
Table of Contents

GENERAL CONDITIONS

00 01 15	List of Drawings
00 22 13	Supplementary Instruction to Offerors
01 11 00	Summary of Work
01 14 00	Work Restrictions
01 20 00	Price and Payment Procedures
01 30 00	Administrative Requirements
01 32 01	Project Schedule
01 33 00	Submittal Procedures
01 35 26	Governmental Safety Requirements
01 42 00	Sources for Reference Publications
01 74 19	Construction Waste Management and Disposal
01 78 00	Closeout Submittals

TECHNICAL SPECS

02 41 00	Demolition and Deconstruction
02 42 51	Carpet Removal and Reclamation
02 84 16	Handling of Lighting Ballasts and Lamps Containing PCBs and Mercury
03 37 13	Shotcrete
05 40 00	Cold Formed Metal Framing
06 20 00	Finish Carpentry
08 14 00	Wood Doors
08 71 00	Door Hardware
09 06 00	Schedules for Finishes
09 29 00	Gypsum Board
09 30 10	Ceramic, Quarry and Glass Tiling
09 51 00	Acoustic Ceilings
09 65 00	Resilient Flooring
09 68 00	Carpeting
09 90 00	Paints and Coatings
10 11 00	Visual Displays
10 21 13	Toilet Partitions
10 28 13	Toilet Accessories
10 51 13	Metal Lockers
11 40 00	Food Service Equipment
12 34 00	Manufactured Plastic Casework
12 36 00	Countertops

FIRE PROTECTION

21 13 13	Wet Pipe Sprinkler System

PLUMBING

22 00 00 Plumbing General Purpose

MECHANICAL

23 00 00 Air Supply, Distribution, Ventilation and Exhaust Systems
23 05 93 Testing, Adjusting and Balancing for HVAC
23 07 00 Thermal Insulation for Mechanical Systems
23 11 25 Facility Gas Piping

ELECTRICAL

26 20 00 Interior Distribution System
26 51 00 Interior Lighting

TECHNOLOGY

27 10 00 Building Telecommunications

FIRE ALARM

28 31 76 Interior Fire Alarm and Mass Notification System, Addressable.

DFAC Addendum A Submittal 04.29.25

DOCUMENT 00 01 15

LIST OF DRAWINGS

02/11

PART 1 GENERAL

1.1 SUMMARY

This section lists the drawings for the project pursuant to contract clause "DFARS 252.236-7001, Contract Drawings, Maps and Specifications."

1.2 CONTRACT DRAWINGS

Contract drawings are as follows:

DRAWING INDEX

DRAWING NO. TITLE

G001	COVER SHEET
G002	SITE PLAN & PROJECT INFO
G003	CODE ANALYSIS PALN
G004	CODE ANALYSIS- CONSTRUCTION INFORMATION
G005	ACCESSIBILITY DETAILS AND NOTES
G006	ACCESSIBILITY DETAILS AND NOTES

S001	GENERAL NOTES
S101	FIRST FLOOR FRAMING PLAN- DINING HALL
S501	CONCRETE DETAILS
S502	CONCRETE DETAILS
S901	EQUIPMENT ANCHORAGE DETAILS

A001	SITE PLAN
AD101	FIRST FLOOR DEMOLITION PLAN
AD102	REFLECTED CEILING DEMOLITION PLAN
A101	FIRST FLOOR PLAN
A102	FIRST FLOOR FURNITURE/EQUIPMENT PLAN
A103	FIRST FLOOR FINISH PLAN
A104	ENLARGED FLOOR PLANS
A105	ELEVATIONS AND ENLARGED FLOOR PLANS
A201	REFLECTED CEILING PLAN
A301	ROOF PLAN
A401	INTERIOR ELEVATIONS
A402	INTERIOR ELEVATIONS
A403	INTERIOR ELEVATIONS
A404	INTERIOR ELEVATIONS
A405	INTERIOR ELEVATIONS
A406	INTERIOR ELEVATIONS
A407	INTERIOR ELEVATIONS
A408	INTERIOR ELEVATIONS
A601	WALL DETAILS
A602	CEILING DETAILS
A603	GENERIC DETAILS
A604	GENERIC DETAILS

A701	SCHEDULES
A702	SCHEDULES
FP101	FIRE PROTECTION EXISTING PLAN
FP102	FIRE PORTECTION PLAN
P001	PLUMBING LEGEND AND GENERAL NOTES
PD101	PLUMBING DEMOLITION FLOOR PLAN
P401	PLUMBING ENLARGED FLOOR PLAN SEWER/VENT
P402	PLUMBING ENLARGED FLOOR PLAN DOMESTIC WATER
P501	PLUMBING DETAILS
P601	PLUMBING SCHEDULES
M001	MECHANICAL LEGEND AND GENERAL NOTES
MD101	MECHANICAL DEMOLITION FLOOR PLAN
MD102	MECHANICAL DEMOLITON ROOF PLAN
M101	MECHANICAL FLOOR PLAN
M102	MECHANICAL FLOOR PLAN
M501	MECHANICAL DETAILS
E001	ELECTRICAL LEGEND AND GENERAL NOTES
ED101	LIGHTING DEMOLITION FLOOR PLAN
ED102	POWER DEMOLITION FLOOR PLAN
ED103	ELECTRICAL DEMOLITON ROOF PLAN
E101	LIGHTING FLOOR PLAN
E101PH	NORMAL PHOTOMETRICS
E101.1PH	PROGRESS PHOTOMETRICS
E102	POWER FLOOR PLAN
E103	ELECTRICAL ROOF PLAN
E401	POWER ENLARGED FLOOR PLAN
E501	ELECTRICAL DETAILS
E601	SINGLE LINE DIAGRAM
E602	FIXTURE SCHEDULE
E603	KITCHEN EQUIPMENT SCHEDULES
E604	KITCHEN EQUIPMENT SCHEDULES
E605	KITCHEN EQUIPMENT SCHEDULES
E606	PANEL SCHEDULE
T000	TECHNOLOGY COVER SHEET
T101	TECHNOLOGY FLOOR PLAN
T201	TECHNOLOGY RCP
T202	TECHNOLOGY DETAILS
FS000	FOODSERVICE NOTES & INDEX
FS001	FOODSERVICE FIXTURE & EQUIP KEY PLAN
FS100	FOODSERVICE FIXTURE & EQUIP FLOOR PLAN
FS101	FOODSERVICE FIXTURE & EQUIP FLOOR PLAN
FS102	FOODSERVICE FIXTURE & EQUIP FLOOR PLAN
FS103	FOODSERVICE FICTURE & EQUIP ISOMETRICS
FS200	FOODSERVICE FIXTURE & EQUIP SCHEDULE
FS201	FOODSERVICE FIXTURE & EQUIP SCHEDULE
FS202	FOODSERVICE FIXTURE & EQUIP SCHEDULE
FS300	FOODSERVICE FIXTURE & EQUIP ELECT. RI
FS301	FOODSERVICE FIXTURE & EQUIP ELECT. RI
FS302	FOODSERVICE FIXTURE & EQUIP ELECT. RI
FS400	FOODSERVICE FIXTURE & EQUIP PLUMB. RI
FS401	FOODSERVICE FIXTURE & EQUIP PLUMB. RI

FS402	FOODSERVICE FIXTURE & EQUIP PLUMB. RI
FS600	FOODSERVICE FIXTURE & EQUIP SPECIAL COND.
FS601	FOODSERVICE FIXTURE & EQUIP SPECIAL COND.
FS700	FOODSERVICE AEROWORKS SHOP DRAWINGS
FS701	FOODSERVICE AEROWORKS SHOP DRAWINGS
FS702	FOODSERVICE AEROWORKS SHOP DRAWINGS
FS800	FOODSERVICE FIXTURE AND EQUIPMENT ELEVATIONS
FS801	FOODSERVICE FIXTURE AND EQUIPMENT ELEVATIONS
FS802	FOODSERVICE FIXTURE AND EQUIPMENT ELEVATIONS
FS803	FOODSERVICE FIXTURE AND EQUIPMENT ELEVATIONS
FS804	FOODSERVICE FIXTURE AND EQUIPMENT ELEVATIONS
FS805	FOODSERVICE FIXTURE AND EQUIPMENT ELEVATIONS
FS806	FOODSERVICE FIXTURE AND EQUIPMENT ELEVATIONS
FS807	FOODSERVICE FIXTURE AND EQUIPMENT ELEVATIONS
FS900	FOODSERVICE STANDARD DETAILS
FS901	FOODSERVICE STANDARD DETAILS

1.3 SUPPLEMENTARY DRAWINGS

These supplementary drawings may not be a part of the contract but are included with the drawings for information.

1.3.1 Reference Drawings

The following reference drawings are intended only to show the original construction. Drawings are the property of the Government and shall not be used for any purpose other than that intended by the contract. The drawings are full size. Full-size drawings are available at the bidder's or Contractor's expense. Information on procuring these full-size drawings may be obtained from the Contracting Officer.

-- End of Document --

DOCUMENT 00 22 13.00 20

SUPPLEMENTARY INSTRUCTIONS TO OFFERORS

02/14

PART 1 GENERAL

1.1 CONTRACT LINE ITEMS

The terms Offeror and Bidder and versions thereof (offer/bid) have the same definition as used within this contract.

Provide the Contract Line Item (CLIN) lump sum price for the following items:

CLIN 0001 - BASE PRICE. Price includes the following:

CLIN 0001AA. Price for the entire work, complete to the 5 foot line outside of the building, in accordance with the drawings and specifications, but excluding work described in Contract Line Item (CLIN) and other price additional alternative work or breakouts.

CLIN	DESCRIPTION	TOTAL PRICE FOR CLIN 0001AA
0001AA	Construction- Default price	\$ _____

CLIN 0001AB-F. Price for the work described below and as shown on working drawings.

CLIN	DESCRIPTION	TOTAL PRICE FOR CLIN 0001AB
0001AB	Item C- Alternative price to provide inspection including camera survey of existing septic drain system to determine cost to fix system as change order. Default price is to make changes to the drain system currently	\$ _____
CLIN	DESCRIPTION	TOTAL PRICE FOR CLIN 0001AD
0001AD	Item L- Alternative price to inspect all kitchen hoods and ensure that they are operational. Provide reports and cost for recommended repairs. If needed provide a price for new hoods. Default price is exiting to remain.	\$ _____
CLIN	DESCRIPTION	TOTAL PRICE FOR CLIN 0001AE

0001AE	Item M- Provide alternative pricing to decommission existing Captive Aire hod washing equipment and controls in all existing locations. Default is to remain as is.	\$ _____
CLIN	DESCRIPTION	TOTAL PRICE FOR CLIN 0001AF
0001AF	Item N- Alternative price to install alarms in existing walk-in coolers and freezers as required by AFMAN 91-201.2.9 at the DFAC Kitchen. Default is to remain as is.	\$ _____
	Items A, B, D, E, F, G, H, I, J, K, P, Q, R, S, T have been removed from the scope of work or integrated into the base bid. Item O was removed from the scope of work and is to be done under a separate HVAC project.	

1.2 GENERAL BID NOTES

- a. Award will be made on the total sum of Contract Line Items 0001AA and the impact of add/alt. options and price information found in Items listed above. If there is a difference between a unit price and the extended total, the unit price will be held to be the intended bid and the total recomputed accordingly. If an Offeror provides a total but fails to enter a unit price, the total divided by the specified quantity will be held to be the intended unit price.
- a. If Options are exercised, additional bonding and consent of surety is required. Consequently, the Performance Bond must reflect 100 percent of the aggregate amount of all Items.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section--

SECTION 01 11 00

SUMMARY OF WORK

08/15

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals
Salvage Plan; G

1.2 WORK COVERED BY CONTRACT DOCUMENTS

1.2.1 Project Description

The work is located at the 19,000 sf. DFAC and includes kitchen equipment replacement, minor structural alternations, renovation of Restrooms, Servery and Dining Areas, and new finishes. The MEP scope will support changes made to the Servery and Dining facility to new or relocated equipment and ceiling conditions. This will also include finish changes and incidental related work.

1.2.2 Location

The work is located at the Shaw AFB Building 417 in Sumter SC>, approximately as indicated. The exact location will be shown by the Contracting Officer.

1.3 OCCUPANCY OF PREMISES

Building will be unoccupied during performance of work under this Contract. A small portion of the building will be occupied and in operation. This office area is completely separate from the DFAC portion of the building and is approximately 2,000 sf. Care shall be given to maintain operation or less than necessary down time of critical utilities and systems. Coordinate plan shutdowns with base representative. Occupancy notifications will be posted in a prominent location in the work area.

Before work is started, arrange with the Contracting Officer a sequence of procedure, means of access, space for storage of materials and equipment, and use of approaches, corridors, and stairways.

1.4 EXISTING WORK

In addition to FAR 52.236-9 Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements:

- a. Remove or alter existing work in such a manner as to prevent injury or damage to any portions of the existing work which remain.

- b. Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as approved by the Contracting Officer. At the completion of operations, existing work must be in a condition equal to or better than that which existed before new work started.

1.6 SALVAGE MATERIAL AND EQUIPMENT

Items designated by the Contracting Officer to be salvaged remain the property of the Government. Segregate, itemize, deliver and off-load the salvaged property at the Government designated storage area located within 20 miles of the construction site.

Provide a salvage plan, listing material and equipment to be salvaged, and their storage location. Maintain property control records for material or equipment designated as salvage. Use a system of property control that is approved by the Contracting Officer. Store and protect salvaged materials and equipment until disposition by the Contracting Officer.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 14 00

WORK RESTRICTIONS

11/11

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

List of Contact Personnel; G

1.2 CONTRACTOR ACCESS AND USE OF PREMISES

1.2.1 Activity Regulations

Ensure that Contractor personnel employed on the Activity become familiar with and obey Activity regulations including safety, fire, traffic and security regulations. Keep within the limits of the work and avenues of ingress and egress. Wear hard hats in designated areas. Do not enter any restricted areas unless required to do so and until cleared for such entry. Mark Contractor equipment for identification.

1.2.1.1 Subcontractors and Personnel Contacts

Provide a list of contact personnel of the Contractor and subcontractors including addresses and telephone numbers for use in the event of an emergency utilizing form 1413. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

1.2.1.2 No Smoking Policy

Smoking is prohibited within and outside of all buildings on installation, except in designated smoking areas. This applies to existing buildings, buildings under construction and buildings under renovation. Discarding tobacco materials other than into designated tobacco receptacles is considered littering and is subject to fines. The Contracting Officer will identify designated smoking areas.

1.2.2 Working Hours

Regular working hours must consist of an 8 1/2 hour period, excluding Government holidays.

1.2.3 Work Outside Regular Hours

Work outside regular working hours requires Contracting Officer approval. Make application 15 calendar days prior to such work to allow arrangements to be made by the Government for inspecting the work in progress, giving

the specific dates, hours, location, type of work to be performed, contract number and project title. Based on the justification provided, the Contracting Officer may approve work outside regular hours. During periods of darkness, the different parts of the work must be lighted in a manner approved by the Contracting Officer. Make utility cutovers after normal working hours or on Saturdays, Sundays, and Government holidays unless directed otherwise.

1.2.4 Occupied and Existing Buildings

The Contractor shall be working in an existing building which is occupied. Do not enter the building without prior approval of the Contracting Officer.

The existing buildings and their contents must be kept secure at all times. Provide temporary closures as required to maintain security as directed by the Contracting Officer.

Provide dust covers or protective enclosures to protect existing work that remains and Government material located in the space during the construction period.

Relocate movable furniture as appropriate away from the Contractor's working area and as required to perform the work, protect the furniture, and replace the furniture in upon completion of the work. Leave attached equipment in place, and protect it against damage, or temporarily disconnect, relocate, protect, and reinstall them at the completion of the work if that is what protects the work the best.

1.2.5 Utility Cutovers and Interruptions

- a. Make utility cutovers and interruptions after normal working hours or on Saturdays, Sundays, and Government holidays. Conform to procedures required in paragraph WORK OUTSIDE REGULAR HOURS.
- b. Ensure that new utility lines are complete, except for the connection, before interrupting existing service.
- c. Interruption to water, sanitary sewer, storm sewer, telephone service, electric service, air conditioning, heating, fire alarm, compressed air, etc. are considered utility cutovers pursuant to the paragraph WORK OUTSIDE REGULAR HOURS. Such interruptions are further limited to agreed upon hours. This time limit includes time for deactivation and reactivation.
- d. Operation of Station Utilities: The Contractor must not operate nor disturb the setting of control devices in the station utilities system, including water, sewer, electrical, and steam services. The Government will operate the control devices as required for normal conduct of the work. The Contractor must notify the Contracting Officer giving reasonable advance notice when such operation is required.

1.3 SECURITY REQUIREMENTS

Contract Clause FAR 52.204-2 Security Requirements and Alternate II and the following apply:

None.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 20 00.00

PRICE AND PAYMENT PROCEDURES

11/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Schedule of Prices G

1.3 SCHEDULE OF PRICES

1.3.1 Data Required

This contract requires the use of a cost-loaded Schedule of Values utilizing AIA G702/703 or approval. The information required for the Schedule of Prices will be entered as an integral part of the Network Analysis Schedule. Within 15 calendar days of notice of award, prepare and deliver to the Contracting Officer a Schedule of Values (construction contract) as directed by the Contracting Officer. Provide a detailed breakdown of the contract price, giving quantities for each of the various kinds of work, unit prices, and extended prices. Costs shall be summarized, and totals provided for each construction category.

1.3.2 Schedule Instructions

Payments will not be made until the AIA Schedule of Values has been submitted to and accepted by the Contracting Officer. Identify the cost for site work, and include incidental work to the 5 ft line. Identify costs for the building(s), and include work out to the 5 ft line. Work out to the 5 ft line shall include construction encompassed within a theoretical line 5 ft from the face of exterior walls and shall include attendant construction, such as pad mounted HVAC cooling equipment, cooling towers, and transformers placed beyond the 5 ft line.

1.3.3 Real Property Assets

The Government will provide the Draft DD Form 1354, Transfer and Acceptance of Military Real Property filled in with the appropriate Real Property Unique Identifiers (RPUID) and related construction Category Codes to summarize the designed real property assets that apply to this contract. The Contractor shall meet with the Contracting Officer and the Real Property Accounting Officer during the Pre-Construction Meeting and the Project Closeout Meetings to modify and include any necessary changes to the DD Form 1354. The Contractor shall provide the Interim DD Form 1354 that uses the appropriate division of the RPUIDs/ Category Codes to represent the final constructed facility and include all associated cost. Coordinate the Contractor's Price and Payment structure with the structure of the RPUIDs/ Category Codes.

Divide detailed asset breakdown into the RPUIDs and related construction Category Codes and populate associated costs which represent all aspects of the work. Where assets diverge into multiple RPUID/ Category Codes, divide the asset and provide the proportion of the assets in each RPUID/ Category Code. Assets and related RPUID/ Category Codes may be modified by the Contracting Officer as necessary during course of the work. Coordinate identification and proportion of these assets with the Government Real Property Accounting Officer.

Cost data accumulated under this section are required in the preparation of DD Form 1354.

1.3.4 Schedule Requirements for HVAC TAB

The field work Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC shall be broken down in the Schedule of Prices and in the Construction Progress Documentation by separate line items which reflect measurable deliverables. Specific payment percentages for each line item shall be determined on a case by case basis for each contract. The line items shall be as follows:

- a. Approval of Design Review Report: The TABS Agency is required to conduct a review of the project plans and specifications to identify any feature, or the lack thereof, that would preclude successful testing and balancing of the project HVAC systems. The resulting findings shall be submitted to the Government to allow correction of the design. The progress payment shall be issued after review and approval of the report.
- b. Approval of the pre-field engineering report: The TABS Agency submits a report which outlines the scope of field work. The report shall contain details of what systems will be tested, procedures to be used, sample report forms for reporting test results and a quality control checklist of work items that must be completed before TABS field work commences.
- c. Season I field work: Incremental payments are issued as the TABS field work progresses. The TABS Agency mobilizes to the project site and executes the field work as outlined in the pre-field engineering report. The HVAC water and air systems are balanced and operational data shall be collected for one seasonal condition (either summer or winter depending on project timing).
- d. Approval of Season I report: On completion of the Season I field

work, the data is compiled into a report and submitted to the Government. The report is reviewed, and approved, after ensuring compliance with the pre-field engineering report scope of work.

- e. Completion of Season I field QA check: Contract QC and Government representatives meet the TABS Agency at the jobsite to retest portions of the systems reported in the Season I report. The purpose of these tests are to validate the accuracy and completeness of the previously submitted Season I report.
- f. Approval of Season II report: The TABS Agency completes all Season II field work, which is normally comprised mainly of taking heat transfer temperature readings, in the season opposite of that under which Season I performance data was compiled. This data shall be compiled into a report and submitted to the Government. On completion of submittal review to ensure compliance with the pre-field engineering report scope, progress payment is issued. Progress payment is less than that issued for the Season I report since most of the water and air balancing work effort is completed under Season I.

1.4 CONTRACT MODIFICATIONS

In conjunction with the Contract Clause NFC 243-1 Changes - Fixed-Price (AUG 1987), and where actual ownership and operating costs of construction equipment cannot be determined from Contractor accounting records, equipment use rates shall be based upon standard government provisions.

1.5 CONTRACTOR'S INVOICE AND CONTRACT PERFORMANCE STATEMENT

1.5.1 Content of Invoice

Requests for payment will be processed in accordance with the Contract Clause NFC-232-27 Prompt Payment for Construction Contracts and NFC-232-5 Payments Under Fixed-Price Construction Contracts. The requests for payment shall include the documents listed below.

- a. The Contractor's invoice, on AIA G702/703 furnished by the Government, showing in summary form, the basis for arriving at the amount of the invoice. and shall include certification by Contractor and Quality Control (QC) Manager.
- b. Updated Project Schedule and reports required by the contract.
- c. Contractor Safety Self Evaluation Checklist.
- d. Other supporting documents as requested.
- e. Updated copy of submittal register.
- f. Invoices not completed in accordance with contract requirements will be returned to the Contractor for correction of the deficiencies.

1.5.2 Submission of Invoices

See SECTION G of Solicitation for Contract Administration Data.

1.5.3 Final Invoice

- a. Final Invoice will be processed and paid in accordance with 01 20 00 and 01 78 00. All Final Invoices shall be presented for payment after all closeout documents and work have been completed to include DD Form 1354 Submission.

1.6 PAYMENTS TO THE CONTRACTOR

Payments will be made on submission of itemized requests by the Contractor which comply with the requirements of this section, and will be subject to reduction for overpayments or increase for underpayments made on previous payments to the Contractor.

1.6.1 Obligation of Government Payments

The obligation of the Government to make payments required under the provisions of this contract will, at the discretion of the Contracting Officer, be subject to reductions and suspensions permitted under the FAR and agency regulations including the following in accordance with FAR 32.503-6 Suspension or Reduction of Payments:

- a. Reasonable deductions due to defects in material or workmanship;
- b. Claims which the Government may have against the Contractor under or in connection with this contract;
- c. Unless otherwise adjusted, repayment to the Government upon demand for overpayments made to the Contractor; and
- d. Failure to provide up to date record drawings not current as stated in Contract Clause "FAC 5252.236-9310, Record Drawings."

1.6.2 Payment for Onsite and Offsite Materials

Progress payments may be made to the contractor for materials delivered on the site, for materials stored off construction sites, or materials that are in transit to the construction sites under the following conditions:

- a. FAR 52.232-5(b) Payments Under Fixed Price Construction Contracts.
- b. Materials delivered on the site but not installed, including completed preparatory work, and off-site materials to be considered for progress payment shall be major high cost, long lead, special order, or specialty items, not susceptible to deterioration or physical damage in storage or in transit to the construction site. Examples of materials acceptable for payment consideration include, but are not limited to, structural steel, non-magnetic steel, non-magnetic aggregate, equipment, machinery, large pipe and fittings, precast/prestressed concrete products, plastic lumber (e.g., fender piles/curbs), and high-voltage electrical cable. Materials not acceptable for payment include consumable materials such as nails, fasteners, conduits, gypsum board, glass, insulation, and wall coverings.
- c. Materials to be considered for progress payment prior to installation shall be specifically and separately identified in the Contractor's estimates of work submitted for the Contracting Officer's approval in accordance with Schedule of Prices requirement of this contract. Requests for progress payment consideration for such items shall be supported by documents establishing their value and that the title requirements of the clause at FAR 52.232-5 Payments Under Fixed-Price Construction Contracts have been met.
- d. Materials are adequately insured and protected from theft and exposure.
- e. Provide a written consent from the surety company with each payment request for offsite materials.
- f. Materials to be considered for progress payments prior to installation shall be stored either in Hawaii, Guam, Puerto Rico, or the Continental United States. Other locations are subject to written approval by the Contracting Officer.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 30 00

ADMINISTRATIVE REQUIREMENTS

08/15

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

1.3 PROGRESS AND COMPLETION PICTURES

Photographically document site conditions prior to start of construction operations. Provide monthly, and within one month of the completion of work, digital photographs, 1600x1200x24 bit true color 1 mg minimum resolution in JPEG file format showing the sequence and progress of work. Take a minimum of 20 digital photographs each week throughout the entire project from a minimum of ten views from points located by the Contracting Officer. Submit with the monthly invoice two sets of digital photographs, each set on a separate compact disc (CD) or data versatile disc (DVD), cumulative of all photos to date. Indicate photographs demonstrating environmental procedures. Provide photographs for each month in a separate monthly directory and name each file to indicate its location on the view location sketch. Also provide the view location sketch on the CD or DVD as a digital file. Include a date designator in file names. Cross reference submittals in the appropriate daily report. Photographs provided are for unrestricted use by the Government.

1.4 MINIMUM INSURANCE REQUIREMENTS

Provide the minimum insurance coverage required by FAR 28.307-2 Liability, during the entire period of performance under this contract. Provide other insurance coverage as required by the State law.

1.5 SUPERVISION

1.5.1 Minimum Communication Requirements

Have at least one qualified superintendent, or competent alternate, capable of reading, writing, and conversing fluently in the English language, on the job-site at all times during the performance of contract work. In addition, if a Quality Control (QC) representative is required on the contract, then that individual must also have fluent English communication skills.

1.5.2 Superintendent Qualifications

The project superintendent must have a minimum of 10 years experience in construction with at least 5 of those years as a superintendent on projects similar in size and complexity. The individual must be familiar with the requirements of standard provisions and have experience in the areas of hazard identification and safety compliance. The individual must be capable of interpreting a critical path schedule and construction drawings. The qualification requirements for the alternate superintendent are the same as for the project superintendent. The Contracting Officer may request proof of the superintendent's qualifications at any point in the project if the performance of the superintendent is in question.

1.5.2.1 Duties

The project superintendent is primarily responsible for managing and coordinating day-to-day production and schedule adherence on the project. The superintendent is required to attend partnering meetings, and quality control meetings. The superintendent or qualified alternative must be on-site at all times during the performance of this contract until the work is completed and accepted.

1.5.3 Non-Compliance Actions

The Project Superintendent is subject to removal by the Contracting Officer for non-compliance with requirements specified in the contract and for failure to manage the project to insure timely completion. Furthermore, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders is acceptable as the subject of claim for extension of time for excess costs or damages by the Contractor.

1.6 PRECONSTRUCTION

After award of the contract but prior to commencement of any work at the site, meet with the Contracting Officer to discuss and develop a mutual understanding relative to the administration of the value engineering and safety program, preparation of the schedule of prices or earned value report, shop drawings, and other submittals, scheduling programming, prosecution of the work, and clear expectations of the "Interim DD Form 1354" Submittal. Major subcontractors who will engage in the work must also attend.

1.7 1.7.1

Informal Partnering

The Contracting Officer will organize the Partnering Sessions with key personnel of the project team, including Contractor personnel and Government personnel.

The Initial Partnering session should be a part of the Pre-Construction Meeting. Partnering sessions will be held at a location agreed to by the Contracting Officer and the Contractor (typically a conference room provided by the PWD FEAD/ROICC Resident Engineer office or the Contractor). The Initial Informal Partnering Session will be conducted and facilitated using electronic media (a video and accompanying forms) provided by the Contracting Officer. The Partners will determine the frequency of the follow-on sessions, at no more than 3 to six month intervals.

1.8 ELECTRONIC MAIL (E-MAIL) ADDRESS

Establish and maintain electronic mail (e-mail) capability along with the capability to open various electronic attachments as text files, pdf files, and other similar formats. Within 10 days after contract award, provide the Contracting Officer a single (only one) e-mail address for electronic communications from the Contracting Officer related to this contract including, but not limited to contract documents, invoice information, request for proposals, and other correspondence. The Contracting Officer may also use email to notify the Contractor of base access conditions when emergency conditions warrant, such as hurricanes or terrorist threats. Multiple email addresses are not allowed.

It is the Contractor's responsibility to make timely distribution of all Contracting Officer initiated e-mail with its own organization including field office(s). Promptly notify the Contracting Officer, in writing, of any changes to this email address.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

--End of Section--

SECTION 01 32 01.00 10

PROJECT SCHEDULE
02/15

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AACE INTERNATIONAL (AACE)

AACE 29R-03 (2011) Forensic Schedule Analysis

AACE 52R-06 (2006) Time Impact Analysis - As Applied
in Construction

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Project Scheduler Qualifications; G

Preliminary Project Schedule; G

Initial Project Schedule; G

Periodic Schedule Update; G

1.3 PROJECT SCHEDULER QUALIFICATIONS

Designate an authorized representative to be responsible for the preparation of the schedule and all required updating and production of reports. The authorized representative must have a minimum of 2-years experience scheduling construction projects similar in size and nature to this project with scheduling software that meets the requirements of this specification. Representative must have a comprehensive knowledge of CPM scheduling principles and application.

PART 2 PRODUCTS

2.1 SOFTWARE

The scheduling software utilized to produce and update the schedules required herein must be capable of meeting all requirements of this specification.

2.1.1 Government Default Software

The Government intends to use Microsoft Project.

2.1.2 Contractor Software

Scheduling software used by the contractor must be commercially available from the software vendor for purchase with vendor software support agreements available. The software routine used to create the required sdef file must be created and supported by the software manufacturer.

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

Prepare for approval a Project Schedule, as specified herein, pursuant to FAR Clause 52.236-15 Schedules for Construction Contracts. Show in the schedule the proposed sequence to perform the work and dates contemplated for starting and completing all schedule activities. The scheduling of the entire project is required. The scheduling of construction is the responsibility of the Contractor. Contractor management personnel must actively participate in its development. Subcontractors and suppliers working on the project must also contribute in developing and maintaining an accurate Project Schedule. Provide a schedule that is a forward planning as well as a project monitoring tool. Use the Critical Path Method (CPM) of network calculation to generate all Project Schedules. Prepare each Project Schedule using the Precedence Diagram Method (PDM).

3.2 BASIS FOR PAYMENT AND COST LOADING

The schedule is the basis for determining contract earnings during each update period and therefore the amount of each progress payment. The aggregate value of all activities coded to a contract CLIN must equal the value of the CLIN.

3.2.1 Activity Cost Loading

Activity cost loading must be reasonable and without front-end loading. Provide additional documentation to demonstrate reasonableness if requested by the Contracting Officer.

3.2.2 Withholdings / Payment Rejection

Failure to meet the requirements of this specification may result in the disapproval of the preliminary, initial or periodic schedule updates and subsequent rejection of payment requests until compliance is met.

In the event that the Contracting Officer directs schedule revisions and those revisions have not been included in subsequent Project Schedule revisions or updates, the Contracting Officer may withhold 10 percent of pay request amount from each payment period until such revisions to the project schedule have been made.

3.3 PROJECT SCHEDULE DETAILED REQUIREMENTS

3.3.1 Level of Detail Required

Develop the Project Schedule to the appropriate level of detail to address major milestones and to allow for satisfactory project planning and execution. Failure to develop the Project Schedule to an appropriate level of detail will result in its disapproval. The Contracting Officer will consider, but is not limited to, the following characteristics and requirements to determine appropriate level of detail:

3.3.2 Activity Durations

Reasonable activity durations are those that allow the progress of ongoing activities to be accurately determined between update periods. Less than 2 percent of all non-procurement activities may have Original Durations (OD) greater than 20 work days or 30 calendar days.

3.3.3 Procurement Activities

Include activities associated with the critical submittals and their approvals, procurement, fabrication, and delivery of long lead materials, equipment, fabricated assemblies, and supplies. Long lead procurement activities are those with an anticipated procurement sequence of over 90 calendar days.

3.3.4 Mandatory Tasks

Include the following activities/tasks in the initial project schedule and all updates.

- a. Submission, review and acceptance of SD-01 Preconstruction Submittals (individual activity for each).
- b. Submission, review and acceptance of features require design completion
Submission, review and acceptance of design packages.
- c. Submission of mechanical/electrical/information systems layout drawings.
- d. Long procurement activities

- e. Submission and approval of O & M manuals.
- f. Submission and approval of as-built drawings.
- g. Submission and approval of DD1354 data and installed equipment lists.
- h. Submission and approval of testing and air balance (TAB).
- i. Submission of TAB specialist design review report.
- j. Submission and approval of fire protection specialist.
- k. Submission and approval of Building Commissioning Plan, test data, and reports: Develop the schedule logic associated with testing and commissioning of mechanical systems to a level of detail consistent with the contract commissioning requirements. All tasks associated with all building testing and commissioning will be completed prior to submission of building commissioning report and subsequent contract completion.
- l. Air and water balancing.
- m. Building commissioning - Functional Performance Testing.
- n. Controls testing plan submission.
- o. Controls testing.
- p. Performance Verification testing.
- q. Other systems testing, if required.
- r. Contractor's pre-final inspection.
- s. Correction of punch list from Contractor's pre-final inspection.
- t. Government's pre-final inspection.
- u. Correction of punch list from Government's pre-final inspection.
- v. Final inspection.

3.3.5 Government Activities

Show Government and other agency activities that could impact progress. These activities include, but are not limited to: environmental permit approvals by State regulators, inspections, utility tie-in, Government Furnished Equipment (GFE) and Notice to Proceed (NTP) for phasing requirements.

3.3.6 Standard Activity Coding Dictionary

Use the activity coding structure defined in the Standard Data Exchange Format (SDEF) in standard provisions. Develop and assign all Activity Codes to activities as detailed herein.

The SDEF format is as follows:

Field	Activity Code	Length	Description
1	WRKP	3	Workers per day
2	RESP	4	Responsible party
3	AREA	4	Area of work
4	MODF	6	Modification Number
5	BIDI	6	Bid Item (CLIN)
6	PHAS	2	Phase of work
7	CATW	1	Category of work
8	FOW	20	Feature of work*
*Some systems require that FEATURE OF WORK values be placed in several activity code fields. The notation shown is for Primavera P6. Refer to the specific software guidelines with respect to the FEATURE OF WORK field requirements.			

3.3.6.1 Workers Per Day (WRKP)

Assign Workers per Day for all field construction or direct work activities, if directed by the Contracting Officer. Workers per day is based on the average number of workers expected each day to perform a task for the duration of that activity.

3.3.6.2 Responsible Party Coding (RESP)

Assign responsibility code for all activities to the Prime Contractor, Subcontractor(s) or Government agency(ies) responsible for performing the activity.

- a. Activities coded with a Government Responsibility code include, but are not limited to: Government approvals, Government design reviews, environmental permit approvals by State regulators, Government Furnished Property/Equipment (GFP) and Notice to Proceed (NTP) for phasing requirements.
- b. Activities cannot have more than one Responsibility Code. Examples of acceptable activity code values are: DOR (for the designer of record); ELEC (for the electrical subcontractor); MECH (for the mechanical subcontractor); and GOVT (for USACE).

3.3.6.3 Area of Work Coding (AREA)

Assign Work Area code to activities based upon the work area in which the activity occurs. Define work areas based on resource constraints or space constraints that would preclude a resource, such as a particular trade or

craft work crew from working in more than one work area at a time due to restraints on resources or space. Examples of Work Area Coding include different areas within a floor of a building, different floors within a building, and different buildings within a complex of buildings. Activities cannot have more than one Work Area Code.

Not all activities are required to be Work Area coded. A lack of Work Area coding indicates the activity is not resource or space constrained.

3.3.6.4 Modification Number (MODF)

Assign a Modification Number Code to any activity or sequence of activities added to the schedule as a result of a Contract Modification, when approved by Contracting Officer. Key all Code values to the Government's modification numbering system. An activity can have only one Modification Number Code.

3.3.6.5 Bid Item Coding (BIDI)

Assign a Bid Item Code to all activities using the Contract Line Item Schedule (CLIN) to which the activity belongs, even when an activity is not cost loaded. An activity can have only one BIDI Code.

3.3.6.6 Phase of Work Coding (PHAS)

Assign Phase of Work Code to all activities. Examples of phase of work are procurement phase and construction phase. Each activity can have only one Phase of Work code.

- a. Code proposed fast track design and construction phases proposed to allow filtering and organizing the schedule by fast track design and construction packages.
- b. If the contract specifies phasing with separately defined performance periods, identify a Phase Code to allow filtering and organizing the schedule accordingly.

3.3.6.7 Category of Work Coding (CATW)

Assign a Category of Work Code to all activities. Category of Work Codes include, but are not limited to construction submittal, procurement, fabrication, weather sensitive installation, non-weather sensitive installation, start-up, and testing activities. Each activity can have no more than one Category of Work Code.

3.3.6.8 Feature of Work Coding (FOW)

Assign a Feature of Work Code to appropriate activities based on the Definable Feature of Work to which the activity belongs based on the approved QC plan.

Definable Feature of Work is defined in Section 01 45 00.00 10 QUALITY CONTROL. An activity can have only one Feature of Work Code.

3.3.7 Contract Milestones and Constraints

Milestone activities are to be used for significant project events including, but not limited to, project phasing, project start and end activities, or interim completion dates. The use of artificial float

constraints such as "zero free float" or "zero total float" are prohibited.

Mandatory constraints that ignore or effect network logic are prohibited. No constrained dates are allowed in the schedule other than those specified herein. Submit additional constraints to the Contracting Officer for approval on a case by case basis.

3.3.7.1 Project Start Date Milestone and Constraint

The first activity in the project schedule must be a start milestone titled "NTP Acknowledged," which must have a "Start On" constraint date equal to the date that the NTP is acknowledged.

3.3.7.2 End Project Finish Milestone and Constraint

The last activity in the schedule must be a finish milestone titled "End Project."

Constrain the project schedule to the Contract Completion Date in such a way that if the schedule calculates an early finish, then the float calculation for "End Project" milestone reflects positive float on the longest path. If the project schedule calculates a late finish, then the "End Project" milestone float calculation reflects negative float on the longest path. The Government is under no obligation to accelerate Government activities to support a Contractor's early completion.

3.3.7.3 Interim Completion Dates and Constraints

Constrain contractually specified interim completion dates to show negative float when the calculated late finish date of the last activity in that phase is later than the specified interim completion date.

3.3.7.3.1 Start Phase

Use a start milestone as the first activity for a project phase. Call the start milestone "Start Phase X" where "X" refers to the phase of work.

3.3.7.3.2 End Phase

Use a finish milestone as the last activity for a project phase. Call the finish milestone "End Phase X" where "X" refers to the phase of work.

3.3.8 Calendars

Schedule activities on a Calendar to which the activity logically belongs. Develop calendars to accommodate any contract defined work period such as a 7-day calendar for Government Acceptance activities, concrete cure times, etc. Develop the default Calendar to match the physical work plan with non-work periods identified including weekends and holidays. Develop Seasonal Calendar(s) and assign to seasonally affected activities as applicable.

If an activity is weather sensitive it should be assigned to a calendar showing non-work days on a monthly basis, with the non-work days selected at random across the weeks of the calendar, using the anticipated adverse weather delay work days provided in the Special Contract. Assign non-work days over a seven-day week as weather records are compiled on seven-day weeks, which may cause some of the

weather related non-work days to fall on weekends.

3.3.9 Open Ended Logic

Only two open ended activities are allowed: the first activity "NTP Acknowledged" may have no predecessor logic, and the last activity -"End Project" may have no successor logic.

Predecessor open ended logic may be allowed in a time impact analyses upon the Contracting Officer's approval.

3.3.10 Default Progress Data Disallowed

Actual Start and Finish dates must not automatically update with default mechanisms included in the scheduling software. Updating of the percent complete and the remaining duration of any activity must be independent functions. Disable program features that calculate one of these parameters from the other. Activity Actual Start (AS) and Actual Finish (AF) dates assigned during the updating process must match those dates provided in the Contractor Quality Control Reports. Failure to document the AS and AF dates in the Daily Quality Control report will result in disapproval of the Contractor's schedule.

3.3.11 Out-of-Sequence Progress

Activities that have progressed before all preceding logic has been satisfied (Out-of-Sequence Progress) will be allowed only on a case-by-case basis subject to approval by the Contracting Officer. Propose logic corrections to eliminate out of sequence progress or justify not changing the sequencing for approval prior to submitting an updated project schedule. Address out of sequence progress or logic changes in the Narrative Report and in the periodic schedule update meetings.

3.3.12 Added and Deleted Activities

Do not delete activities from the project schedule or add new activities to the schedule without approval from the Contracting Officer. Activity ID and description changes are considered new activities and cannot be changed without Contracting Officer approval.

3.3.13 Original Durations

Activity Original Durations (OD) must be reasonable to perform the work item. OD changes are prohibited unless justification is provided and approved by the Contracting Officer.

3.3.14 Leads, Lags, and Start to Finish Relationships

Lags must be reasonable as determined by the Government and not used in place of realistic original durations, must not be in place to artificially absorb float, or to replace proper schedule logic.

- a. Leads (negative lags) are prohibited.
- b. Start to Finish (SF) relationships are prohibited.

3.3.15 Retained Logic

Schedule calculations must retain the logic between predecessors and

successors ("retained logic" mode) even when the successor activity(s) starts and the predecessor activity(s) has not finished (out-of-sequence progress). Software features that in effect sever the tie between predecessor and successor activities when the successor has started and the predecessor logic is not satisfied ("progress override") are not to be allowed.

3.3.16 Percent Complete

Update the percent complete for each activity started, based on the realistic assessment of earned value. Activities which are complete but for remaining minor punch list work and which do not restrain the initiation of successor activities may be declared 100 percent complete to allow for proper schedule management.

3.3.17 Remaining Duration

Update the remaining duration for each activity based on the number of estimated work days it will take to complete the activity. Remaining duration may not mathematically correlate with percentage found under paragraph entitled Percent Complete.

3.3.18 Cost Loading of Closeout Activities

Cost load the "Correction of punch list from Government pre-final inspection" activity(ies) not less than 1 percent of the present contract value. Activity(ies) may be declared 100 percent complete upon the Government's verification of completion and correction of all punch list work identified during Government pre-final inspection(s).

3.3.18.1 As-Built Drawings

If there is no separate contract line item (CLIN) for as-built drawings, cost load the "Submission and approval of as-built drawings" activity not less than \$35,000 or 1 percent of the present contract value, which ever is greater, up to \$200,000. Activity will be declared 100 percent complete upon the Government's approval.

3.3.18.2 O & M Manuals

Cost load the "Submission and approval of O & M manuals" activity not less than \$20,000. Activity will be declared 100 percent complete upon the Government's approval of all O & M manuals.

3.3.19 Early Completion Schedule and the Right to Finish Early

An Early Completion Schedule is an Initial Project Schedule (IPS) that indicates all scope of the required contract work will be completed before the contractually required completion date.

- a. No IPS indicating an Early Completion will be accepted without being fully resource-loaded (including crew sizes and manhours) and the Government agreeing that the schedule is reasonable and achievable.
- b. The Government is under no obligation to accelerate work items it is responsible for to ensure that the early completion is met nor is it responsible to modify incremental funding (if applicable) for the project to meet the contractor's accelerated work.

3.4 PROJECT SCHEDULE SUBMISSIONS

Provide the submissions as described below. The data CD/DVD, reports, and network diagrams required for each submission are contained in paragraph SUBMISSION REQUIREMENTS. If the Contractor fails or refuses to furnish the information and schedule updates as set forth herein, then the Contractor will be deemed not to have provided an estimate upon which a progress payment can be made.

Review comments made by the Government on the schedule(s) do not relieve the Contractor from compliance with requirements of the Contract Documents.

3.4.1 Preliminary Project Schedule Submission

Within 15 calendar days after the NTP is acknowledged submit the Preliminary Project Schedule defining the planned operations detailed for the first 90 calendar days for approval. The approved Preliminary Project Schedule will be used for payment purposes not to exceed 90 calendar days after NTP. Completely cost load the Preliminary Project Schedule to balance the contract award CLINS shown on the Price Schedule. The Preliminary Project Schedule may be summary in nature for the remaining performance period. It must be early start and late finish constrained and logically tied as specified. The Preliminary Project Schedule forms the basis for the Initial Project Schedule specified herein and must include all of the required plan and program preparations, submissions and approvals identified in the contract (for example, Quality Control Plan, Safety Plan, and Environmental Protection Plan) as well as design activities, planned submissions of all early design packages, permitting activities, design review conference activities, and other non-construction activities intended to occur within the first 90 calendar days. Government acceptance of the associated design package(s) and all other specified Program and Plan approvals must occur prior to any planned construction activities. Activity code any activities that are summary in nature after the first 90 calendar days with Bid Item (CLIN) code (BIDI), Responsibility Code (RESP) and Feature of Work code (FOW).

3.4.2 Initial Project Schedule Submission

Submit the Initial Project Schedule for approval within 42 calendar days after notice to proceed is issued. The schedule must demonstrate a reasonable and realistic sequence of activities which represent all work through the entire contract performance period. No payment will be made for work items not fully detailed in the Project Schedule.

3.4.3 Periodic Schedule Updates

Update the Project Schedule on a regular basis, monthly at a minimum. Provide a draft Periodic Schedule Update for review at the schedule update meetings as prescribed in the paragraph PERIODIC SCHEDULE UPDATE MEETINGS. These updates will enable the Government to assess Contractor's progress.

- a. Update information including Actual Start Dates (AS), Actual Finish Dates (AF), Remaining Durations (RD), and Percent Complete is subject to the approval of the Government at the meeting.
- b. AS and AF dates must match the date(s) reported on the Contractor's Quality Control Report for an activity start or finish.

3.5 SUBMISSION REQUIREMENTS

Submit the following items for the Preliminary Schedule, Initial Schedule, and every Periodic Schedule Update throughout the life of the project:

3.5.1 Data CD/DVDs

Provide two sets of data CD/DVDs containing the current project schedule and all previously submitted schedules in the format of the scheduling software (e.g. .xer). Also include on the data CD/DVDs the Narrative Report and all required Schedule Reports. Label each CD/DVD indicating the type of schedule (Preliminary, Initial, Update), full contract number, Data Date and file name. Each schedule must have a unique file name and use project specific settings.

3.5.2 Narrative Report

Provide a Narrative Report with each schedule submission. The Narrative Report is expected to communicate to the Government the thorough analysis of the schedule output and the plans to compensate for any problems, either current or potential, which are revealed through that analysis. Include the following information as minimum in the Narrative Report:

- a. Identify and discuss the work scheduled to start in the next update period.
- b. A description of activities along the two most critical paths where the total float is less than or equal to 20 work days.
- c. A description of current and anticipated problem areas or delaying factors and their impact and an explanation of corrective actions taken or required to be taken.
- d. Identify and explain why activities based on their calculated late dates should have either started or finished during the update period but did not.
- e. Identify and discuss all schedule changes by activity ID and activity name including what specifically was changed and why the change was needed. Include at a minimum new and deleted activities, logic changes, duration changes, calendar changes, lag changes, resource changes, and actual start and finish date changes.
- f. Identify and discuss out-of-sequence work.

3.5.3 Schedule Reports

The format, filtering, organizing and sorting for each schedule report will be as directed by the Contracting Officer. Typically, reports contain Activity Numbers, Activity Description, Original Duration, Remaining Duration, Early Start Date, Early Finish Date, Late Start Date, Late Finish Date, Total Float, Actual Start Date, Actual Finish Date, and Percent Complete. Provide the reports electronically in .pdf format. Provide electronic copy. The following lists typical reports that will be requested:

3.5.3.1 Activity Report

List of all activities sorted according to activity number.

3.5.3.2 Logic Report

List of detailed predecessor and successor activities for every activity in ascending order by activity number.

3.5.3.3 Total Float Report

A list of all incomplete activities sorted in ascending order of total float. List activities which have the same amount of total float in ascending order of Early Start Dates. Do not show completed activities on this report.

3.5.3.4 Earnings Report by CLIN

A compilation of the Total Earnings on the project from the NTP to the data date, which reflects the earnings of activities based on the agreements made in the schedule update meeting defined herein. Provided a complete schedule update has been furnished, this report serves as the basis of determining progress payments. Group activities by CLIN number and sort by activity number. Provide a total CLIN percent earned value, CLIN percent complete, and project percent complete. The printed report must contain the following for each activity: the Activity Number, Activity Description, Original Budgeted Amount, Earnings to Date, Earnings this period, Total Quantity, Quantity to Date, and Percent Complete (based on cost).

3.5.3.5 Schedule Log

Provide a Scheduling/Leveling Report generated from the current project schedule being submitted.

3.5.4 Network Diagram

The Network Diagram is required for the Preliminary, Initial and Periodic Updates. Depict and display the order and interdependence of activities and the sequence in which the work is to be accomplished. The Contracting Officer will use, but is not limited to, the following conditions to review compliance with this paragraph:

3.5.4.1 Continuous Flow

Show a continuous flow from left to right with no arrows from right to left. Show the activity number, description, duration, and estimated earned value on the diagram.

3.5.4.2 Project Milestone Dates

Show dates on the diagram for start of project, any contract required interim completion dates, and contract completion dates.

3.5.4.3 Critical Path

Show all activities on the critical path. The critical path is defined as the longest path.

3.5.4.4 Banding

Organize activities using the WBS or as otherwise directed to assist in

the understanding of the activity sequence. Typically, this flow will group activities by major elements of work, category of work, work area and/or responsibility.

3.5.4.5 Cash Flow / Schedule Variance Control (SVC) Diagram

With each schedule submission, provide a SVC diagram showing 1) Cash Flow S-Curves indicating planned project cost based on projected early and late activity finish dates, and 2) Earned Value to-date.

3.6 PERIODIC SCHEDULE UPDATE

3.6.1 Periodic Schedule Update Meetings

Conduct periodic schedule update meetings for the purpose of reviewing the proposed Periodic Schedule Update, Narrative Report, Schedule Reports, and progress payment. Conduct meetings at least monthly within five days of the proposed schedule data date. Provide a computer with the scheduling software loaded and a projector which allows all meeting participants to view the proposed schedule during the meeting. The Contractor's authorized scheduler must organize, group, sort, filter, perform schedule revisions as needed and review functions as requested by the Contractor and/or Government. The meeting is a working interactive exchange which allows the Government and Contractor the opportunity to review the updated schedule on a real time and interactive basis. The meeting will last no longer than 8 hours. Provide a draft of the proposed narrative report and schedule data file to the Government a minimum of two workdays in advance of the meeting. The Contractor's Project Manager and scheduler must attend the meeting with the authorized representative of the Contracting Officer. Superintendents, foremen and major subcontractors must attend the meeting as required to discuss the project schedule and work. Following the periodic schedule update meeting, make corrections to the draft submission. Include only those changes approved by the Government in the submission and invoice for payment.

3.6.2 Update Submission Following Progress Meeting

Submit the complete Periodic Schedule Update of the Project Schedule containing all approved progress, revisions, and adjustments, pursuant to paragraph SUBMISSION REQUIREMENTS not later than 4 work days after the periodic schedule update meeting.

3.7 WEEKLY PROGRESS MEETINGS

Conduct a weekly meeting with the Government (or as otherwise mutually agreed to) between the meetings described in paragraph entitled PERIODIC SCHEDULE UPDATE MEETINGS for the purpose of jointly reviewing the actual progress of the project as compared to the as planned progress and to review planned activities for the upcoming two weeks. Use the current approved schedule update for the purposes of this meeting and for the production and review of reports. At the weekly progress meeting, address the status of RFIs, RFPs and Submittals.

3.8 REQUESTS FOR TIME EXTENSIONS

Provide a justification of delay to the Contracting Officer in accordance with the contract provisions and clauses for approval within 10 days of a delay occurring. Also prepare a time impact analysis for each Government request for proposal (RFP) to justify time extensions.

3.8.1 Justification of Delay

Provide a description of the event(s) that caused the delay and/or impact to the work. As part of the description, identify all schedule activities impacted. Show that the event that caused the delay/impact was the responsibility of the Government. Provide a time impact analysis that demonstrates the effects of the delay or impact on the project completion date or interim completion date(s). Evaluate multiple impacts chronologically; each with its own justification of delay. With multiple impacts consider any concurrency of delay. A time extension and the schedule fragnet becomes part of the project schedule and all future schedule updates upon approval by the Contracting Officer.

3.8.2 Time Impact Analysis (Prospective Analysis)

Prepare a time impact analysis for approval by the Contracting Officer based on industry standard AACE 52R-06. Utilize a copy of the last approved schedule prior to the first day of the impact or delay for the time impact analysis. If Contracting Officer determines the time frame between the last approved schedule and the first day of impact is too great, prepare an interim updated schedule to perform the time impact analysis. Unless approved by the Contracting Officer, no other changes may be incorporated into the schedule being used to justify the time impact.

3.8.3 Forensic Schedule Analysis (Retrospective Analysis)

Prepare an analysis for approval by the Contracting Officer based on industry standard AACE 29R-03.

3.8.4 Fragmentary Network (Fragnet)

Prepare a proposed fragnet for time impact analysis consisting of a sequence of new activities that are proposed to be added to the project schedule to demonstrate the influence of the delay or impact to the project's contractual dates. Clearly show how the proposed fragnet is to be tied into the project schedule including all predecessors and successors to the fragnet activities. The proposed fragnet must be approved by the Contracting Officer prior to incorporation into the project schedule.

3.8.5 Time Extension

The Contracting Officer must approve the Justification of Delay including the time impact analysis before a time extension will be granted. No time extension will be granted unless the delay consumes all available Project Float and extends the projected finish date ("End Project" milestone) beyond the Contract Completion Date. The time extension will be in calendar days.

Actual delays that are found to be caused by the Contractor's own actions, which result in a calculated schedule delay will not be a cause for an extension to the performance period, completion date, or any interim milestone date.

3.8.6 Impact to Early Completion Schedule

No extended overhead will be paid for delay prior to the original Contract

Completion Date for an Early Completion IPS unless the Contractor actually performed work in accordance with that Early Completion Schedule. The Contractor must show that an early completion was achievable had it not been for the impact.

3.9 FAILURE TO ACHIEVE PROGRESS

Should the progress fall behind the approved project schedule for reasons other than those that are excusable within the terms of the contract, the Contracting Officer may require provision of a written recovery plan for approval. The plan must detail how progress will be made-up to include which activities will be accelerated by adding additional crews, longer work hours, extra work days, etc.

3.9.1 Artificially Improving Progress

Artificially improving progress by means such as, but not limited to, revising the schedule logic, modifying or adding constraints, shortening activity durations, or changing calendars in the project schedule is prohibited. Indicate assumptions made and the basis for any logic, constraint, duration and calendar changes used in the creation of the recovery plan. Any additional resources, manpower, or daily and weekly work hour changes proposed in the recovery plan must be evident at the work site and documented in the daily report along with the Schedule Narrative Report.

3.9.2 Failure to Perform

Failure to perform work and maintain progress in accordance with the supplemental recovery plan may result in an interim and final unsatisfactory performance rating and may result in corrective action directed by the Contracting Officer pursuant to FAR 52.236-15 Schedules for Construction Contracts, FAR 52.249-10 Default (Fixed-Price Construction), and other contract provisions.

3.9.3 Recovery Schedule

Should the Contracting Officer find it necessary, submit a recovery schedule pursuant to FAR 52.236-15 Schedules for Construction Contracts.

3.10 OWNERSHIP OF FLOAT

Except for the provision given in the paragraph IMPACT TO EARLY COMPLETION SCHEDULE, float available in the schedule, at any time, may not be considered for the exclusive use of either the Government or the Contractor including activity and/or project float. Activity float is the number of work days that an activity can be delayed without causing a delay to the "End Project" finish milestone. Project float (if applicable) is the number of work days between the projected early finish and the contract completion date milestone.

3.11 TRANSFER OF SCHEDULE DATA INTO RMS/QCS

Import the schedule data into the Quality Control System (QCS) and export the QCS data to the Government. This data is considered to be additional supporting data in a form and detail required by the Contracting Officer pursuant to FAR 52.232-5 Payments under Fixed-Price Construction Contracts. The receipt of a proper payment request pursuant to FAR 52.232-27 Prompt Payment for Construction Contracts is contingent upon the

Government receiving both acceptable and approvable hard copies and matching electronic export from QCS of the application for progress payment.

3.12 PRIMAVERA P6 MANDATORY REQUIREMENTS

If Primavera P6 is being used, request a backup file template (.xer) from the Government, if one is available, prior to building the schedule. The following settings are mandatory and required in all schedule submissions to the Government:

- a. Activity Codes must be Project Level, not Global or EPS level.
- b. Calendars must be Project Level, not Global or Resource level.
- c. Activity Duration Types must be set to "Fixed Duration & Units".
- d. Percent Complete Types must be set to "Physical".
- e. Time Period Admin Preferences must remain the default "8.0 hr/day, 40 hr/week, 172 hr/month, 2000 hr/year". Set Calendar Work Hours/Day to 8.0 Hour days.
- f. Set Schedule Option for defining Critical Activities to "Longest Path".
- g. Set Schedule Option for defining progressed activities to "Retained Logic".
- h. Set up cost loading using a single lump sum labor resource. The Price/Unit must be \$1/hr, Default Units/Time must be "8h/d", and settings "Auto Compute Actuals" and "Calculate costs from units" selected.
- i. Activity ID's must not exceed 10 characters.
- j. Activity Names must have the most defining and detailed description within the first 30 characters.

-- End of Section --

SECTION 01 33 00

SUBMITTAL PROCEDURES

08/18

PART 1 GENERAL

0.1 DEFINITIONS

0.1.1 Submittal Descriptions (SD)

Submittal requirements are specified in the technical sections. Examples and descriptions of submittals identified by the Submittal Description (SD) numbers and titles follow:

SD-01 Preconstruction Submittals

Preconstruction Submittals include schedules and a tabular list of locations, features, and other pertinent information regarding products, materials, equipment, or components to be used in the work.

Certificates Of Insurance

Surety Bonds

List Of Proposed Subcontractors

List Of Proposed Products

Submittal Register

Schedule Of Prices Or Earned Value Report

Work Plan

Quality Control (QC) plan

SD-02 Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the Contractor for integrating the product or system into the project.

Drawings prepared by or for the Contractor to show how multiple systems and interdisciplinary work will be coordinated.

SD-03 Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials, systems or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

SD-04 Samples

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. Unless specified in another section, testing must have been within three years of date of contract award for the project.

Report that includes findings of a test required to be performed on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report that includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports

Final acceptance test and operational test procedure

SD-07 Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that the product, system, or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a manufacturer, supplier, installer or Subcontractor through Contractor. The document purpose is to further promote the orderly progression of a portion of the work by documenting procedures, acceptability of methods, or personnel qualifications.

Confined space entry permits

Text of posted operating instructions SD-

08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and (SDS) concerning impedances, hazards and safety precautions.

SD-10 Operation and Maintenance Data

Data provided by the manufacturer, or the system provider, including manufacturer's help and product line documentation, necessary to maintain and install equipment, for operating and maintenance use by facility personnel.

Data required by operating and maintenance personnel for the safe and efficient operation, maintenance and repair of the item.

Data incorporated in an operations and maintenance manual or control system.

SD-11 Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

Special requirements necessary to properly close out a construction contract. For example, Record Drawings and as-built drawings. Also, submittal requirements necessary to properly close out a major phase of construction on a multi-phase contract.

0.1.2 Approving Authority

Office or designated person authorized to approve the submittal.

0.1.3 Work

As used in this section, on-site and off-site construction required by contract documents, including labor necessary to produce submittals, construction, materials, products, equipment, and systems incorporated or to be incorporated in such construction. In exception, excludes work to produce SD-01 submittals.

0.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with this section.

SD-01 Preconstruction Submittals

Submittal Register; G

0.3 SUBMITTAL CLASSIFICATION

0.3.1 Government Approved (G)

Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, submittals are considered to be "shop drawings."

0.3.2 For Information Only

Submittals not requiring Government approval will be for information only. Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, they are not considered to be "shop drawings."

0.4 PREPARATION

0.4.1 Transmittal Form

0.4.2 Submittal Format

0.4.2.1 Format of SD-01 Preconstruction Submittals

When the submittal includes a document that is to be used in the project, or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

0.4.2.2 Format for SD-02 Shop Drawings

Provide shop drawings not less than 8 1/2 by 11 inches nor more than 30 by 42 inches, except for full-size patterns or templates. Prepare drawings to accurate size, with scale indicated, unless another form is required. Ensure drawings are suitable for reproduction and of a quality to produce clear, distinct lines and letters, with dark lines on a white background.

- a. Include the nameplate data, size, and capacity on drawings. Also include applicable federal, military, industry, and technical society publication references.
- b. Dimension drawings, except diagrams and schematic drawings. Prepare drawings demonstrating interface with other trades to scale. Use the same unit of measure for shop drawings as indicated on the contract drawings. Identify materials and products for work shown.

0.4.2.2.1 Drawing Identification

Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph IDENTIFYING SUBMITTALS.

Number drawings in a logical sequence. Each drawing is to bear the number of the submittal in a uniform location next to the title block. Place the Government contract number in the margin, immediately below the title block, for each drawing.

Reserve a blank space on the right-hand side of each sheet for the

Government disposition stamp.

0.4.2.3 Format of SD-03 Product Data

Present product data submittals for each section. Include a table of contents, listing the page and catalog item numbers for product data.

Indicate, by prominent notation, each product that is being submitted; indicate the specification section number and paragraph number to which it pertains.

0.4.2.3.1 Product Information

Supplement product data with material prepared for the project to satisfy the submittal requirements where product data does not exist. Identify this material as developed specifically for the project, with information and format as required for submission of SD-07 Certificates.

Provide product data in units used in the Contract documents. Where product data are included in preprinted catalogs with another unit, submit the dimensions in contract document units, on a separate sheet.

0.4.2.3.2 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

0.4.2.3.3 Data Submission

Collect required data submittals for each specific material, product, unit of work, or system into a single submittal that is marked for choices, options, and portions applicable to the submittal. Mark each copy of the product data identically. Partial submittals will not be accepted for expedition of the construction effort.

Submit the manufacturer's instructions before installation.

0.4.2.4 Format of SD-04 Samples

0.4.2.4.1 Sample Characteristics

Furnish samples in the following sizes, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately the same size as specified:

- a. Sample of Equipment or Device: Electronic Sheets
- b. Sample of Materials Less Than 2 by 3 inches: Built up to 8 1/2 by 11

inches.

- c. Sample of Materials Exceeding 8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.
- d. Sample of Linear Devices or Materials: 10 inch length or length to be supplied, if less than 10 inches. Examples of linear devices or materials are conduit and handrails.
- e. Sample Volume of Nonsolid Materials: Pint. Examples of nonsolid materials are sand and paint.
- f. Color Selection Samples: 2 by 4 inches. Where samples are specified for selection of color, finish, pattern, or texture, submit the full set of available choices for the material or product specified. Sizes and quantities of samples are to represent their respective standard unit.
- g. Sample Panel: None on project
- h. Sample Installation: 100 square feet or less, if needed.

0.4.2.4.2 Sample Incorporation

Reusable Samples: Incorporate returned samples into work only if so specified or indicated. Incorporated samples are to be in undamaged condition at the time of use.

Recording of Sample Installation: Note and preserve the notation of any area constituting a sample installation, but remove the notation at the final clean-up of the project.

0.4.2.4.3 Comparison Sample

Samples Showing Range of Variation: Where variations in color, finish, pattern, or texture are unavoidable due to nature of the materials, submit sets of samples of not less than three units showing extremes and middle of range. Mark each unit to describe its relation to the range of the variation.

When color, texture, or pattern is specified by naming a particular manufacturer and style, include one sample of that manufacturer and style, for comparison.

0.4.2.5 Format of SD-05 Design Data

Provide design data and certificates on 8 1/2 by 11 inch paper, electronically.

0.4.2.6 Format of SD-06 Test Reports

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

0.4.2.7 Format of SD-07 Certificates

Provide design data and certificates on 8 1/2 by 11 inch paper,

electronically.

0.4.2.8 Format of SD-08 Manufacturer's Instructions

Present manufacturer's instructions submittals for each section. Include the manufacturer's name, trade name, place of manufacture, and catalog model or number on product data. Also include applicable federal, military, industry, and technical-society publication references. If supplemental information is needed to clarify the manufacturer's data, submit it as specified for SD-07 Certificates.

Submit the manufacturer's instructions before installation.

0.4.2.8.1 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

0.4.2.9 Format of SD-09 Manufacturer's Field Reports

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

0.4.2.10 Format of SD-10 Operation and Maintenance Data (O&M)

Comply with the requirements specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA for O&M Data format.

0.4.2.11 Format of SD-11 Closeout Submittals

When the submittal includes a document that is to be used in the project or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

0.4.3 Source Drawings for Shop Drawings

0.4.3.1 Source Drawings

The entire set of source drawing files (DWG) will not be provided to the Contractor. Request the specific Drawing Number for the preparation of shop drawings. Only those drawings requested to prepare shop drawings will be provided. These drawings are provided only after award.

0.4.3.2 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction data for the referenced project. Any other use or reuse is at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim, and waives to the fullest extent permitted by law any claim or cause of action of any nature against the Government, its agents, or its subconsultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities, or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic source drawing files are not construction documents. Differences may exist between the source drawing files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic source drawing files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. The Contractor is responsible for determining if any conflict exists. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished source drawing files, the signed and sealed construction documents govern. Use of these source drawing files does not relieve the Contractor of the duty to fully comply with the contract documents, including and without limitation the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction data related to this contract, remove all previous indication of ownership (seals, logos, signatures, initials and dates).

0.5 QUANTITY OF SUBMITTALS

0.5.1 Number of SD-01 Preconstruction Submittal Copies

Unless otherwise specified, submit two sets of administrative submittals if done on paper and one electronically.

0.5.2 Number of SD-04 Samples

- a. Submit two samples, or two sets of samples showing the range of variation, of each required item. One approved sample or set of samples will be retained by the approving authority and one will be returned to the Contractor.
- b. Submit one sample panel or provide one sample installation where directed. Include components listed in the technical section or as directed.
- c. Submit one sample installation, where directed.
- d. Submit one sample of nonsolid materials.

0.6 INFORMATION ONLY SUBMITTALS

Submittals without a "G" designation must be certified by the QC manager and submitted to the Contracting Officer for information-only. Approval

of the Contracting Officer is not required on information only submittals. The Contracting Officer will mark "receipt acknowledged" on submittals for information and will return only the transmittal cover sheet to the Contractor. Normally, submittals for information only will not be returned. However, the Government reserves the right to return unsatisfactory submittals and require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

PROJECT SUBMITTAL REGISTER

A sample Project Submittal Register showing items of equipment and materials for when submittals are required by the specifications is provided as "Appendix A - Submittal Register."

0.7 Submittal Management

Prepare and maintain a submittal register, as the work progresses. Do not change data that is output in columns (c), (d), (e), and (f) as delivered by Government; retain data that is output in columns (a), (g), (h), and (i) as approved. As an attachment, provide a submittal register showing items of equipment and materials for which submittals are required by the specifications. This list may not be all-inclusive and additional submittals may be required.

Column (c): Lists specification section in which submittal is required.

Column (d): Lists each submittal description (SD Number. and type, e.g., SD-02 Shop Drawings) required in each specification section.

Column (e): Lists one principal paragraph in each specification section where a material or product is specified. This listing is only to facilitate locating submitted requirements. Do not consider entries in column (e) as limiting the project requirements.

Thereafter, the Contractor is to track all submittals by maintaining a complete list, including completion of all data columns and all dates on which submittals are received by and returned by the Government.

0.8 Preconstruction Use of Submittal Register

Submit the submittal register. Include the QC plan and the project schedule. Verify that all submittals required for the project are listed and add missing submittals. Coordinate and complete the following fields on the register submitted with the QC plan and the project schedule:

Column (a) Activity Number: Activity number from the project schedule.

Column (g) Contractor Submit Date: Scheduled date for the

approving authority to receive submittals.

Column (h) Contractor Approval Date: Date that Contractor needs approval of submittal.

Column (i) Contractor Material: Date that Contractor needs material delivered to Contractor control.

0.9 Contractor Use of Submittal Register

Update the following fields with each submittal throughout the contract.

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (j) Action Code (k): Date of action used to record Contractor's review when forwarding submittals to QC.

Column (l) Date submittal transmitted.

Column (q) Date approval was received.

0.10 Approving Authority Use of Submittal

Register Update the following fields:

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (l) Date submittal was received.

Column (m) through (p) Dates of review actions. Column (q) Date of return.

--End of Section--

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS

11/15

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.34 (2001; R 2012) Protection of the Public on or Adjacent to Construction Sites

ASSP A10.44 (2014) Control of Energy Sources (Lockout/Tagout) for Construction and Demolition Operations

ASTM INTERNATIONAL (ASTM)

ASTM F855 (2015) Standard Specifications for Temporary Protective Grounds to Be Used on De-energized Electric Power Lines and Equipment

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 1048 (2003) Guide for Protective Grounding of Power Lines

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 51B (2014) Standard for Fire Prevention During Welding, Cutting, and Other Hot Work

NFPA 70 (2017; ERTA 1-2 2017; TIA 17-1; TIA 17-2; TIA 17-3; TIA 17-4; TIA 17-5; TIA 17-6; TIA 17-7; TIA 17-8; TIA 17-9; TIA 17-10; TIA 17-11; TIA 17-12; TIA 17-13; TIA 17-14; TIA 17-15; TIA 17-16; TIA 17-17) National Electrical Code

NFPA 70E (2018; TIA 18-1; TIA 81-2) Standard for Electrical Safety in the Workplace

NFPA 241 (2019) Standard for Safeguarding Construction, Alteration, and Demolition Operations

Manual

1.2 DEFINITIONS

1.2.1 Competent Person (CP)

The CP is a person designated in writing, who, through training, knowledge and experience, is capable of identifying, evaluating, and addressing existing and predictable hazards in the working environment or working conditions that are dangerous to personnel, and who has authorization to take prompt corrective measures with regards to such hazards.

1.2.2 Competent Person, Scaffolding

The CP, Scaffolding is a person meeting the competent person designated in writing by the employer to be responsible for immediate supervising, implementing and monitoring of the scaffolding program. The CP for Scaffolding has enough training, knowledge and experience in scaffolding to correctly identify, evaluate and address existing and potential hazards and also has the authority to take prompt corrective measures with regard to these hazards. CP qualifications must be documented and include experience on the specific scaffolding systems/types being used, assessment of the base material that the scaffold will be erected upon, load calculations for materials and personnel, and erection and dismantling. The CP for scaffolding must have a documented, minimum of 8-hours of scaffold training to include training on the specific type of scaffold being used (e.g. mast-climbing, adjustable, tubular frame).

1.2.3 Medical Treatment

Medical Treatment is treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even when provided by a physician or registered personnel.

1.2.4 Near Miss

A Near Miss is a mishap resulting in no personal injury and zero property damage, but given a shift in time or position, damage or injury may have occurred (e.g., a worker falls off a scaffold and is not injured; a crane swings around to move the load and narrowly misses a parked vehicle).

1.2.5 Qualified Person (QP)

The QP is a person designated in writing, who, by possession of a recognized degree, certificate, or professional standing, or extensive knowledge, training, and experience, has successfully demonstrated their ability to solve or resolve problems related to the subject matter, the work, or the project.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Accident Prevention Plan (APP); G

SD-06 Test Reports

Monthly Exposure Reports

Notifications and Reports

Accident Reports; G

SD-07 Certificates

Standard Lift Plan; G

Hot Work Permit

Certificate of Compliance

License Certificates

1.4 MONTHLY EXPOSURE REPORTS

Provide a Monthly Exposure Report and attach to the monthly billing request. This report is a compilation of employee-hours worked each month for all site workers, both Prime and subcontractor. Failure to submit the report may result in retention of up to 10 percent of the voucher.

1.5 REGULATORY REQUIREMENTS

In addition to the detailed requirements included in the provisions of this contract, comply with the most recent edition of state, laws, ordinances, criteria, rules and regulations. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting work.

Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements govern.

1.6 SITE QUALIFICATIONS, DUTIES, AND MEETINGS

1.6.1 Personnel Qualifications

1.6.1.1 Site Safety and Health Officer (SSHO)

The SSHO must ensure that the requirements of 29 CFR 1926.16 are met for the project.

Provide a Safety oversight team that includes a minimum of one (1) person at each project site to function as the Site Safety and Health Officer (SSHO). The SSHO or an equally-qualified Alternate SSHO must be at the work site at all times to implement and administer the Contractor's safety program and government-accepted Accident Prevention Plan. The SSHO and Alternate SSHO must have the required training, experience, and qualifications.

If the SSHO is off-site for a period longer than 24 hours, an equally-qualified alternate SSHO must be provided and must fulfill the same roles and responsibilities as the primary SSHO. When the SSHO is temporarily (up to 24 hours) off-site, a Designated Representative (DR), as identified in the AHA may be used in lieu of an Alternate SSHO, and must be on the project site at all times when work is being performed. Note that the DR is a collateral duty safety position, with safety duties in addition to their full time occupation.

1.6.1.1.1 Additional Site Safety and Health Officer (SSHO) Requirements and Duties

The SSHO may also serve as the Quality Control Manager. The SSHO may also serve as the Superintendent.

1.6.1.2 Competent Person Qualifications

Provide Competent Persons. Competent Persons for high risk activities include confined space, cranes and rigging, excavation/trenching, fall protection, and electrical work. The CP for these activities must be designated in writing, and meet the requirements for the specific activity (i.e. competent person, fall protection).

The Competent Person identified in the Contractor's Safety and Health Program and accepted Accident Prevention Plan, must be on-site at all times when the work that presents the hazards associated with their professional expertise is being performed. Provide the credentials of the Competent Persons(s) to the Contracting Officer for information in consultation with the Safety Office.

1.6.2 Personnel Duties

1.6.2.1 Duties of the Site Safety and Health Officer (SSHO)

The SSHO must:

- a. Conduct daily safety and health inspections and maintain a written log which includes area/operation inspected, date of inspection, identified hazards, recommended corrective actions, estimated and actual dates of corrections. Attach safety inspection logs to the Contractors' daily production report.
- b. Conduct mishap investigations and complete required accident reports. Report mishaps and near misses.
- c. Use and maintain OSHA's Form 300 to log work-related injuries and illnesses occurring on the project site for Prime Contractors and subcontractors, and make available to the Contracting Officer upon request. Post and maintain the Form 300A on the site Safety Bulletin Board.
- d. Maintain applicable safety reference material on the job site.
- e. Attend the pre-construction conference, pre-work meetings including preparatory meetings, and periodic in-progress meetings.
- f. Establish a Safety and Occupational Health (SOH) Deficiency Tracking System that lists and monitors outstanding deficiencies until resolution.
- g. Ensure subcontractor compliance with safety and health requirements.
- h. Maintain a list of hazardous chemicals on site and their material Safety Data Sheets (SDS).
- i. Maintain a weekly list of high hazard activities involving energy, equipment, excavation, entry into confined space, and elevation, and be prepared to discuss details during QC Meetings.
- j. Provide and keep a record of site safety orientation and indoctrination for Contractor employees, subcontractor employees, and site visitors.

Superintendent, QC Manager, and SSHO are subject to dismissal if the above duties are not being effectively carried out. If Superintendent, QC Manager, or SSHO are dismissed, project work will be stopped and will not be allowed to resume until a suitable replacement is approved and the above duties are again being effectively carried out.

1.6.3 Meetings

1.6.3.1 Preconstruction Conference

- a. Contractor representatives who have a responsibility or significant role in accident prevention on the project must attend the

preconstruction conference. This includes the project superintendent, Site Safety and Occupational Health officer, quality control manager, or any other assigned safety and health professionals who participated in the development of the APP (including the Activity Hazard Analyses (AHAs) and special plans, program and procedures associated with it).

- b. Discuss the details of the submitted APP to include incorporated plans, programs, procedures and a listing of anticipated AHAs that will be developed and implemented during the performance of the contract. This list of proposed AHAs will be reviewed at the conference and an agreement will be reached between the Contractor and the Contracting Officer as to which phases will require an analysis. In addition, establish a schedule for the preparation, submittal, and Government review of AHAs to preclude project delays.
- c. Deficiencies in the submitted APP, identified during the Contracting Officer's review, must be corrected, and the APP re-submitted for review prior to the start of construction. Work is not permitted to begin until an APP is established that is acceptable to the Contracting Officer.

1.6.3.2 Safety Meetings

Conduct safety meetings to review past activities, plan for new or changed operations, review pertinent aspects of appropriate AHA (by trade), establish safe working procedures for anticipated hazards, and provide pertinent Safety and Occupational Health (SOH) training and motivation. Conduct meetings at least once a month for all supervisors on the project location. The SSHO, supervisors, foremen, or CDSOs must conduct meetings at least once a week for the trade workers. Document meeting minutes to include the date, persons in attendance, subjects discussed, and names of individual(s) who conducted the meeting. Maintain documentation on-site and furnish copies to the Contracting Officer on request. Notify the Contracting Officer of all scheduled meetings 7 calendar days in advance.

1.7 ACCIDENT PREVENTION PLAN (APP)

A qualified person must prepare the written site-specific APP. The APP must be job-specific and address any unusual or unique aspects of the project or activity for which it is written. The APP must interface with the Contractor's overall safety and health program referenced in the APP in the applicable APP element, and made site-specific. Describe the methods to evaluate past safety performance of potential subcontractors in the selection process. Also, describe innovative methods used to ensure and monitor safe work practices of subcontractors. The Government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the subcontractors. Contractors are responsible for informing their subcontractors of the safety provisions under the terms of the contract and the penalties for noncompliance, coordinating the work to prevent one craft from interfering with or creating hazardous working conditions for other crafts, and inspecting subcontractor operations to ensure that accident prevention responsibilities are being carried out. The APP must be signed by an officer of the firm (Prime Contractor senior person), the individual preparing the APP, the on-site superintendent, the designated SSHO, the Contractor Quality Control Manager, and any designated Certified Safety Professional (CSP) or Certified Health

Physicist (CIH). The SSHO must provide and maintain the APP and a log of signatures by each subcontractor foreman, attesting that they have read and understand the APP, and make the APP and log available on-site to the Contracting Officer. If English is not the foreman's primary language, the Prime Contractor must provide an interpreter.

Submit the APP to the Contracting Officer 15 calendar days prior to the date of the preconstruction conference for acceptance. Work cannot proceed without an accepted APP. Once reviewed and accepted by the Contracting Officer, the APP and attachments will be enforced as part of the contract. Disregarding the provisions of this contract or the accepted APP is cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified. Continuously review and amend the APP, as necessary, throughout the life of the contract. Changes to the accepted APP must be made with the knowledge and concurrence of the Contracting Officer, project superintendent, SSHO and Quality Control Manager. Incorporate unusual or high-hazard activities not identified in the original APP as they are discovered. Should any severe hazard exposure (i.e. imminent danger) become evident, stop work in the area, secure the area, and develop a plan to remove the exposure and control the hazard. Notify the Contracting Officer within 24 hours of discovery. Eliminate and remove the hazard. In the interim, take all necessary action to restore and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public (as defined by ASSP A10.34), and the environment.

1.7.1 Names and Qualifications

Provide plans, including the following:

- a. Names and qualifications (resumes including education, training, experience and certifications) of site safety and health personnel designated to perform work on this project to include the designated Site Safety and Health Officer and other competent and qualified personnel to be used. Specify the duties of each position.
- b. Qualifications of competent and of qualified persons. As a minimum, designate and submit qualifications of competent persons for each of the following major areas: excavation; scaffolding; fall protection; hazardous energy; confined space; health hazard recognition, evaluation and control of chemical, physical and biological agents; and personal protective equipment and clothing to include selection, use and maintenance.

1.8 ACTIVITY HAZARD ANALYSIS (AHA)

Before beginning each activity, task or Definable Feature of Work (DFOW) involving a type of work presenting hazards not experienced in previous project operations, or where a new work crew or subcontractor is to perform the work, the Contractor(s) performing that work activity must prepare an AHA. AHAs must be developed by the Prime Contractor, subcontractor, or supplier performing the work, and provided for Prime Contractor review and approval before submitting to the Contracting

Officer. AHAs must be signed by the SSHO, Superintendent, QC Manager and the subcontractor Foreman performing the work. Submit the AHA for review at least 15 working days prior to the start of each activity task, or DFOV. The Government reserves the right to require the Contractor to revise and resubmit the AHA if it fails to effectively identify the work sequences, specific anticipated hazards, site conditions, equipment, materials, personnel and the control measures to be implemented.

AHAs must identify competent persons required for phases involving high risk activities, including confined entry, crane and rigging, excavations, trenching, electrical work, fall protection, and scaffolding.

1.8.1 AHA Management

Review the AHA list periodically at the Contractor supervisory safety meeting, and update as necessary when procedures, scheduling, or hazards change. Use the AHA during daily inspections by the SSHO to ensure the implementation and effectiveness of the required safety and health controls for that work activity.

1.8.2 AHA Signature Log

Each employee performing work as part of an activity, task or DFOV must review the AHA for that work and sign a signature log specifically maintained for that AHA prior to starting work on that activity. The SSHO must maintain a signature log on site for every AHA. Provide employees whose primary language is other than English, with an interpreter to ensure a clear understanding of the AHA and its contents.

1.9 DISPLAY OF SAFETY INFORMATION

1.9.1 Safety Bulletin Board

Within one calendar day after commencement of work, erect a safety bulletin board at the job site. Where size, duration, or logistics of project do not facilitate a bulletin board, an alternative method, acceptable to the Contracting Officer, that is accessible and includes all mandatory information for employee and visitor review, may be deemed as meeting the requirement for a bulletin board. Include and maintain information on safety bulletin board.

Additional items required to be posted include:

- a. Confined space entry permit.
- b. Hot work permit.

1.9.2 Safety and Occupational Health (SOH) Deficiency Tracking System

Establish a SOH deficiency tracking system that lists and monitors the status of SOH deficiencies in chronological order. Use the tracking system to evaluate the effectiveness of the APP. A monthly evaluation of the data must be discussed in the QC or SOH meeting with everyone on the project. The list must be posted on the project bulletin board and updated daily, and provide the following information:

- a. Date deficiency identified;

- b. Description of deficiency;
- c. Name of person responsible for correcting deficiency;
- d. Projected resolution date;
- e. Date actually resolved.

1.10 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project, including those listed in paragraph REFERENCES. Maintain applicable equipment manufacturer's manuals.

1.11 EMERGENCY MEDICAL TREATMENT

Contractors must arrange for their own emergency medical. Government has no responsibility to provide emergency medical treatment.

1.12 NOTIFICATIONS and REPORTS

1.12.1 Mishap Notification

Notify the Contracting Officer as soon as practical, but no more than twenty-four hours, after any mishaps, including recordable accidents, incidents, and near misses, any report of injury, illness, or any property damage. For LHE or rigging mishaps, notify the Contracting Officer as soon as practical but not more than 4 hours after mishap. The Contractor is responsible for obtaining appropriate medical and emergency assistance and for notifying fire, law enforcement, and regulatory agencies. Immediate reporting is required for electrical mishaps, to include Arc Flash; shock; uncontrolled release of hazardous energy; load handling equipment or rigging; fall from height. These mishaps must be investigated in depth to identify all causes and to recommend hazard control measures.

Within notification include Contractor name; contract title; type of contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (for example, type of construction equipment used and PPE used). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted. Assist and cooperate fully with the Government's investigation(s) of any mishap.

1.12.2 Accident Reports

- a. Conduct an accident investigation for recordable injuries and illnesses, property damage, and near misses, to establish the root cause(s) of the accident. The Contracting Officer will provide copies of any required or special forms.
- b. Near Misses: Near miss reports are considered positive and proactive Contractor safety management actions.

1.13 HOT WORK

1.13.1 Permit and Personnel Requirements

Submit and obtain a written permit prior to performing "Hot Work" i.e. welding or cutting or operating other flame-producing/spark producing devices, from the Fire Division. A permit is required from the Explosives Safety Office for work in and around where explosives are processed, stored, or handled. CONTRACTORS ARE REQUIRED TO MEET ALL CRITERIA BEFORE A PERMIT IS ISSUED. Provide at least two 20 pound 4A:20 BC rated extinguishers for normal "Hot Work". The extinguishers must be current inspection tagged, and contain an approved safety pin and tamper resistant seal. It is also mandatory to have a designated FIRE WATCH for any "Hot Work" done at this activity. The Fire Watch must be trained in accordance with NFPA 51B and remain on-site for a minimum of one hour after completion of the task or as specified on the hot work permit.

When starting work in the facility, require personnel to familiarize themselves with the location of the nearest fire alarm boxes and place in memory the emergency Fire Division phone number. REPORT ANY FIRE, NO MATTER HOW SMALL, TO THE RESPONSIBLE FIRE DIVISION IMMEDIATELY.

1.13.2 Work Around Flammable Materials

Obtain permit approval from a NFPA Certified Marine Chemist for "HOT WORK" within or around flammable materials (such as fuel systems or welding/cutting on fuel pipes) or confined spaces (such as sewer wet wells, manholes, or vaults) that have the potential for flammable or explosive atmospheres.

Whenever these materials, except beryllium and chromium (VI), are encountered in indoor operations, local mechanical exhaust ventilation systems that are sufficient to reduce and maintain personal exposures to within acceptable limits must be used and maintained in accordance with manufacturer's instructions.

PART 2 PRODUCTS

PART 3 EXECUTION

3.1 CONSTRUCTION AND OTHER WORK

Comply with NFPA 70, NFPA 70E, NFPA 241, the APP, the AHA, Federal and State OSHA regulations, and other related submittals and activity fire and safety regulations. The most stringent standard prevails.

PPE is governed in all areas by the nature of the work the employee is performing. Use personal hearing protection at all times in designated noise hazardous areas or when performing noise hazardous tasks. Safety glasses must be worn or carried/available on each person. Mandatory PPE includes:

- a. Hard Hat
- b. Long Pants
- c. Appropriate Safety Shoes

d. Appropriate Class Reflective Vests

3.1.1 Worksite Communication

Employees working alone in a remote location or away from other workers must be provided an effective means of emergency communications (i.e., cellular phone, two-way radios, land-line telephones or other acceptable means). The selected communication must be readily available (easily within the immediate reach) of the employee and must be tested prior to the start of work to verify that it effectively operates in the area/environment. An employee check-in/check-out communication procedure must be developed to ensure employee safety.

3.1.2 Unforeseen Hazardous Material

Contract documents identify materials such as PCB, lead paint, and friable and non-friable asbestos and other OSHA regulated chemicals (i.e. 29 CFR Part 1910.1000). If material(s) that may be hazardous to human health upon disturbance are encountered during construction operations, stop that portion of work and notify the Contracting Officer immediately. Within 14 calendar days the Government will determine if the material is hazardous. If material is not hazardous or poses no danger, the Government will direct the Contractor to proceed without change. If material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification pursuant to FAR 52.243-4 Changes and FAR 52.236-2 Differing Site Conditions.

3.2 UTILITY OUTAGE REQUIREMENTS

Apply for utility outages at least three days in advance. At a minimum, the written request must include the location of the outage, utilities being affected, duration of outage, any necessary sketches, and a description of the means to fulfill energy isolation. Where outages involve Government or Utility personnel, coordinate with the Government on all activities involving the control of hazardous energy.

These activities include, but are not limited to, a review of HEC and HEC procedures, as well as applicable Activity Hazard Analyses (AHAs). Work on energized electrical circuits must not be performed without prior government authorization. Government permission is considered through the permit process and submission of a detailed AHA. Energized work permits are considered only when de-energizing introduces additional or increased hazard or when de-energizing is infeasible.

3.3 OUTAGE COORDINATION MEETING

After the utility outage request is approved and prior to beginning work on the utility system requiring shut-down, conduct a pre-outage coordination. This meeting must include the Prime Contractor, the Prime and subcontractors performing the work, the Contracting Officer, and the Installation representative. All parties must fully coordinate HEC activities with one another. During the coordination meeting, all parties must discuss and coordinate on the scope of work, HEC

procedures (specifically, the lock-out/tag-out procedures for worker and utility protection), the AHA, assurance of trade personnel qualifications, identification of competent persons. Clarify when personal protective equipment is required during switching operations, inspection, and verification.

3.4 CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT)

Provide and operate a Hazardous Energy Control Program (HECP) in accordance with 29 CFR 1910.333, 29 CFR 1915.89, ASSP A10.44, NFPA 70E, and paragraph HAZARDOUS ENERGY CONTROL PROGRAM (HECP).

3.4.1 Safety Preparatory Inspection Coordination Meeting with the Government or Utility

For electrical distribution equipment that is to be operated by Government or Utility personnel, the Prime Contractor and the subcontractor performing the work must attend the safety preparatory inspection coordination meeting, which will also be attended by the Contracting Officer's Representative. The meeting will occur immediately preceding the start of work and following the completion of the outage coordination meeting. Both the safety preparatory inspection coordination meeting and the outage coordination meeting must occur prior to conducting the outage and commencing with lockout/tagout procedures.

3.4.2 Lockout/Tagout Isolation

Where the Government or Utility performs equipment isolation and lockout/tagout, the Contractor must place their own locks and tags on each energy-isolating device and proceed in accordance with the HECP. Before any work begins, both the Contractor and the Government or Utility must perform energy isolation verification testing while wearing required PPE detailed in the Contractor's AHA. Install personal protective grounds, with tags, to eliminate the potential for induced voltage.

3.4.3 Lockout/Tagout Removal

Upon completion of work, conduct lockout/tagout removal procedure in accordance with the HECP. Each lock and tag must be removed from each energy isolating device by the authorized individual or systems operator who applied the device. Provide formal notification to the Government (by completing the Government form if provided by Contracting Officer's Representative), confirming that steps of de-energization and lockout/tagout removal procedure have been conducted and certified through inspection and verification. Government or Utility locks and tags used to support the Contractor's work will not be removed until the authorized Government employee receives the formal notification.

3.5 WORK PLATFORMS

3.5.1 Scaffolding

Provide employees with a safe means of access to the work area on the

scaffold. Climbing of any scaffold braces or supports not specifically designed for access is prohibited. Comply with the following requirements:

- a. Scaffold platforms greater than 20 feet in height must be accessed by use of a scaffold stair system.
- b. Ladders commonly provided by scaffold system manufacturers are prohibited for accessing scaffold platforms greater than 20 feet maximum in height.
- c. An adequate gate is required.
- d. Employees performing scaffold erection and dismantling must be qualified.
- e. Scaffold must be capable of supporting at least four times the maximum intended load, and provide appropriate fall protection as delineated in the accepted fall protection and prevention plan.
- f. Stationary scaffolds must be attached to structural building components to safeguard against tipping forward or backward.
- g. Special care must be given to ensure scaffold systems are not overloaded.
- h. Side brackets used to extend scaffold platforms on self-supported scaffold systems for the storage of material are prohibited. The first tie-in must be at the height equal to 4 times the width of the smallest dimension of the scaffold base.
- i. Scaffolding other than suspended types must bear on base plates upon wood mudsills (2 in x 10 in x 8 in minimum) or other adequate firm foundation.
- j. Scaffold or work platform erectors must have fall protection during the erection and dismantling of scaffolding or work platforms that are more than 6 feet.
- k. Delineate fall protection requirements when working above 6 feet or above dangerous operations in the Fall Protection and Prevention (FP&P) Plan and Activity Hazard Analysis (AHA) for the phase of work.

3.6 EQUIPMENT

3.6.1 Material Handling Equipment (MHE)

- a. Material handling equipment such as forklifts must not be modified with work platform attachments for supporting employees unless specifically delineated in the manufacturer's printed operating instructions. Material handling equipment fitted with personnel work platform attachments are prohibited from traveling or positioning while personnel are working on the platform.
- b. The use of hooks on equipment for lifting of material must be in accordance with manufacturer's printed instructions. Material Handling Equipment Operators must be trained in accordance with OSHA 29 CFR 1910, Subpart N.
- c. Operators of forklifts or power industrial trucks must be licensed in accordance with OSHA.

3.6.2 Machinery and Mechanized Equipment

- a. Proof of qualifications for operator must be kept on the project site for review.
- b. Manufacture specifications or owner's manual for the equipment must be on-site and reviewed for additional safety precautions or requirements that are sometimes not identified by OSHA. Incorporate such additional safety precautions or requirements into the AHAs.

3.7 ELECTRICAL

3.7.1 Conduct of Electrical Work

Electrical work is to be conducted in a de-energized state unless there is no alternative method for accomplishing the work. In those cases, obtain an energized work permit from the Contracting Officer. The energized work permit application must be accompanied by the AHA and a summary of why the equipment/circuit needs to be worked energized. Underground electrical spaces must be certified safe for entry before entering to conduct work. Cables that will be cut must be positively identified and de-energized prior to performing each cut. Attach temporary grounds in accordance with ASTM F855 and IEEE 1048. Perform all high voltage cable cutting remotely using hydraulic cutting tool. When racking in or live switching of circuit breakers, no additional person other than the switch operator is allowed in the space during the actual operation. Plan so that work near energized parts is minimized to the fullest extent possible. Use of electrical outages clear of any energized electrical sources is the preferred method.

When working in energized substations, only qualified electrical workers are permitted to enter. When work requires work near energized circuits as defined by NFPA 70, high voltage personnel must use personal protective equipment that includes, as a minimum, electrical hard hat, safety shoes, insulating gloves and electrical arc flash protection for personnel as required by NFPA 70E. Insulating blankets, hearing protection, and switching suits may also be required, depending on the specific job and as delineated in the Contractor's AHA. Ensure that each employee is familiar with and complies with these procedures and 29 CFR 1910.147.

3.7.2 Qualifications

Electrical work must be performed by QP personnel with verifiable credentials who are familiar with applicable code requirements. Verifiable credentials consist of State, National and Local Certifications or Licenses that a Master or Journeyman Electrician may hold, depending on work being performed, and must be identified in the appropriate AHA. Journeyman/Apprentice ratio must be in accordance with State, and Local requirements applicable to where work is being performed.

3.7.3 Testing

Temporary electrical distribution systems and devices must be inspected,

tested and found acceptable for Ground-Fault Circuit Interrupter (GFCI) protection, polarity, ground continuity, and ground resistance before initial use, before use after modification and at least monthly.

Month
ly inspections and tests must be maintained for each temporary electrical distribution system, and signed by the electrical CP or QP.

-- End of Section--

SECTION 01 42 00

SOURCES FOR REFERENCE PUBLICATIONS

02/19

PART 1 GENERAL

1.1 REFERENCES

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization (e.g. ASTM B564 Standard Specification for Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

1.2 ORDERING INFORMATION

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided.

AACE INTERNATIONAL (AACE)
1265 Suncrest Towne Centre Drive
Morgantown, WV 26505-1876 USA
Ph: 304-296-8444
Fax: 304-291-5728
Internet: <https://web.aacei.org/>

ALUMINUM ASSOCIATION (AA)
1400 Crystal Drive
Suite 430
Arlington, VA 22202
Ph: 703-358-2960
E-Mail: info@aluminum.org
Internet: <https://www.aluminum.org/>

AMERICAN CONCRETE INSTITUTE (ACI)
38800 Country Club Drive
Farmington Hills, MI 48331-3439
Ph: 248-848-3700
Fax: 248-848-3701
Internet: <https://www.concrete.org/>

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)
1330 Kemper Meadow Drive
Cincinnati, OH 45240
Ph: 513-742-2020
Fax: 513-742-3355
Internet: <https://www.acgih.org/>

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)
130 East Randolph, Suite 2000
Chicago, IL 60601

Ph: 312-670-5444
Fax: 312-670-5403
Steel Solutions Center: 866-275-2472
E-mail: solutions@aisc.org
Internet: <https://www.aisc.org/>

AMERICAN IRON AND STEEL INSTITUTE (AISI)
25 Massachusetts Avenue, NW Suite 800
Washington, DC 20001
Ph: 202-452-7100
Internet: <https://www.steel.org/>

AMERICAN LUMBER STANDARDS COMMITTEE (ALSC)
7470 New Technology Way, Suite F
Frederick, MD 21703
Ph: 301-972-1700
Fax: 301-540-8004
E-mail: alsc@alsc.org
Internet: <http://www.alsc.org>

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)
1899 L Street, NW, 11th Floor
Washington, DC 20036
Ph: 202-293-8020
Fax: 202-293-9287
E-mail: storemanager@ansi.org
Internet: <https://www.ansi.org/>

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING
ENGINEERS (ASHRAE)
1791 Tullie Circle, NE
Atlanta, GA 30329
Ph: 404-636-8400 or 800-527-4723
Fax: 404-321-5478
E-mail: ashrae@ashrae.org
Internet: <https://www.ashrae.org/>

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)
520 N. Northwest Highway
Park Ridge, IL 60068
Ph: 847-699-2929
E-mail: customerservice@assp.org
Internet: <https://www.assp.org/>

AMERICAN WELDING SOCIETY (AWS)
8669 NW 36 Street, #130
Miami, FL 33166-6672
Ph: 800-443-9353
Internet: <https://www.aws.org/>

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)
P.O. Box 361784
Birmingham, AL 35236-1784
Ph: 205-733-4077
Fax: 205-733-4075
Internet: <http://www.awpa.com>

ASME INTERNATIONAL (ASME)
Two Park Avenue

New York, NY 10016-5990
Ph: 800-843-2763
Fax: 973-882-1717
E-mail: customercare@asme.org
Internet: <https://www.asme.org/>

ASTM INTERNATIONAL (ASTM)
100 Barr Harbor Drive, P.O. Box C700
West Conshohocken, PA 19428-2959
Ph: 610-832-9500
Fax: 610-832-9555
E-mail: service@astm.org
Internet: <https://www.astm.org/>

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)
355 Lexington Avenue, 15th Floor
New York, NY 10017
Ph: 212-297-2122
Fax: 212-370-9047
Internet: <https://www.buildershardware.com/>

CALIFORNIA AIR RESOURCES BOARD (CARB)
1001 I Street
Sacramento, CA 95814
Ph: 800-242-4450
Email: helpline@arb.ca.gov
Internet: <https://ww2.arb.ca.gov/>

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)
PO Box 997377, MS 0500
Sacramento, CA 95899-7377
Ph: 916-558-1784
Internet: <https://www.cdph.ca.gov/>

CARPET AND RUG INSTITUTE (CRI)
P.O. Box 2048
Dalton, GA 30722-2048
Ph: 706-278-3176
Fax: 706-278-8835
Internet: <https://carpet-rug.org/>

COMPOSITE PANEL ASSOCIATION (CPA)
19465 Deerfield Avenue, Suite 306
Leesburg, VA 20176
Ph: 703-724-1128
Fax: 703-724-1588
Internet: <https://www.compositepanel.org/>

COMPRESSED GAS ASSOCIATION (CGA)
14501 George Carter Way, Suite 103
Chantilly, VA 20151-1788
Ph: 703-788-2700
Fax: 703-961-1831
E-mail: cga@cganet.com
Internet: <https://www.cganet.com/>

DISTRICT OF COLUMBIA MUNICIPAL REGULATIONS (DCMR)
1350 Pennsylvania Avenue, NW, Suite 419

Washington DC 20004
Ph: 202-727-6306
Fax: 202-727-3582
TTY: 711
E-mail: secretary@dc.gov
Internet: <https://os.dc.gov/service/publication-and-regulatory-services>

GREEN SEAL (GS)
1001 Connecticut Avenue, NW
Suite 827
Washington, DC 20036-5525
Ph: 202-872-6400
Fax: 202-872-4324
E-mail: green SEAL@green SEAL.org
Internet: <https://www.green SEAL.org/>

GYP SUM ASSOCIATION (GA)
962 Wayne Ave., Suite 620
Silver Spring, MD 20910
Ph: 301-277-8686
Fax: 301-277-8747
E-mail: info@gyp sum.org
Internet: <https://www.gyp sum.org/>

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)
445 and 501 Hoes Lane
Piscataway, NJ 08854-4141
Ph: 732-981-0060 or 800-701-4333
Fax: 732-981-9667
E-mail: onlinesupport@ieee.org
Internet: <https://www.ieee.org/>

INTERNATIONAL CODE COUNCIL (ICC)
500 New Jersey Avenue, NW
6th Floor, Washington, DC 20001
Ph: 800-786-4452 or 888-422-7233
Fax: 202-783-2348
E-mail: order@iccsafe.org
Internet: <https://www.iccsafe.org/>

INTERNATIONAL SAFETY EQUIPMENT ASSOCIATION (ISEA)
1901 North Moore Street
Arlington, VA 22209-1762
Ph: 703-525-1695
Fax: 703-528-2148
Internet: <https://safetysafetyequipment.org/>

KITCHEN CABINET MANUFACTURERS ASSOCIATION (KCMA)
1899 Preston White Drive
Reston, VA 20191-5435
Ph: 703-264-1690
Fax: 703-620-6530
E-mail: info@kcma.org
Internet: <https://www.kcma.org/>

MASTER PAINTERS INSTITUTE (MPI)
2800 Ingleton Avenue
Burnaby, BC CANADA V5C 6G7

Ph: 1-888-674-8937
Fax: 1-888-211-8708
E-mail: info@paintinfo.com or techservices@mpi.net
Internet: <http://www.mpi.net/>

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)
1300 North 17th Street, Suite 900
Arlington, VA 22209
Ph: 703-841-3200
Internet: <https://www.nema.org>

NATIONAL FENESTRATION RATING COUNCIL (NFRC)
6305 Ivy Lane, Suite 140
Greenbelt, MD 20770
Ph: 301-589-1776
Fax: 301-589-3884
E-Mail: info@nfrc.org
Internet: <http://www.nfrc.org>

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
1 Batterymarch Park
Quincy, MA 02169-7471
Ph: 800-344-3555
Fax: 800-593-6372
Internet: <https://www.nfpa.org>

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)
6830 Raleigh LaGrange Road
PO Box 34518
Memphis, TN 38184
Ph: 901-377-1818
Internet: <https://nhla.com/>

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH)
Patriots Plaza 1
395 E Street, SW, Suite 9200
Washington, DC 20201
Ph: 800-232-4636
Fax: 513-533-8347
Internet: <https://www.cdc.gov/niosh/>

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)
272 Tuttle Road
Cumberland, ME 04021
Ph: 207-829-6901
Fax: 207-829-4293
E-mail: info@nelma.org
Internet: <https://www.nelma.org/>

REDWOOD INSPECTION SERVICE (RIS) OF THE CALIFORNIA REDWOOD
ASSOCIATION (CRA)
818 Grayson Road, Suite 201
Pleasant Hill, CA 94523
Ph: 925-935-1499
Fax: 925-935-1496
Internet:
<https://www.wvpa.org/about-wvpa/redwood-inspection-service>

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)
2000 Powell Street, Suite 600
Emeryville, CA 94608
Ph: 510-452-8000
Fax: 510-452-8001
E-mail: info@SCSglobalservices.com
Internet: <https://www.scsglobalservices.com/>

SOCIETY FOR PROTECTIVE COATINGS (SSPC)
800 Trumbull Drive
Pittsburgh, PA 15205
Ph: 877-281-7772 or 412-281-2331
Fax: 412-444-3591
E-mail: customerservice@sspc.org
Internet: <http://www.sspc.org>

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)
21865 Copley Drive
Diamond Bar, CA 91765
Ph: 909-396-2000
E-mail: webinquiry@aqmd.gov
Internet: <http://www.aqmd.gov>

SOUTHERN PINE INSPECTION BUREAU (SPIB)
P.O. Box 10915
Pensacola, FL 32524-0915
Ph: 850-434-2611 or 800-995-7742
Fax: 850-434-1290
E-mail: spib@spib.org
Internet: <https://www.spib.org/>

STATE OF MARYLAND CODE OF MARYLAND REGULATIONS (COMAR)
Division of State Documents
16 Francis Street - Wineland Building
Annapolis, MD 21401
Ph: 410-974-2486
Fax: 410-280-5647
E-mail: support@sos.state.md.us
Internet: <http://www.dsd.state.md.us/COMAR/ComarHome.html>

STATE OF VIRGINIA ADMINISTRATIVE CODE (VAC)
900 E. Main Street
Pocahontas Building
Richmond, Virginia 23219
Ph: 804-698-1810
E-mail: codes@dls.virginia.gov
Internet: <http://register.dls.virginia.gov>

STEEL DOOR INSTITUTE (SDI/DOOR)
30200 Detroit Road
Westlake, OH 44145
Ph: 440-899-0010
Fax: 440-892-1404
E-mail: info@steeldoors.org
Internet: <https://www.steeldoors.org/>

TILE COUNCIL OF NORTH AMERICA (TCNA)
100 Clemson Research Boulevard
Anderson, SC 29625
Ph: 864-646-8453
Fax: 864-646-2821
E-mail: info@tileusa.com
Internet: <https://www.tcnatile.com/>

U.S. DEPARTMENT OF DEFENSE (DOD)
Order DOD Documents from:
Room 3A750-The Pentagon
1400 Defense Pentagon
Washington, DC 20301-1400
Ph: 703-571-3343
Fax: 215-697-1462
E-mail: customerservice@ntis.gov
Internet: <https://www.ntis.gov/>
Obtain Military Specifications, Standards and Related Publications
from:
Acquisition Streamlining and Standardization Information System
(ASSIST)
Department of Defense Single Stock Point (DODSSP)
Document Automation and Production Service (DAPS)
Building 4/D
700 Robbins Avenue
Philadelphia, PA 19111-5094
Ph: 215-697-6396 - for account/password issues
Internet: <https://assist.dla.mil/online/start/>; account
registration required
Obtain Unified Facilities Criteria (UFC) from:
Whole Building Design Guide (WBDG)
National Institute of Building Sciences (NIBS)
1090 Vermont Avenue NW, Suite 700
Washington, DC 20005
Ph: 202-289-7800
Fax: 202-289-1092
Internet:
<https://www.wbdg.org/ffc/dod/unified-facilities-criteria-ufc>

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)
1200 Pennsylvania Avenue, N.W.
Washington, DC 20004
Ph: 202-564-4700
Internet: <https://www.epa.gov>
--- Some EPA documents are available only from:
National Technical Information Service (NTIS)
5301 Shawnee Road
Alexandria, VA 22312
Ph: 703-605-6060 or 1-800-363-2068
Fax: 703-605-6880
TDD: 703-487-4639
E-mail: info@ntis.gov
Internet: <https://www.ntis.gov/>

U.S. GENERAL SERVICES ADMINISTRATION (GSA)
General Services Administration
1800 F Street, NW

Washington, DC 20405
Ph: 1-844-472-4111
Internet: <https://www.gsaelibrary.gsa.gov/ElibMain/home.do>
Obtain documents from:
Acquisition Streamlining and Standardization Information System
(ASSIST)
Internet: <https://assist.dla.mil/online/start/>; account
registration required

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)
8601 Adelphi Road
College Park, MD 20740-6001
Ph: 866-272-6272
Internet: <https://www.archives.gov/>
Order documents from:
Superintendent of Documents
U.S. Government Publishing Office (GPO)
732 N. Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800 or 866-512-1800
Bookstore: 202-512-0132
Internet: <https://www.gpo.gov/>

UNDERWRITERS LABORATORIES (UL)
2600 N.W. Lake Road
Camas, WA 98607-8542
Ph: 877-854-3577 or 360-817-5500
E-mail: CustomerExperienceCenter@ul.com
Internet: <https://www.ul.com/>
UL Directories available through IHS at <https://ihsmarkit.com/>

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)
6980 S.W. Varns
Tigard, OR 97223
Ph: 503-639-0651
Fax: 503-684-8928
E-mail: info@wclib.org
Internet: <http://www.wclib.org>

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)
1500 SW First Ave., Suite 870
Portland, OR 97201
Ph: 503-224-3930
E-mail: info@wwpa.org
Internet: <http://www.wwpa.org>

WINDOW AND DOOR MANUFACTURERS ASSOCIATION (WDMA)
2025 M Street, NW, Suite 800
Washington, DC 20036-3309
Ph: 202-367-1157
or
330 N Wabash Avenue, Suite 2000
Chicago, IL 60611
Ph: 312-321-6802
E-mail: membersupport@wdma.com
Internet: <https://www.wdma.com/>

WOODWORK INSTITUTE (WI)
3188 Industrial Blvd.

West Sacramento, CA
95691 Ph:
916-372-9943
Fax: 916-372-9950
E-mail: info@woodinst.com
Internet:

<https://woodworkinstitute.com> PART 2 PRODUCTS

Not used

PART 3 EXECUTION

Not used

-- End of Section --

SECTION 01 74 19

CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
02/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 273	Standards for Universal Waste Management
49 CFR 173	Shippers - General Requirements for Shipments and Packagings
49 CFR 178	Specifications for Packagings

1.2 DEFINITIONS

1.2.1 Co-mingle

The practice of placing unrelated materials together in a single container, usually for benefits of convenience and speed.

1.2.2 Construction Waste

Waste generated by construction activities, such as scrap materials, damaged or spoiled materials, temporary and expendable construction materials, and other waste generated by the workforce during construction activities.

1.2.3 Demolition Debris/Waste

Waste generated from demolition activities, including minor incidental demolition waste materials generated as a result of intentional dismantling of all or portions of a building, to include clearing of building contents that have been destroyed or damaged.

1.2.4 Disposal

Depositing waste in a solid waste disposal facility, usually a managed landfill, regulated in the US under the Resource Conservation and Recovery Act (RCRA).

1.2.5 Diversion

The practice of diverting waste from disposal in a landfill, by means of eliminating or minimizing waste, or reuse of materials.

1.2.6 Final Construction Waste Diversion Report

A written assertion by a material recovery facility operator identifying

constituent materials diverted from disposal, usually including summary tabulations of materials, weight in short-ton.

1.2.7 Recycling

The series of activities, including collection, separation, and processing, by which products or other materials are diverted from the solid waste stream for use in the form of raw materials in the manufacture of new products sold or distributed in commerce, or the reuse of such materials as substitutes for goods made of virgin materials, other than fuel.

1.2.8 Reuse

The use of a product or materials again for the same purpose, in its original form or with little enhancement or change.

1.2.9 Salvage

Usable, salable items derived from buildings undergoing demolition or deconstruction, parts from vehicles, machinery, other equipment, or other components.

1.2.10 Source Separation

The practice of administering and implementing a management strategy to identify and segregate unrelated waste at the first opportunity.

1.3 CONSTRUCTION WASTE (INCLUDES DEMOLITION DEBRIS/WASTE)

Divert a minimum of 60 percent by weight of the project from the landfill. Follow applicable industry standards in the management of waste. Apply sound environmental principles in the management of waste.

(1) Practice efficient waste management when sizing, cutting, and installing products and materials and (2) use all reasonable means to divert construction waste and demolition debris/waste from landfills and incinerators and to facilitate the recycling or reuse of excess construction materials.

1.4 CONSTRUCTION WASTE MANAGEMENT

Implement a construction waste management program for the project. Take a pro-active, responsible role in the management of construction waste, recycling process, disposal of demolition debris/waste, and require all subcontractors, vendors, and suppliers to participate in the construction waste management program. Establish a process for clear tracking, and documentation of construction waste and demolition debris/waste.

1.4.1 Implementation of Construction Waste Management Program

Develop and document how the construction waste management program will be implemented in a construction waste management plan. Submit a Construction Waste Management Plan to the Contracting Officer for approval. Construction waste and demolition debris/waste materials include un-used construction materials not incorporated in the final work, as well as demolition debris/waste materials from demolition activities or deconstruction activities. In the management of waste, consider the availability of viable markets, the condition of materials, the ability to

provide material in suitable condition and in a quantity acceptable to available markets, and time constraints imposed by internal project completion mandates.

1.4.2 Special Programs

Implement any special programs involving rebates or similar incentives related to recycling of. Retain revenue or savings from salvaged or recycling, unless otherwise directed. Ensure firms and facilities used for recycling, reuse, and disposal are permitted for the intended use to the extent required by federal, state, and local regulations.

1.4.3 Special Instructions

Provide on-site instruction of appropriate separation, handling, recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the projects. Designation of single source separating or commingling will be clearly marked on the containers.

1.4.4 Waste Streams

Delineate waste streams and characterization, including estimated material types and quantities of waste, in the construction waste management plan. Manage all waste streams associated with the project. Typical waste streams are listed below, as appropriate. Include additional waste streams not listed:

- a. Land Clearing Debris
- b. Asphalt
- c. Masonry and CMU
- d. Concrete
- e. Metals (e.g. banding, stud trim, ductwork, piping, rebar, roofing, other trim, steel, iron, galvanized, stainless steel, aluminum, copper, zinc, bronze, etc.)
- f. Wood (nails and staples allowed)
- g. Glass
- h. Paper
- i. Plastics (PET, HDPE, PVC, LDPE, PP, PS, Other)
- j. Gypsum
- k. Non-hazardous paint and paint cans
- l. Carpet
- m. Ceiling Tiles
- n. Insulation
- o. Beverage Containers

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Construction Waste Management Plan; G

SD-06 Test Reports

Quarterly Reports

Annual Report

SD-11 Closeout Submittals

Final Construction Waste Diversion Report; S

1.6 MEETINGS

Conduct Construction Waste Management meetings. After award of the Contract and prior to commencement of work, schedule and conduct a meeting with the Contracting Officer to discuss the proposed construction waste management plan and to develop a mutual understanding relative to the management of the construction waste management program and how waste diversion requirements will be met.

At a minimum, discuss and document waste management goals at following meetings:

- a. Preconstruction meeting.
- b. Regular meetings.
- c. Work safety meeting.

1.7 CONSTRUCTION WASTE MANAGEMENT PLAN

Submit Construction Waste Management Plan within 15 days after notice to proceed. Revise and resubmit Construction Waste Management Plan until it receives final approval from the Contracting Officer, in order for construction to begin. Execute demolition or deconstruction activities in accordance with Section 02 41 00 DEMOLITIONANDDECONSTRUCTION. Manage demolition debris/waste or deconstruction materials in accordance with the approved construction waste management plan.

An approved construction waste management plan will not relieve the Contractor of responsibility for compliance with applicable environmental regulations or meeting project cumulative waste diversion requirement. Ensure all subcontractors receive a copy of the approved Construction Waste Management Plan. The plan demonstrates how to meet the project waste diversion requirement. Also, include the following in the plan:

- a. Identify the names of individuals responsible for waste management and waste management tracking, along with roles and responsibilities on the project.
- b. Actions that will be taken to reduce solid waste generation, including coordination with subcontractors to ensure awareness and participation.
- c. Description of the regular meetings to be held to address waste management.
- d. Description of the specific approaches to be used in recycling/reuse of the various materials generated, including the areas on site and equipment to be used for processing, sorting, and temporary storage of materials.

- e. Name of landfill and/or incinerator to be used.
- f. Identification of local and regional re-use programs, including non-profit organizations such as schools, local housing agencies, and organization that accept used materials such as material exchange networks and resale stores. Include the name, location, phone number for each re-use facility identified, and provide a copy of the permit or license for each facility.
- g. List of specific materials, by type and quantity, that will be salvaged for resale, salvaged and reused on the current project, salvaged and stored for reuse on a future project, or recycled. Identify the recycling facilities by name, address, and phone number.
- h. Identification of materials that cannot be recycled or reused with an explanation or justification, to be approved by the Contracting Officer.
- i. Description of the means by which any materials identified in item (g) above will be protected from contamination.
- j. Description of the means of transportation of the recyclable materials (whether materials will be site-separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler and removed from the site).
- k. Copy of training plan for subcontractors and other services to prevent contamination by co-mingling materials identified for diversion and waste materials.
- n. Facilities or subcontractors offering construction waste transport on-site or off-site must ensure that proper shipping orders, bill of lading, manifests, or other shipping documents containing waste diversion information meet requirements of 40 CFR 273 Universal Waste Management, 49 CFR 173 Shippers - General Requirements for Shipments and Packagings, and 49 CFR 178 Specifications for Packaging. Individuals signing manifests or other shipping documents should meet the minimum training requirements.
- o. List each supplier who deliver construction materials, in bulk, or package products in returnable containers or returnable packaging, or have take-back programs. List each program and the applicable material to actively monitor and track to assist in meeting waste diversion requirements on the project.
- p. Identify any local jurisdiction requirements for waste management. Include those requirements, points of contact, etc.

Distribute copies of the waste management plan to each subcontractor, and the Contracting Officer.

1.8 RECORDS (DOCUMENTATION)

1.8.1 General

Maintain records to document the types and quantities of waste generated

and diverted through re-use, recycling and/or sale to third parties; through disposal to a landfill or incinerator facility. Provide explanations for any materials not recycled, reused or sold. Collect and retain manifests, weight tickets, sales receipts, and invoices specifically identifying diverted project waste materials or disposed materials.

1.8.2 Accumulated

Maintain a running record of materials generated and diverted from landfill disposal, including accumulated diversion rates for the project. Make records available to the Contracting Officer during construction or incidental demolition activities. Provide a copy of the diversion records to the Contracting Officer upon completion of the construction, incidental demolitions or minor deconstruction activities.

1.9 FINAL CONSTRUCTION WASTE DIVERSION REPORT

A Final Construction Waste Diversion Report is required at the end of the project. Provide Final Construction Waste Diversion Report 6030 days prior to the Beneficial Occupancy Date (BOD). The final Construction Waste Diversion Report must be included in the Sustainability eNotebook in accordance with Section 01 33 29 SUSTAINABILITY REPORTING.

1.10 COLLECTION

Collect, store, protect, and handle reusable and recyclable materials at the site in a manner which prevents contamination, and provides protection from the elements to preserve their usefulness and monetary value. Provide receptacles and storage areas designated specifically for recyclable and reusable materials and label them clearly and appropriately to prevent contamination from other waste materials. Keep receptacles or storage areas neat and clean.

1.10.1 Source Separation Method

Separate waste products and materials that are recyclable from trash and sort as described below into appropriately marked separate containers and then transport to the respective recycling facility for further processing. Deliver materials in accordance with recycling or reuse facility requirements (e.g., free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process). Separate materials into the category types as defined in the construction waste management plan.

1.10.2 Other Methods

Other methods proposed by the Contractor may be used when approved by the Contracting Officer.

1.11 DISPOSAL

Control accumulation of waste materials and trash. Recycle or dispose of collected materials off-site at intervals approved by the Contracting Officer and in compliance with waste management procedures as described in the waste management plan. Except as otherwise specified in other sections of the specifications, dispose of in accordance with the

following:

1.11.1 Reuse

Give first consideration to reusing construction and demolition materials as a disposition strategy. Recover for reuse materials, products, and components as described in the approved construction waste management plan. Coordinate with the Contracting Officer to identify onsite reuse opportunities or material sales or donation available through Government resale or donation programs. Sale of recovered materials is not allowed on the Installation.

1.11.2 Recycle

Recycle non-hazardous construction and demolition/debris materials that are not suitable for reuse. Track rejection of contaminated recyclable materials by the recycling facility. Rejected recyclables materials will not be counted as a percentage of diversion calculation. Recycle all fluorescent lamps, HID lamps, mercury (Hg) -containing thermostats and ampoules, and PCBs-containing ballasts and electrical components as directed by the Contracting Officer. Do not crush lamps on site as this creates a hazardous waste stream with additional handling requirements.

1.11.3 Waste

Dispose by landfill or incineration only those waste materials with no practical use, economic benefit, or recycling opportunity.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

--End of Section--

SECTION 01 78 00

CLOSEOUT SUBMITTALS

05/19

PART 1 GENERAL

1.1 DEFINITIONS

1.1.1 As-Built Drawings

As-built drawings are the marked-up drawings, maintained by the Contractor on-site, that depict actual conditions and deviations from the Contract Documents. These deviations and additions may result from coordination required by, but not limited to: contract modifications; official responses to submitted Requests for Information (RFI's); direction from the Contracting Officer; design that is the responsibility of the Contractor, and differing site conditions. Maintain the as-builts throughout construction as red-lined hard copies on site. These files serve as the basis for the creation of the record drawings.

1.1.2 Record Drawings

The record drawings are the final compilation of actual conditions reflected in the as-built drawings.

1.2 SOURCE DRAWING FILES

Request the full set of electronic drawings, in the source format, for Record Drawing preparation, after award and at least 30 days prior to required use.

1.2.1 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction data for the referenced project. Any other use or reuse shall be at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim and waives to the fullest extent permitted by law, any claim or cause of action of any nature against the Government, its agents or sub consultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic CAD drawing files are not construction documents. Differences may exist between the CAD files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic CAD files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished Source drawing files, the signed and sealed construction documents govern. The Contractor is responsible for determining if any conflict exists. Use of these Source Drawing files does not relieve the

Contractor of duty to fully comply with the contract documents, including and without limitation, the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction data related to this contract, remove all previous indicia of ownership (seals, logos, signatures, initials and dates).

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Warranty Tags

SD-08 Manufacturer's Instructions

Posted Instructions

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G

SD-11 Closeout Submittals

As-Built Drawings; G

Record Drawings; G

Final Approved Shop Drawings;

1.4 WARRANTY MANAGEMENT

1.4.1 Warranty Management Plan

Develop a warranty management plan which contains information relevant to NFC-246-21 Warranty of Construction. At least 30 days before the planned pre-warranty conference, submit one set of the warranty management plan. Include within the warranty management plan all required actions and documents to assure that the Government receives all warranties to which it is entitled. The plan narrative must contain sufficient detail to render it suitable for use by future maintenance and repair personnel,

whether tradesmen, or of engineering background, not necessarily familiar with this contract. The term "status" as indicated below must include due date and whether item has been submitted or was accomplished. Submit warranty information, made available during the construction phase, to the Contracting Officer for approval prior to each monthly pay estimate. Assemble approved information in a binder and turn over to the Government upon acceptance of the work. The construction warranty period must begin on the date of project acceptance and continue for the full product warranty period. Conduct a joint 4 month and 9 month warranty inspection, measured from time of acceptance; with the Contractor, Contracting Officer and the Customer Representative. The warranty management plan must include, but is not limited to, the following:

- a. Roles and responsibilities of personnel associated with the warranty process, including points of contact and telephone numbers within the organizations of the Contractors, subcontractors, manufacturers or suppliers involved.
- b. For each warranty, the name, address, telephone number, and e-mail of each of the guarantor's representatives nearest to the project location.
- c. A list and status of delivery of Certificates of Warranty for extended warranty items, including roofs, HVAC balancing, pumps, motors, transformers, and for commissioned systems, such as fire protection and alarm systems, sprinkler systems, and lightning protection systems.
- d. As-Built Record of Equipment and Materials list for each warranted equipment, item, feature of construction or system indicating:
 - (1) Name of item.
 - (2) Model and serial numbers.
 - (3) Location where installed.
 - (4) Name and phone numbers of manufacturers or suppliers.
 - (5) Names, addresses and telephone numbers of sources of spare parts.
 - (6) Warranties and terms of warranty. Include one-year overall warranty of construction, including the starting date of warranty of construction. Items which have warranties longer than one year must be indicated with separate warranty expiration dates.
 - (7) Cross-reference to warranty certificates as applicable.
 - (8) Starting point and duration of warranty period.
 - (9) Summary of maintenance procedures required to continue the warranty in force.
 - (10) Cross-reference to specific pertinent Operation and Maintenance manuals.
 - (11) Organization, names and phone numbers of persons to call for warranty service.
 - (12) Typical response time and repair time expected for various warranted equipment.
- e. The plans for attendance at the 4 and 9 month post-construction warranty inspections conducted by the Government.
- f. Procedure and status of tagging of equipment covered by warranties longer than one year.
- g. Copies of instructions to be posted near selected pieces of equipment where operation is critical for warranty or safety reasons.

1.4.2 Performance Bond

The Performance Bond must remain effective throughout the construction and warranty period.

- a. In the event the Contractor fails to commence and diligently pursue any construction warranty work required, the Contracting Officer will have the work performed by others, and after completion of the work, will charge the remaining construction warranty funds of expenses incurred by the Government while performing the work, including, but not limited to administrative expenses.
- b. In the event sufficient funds are not available to cover the construction warranty work performed by the Government at the Contractor's expense, the Contracting Officer will have the right to recoup expenses from the bonding company.
- c. Following oral or written notification of required construction warranty repair work, respond in a timely manner. Written verification will follow oral instructions. Failure to respond will be cause for the Contracting Officer to proceed against the Contractor.

1.4.3 Pre-Warranty Conference

Prior to contract completion, and at a time designated by the Contracting Officer, meet with the Contracting Officer to develop a mutual understanding with respect to the requirements of this section. At this meeting, establish and review communication procedures for Contractor notification of construction warranty defects, priorities with respect to the type of defect, reasonable time required for Contractor response, and other details deemed necessary by the Contracting Officer for the execution of the construction warranty. In connection with these requirements and at the time of the Contractor's quality control completion inspection, furnish the name, telephone number and address of a licensed and bonded company which is authorized to initiate and pursue construction warranty work action on behalf of the Contractor. This point of contact must be located within the local service area of the warranted construction, be continuously available, and be responsive to Government inquiry on warranty work action and status. This requirement does not relieve the Contractor of any of its responsibilities in connection with other portions of this provision.

1.4.4 Warranty Tags

At the time of installation, tag each warranted item with a durable, oil and water resistant tag approved by the Contracting Officer. Attach each tag with a copper wire and spray with a silicone waterproof coating. Also, submit two, one paper one electronic record copies of the warranty tags showing the layout and design. The date of acceptance and the QC signature must remain blank until the project is accepted for beneficial occupancy. Show the following information on the tag.

Type of product/material	
Model number	

Serial number	
Contract number	
Warranty period from/to	
Inspector's signature	
Construction Contractor	
Address	
Telephone number	
Warranty contact	
Address	
Telephone number	
Warranty response time priority code	
WARNING - PROJECT PERSONNEL TO PERFORM ONLY OPERATIONAL MAINTENANCE DURING THE WARRANTY PERIOD.	

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 AS-BUILT DRAWINGS

3.1.1 Markup Guidelines

Make comments and markup the drawings complete without reference to letters, memos, or materials that are not part of the As-Built drawing. Show what was changed, how it was changed, where item(s) were relocated and change related details. These working as-built markup prints must be neat, legible and accurate as follows:

- a. Use base colors of red, green, and blue. Color code for changes as follows:
 - (1) Special (Blue) - Items requiring special information, coordination, or special detailing or detailing notes.
 - (2) Deletions (Red) - Over-strike deleted graphic items (lines), lettering in notes and leaders.
 - (3) Additions (Green) - Added items, lettering in notes and leaders.
- b. Provide a legend if colors other than the "base" colors of red, green, and blue are used.

- c. Add and denote any additional equipment or material facilities, service lines, incorporated under As-Built Revisions if not already shown in legend.
- d. Use frequent written explanations on markup drawings to describe changes. Do not totally rely on graphic means to convey the revision.
- e. Use legible lettering and precise and clear digital values when marking prints. Clarify ambiguities concerning the nature and application of change involved.
- f. Wherever a revision is made, also make changes to related section views, details, legend, profiles, plans and elevation views, schedules, notes and call out designations, and mark accordingly to avoid conflicting data on all other sheets.
- g. For deletions, cross out all features, data and captions that relate to that revision.
- h. For changes on small-scale drawings and in restricted areas, provide large-scale inserts, with leaders to the applicable location.
- i. Indicate one of the following when attaching a print or sketch to a markup print:
 - 1) Add an entire drawing to contract drawings
 - 2) Change the contract drawing to show
 - 3) Provided for reference only to further detail the initial design.
- j. Incorporate all shop and fabrication drawings into the markup drawings.

3.1.2 As-Built Drawings Content

Show on the as-built drawings, but not limited to, the following information:

- a. The actual location, kinds and sizes of all sub-surface utility lines. In order that the location of these lines and appurtenances may be determined in the event the surface openings or indicators become covered over or obscured, show by offset dimensions to two permanently fixed surface features the end of each run including each change in direction on the record drawings. Locate valves, splice boxes and similar appurtenances by dimensioning along the utility run from a reference point. Also record the average depth below the surface of each run.
- b. The location and dimensions of any changes within the building structure.
- c. Layout and schematic drawings of electrical circuits and piping.
- d. Correct grade, elevations, cross section, or alignment of roads, earthwork, structures or utilities if any changes were made from contract plans.
- e. Changes in details of design or additional information obtained from working drawings specified to be prepared or furnished by the Contractor; including but not limited to shop drawings, fabrication,

erection, installation plans and placing details, pipe sizes, insulation material, dimensions of equipment, and foundations.

- f. The topography, invert elevations and grades of drainage installed or affected as part of the project construction.
- g. Changes or Revisions which result from the final inspection.
- h. Where contract drawings or specifications present options, show only the option selected for construction on the working as-built markup drawings.
- i. If borrow material for this project is from sources on Government property, or if Government property is used as a spoil area, furnish a contour map of the final borrow pit/spoil area elevations.
- j. Systems designed or enhanced by the Contractor, such as HVAC controls, fire alarm, fire sprinkler, and irrigation systems.
- k. Changes in location of equipment and architectural features.
- l. Modifications.
- m. Actual location of anchors, construction and control joints, etc., in concrete.
- n. Unusual or uncharted obstructions that are encountered in the contract work area during construction.
- o. Location, extent, thickness, and size of stone protection particularly where it will be normally submerged by water.

3.2 RECORD DRAWINGS

3.3 OPERATION AND MAINTENANCE MANUALS

Provide project operation and maintenance manuals as specified in Section 01 78 23 OPERATION AND MAINTENANCE MANUALS DATA. Provide electronic copies of the Operation and Maintenance Manual files. Submit to the Contracting Officer for approval within 60 calendar days of the Beneficial Occupancy Date (BOD). Update and resubmit files for final approval at BOD.

3.4 CLEANUP

Leave premises "broom clean." Clean interior and exterior glass surfaces exposed to view; remove temporary labels, stains and foreign substances; polish transparent and glossy surfaces; vacuum carpeted and soft surfaces. Clean equipment and fixtures to a sanitary condition. Clean filters of operating equipment. Clean debris from roofs, gutters, downspouts and drainage systems. Sweep paved areas and rake clean landscaped areas. Remove waste and surplus materials, rubbish and construction facilities from the site.

-- End of Section --

SECTION 02 41 00

DEMOLITION AND DECONSTRUCTION

05/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.6 (2006) Safety & Health Program Requirements for Demolition Operations - American National Standard for Construction and Demolition Operations

CARPET AND RUG INSTITUTE (CRI)

CRI 104 (2015) Carpet Installation Standard for Commercial Carpet

CRI 105 (2015) Carpet Installation Standard for Residential Carpet

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 61 National Emission Standards for Hazardous Air Pollutants

1.2 PROJECT DESCRIPTION

1.2.1 Definitions

1.2.1.1 Demolition

Demolition is the process of wrecking or taking out any load-supporting structural member of a facility together with any related handling and disposal operations.

1.2.1.2 Deconstruction

Deconstruction is the process of taking apart a facility with the primary goal of preserving the value of all useful building materials.

1.2.1.3 Demolition Plan

Demolition Plan is the planned steps and processes for managing demolition activities and identifying the required sequencing activities and disposal mechanisms.

1.2.1.4 Deconstruction Plan

Deconstruction Plan is the planned steps and processes for dismantling all or portions of a structure or assembly, to include managing sequencing activities, storage, re-installation activities, salvage and disposal mechanisms.

1.2.2 Demolition/Deconstruction Plan

Prepare a Demolition Plan and submit proposed salvage, demolition, deconstruction, and removal procedures for approval before work is started. Include in the plan procedures for careful removal and disposition of materials specified to be salvaged, coordination with other work in progress a detailed description of methods and equipment to be used for each operation and of the sequence of operations. Coordinate with Waste Management Plan in accordance with Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL. Provide procedures for safe conduct of the work in accordance with EM 385-1-1. Plan shall be approved by Contracting Officer prior to work beginning.

1.2.3 General Requirements

Do not begin demolition or deconstruction until authorization is received from the Contracting Officer. Remove rubbish and debris from the project site; do not allow accumulations inside or outside the building. The work includes demolition, deconstruction, salvage of identified items and materials, and removal of resulting rubbish and debris. Remove rubbish and debris from Government property daily, unless otherwise directed. Store materials that cannot be removed daily in areas specified by the Contracting Officer. In the interest of occupational safety and health, perform the work in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections.

1.3 ITEMS TO REMAIN IN PLACE

Take necessary precautions to avoid damage to existing items to remain in place, to be reused, or to remain the property of the Government. Repair or replace damaged items as approved by the Contracting Officer. Coordinate the work of this section with all other work indicated. Construct and maintain shoring, bracing, and supports as required. Ensure that structural elements are not overloaded. Increase structural supports or add new supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract. Do not overload structural elements. Provide new supports and reinforcement for existing construction weakened by demolition, deconstruction, or removal work. Repairs, reinforcement, or structural replacement require approval by the Contracting Officer prior to performing such work.

1.3.1 Existing Construction Limits and Protection

Do not disturb existing construction beyond the extent indicated or necessary for installation of new construction. Provide temporary shoring and bracing for support of building components to prevent settlement or other movement. Provide protective measures to control accumulation and migration of dust and dirt in all work areas. Remove dust, dirt, and debris from work areas daily.

1.3.2 Weather Protection

For portions of the building to remain, protect building interior and materials and equipment from the weather at all times. Where removal of existing roofing is necessary to accomplish work, have materials and workmen ready to provide adequate and temporary covering of exposed areas.

1.4 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted.

1.5 AVAILABILITY OF WORK AREAS

Areas in which the work is to be accomplished will be available in accordance with the following schedule:

Schedule	
Area	Date
TBD	TBD

1.6 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Demolition Plan; G

Existing Conditions

SD-07 Certificates

Notification; G

SD-11 Closeout Submittals

Receipts

1.7 QUALITY ASSURANCE

Submit timely notification of demolition and renovation projects to Federal, State, regional, and local authorities in accordance with 40 CFR 61, Subpart M. Notify the Contracting Officer in writing 10 working days prior to the commencement of work in accordance with 40 CFR 61, Subpart M. Comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the "Contract Clauses," conform to the safety requirements contained in ASSP A10.6. Comply with the Environmental

Protection Agency requirements specified. Use of explosives will not be permitted.

1.7.1 Dust and Debris Control

Prevent the spread of dust and debris to occupied portions of the building and avoid the creation of a nuisance in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution.

1.8 PROTECTION

1.8.1 Protection of Personnel

Before, during and after the demolition work continuously evaluate the condition of the structure being deconstructed and take immediate action to protect all personnel working in and around the project site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.9 RELOCATIONS

Perform the removal and reinstallation of relocated items as indicated with workmen skilled in the trades involved. Repair or replace items to be relocated which are damaged by the Contractor with new undamaged items as approved by the Contracting Officer.

1.10 EXISTING CONDITIONS

Before beginning any demolition or deconstruction work, survey the site and examine the drawings and specifications to determine the extent of the work. Record existing conditions in the presence of the Contracting Officer showing the condition of structures and other facilities adjacent to areas of alteration or removal. Photographs sized 4 inch will be acceptable as a record of existing conditions. Include in the record the elevation of the top of foundation walls, finish floor elevations, possible conflicting electrical conduits, plumbing lines, alarms systems, the location and extent of existing cracks and other damage and description of surface conditions that exist prior to before starting work. It is the Contractor's responsibility to verify and document all required outages which will be required during the course of work, and to note these outages on the record document. Submit survey results.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 EXISTING FACILITIES TO BE REMOVED

Inspect and evaluate existing structures onsite for reuse. Existing construction scheduled to be removed for reuse shall be disassembled. Dismantled and removed materials are to be separated, set aside, and prepared as specified, and stored or delivered to a collection point for

reuse, remanufacture, recycling, or other disposal, as specified. Materials shall be designated for reuse onsite whenever possible.

3.1.1 Concrete

Saw concrete along straight lines to a depth of a minimum 2 inch. Make each cut in walls perpendicular to the face and in alignment with the cut in the opposite face. Break out the remainder of the concrete provided that the broken area is concealed in the finished work, and the remaining concrete is sound. At locations where the broken face cannot be concealed, grind smooth or saw cut entirely through the concrete.

3.1.3 Miscellaneous Metal

Salvage shop-fabricated items such as access doors and frames, steel gratings, metal ladders, wire mesh partitions, metal railings, metal windows and similar items as whole units. Salvage light-gage and cold-formed metal framing, such as steel studs, steel trusses, metal gutters, roofing and siding, metal toilet partitions, toilet accessories and similar items. Recycle scrap metal as part of demolition and deconstruction operations. Provide separate containers to collect scrap metal and transport to a scrap metal collection or recycling facility, in accordance with the Waste Management Plan.

3.1.4 Carpentry

Salvage for recycling lumber, millwork items, and finished boards, and sort by type and size. Chip or shred and recycle salvaged wood unfit for reuse, except stained, painted, or treated wood. Remove windows, doors, frames, and cabinets, and similar items as whole units, complete with trim and accessories. Do not remove hardware attached to units, except for door closers.

3.1.5 Carpet

Remove existing carpet for reclamation in accordance with manufacturer recommendations and as follows. Remove used carpet in large pieces, roll tightly, and pack neatly in a container. Remove adhesive according to recommendations of the Carpet and Rug Institute (CRI). Adhesive removal solvents shall comply with CRI 104/CRI 105. Recycle removed carpet cushion.

3.1.6 Acoustic Ceiling Tile

Remove, neatly stack, and recycle acoustic ceiling tiles. Recycling may be available with manufacturer. Otherwise, priority shall be given to a local recycling organization. Recycling is not required if the tiles contain or may have been exposed to asbestos material.

3.1.7 Patching

Where removals leave holes and damaged surfaces exposed in the finished work, patch and repair these holes and damaged surfaces to match adjacent finished surfaces, using on-site materials when available. Where new work is to be applied to existing surfaces, perform removals and patching in a manner to produce surfaces suitable for receiving new work. Finished surfaces of patched area shall be flush with the adjacent existing surface and shall match the existing adjacent surface as closely as possible as to

texture and finish. Patching shall be as specified and indicated, and shall include:

- a. Concrete and Masonry: Completely fill holes and depressions, caused by previous physical damage or left as a result of removals in existing masonry walls to remain, with an approved masonry patching material, applied in accordance with the manufacturer's printed instructions.
- b. Where existing partitions have been removed leaving damaged or missing resilient tile flooring, patch to match the existing floor tile.
- c. Patch acoustic lay-in ceiling where partitions have been removed. The transition between the different ceiling heights shall be effected by continuing the higher ceiling level over to the first runner on the lower ceiling and closing the vertical opening with a painted sheet metal strip.

3.1.8 Air Conditioning Equipment

Remove air conditioning, refrigeration, and other equipment containing refrigerants without releasing chlorofluorocarbon refrigerants to the atmosphere in accordance with the Clean Air Act Amendment of 1990. Recover all refrigerants prior to removing air conditioning, refrigeration, and other equipment containing refrigerants and dispose of in accordance with the paragraph entitled "Disposal of Ozone Depleting Substance (ODS)."

3.1.10 Mechanical Equipment and Fixtures

Disconnect mechanical hardware at the nearest connection to existing services to remain, unless otherwise noted. Disconnect mechanical equipment and fixtures at fittings. Remove service valves attached to the unit. Salvage each item of equipment and fixtures as a whole unit; listed, indexed, tagged, and stored. Salvage each unit with its normal operating auxiliary equipment. Transport salvaged equipment and fixtures, including motors and machines, to a designated storage area as directed by the Contracting Officer. Do not remove equipment until approved. Do not offer low-efficiency equipment for reuse.

3.1.10.1 Preparation for Storage

Remove water, dirt, dust, and foreign matter from units; tanks, piping and fixtures shall be drained; interiors, if previously used to store flammable, explosive, or other dangerous liquids, shall be steam cleaned. Seal openings with caps, plates, or plugs. Secure motors attached by flexible connections to the unit. Change lubricating systems with the proper oil or grease.

3.1.10.2 Piping

Disconnect piping at unions, flanges and valves, and fittings as required to reduce the pipe into straight lengths for practical storage. Store salvaged piping according to size and type. If the piping that remains can become pressurized due to upstream valve failure, end caps, blind flanges, or other types of plugs or fittings with a pressure gage and bleed valve shall be attached to the open end of the pipe to ensure positive leak control. Carefully dismantle piping that previously contained gas, gasoline, oil, or other dangerous fluids, with precautions taken to prevent injury to persons

and property. Store piping outdoors until all fumes and residues are removed. Box prefabricated supports, hangers, plates, valves, and specialty items according to size and type. Wrap sprinkler heads individually in plastic bags before boxing. Classify piping not designated for salvage, or not reusable, as scrap metal.

3.1.10.3 Ducts

Classify removed duct work as scrap metal.

3.1.10.4 Fixtures, Motors and Machines

Remove and salvage fixtures, motors and machines associated with plumbing, heating, air conditioning, refrigeration, and other mechanical system installations. Salvage, box and store auxiliary units and accessories with the main motor and machines. Tag salvaged items for identification, storage, and protection from damage. Classify broken, damaged, or otherwise unserviceable units and not caused to be broken, damaged, or otherwise unserviceable as debris to be disposed of by the Contractor.

3.1.11 Electrical Equipment and Fixtures

Salvage motors, motor controllers, and operating and control equipment that are attached to the driven equipment. Salvage wiring systems and components. Box loose items and tag for identification. Disconnect primary, secondary, control, communication, and signal circuits at the point of attachment to their distribution system.

3.1.11.1 Fixtures

Remove and salvage electrical fixtures. Salvage unprotected glassware from the fixture and salvage separately. Salvage incandescent, mercury-vapor, and fluorescent lamps and fluorescent ballasts manufactured prior to 1978, boxed and tagged for identification, and protected from breakage.

3.1.11.2 Electrical Devices

Remove and salvage switches, switchgear, transformers, conductors including wire and nonmetallic sheathed and flexible armored cable, regulators, meters, instruments, plates, circuit breakers, panelboards, outlet boxes, and similar items. Box and tag these items for identification according to type and size.

3.1.11.3 Wiring Ducts or Troughs

Remove and salvage wiring ducts or troughs. Dismantle plug-in ducts and wiring troughs into unit lengths. Remove plug-in or disconnecting devices from the busway and store separately.

3.1.11.4 Conduit and Miscellaneous Items

Salvage conduit except where embedded in concrete or masonry. Consider corroded, bent, or damaged conduit as scrap metal. Sort straight and undamaged lengths of conduit according to size and type. Classify supports, knobs, tubes, cleats, and straps as debris to be removed and disposed.

3.2 DISPOSITION OF MATERIAL

3.2.1 Title to Materials

Except for salvaged items specified in related Sections, and for materials or equipment scheduled for salvage, all materials and equipment removed and not reused or salvaged, shall become the property of the Contractor and shall be removed from Government property. Title to materials resulting from demolition and deconstruction, and materials and equipment to be removed, is vested in the Contractor upon approval by the Contracting Officer of the Contractor's demolition, deconstruction, and removal procedures, and authorization by the Contracting Officer to begin demolition and deconstruction. The Government will not be responsible for the condition or loss of, or damage to, such property after contract award. Showing for sale or selling materials and equipment on site is prohibited.

3.2.2 Reuse of Materials and Equipment

Remove and store materials and equipment listed in the Demolition Plan and other construction documents to be reused or relocated to prevent damage, and reinstall as the work progresses. Coordinate the re-use of materials and equipment with the re-use requirements in accordance with Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL. Capture re-use of materials in the diversion calculations for the project.

3.2.3 Salvaged Materials and Equipment

Remove materials and equipment that are listed Demolition Plan and other construction documents to be removed by the Contractor and that are to remain the property of the Government, and deliver to a storage site, as directed.

- a. Salvage items and material to the maximum extent possible.
- b. Store all materials salvaged for the Contractor as approved by the Contracting Officer and remove from Government property before completion of the contract. Coordinate the salvaged materials with tracking requirements in accordance with Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL. Capture salvaged materials in the diversion calculations for the project.
- c. Remove salvaged items to remain the property of the Government in a manner to prevent damage, and packed or crated to protect the items from damage while in storage or during shipment. Items damaged during removal or storage must be repaired or replaced to match existing items. Properly identify the contents of containers. Deliver the following items reserved as property of the Government to the areas designated.
- d. Remove the following items reserved as property of the using service prior to commencement of work under this contract.
- e. Remove historical items in a manner to prevent damage. Deliver the following historical items to the Government for disposition: Corner stones, contents of corner stones, and document boxes wherever located on the site.

3.3 CLEANUP

Remove debris and rubbish from basement and similar excavations. Remove and transport the debris in a manner that prevents spillage on streets or adjacent areas. Apply local regulations regarding hauling and disposal.

3.4 DISPOSAL OF REMOVED MATERIALS

3.4.1 Regulation of Removed Materials

Dispose of debris, rubbish, scrap, and other nonsalvageable materials resulting from removal operations with all applicable federal, state and local regulations as contractually specified in the Waste Management Plan.

3.4.2 Burning on Government Property

Burning of materials removed from demolished and deconstructed structures will not be permitted on Government property

3.4.3 Removal to Spoil Areas on Government Property

Transport noncombustible materials removed from demolition and deconstruction structures to designated spoil areas on Government property.

3.4.4 Removal from Government Property

Transport waste materials removed from demolished and deconstructed structures, except waste soil, from Government property for legal disposal. Dispose of waste soil as directed.

3.5 REUSE OF SALVAGED ITEMS

Recondition salvaged materials and equipment designated for reuse before installation. Replace items damaged during removal and salvage operations or restore them as necessary to usable condition.

-- End of Section --

SECTION 02 42 51

CARPET REMOVAL AND RECLAMATION

11/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.6 (2006) Safety & Health Program Requirements for Demolition Operations - American National Standard for Construction and Demolition Operations

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 340/1-90/018 (1990) Asbestos/NESHAP Regulated Asbestos Containing Materials Guidance

EPA AP-42 (1995) Compilation of Air Pollution Emission Factors

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 61-SUBPART M National Emission Standard for Asbestos

40 CFR 247 Comprehensive Procurement Guideline for Products Containing Recovered Materials

1.2 SUMMARY

Furnish a contract for used carpet reclamation, including planned procedures for removal and reclamation of used carpet.

Refer to related Section 09 68 00 CARPETING for floor preparation prior to installation of new carpet.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Dust-Control Measures; G

Packing and Transportation Measures; G

Schedule of Carpet Reclamation Activities; G

Carpet Reclamation Agency Records; G

1.4 QUALITY CONTROL

1.4.1 Carpet Reclamation Agency

Provide documentation of being a Carpet America Recovery Efforts (CARE) approved carpet removal contractor (or designated agent firm) providing used carpet recycling under the most current EPA recognized Carpet Reclamation Program, or equivalent from alternate recycling agent.

1.4.2 Carpet Remover Requirements

Submit details for the following:

dust-control measures

packing and transportation measures

1.4.3 Carpet Reclamation Agency Submittal

Submit a copy of carpet reclamation agency records verifying receipt and disposition of used carpet.

1.4.4 Regulatory Requirements

Comply with governing regulations; including, but not limited to:

- a. EPA 340/1-90/018
- b. EPA AP-42
- c. 40 CFR 61-SUBPART M
- d. ASSP A10.6
- e. 40 CFR 247

Comply with hauling and disposal regulations of authorities having jurisdiction. Record and maintain records of all off-site removal of debris and materials.

Provide the following information regarding the removed materials within the schedule of carpet reclamation activities:

- a. Time and Date of Removal.
- b. Type of Material.
- c. Weight and Quantity of Materials.
- d. Final Destination of Materials.

1.4.4.1 Carpet Reclamation Agency and Carpet Remover Certification

Certify in writing that used carpet was removed and recycled in accordance with the current EPA recognized Carpet Reclamation Program. Do not place removed carpet and associated materials in a landfill.

1.5 PROJECT/SITE CONDITIONS

1.5.1 Environmental Requirements

Obtain approval of Owner before performing operations which generate contaminants.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

2.1.1 Carpet Reclamation Agency

The current approved reclamation agency is Carpet America Recovery Effort (CARE).

2.1.2 Carpet Removers

Submit documentation of being a CARE approved carpet removal contractor.

2.2 MATERIALS

2.2.1 Adhesive Removal Solvents

Comply with Carpet and Rug Institute Publication 104.

2.2.2 Used Carpet

Maintain possession of removed used carpet. Immediately remove from site and place in container or trailer.

Carefully remove, store, and protect designated materials and equipment for re-installation under other Sections or for retention by Owner.

2.2.3 Carpet Pad

Provide recycling of carpet padding where locally available or as designated by Carpet Reclamation Agency.

PART 3 EXECUTION

3.1 EXAMINATION

3.1.1 Verification of Conditions

Examine areas and conditions under which work is to be performed. Identify conditions detrimental to proper or timely completion. Do not proceed until unsatisfactory conditions have been corrected.

3.2 PREPARATION

Provide, erect, and maintain barricades, lighting, and guardrails as required to protect general public, workers, and adjoining property.

Vacuum used carpet before removal.

3.3 APPLICATION

3.3.1 Carpet Removal

Remove used carpets in large pieces, roll tightly, and pack neatly in container. Include carpet scrap and waste from new installation.

Deposit only clean, dry carpet in containers. "Clean" is defined as free from demolition debris, asbestos contamination, garbage, and tack strips.

Remove adhesive according to recommendations of the Carpet and Rug Institute (CRI).

3.3.2 Container Disposal

Place used carpet in fully-enclosed, front end loading 40-yard container supplied by Carpet Reclamation Agency or as appropriate. Place only used commercial carpeting in collection container. Keep container locked or supervised.

Use effective packing techniques to maximize the amount of material in the container. On average, a container holds 2,000-3,000 square yards. Neatly stack carpet tiles or repack in cardboard boxes before placing in container.

When container is full, contact Carpet Reclamation Agency to coordinate pickup and drop-off of replacement container. If container is locked for security purposes, remove lock before pickup.

3.3.3 Truck Trailer Disposal

Place used carpet in a 53 foot trailer supplied by Carpet Reclamation Agency. Place only used commercial carpeting in trailer. Keep trailer locked or supervised.

Use effective packing techniques to maximize the amount of material in the trailer. Comply with Department of Transportation regulations for weight limits. Typical maximum weight of used carpet on trailers is 45,000 pounds.

Neatly stack carpet tiles or repack in cardboard boxes before placing in trailer. Do not stack higher than 6 feet. When trailer is full, contact Carpet Reclamation Agency to coordinate pickup and drop-off of replacement trailer. If trailer is locked for security purposes, remove lock before pickup.

3.3.4 Interior Operations

Seal doors and other openings with duct tape at heads, jambs, and sills to contain contaminants from work which occurs within a single room.

Use window exhaust systems to establish negative pressure in contaminant-producing work areas, ensuring continuous flow of air into work area.

Do not open windows in work area except when an exhaust fan is used. Close windows at end of each work shift. Seal exhaust system ductwork which might leak into building or mechanical systems.

Damp mop hard surface floors in work area daily to minimize tracking of contaminants from work area. In carpeted areas, protect carpet with plastic and plywood. Provide hard-surfaced area at entrances for daily damp mopping.

-- End of Section --

SECTION 02 84 16

HANDLING OF LIGHTING BALLASTS AND LAMPS CONTAINING PCBs AND MERCURY

04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

DISTRICT OF COLUMBIA MUNICIPAL REGULATIONS (DCMR)

20 DCMR (2007) Environment - Chapters 42 and 43,
Hazardous Waste Management

STATE OF MARYLAND CODE OF MARYLAND REGULATIONS (COMAR)

COMAR 26.13 Chapters .01- .13, Disposal of Controlled
Hazardous Substances

STATE OF VIRGINIA ADMINISTRATIVE CODE (VAC)

9 VAC 20-60 Title 9, Agency 20, Chapter 60: Virginia
Hazardous Waste Management Regulations

9 VAC 20-80 Title 9, Agency 20, Chapter 80: Solid Waste
Management Regulations

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1000 Air Contaminants

40 CFR 260 Hazardous Waste Management System: General

40 CFR 261 Identification and Listing of Hazardous Waste

40 CFR 262 Standards Applicable to Generators of
Hazardous Waste

40 CFR 263 Standards Applicable to Transporters of
Hazardous Waste

40 CFR 264 Standards for Owners and Operators of
Hazardous Waste Treatment, Storage, and
Disposal Facilities

40 CFR 265 Interim Status Standards for Owners and
Operators of Hazardous Waste Treatment,
Storage, and Disposal Facilities

40 CFR 268 Land Disposal Restrictions

40 CFR 270	EPA Administered Permit Programs: The Hazardous Waste Permit Program
40 CFR 273	Standards for Universal Waste Management
40 CFR 761	Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions
49 CFR 178	Specifications for Packagings

1.2 REQUIREMENTS

Removal and disposal of PCB containing lighting ballasts and associated mercury-containing lamps. Contractor may encounter leaking PCB ballasts.

1.3 DEFINITIONS

1.3.1 Certified Industrial Hygienist (CIH)

An industrial hygienist hired by the contractor shall be certified by the American Board of Industrial Hygiene.

1.3.2 Leak

Leak or leaking means any instance in which a PCB article, PCB container, or PCB equipment has any PCBs on any portion of its external surface.

1.3.3 Lamps

Lamp, also referred to as "universal waste lamp", is defined as the bulb or tube portion of an electric lighting device. A lamp is specifically designed to produce radiant energy, most often in the ultraviolet, visible, and infra-red regions of the electromagnetic spectrum. Examples of common universal waste electric lamps include, but are not limited to, fluorescent, high intensity discharge, neon, mercury vapor, high pressure sodium, and metal halide lamps.

1.3.4 Polychlorinated Biphenyls (PCBs)

PCBs as used in this specification shall mean the same as PCBs, PCB containing lighting ballast, and PCB container, as defined in 40 CFR 761, Section 3, Definitions.

1.3.5 Spill

Spill means both intentional and unintentional spills, leaks, and other uncontrolled discharges when the release results in any quantity of PCBs running off or about to run off the external surface of the equipment or other PCB source, as well as the contamination resulting from those releases.

1.3.6 Universal Waste

Universal Waste means any of the following hazardous wastes that are managed under the universal waste requirements 40 CFR 273:

- (1) Batteries as described in Sec. 273.2 of this chapter;

- (2) Pesticides as described in Sec. 273.3 of this chapter;
- (3) Thermostats as described in Sec. 273.4 of this chapter; and
- (4) Lamps as described in Sec. 273.5 of this chapter.

1.4 QUALITY ASSURANCE

1.4.1 Regulatory Requirements

Perform PCB related work in accordance with 40 CFR 761 Perform mercury-containing lamps storage and transport in accordance with 40 CFR 261, 40 CFR 264, 40 CFR 265, 40 CFR 273.

1.4.2 Training

Certified industrial hygienist (CIH) shall instruct and certify the training of all persons involved in the removal of PCB containing lighting ballasts and mercury-containing lamps. The instruction shall include: The dangers of PCB and mercury exposure, decontamination, safe work practices, and applicable OSHA and EPA regulations. The CIH shall review and approve the PCB and Mercury-Containing Lamp Removal Work Plans.

1.4.3 Regulation Documents

Maintain at all times one copy each at the office and one copy each in view at the job site of 29 CFR 1910.1000, 40 CFR 260, 40 CFR 261, 40 CFR 262, 40 CFR 263, 40 CFR 265, 40 CFR 268, 40 CFR 270, 40 CFR 273 and of the Contractor removal work plan and disposal plan for PCB and for associated mercury-containing lamps.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-07 Certificates

Qualifications of CIH; G

PCB and Lamp Removal Work Plan; G

PCB and Lamp Disposal Plan; G

SD-11 Closeout Submittals

Certificate of Disposal and/or recycling. Submit to the Government before application for payment within 30 days of the date that the disposal of the PCB and mercury-containing lamp waste identified on the manifest was completed.

DD Form 1348-1

1.6 ENVIRONMENTAL REQUIREMENTS

Use special clothing:

- a. Disposable gloves (polyethylene)
- b. Eye protection
- c. PPE as required by CIH

1.7 SCHEDULING

Notify the Contracting Officer 20 days prior to the start of PCB and mercury-containing lamp removal work.

1.8 QUALITY ASSURANCE

1.8.1 Qualifications of CIH

Submit the name, address, and telephone number of the Industrial Hygienist selected to perform the duties in paragraph entitled "Certified Industrial Hygienist." Submit training certification that the Industrial Hygienist is certified, including certification number and date of certification or re certification.

1.8.2 PCB and Lamp Removal Work Plan

Submit a job-specific plan within 20 calendar days after award of contract of the work procedures to be used in the removal, packaging, and storage of PCB-containing lighting ballasts and associated mercury-containing lamps. Include in the plan: Requirements for Personal Protective Equipment (PPE), spill cleanup procedures and equipment, eating, smoking and restroom procedures. The plan shall be approved and signed by the Certified Industrial Hygienist. Obtain approval of the plan by the Contracting Officer prior to the start of PCB and/or lamp removal work.

1.8.3 PCB and Lamp Disposal Plan

Submit a PCB and lamp Disposal Plan with 45 calendar days after award of contract. The PCB and Lamp Disposal Plan shall comply with applicable requirements of federal, state, and local PCB and Universal waste regulations and address:

- a. Estimated quantities of wastes to be generated, disposed of, and recycled.
- b. Names and qualifications of each Contractor that will be transporting, storing, treating, and disposing of the wastes. Include the facility location. Furnish two copies of EPA and state PCB and mercury-containing lamp waste permit applications and EPA identification numbers, as required.
- c. Names and qualifications (experience and training) of personnel who will be working on-site with PCB and mercury-containing lamp wastes.
- d. Spill prevention, containment, and cleanup contingency measures to be implemented.

- e. Work plan and schedule for PCB and mercury-containing lamp waste removal, containment, storage, transportation, disposal and or recycling. Wastes shall be cleaned up and containerize daily.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 WORK PROCEDURE

Furnish labor, materials, services, and equipment necessary for the removal of PCB containing lighting ballasts, associated mercury-containing fluorescent lamps, in accordance with local, state, or federal regulations. Do not expose PCBs to open flames or other high temperature sources since toxic decomposition by-products may be produced. Do not break mercury containing fluorescent lamps or high intensity discharge lamps.

3.1.1 Work Operations

Ensure that work operations or processes involving PCB or PCB-contaminated materials are conducted in accordance with 40 CFR 761, 40 CFR 262 40 CFR 263, and the applicable requirements of this section, including but not limited to:

- a. Obtaining suitable PCB and mercury-containing lamp storage sites.
- b. Notifying Contracting Officer prior to commencing the operation.
- c. Reporting leaks and spills to the Contracting Officer.
- d. Cleaning up spills.
- e. Inspecting PCB and PCB-contaminated items and waste containers for leaks and forwarding copies of inspection reports to the Contracting Officer.
- f. Maintaining inspection, inventory and spill records.

3.2 PCB SPILL CLEANUP REQUIREMENTS

3.2.1 PCB Spills

Immediately report to the Contracting Officer any PCB spills.

3.2.2 PCB Spill Control Area

Rope off an area around the edges of a PCB leak or spill and post a "PCB Spill Authorized Personnel Only" caution sign. Immediately transfer leaking items to a drip pan or other container.

3.2.3 PCB Spill Cleanup

40 CFR 761, subpart G. Initiate cleanup of spills as soon as possible, but no later than 24 hours of its discovery. Mop up the liquid with rags or

other conventional absorbent. The spent absorbent shall be properly contained and disposed of as solid PCB waste.

3.2.4 Records and Certification

Document the cleanup with records of decontamination in accordance with 40 CFR 761, Section 125, Requirements for PCB Spill Cleanup. Provide test results of cleanup and certification of decontamination.

3.3 REMOVAL

3.3.1 Ballasts

As ballast are removed from the lighting fixture, inspect label on ballast. Ballasts without a "No PCB" label shall be assumed to contain PCBs and containerized and disposed of as required under paragraphs STORAGE FOR DISPOSAL and DISPOSAL. If there are less than 1600 "No PCB" labeled lighting ballasts dispose of them as normal demolition debris.

3.3.2 Lighting Lamps

Remove lighting tubes/lamps from the lighting fixture and carefully place (unbroken) into appropriate containers (original transport boxes or equivalent). In the event of a lighting tube/lamp breaking, sweep and place waste in double plastic taped bags and dispose of as universal waste as specified herein.

3.4 STORAGE FOR DISPOSAL

3.4.1 Storage Containers for PCBs

49 CFR 178. Store PCB in containers approved by DOT for PCB.

3.4.2 Storage Containers for lamps

Store mercury containing lamps in appropriate DOT containers. The boxes shall be stored and labeled for transport in accordance with 40 CFR 273.

3.4.3 Labeling of Waste Containers

Label with the following:

- a. Date the item was placed in storage and the name of the cognizant activity/building.
- b. "Caution Contains PCB," conforming to 40 CFR 761, CFR Subpart C. Affix labels to PCB waste containers.
- c. Label mercury-containing lamp waste in accordance with 40 CFR 273. Affix labels to all lighting waste containers.

3.5 DISPOSAL

Dispose of off Government property in accordance with EPA, DOT, and local regulations at a permitted site.

3.5.1 Identification Number

Federal regulations 40 CFR 761, and 40 CFR 263 require that generators, transporters, commercial storers, and disposers of PCB waste possess U.S. EPA identification numbers. The contractor shall verify that the activity has a U.S. EPA generator identification number for use on the Uniform Hazardous Waste manifest. If not, the contractor shall advise the activity that it must file and obtain an I.D. number with EPA prior to commencement of removal work. For mercury containing lamp removal, Federal regulations 40 CFR 273 require that large quantity handlers of Universal waste (LQHUW) must provide notification of universal waste management to the appropriate EPA Region (or state director in authorized states), obtain an EPA identification number, and retain for three years records of off-site shipments of universal waste. The contractor shall verify that the activity has a U.S. EPA generator identification number for use on the Universal Waste manifest. If not, the contractor shall advise the activity that it must file and obtain an I.D. number with EPA prior to commencement of removal work.

3.5.2 Transporter Certification

Comply with disposal and transportation requirements outlined in 40 CFR 761 and 40 CFR 263. Before transporting the PCB waste, sign and date the manifest acknowledging acceptance of the PCB waste from the Government. Return a signed copy to the Government before leaving the job site. Ensure that the manifest accompanies the PCB waste at all times. Submit transporter certification of notification to EPA of their PCB waste activities (EPA Form 7710-53).

3.5.2.1 Certificate of Disposal and/or Recycling

40 CFR 761. Certificate for the PCBs and PCB items disposed shall include:

- a. The identity of the disposal and or recycling facility, by name, address, and EPA identification number.
- b. The identity of the PCB waste affected by the Certificate of Disposal including reference to the manifest number for the shipment.
- c. A statement certifying the fact of disposal and or recycling of the identified PCB waste, including the date(s) of disposal, and identifying the disposal process used.
- d. A certification as defined in 40 CFR 761.

3.5.3 Disposal by the Government

Comply with disposal and transportation requirements outlined in 40 CFR 761 and 40 CFR 263. Load and haul PCBs to the storage site. If the primary site is filled to capacity, contact the Contracting Officer.

3.5.3.1 Delivery

Contact DRMO at least 5 working days in advance to make arrangements for delivery of PCB to the storage site.

3.5.3.2 DD Form 1348-1

Prepare DD Form 1348-1 Turn-in Document (TID), which will accompany the PCB to the storage site. Ensure that a responsible person from the activity that owns the PCB signs the DD Form 1348-1.

-- End of Section --

SECTION 03 37 13

SHOTCRETE
02/18

PART 1 GENERAL

1.1 SCOPE

1.1.1 Work Specified

This Specification covers the requirements for shotcrete as specified by the Contracting Officer. Included are the requirements for materials; proportioning; and application of structural wet-mixture shotcrete.

1.1.2 Unit of Measure

Unit of measure: cubic yard.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 117	(2010; Errata 2011) Specifications for Tolerances for Concrete Construction and Materials and Commentary
ACI 301	(2016) Specifications for Structural Concrete

ASTM INTERNATIONAL (ASTM)

ASTM C33/C33M	(2018) Standard Specification for Concrete Aggregates
ASTM C94/C94M	(2018) Standard Specification for Ready-Mixed Concrete
ASTM C127	(2015) Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Coarse Aggregate
ASTM C128	(2015) Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Fine Aggregate
ASTM C150/C150M	(2018) Standard Specification for Portland Cement
ASTM C171	(2016) Standard Specification for Sheet Materials for Curing Concrete

ASTM C231/C231M	(2017a) Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C309	(2011) Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C494/C494M	(2017) Standard Specification for Chemical Admixtures for Concrete
ASTM C618	(2019) Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C642	(2013) Density, Absorption, and Voids in Hardened Concrete
ASTM C685/C685M	(2017) Standard Specification for Concrete Made by Volumetric Batching and Continuous Mixing
ASTM C928/C928M	(2013) Packaged, Dry, Rapid-Hardening Cementitious Materials for Concrete Repairs
ASTM C1059/C1059M	(2013) Standard Specification for Latex Agents for Bonding Fresh to Hardened Concrete
ASTM C1064/C1064M	(2017) Standard Test Method for Temperature of Freshly Mixed Hydraulic-Cement Concrete
ASTM C1116/C1116M	(2010a; R 2015) Standard Specification for Fiber-Reinforced Concrete
ASTM C1140/C1140M	(2011) Standard Practice for Preparing and Testing Specimens from Shotcrete Test Panels
ASTM C1141/C1141M	(2015) Standard Specification for Admixtures for Shotcrete
ASTM C1293	(2008; R 2015) Standard Test Method for Determination of Length Change of Concrete Due to Alkali-Silica Reaction
ASTM C1315	(2011) Standard Specification for Liquid Membrane-Forming Compounds Having Special Properties for Curing and Sealing Concrete
ASTM C1385/C1385M	(2010; R 2017) Standard Practice for Sampling Materials for Shotcrete
ASTM C1436	(2013) Standard Specification for Materials for Shotcrete
ASTM C1480/C1480M	(2007; R 2012) Standard Specification for Packaged, Pre-Blended, Dry, Combined

Materials for Use in Wet or Dry Shotcrete Application

ASTM C1567	(2013) Standard Test Method for Potential Alkali-Silica Reactivity of Combinations of Cementitious Materials and Aggregate (Accelerated Mortar-Bar Method)
ASTM C1583/C1583M	(2013) Standard Test Method for Tensile Strength of Concrete Surfaces and the Bond Strength or Tensile Strength of Concrete Repair and Overlay Materials by Direct Tension (Pull-off Method)
ASTM C1602/C1602M	(2018) Standard Specification for Mixing Water Used in Production of Hydraulic Cement Concrete
ASTM C1604/C1604M	(2005; R 2012) Standard Test Method for Obtaining and Testing Drilled Cores of Shotcrete
ASTM C1778	(2016) Standard Guide for Reducing the Risk of Deleterious Alkali-Aggregate Reaction in Concrete

1.3 DEFINITIONS

1.3.1 Accepted

Determined to be satisfactory by the Contracting Officer.

1.3.2 Contractor

The person, firm, or corporation with whom the Contracting Officer enters into an agreement for construction of the Work.

1.3.3 Fiber-reinforced shotcrete (FRS)

Shotcrete containing discontinuous discrete fibers.

1.3.4 Gun finish

Undisturbed final layer of shotcrete as applied from a nozzle without further finishing.

1.3.5 Overspray

Waste shotcrete material deposited away from intended receiving surface.

1.3.6 Permitted

Accepted by or acceptable to the Contracting Officer; usually pertains to a request by Contractor, or when specified in contract documents.

1.3.7 Predampening

In the dry-mixture process, adding water to the aggregate before mixing to bring its moisture content to a specified amount, usually 3 to 6 percent.

1.3.8 Rod finish

A sharp-edged cutting screed to be used to trim shotcrete forms or ground wires.

1.3.9 Shotcrete

Concrete or mortar conveyed through a hose and pneumatically projected at high velocity onto a surface to achieve compaction.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-06 Test Reports

Testing During Construction; G
Aggregate
Water
Mixture Proportions; G

Resistance To Alkali-Silica Reaction

SD-07 Certificates

Qualifications; G
Cement
Supplementary Cementitious Materials
Admixtures; G
Reinforcement
Curing Materials
Testing Agency; G

1.5 QUALIFICATIONS

Submit qualifications and experience of the proposed workers including the supervisor, nozzle men, and crew. For structural or FRS shotcrete, submit evidence of ACI certification of nozzle men proposed for the Work.

1.5.1 Structural Concrete

Submit proof of experience for the Contractor and the shotcrete crew foreman to include at least five projects of similar size and complexity. Proof shall include a description of previous project's size, density of reinforcing materials, and volume of shotcrete placed.

1.5.2 Nonstructural Concrete

Submit proof that the Contractor and crew foreman have at least 3 years' experience in that type of shotcrete application.

1.6 PRECONSTRUCTION TESTING

1.6.1 General Requirements

- a. Testing of materials required as part of the preconstruction program shall be conducted by the Contractor's testing agency. Agency selection shall be acceptable to the Contracting Officer.
- b. Notify the Contracting Officer of the time and place of preconstruction testing and provide the Contracting Officer with copies of testing reports.
- c. Construct preconstruction test panels for examination by the Contracting Officer prior to project shotcrete placement. Preparation and testing shall comply with ASTM C1140/C1140M. Mixture proportions shall meet the requirements of the paragraph titled "MIXTURE PROPORTIONS".
- d. Construct test panels for each proposed shotcrete mixture, each anticipated shooting orientation, and each proposed nozzleman.
- e. Testing required as part of the preconstruction test program shall be provided by the Contractor's testing agency.
- f. Test specimens cored or sawed from the panels for compliance with the specified compressive strength in accordance with ASTM C1604/C1604M.
- h. Prepare additional panels with the specified reinforcement. Core panels in accordance with ASTM C1140/C1140M. Cores containing reinforcement shall be provided to the Contracting Officer for visual examination to determine acceptance. Cores for examination shall have a minimum diameter of 3.75 in. and be the full thickness of the panel.
- i. If the initial prequalification test panel is rejected, a second panel may be shot and tested. If this panel is acceptable, Work may proceed. If the second panel is not acceptable, the Contractor shall change procedures, mixture proportions, nozzle men, or shotcrete equipment as necessary before repeating the preconstruction testing. Do not proceed with Work until preconstruction test results are satisfactory to Contracting Officer.

1.6.2 Preplacement Verification

- a. The forms shall be to line and grade and have adequate support to remain rigid during shooting.
- b. The formwork, substrata preparation, and cleanliness shall be the same as specified herein.
- c. The reinforcement type, size, grade, amount, placement, cleanliness, and other requirements shall be the same as specified on drawings.

- d. The placement of and clearance around reinforcement shall permit complete encasement of reinforcement with shotcrete.
- e. The mixture proportions shall be the same as the approved submittal.

1.7 TESTING DURING CONSTRUCTION

1.7.1 Quality Assurance

Provide submittals for the "Quality Control Plan", "Quality Control Personnel Certifications", and Laboratory Qualifications for Concrete Qualification Testing per section 03 30 00 CAST-IN-PLACE CONCRETE.

1.7.2 Testing Shotcrete

- a. Compressive strength samples: Obtain test specimens from job-site test panels. Use in-place shotcrete test specimens.
- b. Test samples: Sample shotcrete in accordance with ASTM C1385/C1385M. The Contractor is responsible for the curing and protection of test panels on site prior to the time that they are transported to the testing agency's laboratory.
- d. Air content of mixture: For wet-mixture shotcrete test air content at discharge from the truck chute in accordance with ASTM C231/C231M prior to placement.
- e. Temperature of shotcrete mixture: Determine the temperature of the mixture using material sampled prior to discharge from the truck chute into the pump for wet-mixture shotcrete or the shotcrete machine for dry-mix shotcrete. Testing shall be completed in accordance with ASTM C1064/C1064M.

1.7.3 Testing Shotcrete Bond to Substrate

Conduct bond testing of the shotcrete to the substrate in accordance with ASTM C1583/C1583M.

1.7.4 Reporting of Quality Assurance Test Results

Provide copies of any test results generated for quality assurance to the Contractor, Contracting Officer, and concrete supplier.

1.7.5 Action required for shotcrete defects

Submit repair of shotcrete procedures for defects for the Contracting Officer's acceptance. Refer to the paragraph titled "REPAIR OF SHOTCRETE" for details.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Cement

Cement shall comply with ASTM C150/C150M Type I.
Submit cement test reports showing manufacturing location, and compliance with applicable ASTM standards.

2.1.2 Supplementary cementitious materials

Supplementary cementitious materials (SCMs) shall comply with ASTM C618 for fly ash and natural pozzolans
The types and dosages of supplementary cementing material shall meet ACI 301 requirements.

Submit supplementary cementitious material types, test reports showing manufacturing location, and compliance with applicable ASTM standards.

2.1.3 Aggregate

Aggregates shall comply with ASTM C33/C33M for normal weight aggregates. The combined aggregate gradation shall comply with grading No. 2 of ASTM C1436.

Submit aggregate absorption in accordance with ASTM C127 for coarse aggregate and ASTM C128 for fine aggregate.

2.1.4 Water

Water shall be potable or non-potable and comply with ASTM C1602/C1602M requirements. Wash water shall not be permitted unless accepted by Contracting Officer.

For non-potable water, submit the source and reports confirming compliance with ASTM C1602/C1602M to officer.

2.1.5 Admixtures

Admixtures shall comply with ASTM C1141/C1141M or, for hydration control admixtures, with ASTM C494/C494M.

Submit admixture types, brand names, producers, manufacturer's technical data sheets describing technical properties and performance in shotcrete and showing compatibility with each other and the project cementitious materials.

2.1.6 Reinforcement

Follow the requirements included in the contract documents 03 30 00 CAST-IN-PLACE CONCRETE for non-fiber types of reinforcement.

Submit mill certificate showing conformance for reinforcing steel or welded wire reinforcement.

2.1.7 Curing materials

2.1.7.1 Sheet materials

Sheet materials for curing shall comply with ASTM C171.

2.1.7.2 Curing compounds

Curing compounds shall comply with ASTM C309 or ASTM C1315. Volatile organic compounds (VOC) content shall be in compliance with local air quality standards if those requirements are more stringent.

2.1.7.3 Architectural finishes

Do not use curing materials that cause stains for shotcrete having an architectural finish.

2.1.8 Packaged Shotcrete Materials

Packaged, preblended, dry combined materials shall comply with ASTM C1480/C1480M.

2.2 SHOTCRETE PROPERTIES

2.2.1 Compressive strength

The compressive strength required shall be 4000 psi.

2.2.2 Water-cementitious ratio

The maximum w/cm based on project service conditions shall be .5.

2.2.3 Air content

The percent air content of concrete shall be 6.5% plus or minus ($\pm$) 1.0 percent.

2.2.4 Voids and absorption properties

The voids and absorption properties shall be measured using ASTM C642 and shall not exceed 1/2".

2.2.5 Resistance to alkali-silica reaction

Use one of the three options below for qualifying concrete mixtures to reduce the potential of alkali-silica reaction.

- b. For each aggregate used in concrete, the expansion result of the aggregate and cementitious materials combination determined in accordance with ASTM C1567 shall not exceed 0.10 percent at an age of 16 days.
- c. Alkali content in concrete shall not exceed 4 pounds per cubic yard for moderately reactive aggregate or 3 pounds per cubic yard for highly reactive aggregate. Reactivity shall be determined by testing in accordance with ASTM C1293 and categorized in accordance with ASTM C1778.

2.3 MIXTURE PROPORTIONS

Proportion shotcrete mixture by mass complying with ASTM C94/C94M by volume complying with ASTM C685/C685M, to satisfy the specified properties. For FRS, proportion in compliance with ASTM C1116/C1116M. Submit shotcrete mixture proportions. Submittals shall show constituent proportions by mass in the case of batching by weight or proportions by volume in the case of volumetric batching. For prepackaged materials meeting ASTM C1480/C1480M, submit suppliers' technical data showing compliance with requirements. Submit water-cementitious materials ratio (w/cm) for wet-mixture shotcrete only.

2.4 BATCHING, MIXING, AND DELIVERY

Batch, mix, and deliver wet-mixture shotcrete in accordance with ASTM C94/C94M, ASTM C685/C685M, or ASTM C1116/C1116M as applicable. For dry-mixture, batching, mixing and delivering shall be in accordance with ASTM C685/C685M or ASTM C1116/C1116M. Predampening or other methods suitable for prewetting the dry materials shall be used with packaged preblended material for dry-mixture shotcrete.

PART 3 EXECUTION

3.1 PREPARATION OF SURFACE TO RECEIVE SHOTCRETE

3.1.1 Earth

Surfaces shall be prepared to line and grade. Dampen surfaces immediately prior to shooting. No standing water shall be visible.

3.1.2 Concrete, masonry, and shotcrete

Remove all deteriorated, loose, unsound material or contaminants that will inhibit bonding. Receiving surface shall be dampened and allowed to dry to a saturated surface-dry (SSD) condition just prior to shotcrete application. Further surface preparations include:

- a. Chipping surfaces to receive shotcrete to remove offsets causing abrupt changes in thickness.
- b. Roughening receiving surfaces that have been saw cut.

3.1.3 Rock

Remove loose material, mud, or other foreign material that will inhibit bonding. Clean surface prior to shotcrete placement. Dampen surface in accordance with the paragraph titled "Earth".

3.1.4 Reinforcement

3.1.4.1 Surface condition

The surface of the reinforcement shall be free of overspray or other deleterious materials that inhibit development of bond with the shotcrete.

3.1.4.2 Reinforcement laps

Laps shall be noncontact and shall be separated with a clearance of at least three times the diameter of the largest reinforcing bar; three times the maximum size aggregate; or 2 in., whichever is least. Bars spliced by noncontact lap splices in flexural members shall not be spaced transversely farther apart than the smaller of 1/5 the required lap splice length and 6 in. The use of contact lap splices necessary for support of the reinforcing is permitted when approved by the Contracting Officer. Lapped bars shall be in the same plane and parallel to the direction of shooting. Welded splices are permitted.

Secure reinforcement to prevent movement. The use of mechanical splices is permitted when approved.

3.1.5 Forms

Use material of adequate thickness for formwork to resist movement during shooting. Reinforce, secure, and brace forms to minimize the effects of vibration during shooting. Construct forms to allow escape of placement air, overspray, and rebound. Use form-release coating material on removable forms unless the formed surface is to subsequently receive an additional coating.

3.2 JOINTS

3.2.1 Construction joints

Taper construction joints at approximately 45 degrees from receiving surface. Form joints by cutting plastic shotcrete. Joints at slab intersections shall be made at 90 degrees. Roughen shotcrete in the joint face while it is still plastic.

3.2.2 Control joints

Place control joints as indicated in the Contract Document Discontinue reinforcement at control joints.

3.3 ALIGNMENT CONTROL

To establish thickness and plane of required surface, install taut ground wires or other means to guide the nozzleman. Install alignment control means at corners or offsets not established by forms.

3.4 APPLICATION

3.4.1 Placement techniques

- a. Use the same shotcrete mixture and equipment that was used during prequalification testing for the production shotcrete.
- b. Use temporary coverings to protect adjacent surfaces from the deposit of overspray or impact from the nozzle stream.
- c. Install sufficient lighting and ventilation to provide the shotcrete crew with a clear view of the shooting area. Suspend Work and adopt corrective measures if visibility is unsuitable for the application of quality shotcrete.

- d. Provide a working surface that permits nozzlemen unobstructed access to the receiving surface. Place shotcrete first in corners, recesses, and other areas where rebound or overspray cannot easily escape.
 - e. The supply of shotcrete material and air pressure at the nozzle shall be uniform, providing a steady, continuous flow of shotcrete with no detrimental surging or pulsing. Maintain the velocity and consistency of shotcrete exiting the nozzle at a uniform rate appropriate for the given job conditions so that satisfactory material consolidation and minimum rebound is achieved.
 - f. Place shotcrete perpendicular to the receiving surface with the nozzle held at such a distance to produce maximum consolidation of the shotcrete and full encapsulation of the reinforcement.
 - g. Shoot dry-mixture shotcrete material within 45 min after batching or, in the case of prepackaged material, within 45 min after predampening. Shoot wet-mixture shotcrete material within the time limits in ASTM C94/C94M.
 - h. Apply shotcrete using a circular or elliptical motion of the nozzle while building the required thickness.
 - i. Use sufficient material velocity, material consistency, and distance from the end of the nozzle to the receiving surface to produce maximum consolidation of the shotcrete and full encapsulation of the reinforcing steel.
 - j. In corners, direct the nozzle to bisect the corner angle. Apply shotcrete so sagging or sloughing does not occur. Where there is potential for accumulated rebound or overspray material to be incorporated into the Work at congested areas of steel reinforcement, embedded obstructions, corners, and recesses, use a compressed air blow pipe to remove loose material from the Work.
 - k. Discontinue placement of shotcrete or shield the nozzle stream if wind causes separation of ingredients in the nozzle stream.
 - l. Do not reuse rebound or overspray in the Work.
 - m. Remove laitance from shotcrete surfaces that are to receive additional shotcrete layers.
 - n. Surface preparation prior to the shooting of shotcrete shall comply with the paragraph titled PREPARATION OF SURFACE TO RECEIVE SHOTCRETE.
 - o. Do not apply shotcrete to surfaces with standing or flowing water.
 - p. Remove hardened overspray and rebound from adjacent surfaces, including exposed reinforcement.
- 3.4.2 Intermediate surfaces
- a. When applying more than one layer of shotcrete, use a cutting rod, brush with a stiff bristle, or other suitable equipment to remove all loose material, overspray, laitance, or other material that may compromise

the bond of the subsequent layer of shotcrete. Conduct removal immediately after shotcrete reaches initial set.

- b. Allow shotcrete to stiffen sufficiently before applying subsequent layers. If shotcrete has hardened, clean the surface of all loose material, laitance, overspray, or other material that may compromise the bond of subsequent layers. Bring the surface to a saturated surface-dry condition at the time of application of the next layer of shotcrete.

3.4.3 Encasement of reinforcement

- a. Place shotcrete to encase reinforcement and other embedments, and provide a minimum cover of 1.5".
- b. Adjust air volume, material feed volume, and distance of the nozzle from the Work as necessary to encase reinforcement.
- c. Keep the front face of the reinforcement clean during shooting operations so that shotcrete builds up from behind to encase the reinforcement without the formation of shadows or voids.
- d. Shotcrete crew shall continuously remove accumulations of rebound and overspray using a compressed air blowpipe, or other suitable device, in advance of deposition of new shotcrete.

3.4.4 Hot weather shotcreting

Do not place shotcrete when shotcrete temperature is above 95°F, unless PREQUALIFICATION TESTING shows that the required quality of materials can be achieved at higher temperatures. The temperature of reinforcement and receiving surfaces shall be below 90°F prior to shotcrete placement.

3.4.5 Cold weather shotcreting

Shooting may proceed when ambient temperature is 40°F and rising. Stop shooting when ambient temperature is 40°F and falling, unless measures are taken to protect the shotcrete. Shotcrete material temperature, when shot, shall not be less than 50°F. Do not place shotcrete against frozen surfaces.

3.5 FINISH

3.5.1 Cutting Screed

After the surface has taken its initial set (crumbling slightly when cut), excess material outside the forms and ground wires shall be sliced off with a downward cutting motion using a sharp-edged cutting screed. The ground wires shall then be removed and the irregularities floated.

3.5.2 Float and Trowel Finish

Final surface finish shall be provided using steel trowel. Troweling of thin sections of shotcrete shall be avoided unless both troweling and commencement of moisture curing take place within a relatively short period after placement of shotcrete.

3.6 CURING

When the daily mean temperature is above 40°F, curing shall be continuous for a minimum of 7 consecutive days or for the time necessary to attain 70 percent of the specified compressive or flexural strength, whichever period is less.

If shotcrete is placed with daily mean temperatures 40°F or lower, cold weather protection shall be provided until the shotcrete achieves 70 percent of the specified strength.

Complete moist curing by one of the following methods:

- a. Ponding or continuous sprinkling for a minimum of 7 days;
- b. Covering with an absorptive mat or sand that is kept continuously wet;
- c. Covering with impervious sheet material;
- d. Use of curing compounds; apply twice the rate for formed surfaces as recommended by manufacturer if the surface is a gun finish.

Do not use natural curing in lieu of that specified in this paragraph unless the relative humidity of the air in contact with the shotcrete remains at or above 85 percent and such curing is authorized by Contracting Officer. Submit curing materials and curing procedures for shotcrete including product data sheets indicating conformance with specification requirements.

3.7 PROTECTION

Immediately after placement, protect shotcrete from premature drying or excessively hot or cold temperatures and mechanical injury. Maintain shotcrete protection to prevent freezing of the shotcrete and to ensure the necessary strength development for structural safety. Remove protection in such a manner that the maximum decrease in temperature measured at the surface of the shotcrete in a 24-hour period shall not exceed the following:

- a. 50°F for sections less than 12 in. in the least dimension;
- b. 40°F for sections from 12 to 36 in. in the least dimension.

Protect surfaces not intended for shotcrete placement against deposit of rebound and overspray or impact from nozzle stream.

3.8 TOLERANCES

Dimensional tolerances of shotcrete shall comply with ACI 117

3.9 REPAIR OF SHOTCRETE

3.9.1 General

- a. Submit repair procedure for shotcrete defects for the Contracting Officer's acceptance. The submittal shall include proposed materials, surface preparation, bonding procedures, and final surface finish.

- b. Remove voids, shadows, sagging, or other defects in the hardened shotcrete using light-duty chipping hammers maximum 18 lbs followed by high-pressure water blasting or grit blasting to remove bruised shotcrete surface.
- c. Conduct removal of defective shotcrete without the creation of feather edges.
- d. In the repair of core hole surfaces and saw cut edges, roughen the core hole or cut surface and predampen prior to repair.

3.9.2 Shotcrete repair with commercial patching products

Repair shotcrete with commercial patching products, including:

- a. Portland cement mortar, modified with a latex bonding agent conforming to ASTM C1059/C1059M, Type II;
- b. Packaged, dry concrete repair materials conforming to ASTM C928/C928M.

3.9.3 Removal of stains, rust, efflorescence, and surface deposits

Remove stains, rust, efflorescence, and surface deposits considered objectionable by Contracting Officer by methods acceptable to the Contracting Officer.

3.10 ACCEPTANCE OF WORK

3.10.1 General

- a. Remove and replace defective areas larger than 48 square inches or 2 inches deep. Defects in shotcrete include honeycombing, laminations, dry patches, voids, or sand pockets. Defective areas shall be removed in accordance with the procedures described in paragraph titled "REPAIR OF SHOTCRETE".
- b. Shotcrete Work that meets specifications shall be accepted.
- c. Shotcrete Work that has previously failed to meet one or more requirements, but has been repaired to bring it into compliance shall be accepted.
- d. Shotcrete Work that fails to meet one or more requirements and that cannot be brought into compliance shall be either accepted or rejected by Contracting Officer. Modifications to the mixture proportions or the shotcreting procedures shall be implemented to assure that remaining Work complies with the requirements.
- e. The basis for acceptance or rejection of shotcrete properties shall be the specified compressive or flexural strength. When additional criteria, properties, or both are required in the contract documents, acceptance criteria shall include compliance with those requirements.

3.10.2 Compliance with test properties

3.10.2.1 Compressive strength

Consider the compressive strength adequate if the average of the three cores from a test panel or from in-place shotcrete exceeds 85 percent of the specified compressive strength and no single core is less than 75 percent of the specified compressive strength.

-- End of Section --

SECTION 05 40 00

COLD-FORMED METAL FRAMING

05/15

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 318 (2014; Errata 1-2 2014; Errata 3-5 2015; Errata 6 2016; Errata 7-9 2017) Building Code Requirements for Structural Concrete (ACI 318-14) and Commentary (ACI 318R-14)

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI S100 (2012) North American Specification for the Design of Cold-Formed Steel Structural Members

AISI S110 (2007; Suppl 1; Reaffirmed 2012) Standard for Seismic Design of Cold-Formed Steel Structural Systems - Special Bolted Moment Frames

AISI S200 (2007) North American Standard for Cold-Formed Steel Framing - General Provision

AISI S201 (2007) North American Standard for Cold-Formed Steel Framing - Product Data

AISI S202 (2011) Code of Standard Practice for Cold-formed Steel Structural Framing

AISI S211 (2007) North American Standard for Cold-Formed Steel Framing - Wall Stud Design

AISI S212 (2007) North American Standard for Cold-Formed Steel Framing - Header Design

AISI S213 (2007; Suppl 1 2009) North American Standard for Cold-Formed Steel Framing - Lateral Design

AISI S214 (2012) North American Standard for Cold-Formed Steel Framing - Truss Design

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2015; Errata 1 2015; Errata 2 2016) Structural Welding Code - Steel
AWS D1.3/D1.3M	(2018) Structural Welding Code - Sheet Steel
ASTM INTERNATIONAL (ASTM)	
ASTM A123/A123M	(2017) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A153/A153M	(2016) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A307	(2014; E 2017) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM A1003/A1003M	(2015) Standard Specification for Steel Sheet, Carbon, Metallic- and Nonmetallic-Coated for Cold-Formed Framing Members
ASTM C955	(2017) Standard Specification for Cold-Formed Steel Structural Framing Members
ASTM C1007	(2011a) Standard Specification for Installation of Load Bearing (Transverse and Axial) Steel Studs and Related Accessories
ASTM C1513	(2018) Standard Specification for Steel Tapping Screws for Cold-Formed Steel Framing Connections
ASTM E329	(2018) Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection
ASTM E488/E488M	(2015) Standard Test Methods for Strength of Anchors in Concrete and Masonry Elements
ASTM F1554	(2018) Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength
ASTM F1941	(2010) Standard Specification for Electrodeposited Coatings on Threaded Fasteners (Unified Inch Screw Threads (UN/UNR))
ASTM F2329/F2329M	(2015) Standard Specification for Zinc Coating, Hot-Dip, Requirements for Application to Carbon and Alloy Steel Bolts, Screws, Washers, Nuts, and Special Threaded Fasteners

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC

(2018) International Building Code

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-301-01

(2013; with Change 4, 2018) Structural
Engineering

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29, SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

1.3 DELIVERY, STORAGE, AND HANDLING

Steel framing and related accessories shall be stored and handled in accordance with the AISI S202, "Code of Standard Practice for Cold-Formed Steel Structural Framing".

1.4 MAXIMUM DEFLECTION

Deflections of structural members shall not exceed the more restrictive of the limitations of ICC IBC and UFC 3-301-01.

1.5 QUALITY ASSURANCE

- a. Engineering Responsibility: Preparation of Shop Drawings, design calculations, and other structural data by a registered professional engineer.
- b. Testing Agency Qualifications: An independent testing agency, acceptable to authorities having jurisdiction, qualified according to ASTM E329 for testing indicated.
- c. Product Tests: Mill certificates or data from a qualified independent testing agency, or in-house testing with calibrated test equipment indicating steel sheet complies with requirements, including base-metal thickness, yield strength, tensile strength, total elongation, chemical requirements, and metallic-coating thickness.
- d. Welding Qualifications: Qualify procedures and personnel according to the following:
 - (1) AWS D1.1/D1.1M, "Structural Welding Code - Steel".
 - (2) AWS D1.3/D1.3M, "Structural Welding Code - Sheet Steel".
- e. AISI Specifications and Standards: Comply with:
 - (1) AISI S100, "North American Specification for the Design of Cold-Formed Steel Structural Members".

- (2) AISI S110, "Standard for Seismic Design of Cold-Formed Steel Structural Systems - Special Bolted Moment Frames".
- (3) AISI S200, "North American Standard for Cold-Formed Steel Framing - General Provision".
- (4) AISI S201, "North American Standard for Cold-Formed Steel Framing - Product Data".
- (5) AISI S202, "Code of Standard Practice for Cold-Formed Steel Structural Framing".
- (6) AISI S211, "North American Standard for Cold-Formed Steel Framing - Wall Stud Design".
- (7) AISI S212, "North American Standard for Cold-Formed Steel Framing - Header Design".
- (8) AISI S213, "North American Standard for Cold-Formed Steel Framing - Lateral Design".
- (9) AISI S214, "North American Standard for Cold-Formed Steel Framing - Truss Design".

PART 2 PRODUCTS

2.1 STEEL STUDS, JOISTS, TRACKS, BRACING, BRIDGING AND ACCESSORIES

Framing components shall comply with ASTM C955 and the following.

- a. Provide products with an average recycled content of steel products so postconsumer recycled content plus one half of preconsumer recycled content not less than 25 percent.
- b. Steel Sheet: ASTM A1003/A1003M, Structural Grade, Type H, metallic coated, of grade and coating weight as follows:
 - (1) As required by structural performance.
- c. Steel Studs: Manufacturer's standard C-shaped steel studs, of web depths indicated, punched, with stiffened flanges, and as follows:
 - (1) Minimum Base-Metal Thickness: See construction documents.
 - (2) Flange Width: See construction documents.
- d. Steel Track: Manufacturer's standard U-shaped steel track, of web depths indicated, unpunched, with straight flanges, and as follows:
 - (1) Minimum Base-Metal Thickness: Matching steel studs. See construction documents.
 - (2) Flange Width: See construction documents.

2.1.1 Sizes, Thickness, Section Modulus, and Other Structural Properties

Size and thickness as indicated. Match existing conditions at infill and furring locations and as directed in construction documents.

2.2 MARKINGS

Studs and track shall have product markings stamped on the web of the section. The markings shall be repeated throughout the length of the member at a maximum spacing of 4 feet on center and shall be legible and easily read. The product marking shall include the following:

- a. An ICC number.
- b. Manufacturer's identification.
- c. Minimum delivered uncoated steel thickness.
- d. Protective coating designator.
- e. Minimum yield strength.

2.3 CONNECTIONS

2.3.1 Steel-To-Concrete Connections

- a. Anchor Rods: ASTM F1554, galvanized per ASTM A153/A153M.
- b. Post-Installed Concrete Anchors: Adhesive or expansion anchors fabricated from corrosion-resistant materials with allowable load capacities in accordance with ICC-ES AC193 and ACI 318 greater than or equal to the design load as determined by testing per ASTM E488/E488M conducted by a qualified testing agency.
- c. Power-Actuated Fasteners: Fabricated from corrosion-resistant materials with allowable load capacities in accordance with ICC-ES AC 70 greater than or equal to the design load as determined by testing per ASTM E1190 conducted by a qualified testing agency.

2.3.2 Steel-To-Steel Connections

- a. Screws: ASTM C1513, corrosion-resistant-coated, self-drilling, self-tapping steel screws of the type and size indicated. Provide low-profile head beneath sheathing and manufacturer's standard elsewhere. Electroplated to a minimum of 5 micron zinc coating per ASTM F1941 or hot-dipped galvanized per ASTM A123/A123M or ASTM A153/A153M.
- b. Bolts: ASTM A307 coated by hot-dip process per ASTM F2329/F2329M or zinc-coated by mechanical-deposition process per ASTM B695, Class 55.
- c. Welding Electrodes: Comply with AWS standards.

2.4 PLASTIC GROMMETS

Supply plastic grommets for stud webs as recommended by stud manufacturer, to protect electrical wires and plumbing piping. Prevent metal-to-metal contact between wiring/piping and studs.

2.5 SEALER GASKET

Closed-cell neoprene foam, 1/4-inch thick, selected from manufacturer's standard widths to match width of bottom track on concrete slab or foundation.

PART 3 EXECUTION

3.1 FASTENING

Fasten framing members together by welding or by using self-drilling, self-tapping screws. Electrodes and screw connections shall be as required and indicated in the design calculations.

3.1.1 Welds

All welding shall be performed in accordance with AWS D1.3/D1.3M, as modified by AISI S100. All welders, welding operations, and welding procedures shall be qualified according to AWS D1.3/D1.3M. Submit certified copies of welder qualifications test records showing qualification in accordance with AWS D1.3/D1.3M. All welds shall be cleaned and coated with rust inhibitive galvanizing paint. Do not field weld materials lighter than 43 mils.

3.1.2 Screws

Screws shall be of the self-drilling self-tapping type, size, and location as indicated. Screw penetration through joined materials shall not be less than three exposed threads. Minimum spacings and edge distances for screws shall be as specified in AISI S100. Screws covered by sheathing materials shall have low profile heads.

3.1.3 Anchors

Anchors shall be of the type, size, and location as indicated on drawings.

3.1.4 Powder-Actuated Fasteners

Powder-actuated fasteners shall be of the type, size, and location as as required.

3.2 INSTALLATION

Install cold-formed framing in accordance with ASTM C1007 and AISI S200.

Install cold-formed steel framing according to AISI S202 and to manufacturer's written instructions unless more stringent requirements are indicated.

3.2.1 Tracks

Provide accurately aligned runners at top and bottom of studs. Install sealer gasket under bottom of track on concrete slab or foundation. Anchor tracks as indicated in design calculations. Butt weld joints in tracks or splice with stud inserts. Fasteners shall be at least 3 inches from the edge of concrete slabs.

3.2.2 Studs

Cut studs square and set with firm bearing against webs of top and bottom tracks. Position studs vertically in tracks and space as indicated in design. Do not splice studs. Provide at least two studs at jambs of doors and other openings 2 feet wide or larger. Provide jack studs over openings, as necessary, to maintain indicated stud spacing. Provide tripled studs at corners, positioned to receive interior and exterior finishes. Fasten studs to top and bottom tracks by welding or screwing both flanges to the tracks. Framed wall openings shall include headers and supporting components as shown on the drawings. Headers shall be installed in all openings that are larger than the stud spacing in a wall. In curtain wall construction, provide for vertical movement where studs connect to the structural frame. Provide horizontal bracing in accordance with the design calculations and AISI S100. Bracing shall be not less than the following:

LOAD	HEIGHT	BRACING
Wind load only	Up to 10 feet	One row at mid-height
	Over 10 feet	Rows 5'-0" o.c. maximum
Axial load	Up to 10 feet	Two rows at 1/3 points
	Over 10 feet	Rows 3'-4" o.c. maximum

3.2.3 Erection Tolerances

- a. Framing members which will be covered by finishes such as wallboard, plaster, or ceramic tile set in a mortar setting bed, shall be within the following limits:
 - (1) Layout of walls and partitions: 1/4 inch from intended position;
 - (2) Plates and runners: 1/4 inch in 8 feet from a straight line;
 - (3) Studs: 1/4 inch in 8 feet out of plumb, not cumulative; and
 - (4) Face of framing members: 1/4 inch in 8 feet from a true plane.
- b. Framing members which will be covered by ceramic tile set in dry-set mortar, latex-portland cement mortar, or organic adhesive shall be within the following limits:
 - (1) Layout of walls and partitions: 1/4 inch from intended position;
 - (2) Plates and runners: 1/8 inch in 8 feet from a straight line;

- (3) Studs: 1/8 inch in 8 feet out of plumb, not cumulative; and
- (4) Face of framing members: 1/8 inch in 8 feet from a true plane.

-- End of Section --

SECTION 06 20 00

FINISH CARPENTRY

08/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN LUMBER STANDARDS COMMITTEE (ALSC)

ALSC PS 20 (2015) American Softwood Lumber Standard

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)

AWPA U1 (2017) Use Category System: User Specification for Treated Wood

ASME INTERNATIONAL (ASME)

ASME B18.2.1 (2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)

ASME B18.2.2 (2015) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)

ASME B18.6.1 (2016) Wood Screws (Inch Series)

ASTM INTERNATIONAL (ASTM)

ASTM F547 (2017) Standard Terminology of Nails for Use with Wood and Wood-Base Materials

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.9 (2015) Cabinet Hardware

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350 (2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

COMPOSITE PANEL ASSOCIATION (CPA)

CPA A208.1 (2016) Particleboard

GREEN SEAL (GS)

GS-36 (2013) Adhesives for Commercial Use

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI/NEMA LD 3 (2005) Standard for High-Pressure Decorative Laminates

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)

NHLA Rules (2015) Rules for the Measurement & Inspection of Hardwood & Cypress

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)

NELMA Grading Rules (2013) Standard Grading Rules for Northeastern Lumber

REDWOOD INSPECTION SERVICE (RIS) OF THE CALIFORNIA REDWOOD ASSOCIATION (CRA)

RIS Grade Use (1998) Redwood Lumber Grades and Uses

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168 (2017) Adhesive and Sealant Applications

SOUTHERN PINE INSPECTION BUREAU (SPIB)

SPIB 1003 (2014) Standard Grading Rules for Southern Pine Lumber

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)

WCLIB 17 (2015) Standard Grading Rules

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)

WWPA G-5 (2017) Western Lumber Grading Rules

WOODWORK INSTITUTE (WI)

NAAWS 3.1 (2017; 2018 Errata Edition) North American Architectural Woodwork Standards

1.2 DELIVERY, STORAGE, AND HANDLING

Deliver wood products to the jobsite in an undamaged condition. Stack materials to ensure ventilation and drainage. Protect against dampness before and after delivery. Store materials under cover in a well-ventilated enclosure and protect against extreme changes in temperature and humidity. Keep materials wrapped and separated from off-gassing materials (such as drying paints and adhesives). Do not use materials that have visible moisture or biological growth. Do not store products in building until wet trade materials are dry and humidity of the space is within wood manufacturer's tolerance limits for storage.

PART 2 PRODUCTS

2.1 WOOD PRODUCTS

2.1.1 Sizes and Patterns of Wood Products

Provide yard and board lumber sizes in accordance with ALSC PS 20. Provide shaped lumber and millwork in the patterns indicated and in standard patterns of the association covering the species. Size references, unless otherwise specified, are nominal sizes. Provide actual sizes within manufacturing tolerances allowed by the applicable standard.

2.1.2 Species and Grades

Provide in accordance with AWWPA U1 Use Category System Tables unless otherwise specified herein.

2.1.3 Trim, Finish, and Frames

Provide species and grades listed in the table below for wood materials that must be painted. For materials that must be stained, have a natural, or a transparent finish, provide materials one grade higher than those listed in the table below. Provide trim, except window stools and aprons with hollow backs.

TABLE OF GRADES FOR WOOD TO RECEIVE PAINT FINISH		
Grading Rules	Species	Exterior and Interior Trim, Finish, and Frames
WWPA G-5 standard grading rules	Aspen, Douglas Fir-Larch, Douglas Fir South, Engelmann Spruce-Lodgepole Pine, Engelmann Spruce, Hem-Fir, Idaho White Pine, Lodgepole Pine, Mountain Hemlock, Mountain Hemlock-Hem-Fir, Ponderosa Pine-Sugar Pine, (Ponderosa Pine-Lodgepole Pine,) White Woods, (Western Woods,) Western Cedars, Western Hemlock	All Species: C & BTR. Select (Choice & BTR Idaho White Pine) or Superior Finish. Western Red Cedar may be graded C & BTR. Select or A & BTR in accordance with Special Western Red Cedar Rules.
WCLIB 17 standard grading rules	Douglas Fir-Larch, Hem-Fir, Mountain Hemlock, Sitka Spruce, Western Cedars, Western Hemlock	All Species: C & BTR VG, except A for Western Red Cedar
SPIB 1003 standard grading rules	Southern Pine	C & BTR

NHLA Rules	Cypress	C-Select
NELMA Grading Rules standard grading rules **	Balsam Fir, Eastern Hemlock-Tamarack, Eastern Spruce, Eastern White Pine, Northern Pine, Northern Pine, Northern White Cedar	All Species: C-Select except C & BTR for Eastern White Pine and Norway Pine
RIS Grade Use standard specifications	Redwood	Clear, Clear All Heart
NHLA Rules	Cypress	B Finish
	Red Gum, Soft Elm, Birch	Select or BTR (for interior use only)

Note: ** <http://www.nelma.org/library/2013-standard-grading-rules-for-northeastern-lumber/>

2.1.4 Medium Density Fiberboard (MDF) and Particleboard

CPA A208.1, Grade 1-M-2 or 2-M-2 or better. For products located on the interior of the building (inside of the weatherproofing system), provide certification of indoor air quality for MDF and particleboard.

Provide products with 80 percent total recovered materials content. Provide data identifying percentage of recycled content for MDF/particleboard.

2.1.5 Shoe Mould

Clear red or white oak, 1/2 by 5/8 inch unless otherwise indicated.

2.1.6 Wood Seats

Clear maple, oak, or other suitable hardwood, not less than 1-5/8 inches thick, with rounded edges. Provide stainless steel stanchions or brackets.

2.2 FASCIAS AND TRIM

2.2.1 Wood

Provide species and grades for all fascia and trim, including exterior door and window casings, in accordance with AWP A U1 Use Category System Tables. Provide sizes indicated. Metal corners may be provided in lieu of wood corner boards for horizontal siding. If metal corners are used, provide galvanized steel or aluminum, completely coated with primer compatible for the specific metal substrate.

2.3 COUNTERTOPS

2.3.1 Laminated Plastic-faced Countertops

ANSI/NEMA LD 3.

2.3.1.1 Countertop Finishes

High pressure plastic laminate, Grade GP 50 or PF 42, satin or textured finish. Provide color and pattern as shown on the construction documents.

2.3.1.2 Backing Sheet

Heavy gauge, BK 20.

2.3.2 Solid Surface

For solid surface countertops refer to construction documents.

2.4 HARDWARE AND ACCESSORIES

Provide sizes, types, and spacings of hardware and accessories as recommended in writing by the wood product manufacturer, except as otherwise specified.

2.4.1 Wood Screws

ASME B18.6.1.

2.4.2 Bolts, Nuts, Lag Screws, and Studs

ASME B18.2.1 and ASME B18.2.2.

2.4.3 Nails

Use nails of a size and type best suited for each application and in accordance with ASTM F547. Use hot-dipped galvanized or aluminum nails for exterior applications. For siding, provide nails of sufficient length to extend 1-1/2 inches into supports, including wood sheathing over framing. Where nailing is impractical, provide screws of a size and type best suited for each application.

2.5 FABRICATION

2.5.1 Quality Standards (QS)

2.5.1.1 Grades

The terms "Premium," "Custom," and "Economy" refer to the quality grades defined in NAAWS 3.1. Provide items not otherwise specified in a specific grade as "Custom" grade.

2.5.1.2 Adhesives

Select adhesives for durability and permanent bonding. Address factors such as materials that must be bonded, expansion and contraction, bond strength, fire rating, moisture resistance, and manufacturer's recommendations.

Provide non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or

classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide aerosol adhesives used on the interior of the building meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of GS-36. Provide certification or validation of indoor air quality for non-aerosol adhesives applied on the interior of the building (inside of the weatherproofing system). Provide certification or validation of indoor air quality for aerosol adhesives used on the interior of the building.

2.5.2 Countertops

Fabricate with lumber and a core of appropriate plywood or particleboard, glued and screwed to form an integral unit. Bond laminated plastic under pressure to exposed surfaces, using adhesive as recommended by the plastic manufacturer. Provide backsplashes not less than 3-1/2 inches nor more than 4-1/2 inches high.

2.5.3 Cabinets

Unless specified otherwise, provide wall and base cabinets of the same construction, materials, and finishes as countertops. Fabricate cabinets with solid ends and frame fronts, or with frames all around. Provide frames of solid hardwood not less than 3/4 by 1-1/2 inches. Provide ends, bottoms, backs, partitions, and doors as hardwood plywood. Mortise and tenon, dovetail, or dowel and glue joints to produce a rigid unit. Cover exposed edges of plywood with hardwood strips. Provide cabinet doors, frames, and solid exposed ends 3/4 inch thick minimum. Provide cabinet bottoms, partitions, and framed ends to be 1/2 inch minimum. Provide shelves to be 5/8 inch thick minimum. Provide cabinet backs 1/4 inch thick minimum.

2.5.3.1 Cabinet Hardware

ANSI/BHMA A156.9. Provide cabinet hardware including two self, closing hinges for each door, two side mounted metal drawer slides for each drawer, and pulls for all doors and drawers as follows. Provide hardware exposed to view as bright chromium plated. Comply with the following requirements for all cabinet hardware:

- a. Provide frameless concealed European style, back mounted hinges with 165 degree opening and a self closing feature when at less than 90 degrees open.
- b. Provide drawer slides having a static rating capacity of 100 lbs.. Slides to have a self closing/stay closed action, zinc or epoxy coated steel finish, ball bearing rollers, and positive stop with lift out design.
- c. Provide drawer pulls as wire type pulls with center-to-center dimension of not less than 3-1/2 inches and a cross sectional diameter of 5/16 inch. Provide handle projections not less than 1-5/16 inches.
- d. Provide heavy duty magnetic drawer catches.

2.5.3.2 Finish

Provide a clear factory finish on wood surfaces after fabrication. Provide fabricator's standard natural finish equivalent to one coat of sealer, one coat of varnish on all surfaces and a second coat of varnish on surfaces exposed to view. Provide spar varnish in exterior or wet area applications. Sand lightly and wipe clean between coats.

2.5.4 Casework with High Pressure Laminate Finish

2.5.4.1 AWI Quality Grade

Premium grade.

2.5.4.2 Construction

Provide flush overlay design details.

2.5.4.3 Exposed Surfaces

High pressure plastic laminate, color and pattern as indicated on construction documents.

2.5.4.4 Semi-Exposed Surfaces

As specified in the NAAWS 3.1 for the grade selected.

PART 3 EXECUTION

Do not install building construction materials that show visual evidence of biological growth.

3.1 FINISH WORK

Apply primer to finish work before installing. Where practicable, shop assemble and finish millwork items. Construct joints tight and in a manner to conceal shrinkage but to avoid cupping, twisting and warping after installation. Miter trim and mouldings at exterior angles; cope at interior angles and at returns. Provide millwork and trim in maximum practical lengths. Fasten finish work with finish nails. Provide blind nailing where practicable. Set face nails for putty stopping.

3.1.1 Interior Finish Work

After installation, sand exposed surfaces smooth. Provide window and door trim in single lengths.

3.1.2 Bases

Provide flat member with a moulded top. Fasten base to framing or to grounds. Set shoe mould one-piece wood base after finish flooring is in place.

3.2 MISCELLANEOUS

3.2.1 Countertops

Conceal fastenings where practicable. Fit counters tight to adjoining surfaces and scribe where necessary. Provide scribed joints neat and flush.

Provide counter sections in longest lengths practicable with a minimum number of joints. Where joints are necessary, provide tight joints drawn up with concealed type heavy pull-up bolts. Glue joints with water resistant glue and make rigid with screws, bolts, or other approved fastenings.

3.2.2 Cabinets

Provide cabinets level, plumb, true, and tight to adjacent walls. Secure cabinets to walls with concealed toggle bolts. Secure top to cabinet with concealed screws. Make cutouts for fixtures from templates supplied by fixture manufacturer. Locate cutouts for pipes so that edges of holes are covered by escutcheons after installation.

3.3 MOULDING AND INTERIOR TRIM

Install mouldings and interior trim straight, plumb, level and with closely fitted joints. Provide exposed surfaces machine sanded at the shop. Cope returns and interior angles at moulded items and miter external corners. Shoulder intersections of flatwork to ease any inherent changes in plane. Provide window and door trim in single lengths. Blind nail to the extent practicable. Set and stop face nailing with a nonstaining putty to match the applied finish. Use screws for attachment to metal; set and stop screws in accordance with the same quality requirements for nails.

-- End of Section --

SECTION 08 14 00

WOOD DOORS

08/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

CALIFORNIA AIR RESOURCES BOARD (CARB)

CARB 93120 (2007) Airborne Toxic Control Measure (ATCM) to Reduce Formaldehyde Emissions from Composite Wood Products

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 770 Formaldehyde Standards for Composite Wood Products

WINDOW AND DOOR MANUFACTURERS ASSOCIATION (WDMA)

ANSI/WDMA I.S.1A (2013) Interior Architectural Wood Flush Doors

WOODWORK INSTITUTE (WI)

NAAWS 3.1 (2017; 2018 Errata Edition) North American Architectural Woodwork Standards

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.\\corp.salasobrien.com\sea\Drawings\SPECSINTACTWD\Jobs\SHAWAFBB1518\prntdata\Word\Word\docx Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Doors; G

Submit drawings or catalog data showing each type of door unit. Indicate within drawings and data the door types and construction, sizes, and thickness.

SD-03 Product Data

Doors; G

Accessories

SD-04 Samples

Doors

Door Finish Colors; G

Submit a minimum of three color selection samples, minimum in size representing wood stain for selection by the Contracting Officer or other on site reviewer.

SD-07 Certificates

Certificates of Grade

SD-11 Closeout Submittals

Warranty

1.3 CERTIFICATIONS

1.3.1 Certified Wood Grades

Provide certificates of grade from the grading agency on doors. 1.3.2 Indoor Air Quality Certification

1.3.2.1 Composite Wood, Wood Structural Panel and Agrifiber Products

For purposes of this specification, composite wood and agrifiber products include particleboard, medium density fiberboard (MDF), wheatboard, strawboard, panel substrates, and door cores. Provide products certified to meet requirements of both 40 CFR 770 and CARB 93120. Provide current product certification documentation from certification body.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver doors to the site in an undamaged condition and protect against damage and dampness. Stack doors flat under cover. Support on blocking, a minimum of 4 inch thick, located at each end and at the midpoint of the door. Store doors in a well-ventilated building so that they will not be exposed to excessive moisture, heat, dryness, direct sunlight, or extreme changes of temperature and humidity. Do not store in a building under construction until concrete, masonry work, and plaster are dry. Replace defective or damaged doors with new ones.

1.5 WARRANTY

Warrant doors free of defects as set forth in the door manufacturer's standard door warranty.

PART 2 PRODUCTS

2.1 DOORS AND FRAMES

Provide doors of the types, sizes, and designs as indicated on plans. All doors shall match existing conditions. Provide Hollow metal door frame pre-finished with primer to receive field painted Semi-gloss finish. Color as indicated on plans. Hardware to Storeroom Function.

2.1.1 Flush Doors

Conform to ANSI/WDMA I.S.1A for flush doors. Provide hollow core doors with lock blocks and 1 inch minimum thickness hinge stile. Hardwood stile edge bands of doors receives a natural finish, compatible with face veneer. Provide mill option for stile edge of doors scheduled to be painted. No visible finger joints will be accepted in stile edge bands. When used, locate finger-joints under hardware.

2.1.1.1 Interior Flush Doors

Provide solid core, Type II flush doors conforming to ANSI/WDMA I.S.1A with faces of sound grade hardwood premium grade natural veneer doors that match existing conditions in style, finish, etc. Door cores must have a minimum recycled content of 45 percent. Provide data identifying percentage of recycled content for door cores.

2.2 FABRICATION

2.2.1 Quality and Construction

Identify the standard on which the construction of the door was based and identify doors having a Type I glue bond.

2.2.2 Preservative Treatment

Treat doors scheduled for restrooms, janitor closets and other possible wet locations including exterior doors with a water-repellent preservative treatment and so marketed at the manufacturer's plant.

2.2.3 Adhesives and Bonds

ANSI/WDMA I.S.1A. Use Type I bond for exterior doors and Type II bond for interior doors. Provide a nonstaining adhesive on doors with a natural finish.

2.2.4 Prefitting

Provide factory finished and factory prefitted doors for the specified hardware, door frame and door-swing indicated. Machine and size doors at the factory by the door manufacturer in accordance with the standards under which the doors are produced and manufactured. The work includes sizing, beveling edges, mortising, and drilling for hardware and providing necessary beaded openings for glass and louvers. Provide the door manufacturer with the necessary hardware samples, and frame and hardware schedules to coordinate the work.

2.2.5 Finishes

2.2.5.1 Field Painting

Factory prime or seal doors, and field paint.

2.2.5.2 Factory Finish

Provide doors finished at the factory by the door manufacturer as follows: NAAWS 3.1 Section 1500, specification for System No. 4 Conversion varnish alkyd urea or System No. 5 Vinyl catalyzed. The coating is NAAWS 3.1 premium, medium rubbed sheen, grain effect to match existing. Use stain when required to produce the finish specified for color. Seal edges, cutouts, trim, and wood accessories, and apply two coats of finish compatible with the door face finish. Touch-up finishes that are scratched or marred, or where exposed fastener holes are filled, in accordance with the door manufacturer's instructions. Match color and sheen of factory finish using materials compatible for field application. Stain may have to be custom to match existing.

2.2.5.3 Color

See door finish colors in accordance with Section 09 06 00 SCHEDULES FOR FINISHES.

2.3 SOURCE QUALITY CONTROL

Meet or exceed the following minimum performance criteria of stiles of "B" and "C" label fire doors utilizing standard mortise leaf hinges:

- a. Cycle-slam: Standard Duty Doors: 250,000 cycles with no loose hinge screws or other visible signs of failure when tested in accordance with the requirements of ANSI/WDMA I.S.1A.
- b. Hinge loading resistance: Averages of ten test samples not less than Standard Duty doors: 400 pounds force. Drill 5/32 inch pilot hole, use 1-1/2 inch opening around screw for bearing surface, and engage screw full, except for last 1/8 inch. Do not use a steel plate to reinforce screw area.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

Before installation, seal top and bottom edges of doors with the approved water-resistant sealer. Seal cuts made on the job immediately after cutting using approved water-resistant sealer. Fit, trim, and hang doors with a minimum, 1/8 inch maximum clearance at sides and top, and a 1/4 inch maximum clearance over thresholds. Provide 3/8 inch minimum, maximum clearance at bottom where no threshold occurs. Bevel edges of doors at the rate of 1/8 inch in 2 inch. Door warp must not exceed 1/4 inch when measured in accordance with ANSI/WDMA I.S.1A.

3.1.1 Prehung Doors

Install doors in accordance with the manufacturer's instructions and details. Provide fasteners for stop sand casing trim within 3 inch of each end and spaced 11 inch on center maximum. Provide side and head jambs joined together with a dado or notch of 3/16 inch minimum depth.

-- End of Section --

SECTION 08 71 00

DOOR HARDWARE

02/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E283	(2004; R 2012) Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.1	(2016) Butts and Hinges
ANSI/BHMA A156.2	(2017) Bored and Preamsembled Locks and Latches
ANSI/BHMA A156.3	(2014) Exit Devices
ANSI/BHMA A156.4	(2013) Door Controls - Closers
ANSI/BHMA A156.7	(2016) Template Hinge Dimensions
ANSI/BHMA A156.8	(2015) Door Controls - Overhead Stops and Holders
ANSI/BHMA A156.12	(2013) Interconnected Locks & Latches
ANSI/BHMA A156.13	(2017) Mortise Locks & Latches Series 1000
ANSI/BHMA A156.16	(2018) Auxiliary Hardware
ANSI/BHMA A156.18	(2016) Materials and Finishes
ANSI/BHMA A156.22	(2017) Door Gasketing and Edge Seal Systems

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 72	(2019; TIA 19-1; ERTA 2019) National Fire Alarm and Signaling Code
NFPA 80	(2016; TIA 16-1) Standard for Fire Doors and Other Opening Protectives

NFPA 101 (2018; TIA 18-1; TIA 18-2; TIA 18-3) Life Safety Code

NFPA 252 (2017) Standard Methods of Fire Tests of Door Assemblies

STEEL DOOR INSTITUTE (SDI/DOOR)

SDI/DOOR A250.8 (2003; R2008) Recommended Specifications for Standard Steel Doors and Frames

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191 Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines

UNDERWRITERS LABORATORIES (UL)

UL Bld Mat Dir (updated continuously online) Building Materials Directory

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Hardware Schedule; G

SD-03 Product Data

Hardware Items; G

SD-08 Manufacturer's Instructions

Installation

SD-10 Operation and Maintenance Data

Hardware Schedule Items, Data Package 1; G

1.3 SHOP DRAWINGS

Submit manufacturer's cut sheets and scheduling indicating all hardware assembly components. Base shop drawings on verified field measurements and include verification of existing conditions.

1.4 PRODUCT DATA

Provide documentation of ABA/ADA accessibility compliance of applicable components, as required by 36 CFR 1191 Appendix D - Technical.

1.5 HARDWARE SCHEDULE

Prepare and submit hardware schedule in the following form:

Hardware Item	Quantity	Size	Reference Publication Type No.	Finish	Mfr Name and Catalog No.	Key Control Symbols	UL Mark (If fire-rated and listed)	BHMA Finish Designation

In addition, submit hardware schedule data package 1 in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.6 QUALITY ASSURANCE

1.6.1 Hardware Manufacturers and Modifications

Provide, as far as feasible, handles, locks, hinges, pivots, and closers of one lock, hinge, pivot, or closer manufacturer's make. Modify hardware as necessary to provide features indicated or specified.

1.7 DELIVERY, STORAGE, AND HANDLING

Deliver hardware in original individual containers, complete with necessary appurtenances including fasteners and instructions. Mark each individual container with item number as shown on hardware schedule. Deliver permanent keys to the Contracting Officer, either directly or by certified mail. Deliver construction master keys with the locks.

PART 2 PRODUCTS

2.1 TEMPLATE HARDWARE

Hardware applied to metal or to prefinished doors must be manufactured using a template. Provide templates to door and frame manufacturers in accordance with ANSI/BHMA A156.7 for template hinges. Coordinate hardware items to prevent interference with other hardware.

2.2 HARDWARE FOR FIRE DOORS AND EXIT DOORS

Provide all hardware necessary to meet the requirements of NFPA 72 for door alarms, NFPA 80 for fire doors, NFPA 101 for exit doors, NFPA 252 for fire tests of door assemblies, ABA/ADA accessibility requirements, and all other requirements indicated, even if such hardware is not specifically mentioned in paragraph HARDWARE SCHEDULE. Provide Underwriters Laboratories, Inc. labels for such hardware in accordance with UL Bld Mat Dir or equivalent labels in accordance with another testing laboratory approved in writing by the Contracting Officer.

2.3 HARDWARE ITEMS

Clearly and permanently mark with the manufacturer's name or trademark, hinges, pivots, locks, latches, exit devices, bolts and closers where the identifying mark is visible after the item is installed. For closers with covers, the name or trademark may be beneath the cover. Retrofit locations with existing electronic locking components shall be maintained.

2.3.1 Hinges

Provide in accordance with ANSI/BHMA A156.1. Provide hinges that are 4-1/2 by 4-1/2 inch unless otherwise indicated or if building standard is present, match building standard. Construct loose pin hinges for interior doors and reverse-bevel exterior doors so that pins are non-removable when door is closed. Other anti-friction bearing hinges may be provided in lieu of ball bearing hinges.

2.3.1.1 Protection Devices

Provide full height hand and finger protection device at the hinge-side area opening of doors and gates. Provide hinge-side protection devices on both sides of doors and gates, covering hinges and space between door and frame when doors are in the open position. The installed device must push hand and fingers out of the opening and away from a crushing hazard.

2.3.2 Locks and Latches

- a. At exterior locations provide locksets of full stainless steel type 302 or 304 construction including fronts, strike, escutcheons, knobs, bolts and all interior working parts. Marine Grade I, fully non-ferrous. When applicable.

2.3.2.1 Bored Locks and Latches

Provide in accordance with ANSI/BHMA A156.2, Series 4000, Grade 1.

2.3.2.2 Interconnected Locks and Latches

Provide in accordance with ANSI/BHMA A156.12. Provide F96 or F97, unless otherwise specified.

2.3.3 Exit Devices

Provide in accordance with ANSI/BHMA A156.3, Grade 1. Provide adjustable strikes for rim type and vertical rod devices. Provide open back strikes for pairs of doors with mortise and vertical rod devices.

Use stainless steel or bronze base metal with plated finishes. Also include stainless steel fasteners and screws.

2.3.4 Cylinders and Cores

Provide cylinders and cores for new locks, including locks provided under other sections of this specification. Provide cylinders and cores with six pin tumblers. Provide cylinders from the products of one manufacturer, and provide cores from the products of one manufacturer. Rim cylinders, and knobs of bored locksets have interchangeable cores which are removable by

special control keys. Stamp each interchangeable core with a key control symbol in a concealed place on the core.

2.3.5 Keying System

Provide an extension of the existing keying system, when applicable.

2.3.6 Lock Trim

Provide cast, forged, or heavy wrought construction and commercial plain design for lock trim.

2.3.6.1 Knobs and Roses

Provide in accordance with ANSI/BHMA A156.2 and ANSI/BHMA A156.13 for knobs, roses, and escutcheons. For unreinforced knobs, roses, and escutcheons, provide a 0.050 inch thickness. For reinforced knobs, roses, and escutcheons, provide an outer shell thickness of 0.035 inch and a combined total thickness of 0.070 inch, except at knob shanks. Provide knob shanks 0.060 inch thick.

2.3.6.2 Lever Handles

Provide lever handles. Levers shall be ADA compliant and match building standard. Provide in accordance with ANSI/BHMA A156.3 for mortise locks of lever handles for exit devices. Provide lever handle locks with a breakaway feature (such as a weakened spindle or a shear key) to prevent irreparable damage to the lock when force in excess of that specified in ANSI/BHMA A156.13 is applied to the lever handle. Provide lever handles return to within 1/2 inch of the door face.

2.3.6.3 Texture

Provide knurled or abrasive coated knobs or lever handles for doors which are accessible to blind persons and which lead to dangerous areas.

2.3.7 Keys

Provide keys as directed by commanding officer.

2.3.8 Door Bolts

Provide in accordance with ANSI/BHMA A156.16. Provide dustproof strikes for bottom bolts, except at doors having metal thresholds. Provide automatic latching flush bolts in accordance with ANSI/BHMA A156.3, Type 25.

2.3.9 Closers

Provide in accordance with ANSI/BHMA A156.4, Series C02000, Grade 1, with PT 4C. Provide with brackets, arms, mounting devices, fasteners, full size covers, except at storefront mounting, pivots, and other features necessary for the particular application. Size closers in accordance with manufacturer's printed recommendations, or provide multi-size closers, Sizes 1 through 6, and list sizes in the Hardware Schedule. Provide manufacturer's 10 year warranty.

Use stainless steel inside bracketed or door mounted closers on exterior doors. On interior doors use closers of 302 or 304 stainless steel or non-ferrous materials. On surface-mounted closers use or apply rust inhibiting finish on all ferrous parts. Also apply this finish on concealed closers.

2.3.9.1 Identification Marking

Engrave each closer with manufacturer's name or trademark, date of manufacture, and manufacturer's size designation in locations that will be visible after installation.

2.3.10 Overhead Holders

Provide in accordance with ANSI/BHMA A156.8.

2.3.11 Door Stops and Silencers

Provide in accordance with ANSI/BHMA A156.16. Silencers Type L03011. Provide three silencers for each single door, two for each pair.

2.3.12 Weatherstripping Gasketing

Provide in accordance with ANSI/BHMA A156.22. Provide the type and function designation where specified in paragraph HARDWARE SCHEDULE. Provide a set to include head and jamb seals. Air leakage of weather stripped doors not to exceed 0.5 cubic feet per minute of air per square foot of door area when tested in accordance with ASTM E283. Provide weatherstripping with one of the following:

2.3.12.1 Extruded Aluminum Retainers

Extruded aluminum retainers not less than 0.050 inch wall thickness with vinyl, neoprene, silicone rubber, or polyurethane inserts. Provide dark bronze anodized aluminum.

2.3.12.2 Interlocking Type

Zinc or bronze not less than 0.018 inch thick.

2.3.12.3 Spring Tension Type

Spring bronze or stainless steel not less than 0.008 inch thick.

2.3.13 Auxiliary Hardware (Other than locks)

Provide in accordance with ANSI/BHMA A156.16, Grade 1.

2.3.14 Special Tools

Provide special tools, such as spanner and socket wrenches and dogging keys, as required to service and adjust hardware items.

2.3.15 Hardware Selections

See hardware schedule for selections. Provide stainless steel construction at door to dish drop. (Wet area)

2.4 FASTENERS

Provide fasteners of type, quality, size, and quantity appropriate to the specific application. Fastener finish to match hardware. Provide stainless steel or nonferrous metal fasteners in locations exposed to weather. Verify metals in contact with one another are compatible and will avoid galvanic corrosion when exposed to weather.

2.5 FINISHES

Provide in accordance with ANSI/BHMA A156.18. Provide hardware that matches existing conditions. Finish surface door closers in bronze paint for aluminum doors. Provide steel hinges in matching finish.

PART 3 EXECUTION

3.1 INSTALLATION

Provide hardware in accordance with manufacturers' printed installation instructions. Fasten hardware to wood surfaces with full-threaded wood screws or sheet metal screws. Provide machine screws set in expansion shields for fastening hardware to solid concrete and masonry surfaces. Provide toggle bolts where required for fastening to hollow core construction. Provide through bolts where necessary for satisfactory installation.

3.1.1 Weatherstripping Installation

Provide full contact, weathertight seals that allow operation of doors without binding the weatherstripping.

3.1.2 Threshold Installation

Extend thresholds the full width of the opening and notch end for jamb stops. Set thresholds in a full bed of sealant and anchor to floor with cadmium-plated, countersunk, steel screws in expansion sleeves. For aluminum thresholds placed on top of concrete surfaces, coat the underside surfaces that are in contact with the concrete with fluid applied waterproofing as a separation measure prior to placement.

3.2 FIRE DOORS AND EXIT DOORS

Provide hardware in accordance with NFPA 72 for door alarms, NFPA 80 for fire doors, NFPA 101 for exit doors, and NFPA 252 for fire tests of door assemblies.

3.3 HARDWARE LOCATIONS

Provide in accordance with SDI/DOOR A250.8, unless indicated or specified otherwise.

- a. Kick Plates: Push side of single-acting doors.

3.4 FIELD QUALITY CONTROL

After installation, protect hardware from paint, stains, blemishes, and other damage until acceptance of work. Submit notice of testing 15 days before scheduled, so that testing can be witnessed by the Contracting Officer. Adjust hinges, locks, latches, bolts, holders, closers, and other items to operate properly. Demonstrate that permanent keys operate respective locks and give keys to the Contracting Officer. Correct, repair, and finish, errors in cutting and fitting and damage to adjoining work.

-- End of Section --

SECTION 09 06 00

SCHEDULES FOR FINISHES

05/09

PART 1 GENERAL

1.1 SUMMARY

This section covers only the color of exterior and interior materials and products that are exposed to view in the finished construction. The word "color", as used herein, includes surface color and pattern. Requirements for quality, product specifications, and method of installation are covered in other appropriate sections of the specifications. Specific locations where the various materials are required are shown on the drawings if not identified in this specification. Items not designated for color in this section may be specified in other sections. When color is not designated for items, propose a color for approval.

PART 2 PRODUCTS

2.1 COLOR SCHEDULE

The color schedule information provided in the following paragraphs lists the colors, patterns and textures required for exterior and interior finishes, including both factory applied and field applied colors. Where color is shown as being specific to one manufacturer, an equivalent color by another manufacturer may be submitted for approval. Manufacturers and materials specified are not intended to limit the selection of equal colors from other manufacturers. In the case of difference between the drawings and specifications, colors identified in this specification govern.

2.2 EXTERIOR FINISHES

Reference drawings for additional information including manufacturer and color information.

2.3 INTERIOR FINISHES-

2.3.1 Interior Floor Finishes.

Provide flooring materials to match the colors listed below.

2.3.1.1 Carpet Tile

See finish schedule.

2.3.1.2 Porcelain Tile

Omit.

2.3.1.3 Quarry Tile

See finish schedule.

2.3.1.4 Ceramic Tile

See finish schedule.

2.3.1.5 Grout

See finish schedule.

2.3.1.6 Entrance Mat

See finish schedule.

2.3.1.7 Plastic Laminate

See finish schedule.

2.3.2 Interior Base Finishes

Provide base materials to match the colors listed below.

2.3.2.1 Resilient Base and Moldings

See Finish Schedule.

2.3.2.2 Porcelain Tile

See finish schedule.

2.3.2.3 Quarry Tile

See finish schedule.

2.3.2.4 Ceramic Tile

See finish schedule.

2.3.2.5 Grout

See finish schedule.

2.3.3 Interior Wall Finishes

Apply interior wall color to the entire wall surface, including reveals, vertical furred spaces and columns, grilles, diffusers, electrical and access panels, and piping and conduit adjacent to wall surfaces unless otherwise specified. Paint items not specified in other paragraphs to match adjacent wall surface. Provide wall materials to match the colors listed below.

2.3.3.1 Paint

See construction documents.

2.3.3.2 Porcelain Tile

See finish schedule.

2.3.3.3 Ceramic Tile

See finish schedule.

2.3.3.4 Grout

See finish schedule.

2.3.3.5 Fiberglass Reinforced Panels

See finish Schedule.

2.3.4 Interior Ceiling Finishes

Apply ceiling colors to ceiling surfaces including soffits, furred down areas, grilles, diffusers, registers, and access panels. In addition, apply ceiling color to joists, underside of roof deck, and conduit and piping where joists and deck are exposed and required to be painted. Provide ceiling materials to match the colors listed below.

2.3.4.1 Acoustical Tile and Grid

Manufacturers Standard Color White. See documents.

2.3.5 Interior Trim

Provide interior trim to match the colors listed below.

2.3.5.1 Steel Door Frames

Painted, see construction documents.

2.3.5.2 Wood Doors

Match existing wood finish with other doors.

2.3.5.3 Decorative Resin Panels

See Finish Schedule.

2.3.6 Interior Miscellaneous

Provide miscellaneous items selected from standard colors.

2.3.6.1 Toilet Partitions and Urinal Screens

See finish schedule.

2.3.6.2 Casework

See finish schedule.

2.3.6.3 Plastic Laminate

See finish schedule.

2.3.6.4 Solid Surfacing Material

See finish schedule.

2.3.6.5 Quartz Countertops

See finish schedule.

2.3.6.6 Corner Guards

Stainless steel

2.3.6.7 Lockers

See Finish Schedule

2.3.6.8 Wall Switch Handles and Standard Receptacle Bodies

Match existing ivory or steel in server area.

2.3.6.9 Electrical Device Cover Plates

Match existing ivory or steel in server area.

PART 3 EXECUTION

Not Used

PART 4 FINISH SCHEDULE

FINISH SCHEDULE					
NO.	DESCRIPTION	MANUFACTURER	PRODUCT	COLOR	REMARKS
ACT-1	2' X 4' X 5/8" CEILING TILE	ARMSTRONG	CERAMAGUARD UNPERFORATED	WHITE	SQUARE LAY IN $\frac{1}{8}$ " GRID; PRELUDE PLUS XL EXPOSED GRID $\frac{1}{8}$ " CERAMAGUARD WHITE ALUMINUM (.86% LIGHT REFLECTANCE)
ACT-2	2' X 2' X 3/4" CEILING TILE	ARMSTRONG	OPTIMA	WHITE	SQUARE LAY IN $\frac{1}{8}$ " GRID; PRELUDE XL EXPOSED GRID $\frac{1}{8}$ " WHITE (.88% LIGHT REFLECTANCE)
ACT-3	2' X 2' X 5/8" CEILING TILE	ARMSTRONG	ULTIMA VECTOR KITCHEN ZONE	WHITE	SQUARE LAY IN $\frac{1}{8}$ " GRID; PRELUDE XL EXPOSED $\frac{1}{8}$ " WHITE (.89% LIGHT REFLECTANCE)
CG-1	CORNER GUARDS	INPRO	STAINLESS STEEL 2" X 2" X 48"	STAINLESS STEEL	INSTALL ABOVE SCHEDULED WALL BASE PER MANF INSTRUCTIONS
CPT-1	CARPET TILE	J+J FLOORING	CUMULUS 7480	3485 ALTO NATURAL	SEE FINISH PLAN FOR LOCATION; INSTALLATION: ASHLAR
CPT-2	NOT USED	NOT USED	NOT USED	NOT USED	NOT USED
CPT-3	WALK OFF MAT	PEDIMAT	MONOTUFT	ANTHRACITE	SEE DETAIL F1/A603
CT-1	CERAMIC TILE FLOOR (FIELD)	DALTILE	SOCIETY 12 X 24	MONUMENT WHITE S045	INSTALLATION: ASHLAR
CT-2	CERAMIC TILE FLOOR (FIELD)	DALTILE	SOCIETY 12 X 24	UNION SMOKE S048	FOH & BOH RESTROOM FLOORS; INSTALLATION: ASHLAR
CT-3	CERAMIC TILE COVE BASE	DALTILE	SOCIETY 6 X 12 COVE BASE	MONUMENT WHITE S045	GROUT TO ALIGN WITH FLOOR TILE
CT-4	CERAMIC WALL TILE (SERVERY)	DALTILE	REMEDY; 2-3/8 X 9-1/2 GLOSSY	HYDRO RD22	INSTALLATION: BRICK FIELD WITH VERTICAL SOLDIER TRIM, SEE ELEVATIONS
CT-5	CERAMIC WALL TILE	DALTILE	RIGID CLAY 12 X 24	SALT RECTANGLE RIDGE RC10	FOH & BOH RESTROOM WALLS; INSTALL HORIZONTAL STACKED
CT-6	CERAMIC TILE COVE BASE	DALTILE	SOCIETY 6 X 12 COVE BASE	UNION SMOKE S048	GROUT TO ALIGN WITH FLOOR TILE
FRP-1	FIBERGLASS REINFORCED PLASTIC	MARLITE	STANDARD	WHITE	SURROUNDING DISH DROP; SEE ELEVATIONS
GT-1	EPOXY GROUT (QUARRY TILE)	TO MATCH EXISTING	TO MATCH EXISTING	TO MATCH EXISTING	TO BE USED AT ALL LOCATIONS WHERE QUARRY TILE WILL BE PATCHED
GT-2	GROUT (CT-1/CT-3/CT-4)	MAPEI	KERAPOXY CQ	PEWTER	-
GT-3	GROUT (CT-2/CT-6)	MAPEI	KERAPOXY CQ	IRON	-
GT-4	GROUT (CT-5)	MAPEI	KERAPOXY CQ	FROST	-
LVT-1	LUXURY VINYL TILE	SHAW	SOLITUDE 0648V	COCOA 48103	INSTALLATION: ASHLAR, OFFSET BY THIRDS
PT-1	INTERIOR PAINT (FIELD)	SHERWIN WILLIAMS	SATIN	DRIFT OF MIST 9166	SEE NOTE #2 BELOW FOR PAINT FINISH LOCATIONS OF PAINT @ CMU WALLS
PT-2	INTERIOR PAINT (ACCENT)	SHERWIN WILLIAMS	SATIN	DOVETAIL 7018	SEMI-GLOSS AT SERVERY LOCATIONS
PT-3	INTERIOR PAINT (ACCENT)	SHERWIN WILLIAMS	SATIN	DEEP SEA DIVE 7618	SEMI-GLOSS AT SERVERY LOCATIONS
PT-4	INTERIOR CEILING PAINT	SHERWIN WILLIAMS	FLAT	HIGH REFLECTIVE WHITE 7757	-
PT-5	INTERIOR PAINT (ACCENT)	SHERWIN WILLIAMS	SATIN	IRON ORE 7069	WALL CAP @ RESIN PANEL WALLS
PL-1	PLASTIC LAMINATE	FORMICA	WOODBUSH (WB)	NATURAL ASH 8843	-
PL-2	PLASTIC LAMINATE	PIONITE	TEXTURED/SUEDE (SD)	SUMMER VACATION SB027	-
QT-1	QUARRY TILE (6X6)	MATCH EXISTING	MATCH EXISTING	MATCH EXISTING	FOR PATCH & REPAIR WHERE REQUIRED TO MATCH EXISTING
QT-2	QUARRY TILE COVE BASE (6X6)	MATCH EXISTING	MATCH EXISTING	MATCH EXISTING	INSTALL ALL SPECIALTY TRIMS (INSIDE/OUTSIDE CORNERS & COVE BASE CORNER) FOR PATCH/REPAIR TO MATCH EXISTING
RB-1	4" RUBBER BASE	ROPPE	4" COVE	CHARCOAL	-
RP-1	RESIN PANEL	LUMICOR	NATURAL	MEADOW	DINING ROOMS & LOBBY
SS-1	SOLID SURFACE SERVERY & RESTROOM COUNTERS	DALTILE	ONE QUARTZ	LINCOLN WHITE	-

PART 5 ROOM FINISH SCHEDULE

ROOM FINISH SCHEDULE								
NO.	ROOM NAME	NORTH WALL	EAST WALL	SOUTH WALL	WEST WALL	CEILING	FLOOR	REMARKS
A100	VESTIBULE	PT-1	PT-1	PT-1	PT-1	PT-4	SEE FLOOR FINISH PLAN	
A101	LOBBY	PT-1	PT-1	PT-1	PT-1	PT-4	SEE FLOOR FINISH PLAN	
A102	CORRIDOR	PT-1	PT-1	PT-1	PT-1	PT-4	SEE FLOOR FINISH PLAN	
A103	JANITOR	-	-	-	-	-	SEE FLOOR FINISH PLAN	(E) FINISHES TO REMAIN
A104	MEN'S VESTIBULE	PT-1	PT-1	PT-1	PT-1	-	SEE FLOOR FINISH PLAN	
A105	MEN'S TOILET	PT-1 / CT-5	PT-1 / CT-5	PT-1 / CT-5	PT-1 / CT-5	-	SEE FLOOR FINISH PLAN	SEE A405 & A406 PLAN & ELEVATIONS FOR FINISH LOCATIONS
A106	WOMEN'S VESTIBULE	PT-1	PT-1	PT-1	PT-1	-	SEE FLOOR FINISH PLAN	
A107	WOMEN'S TOILET	PT-1 / CT-5	PT-1 / CT-5	PT-1 / CT-5	PT-1 / CT-5	-	SEE FLOOR FINISH PLAN	SEE A405 & A406 PLAN & ELEVATIONS FOR FINISH LOCATIONS
A108	MECH RM #1	-	-	-	-	-	SEE FLOOR FINISH PLAN	(E) FINISHES TO REMAIN
A109	MEN'S LOCKERS	PT-1	PT-1	PT-1	PT-1	PT-4	SEE FLOOR FINISH PLAN	
A110	MEN'S TOILET	PT-1 / CT-5	PT-1 / CT-5	PT-1 / CT-5	PT-1 / CT-5	PT-4	SEE FLOOR FINISH PLAN	SEE A407 PLAN & ELEVATIONS FOR FINISH LOCATIONS
A111	JANITOR	-	-	-	-	-	SEE FLOOR FINISH PLAN	
A112	WOMEN'S TOILET	PT-1 / CT-5	PT-1 / CT-5	PT-1 / CT-5	PT-1 / CT-5	PT-4	SEE FLOOR FINISH PLAN	SEE A408 PLAN & ELEVATIONS FOR FINISH LOCATIONS
A113	WOMEN'S LOCKERS	PT-1	PT-1	PT-1	PT-1	PT-4	SEE FLOOR FINISH PLAN	
A114	CORRIDOR	PT-1	PT-1	PT-1	PT-1	ACT-3	SEE FLOOR FINISH PLAN	
A115	ELECT RM	-	-	-	-	-	SEE FLOOR FINISH PLAN	(E) FINISHES TO REMAIN
A116	VESTIBULE	-	-	-	-	-	SEE FLOOR FINISH PLAN	
A117A	SERVER RM	-	-	-	-	-	SEE FLOOR FINISH PLAN	
A117	COMM RM	-	-	-	-	-	SEE FLOOR FINISH PLAN	
A118	OFFICE	PT-1	PT-1	PT-1	PT-1	ACT-2	SEE FLOOR FINISH PLAN	
A119	OFFICE	PT-1	PT-1	PT-1	PT-1	ACT-2	SEE FLOOR FINISH PLAN	
A120	OFFICE	PT-1	PT-1	PT-1	PT-1	ACT-2	SEE FLOOR FINISH PLAN	
A121	KITCHEN	PT-1	PT-1	PT-1	PT-1	ACT-3	SEE FLOOR FINISH PLAN	
A122	RECEIVING	-	-	-	-	ACT-2	SEE FLOOR FINISH PLAN	(E) FINISHES TO REMAIN
A123	DRY STORAGE	-	-	-	-	ACT-3	SEE FLOOR FINISH PLAN	(E) FINISHES TO REMAIN
A124	OFFICE	PT-1	PT-1	PT-1	PT-1	ACT-2	SEE FLOOR FINISH PLAN	
A125	STORAGE	-	-	-	-	ACT-3	SEE FLOOR FINISH PLAN	(E) FINISHES TO REMAIN
A126	PAN STOR	-	-	-	-	ACT-3	SEE FLOOR FINISH PLAN	CLARIFY IF ANY FINISHES ARE TO BE REFRESHED
A127	CASHIER'S OFFICE	PT-1	PT-1	PT-1	PT-1	ACT-2	SEE FLOOR FINISH PLAN	
A128	POT WASH	(E)	(E)	(E)	(E)	ACT-3	SEE FLOOR FINISH PLAN	(E) ST STL PANELS TO REMAIN. NEW WALLS TO RECEIVE NEW ST STL PANELS TO MATCH (E). FRP PANELS AT OPENING.
A129	DISH WASH	(E)	(E)	(E)	(E)	ACT-3	SEE FLOOR FINISH PLAN	(E) ST STL PANELS TO REMAIN. NEW WALLS TO RECEIVE NEW ST STL PANELS TO MATCH (E). FRP PANELS AT OPENING.
A130	CORRIDOR	PT-1	PT-1	PT-1	PT-1	ACT-3	SEE FLOOR FINISH PLAN	
A131	COOK'S REF	-	-	-	-	-	SEE FLOOR FINISH PLAN	
A132	HOT LINE SERVING	CT-4/PT-1	CT-4/PT-1	-	CT-4/PT-1	ACT-1	SEE FLOOR FINISH PLAN	
A133	SELF SERVE	-	-	-	-	ACT-2/GWB /PT-4	SEE FLOOR FINISH PLAN	
A134	GRILLE	CT-4/PT-1	CT-4/PT-1	PT-1	-	ACT-1	SEE FLOOR FINISH PLAN	
A135	DINING AREA A	-	PT-3	PT-2	PT-2	ACT-2 / GWB PT-4	SEE FLOOR FINISH PLAN	
A136	DINING AREA B	-	PT-3	PT-2	PT-3	ACT-2 / GWB PT-4	SEE FLOOR FINISH PLAN	
A137	DINING AREA C	-	PT-3/PT-2	PT-2	PT-3	ACT-2 / GWB PT-4	SEE FLOOR FINISH PLAN	
A138	POSTAL SORTING & STORAGE AREA	-	-	-	-	-	-	NIC
A139	POSTAL LOBBY	-	-	-	-	-	-	NIC
A140	OFFICE	-	-	-	-	-	-	NIC
A141	MECH RM #2	-	-	-	-	-	-	(E) FINISHES TO REMAIN
A142	BOILER RM	-	-	-	-	-	-	(E) FINISHES TO REMAIN
A145	PIZZA	-	-	PT-1	CT-4/PT-1	ACT-1	-	

-- End of Section --

SECTION 09 29 00

GYPSUM BOARD

08/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C475/C475M	(2017) Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board
ASTM C840	(2018b) Standard Specification for Application and Finishing of Gypsum Board
ASTM C954	(2018) Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs from 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness
ASTM C1002	(2018) Standard Specification for Steel Self-Piercing Tapping Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs
ASTM C1047	(2014a) Standard Specification for Accessories for Gypsum Wallboard and Gypsum Veneer Base
ASTM C1396/C1396M	(2017) Standard Specification for Gypsum Board

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

GYPSUM ASSOCIATION (GA)

GA 214	(2010) Recommended Levels of Gypsum Board Finish
GA 216	(2010) Application and Finishing of Gypsum Panel Products

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Water-Resistant Gypsum Backing Board

Accessories

Submit for each type of gypsum board and for cementitious backer units.

Gypsum Board

1.3 CERTIFICATIONS

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 Delivery

Deliver materials in the original packages, containers, or bundles with each bearing the brand name, applicable standard designation, and name of manufacturer, or supplier.

1.4.2 Storage

Keep materials dry by storing inside a sheltered building. Where necessary to store gypsum board and cementitious backer units outside, store off the ground, properly supported on a level platform, and protected from direct exposure to rain, snow, sunlight, and other extreme weather conditions. Provide adequate ventilation to prevent condensation. Store per manufacturer's recommendations for allowable temperature and humidity range. Do not store panels near materials that may off gas or emit harmful fumes, such as kerosene heaters, fresh paint, or adhesives. Do not use materials that have visible moisture or biological growth.

1.4.3 Handling

Neatly stack gypsum board and cementitious backer units flat to prevent sagging or damage to the edges, ends, and surfaces.

1.5 QUALIFICATIONS

Furnish type of gypsum board work specialized by the installer with a minimum of 3 years of documented successful experience.

1.6 ENVIRONMENTAL REQUIREMENTS

Do not expose the gypsum board to excessive sunlight prior to gypsum board application. Maintain a continuous uniform temperature of not less than 50 degrees F and not more than 80 degrees F for at least one week prior to the application of gypsum board work, while the gypsum board application is being done, and for at least one week after the gypsum board is set. Shield air supply and distribution devices to prevent any uneven flow of air across the plastered surfaces. Provide ventilation to exhaust moist air to the outside during gypsum board application, set, and until gypsum board jointing is dry. In glazed areas, keep windows open top and bottom or side to side 3 to 4 inches. Reduce openings in cold weather to prevent freezing of joint compound when applied. For enclosed areas lacking natural ventilation, provide temporary mechanical means for ventilation. In unglazed areas subjected to hot, dry winds or temperature differentials from day to night of 20 degrees F or more, screen openings with cheesecloth or similar materials. Avoid rapid drying. During periods of low indoor humidity, provide minimum air circulation following gypsum boarding and until gypsum board jointing complete and is dry.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to specifications, standards and requirements specified. Provide gypsum board types, gypsum backing board types, cementitious backing units, and joint treating materials manufactured from asbestos free materials only.

2.1.1 Gypsum Board

ASTM C1396/C1396M. Provide gypsum wall board and panels meeting the emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type).

2.1.2 Joint Treatment Materials

ASTM C475/C475M. Product must be low emitting VOC types with VOC limits not exceeding 50 g/L. Provide data identifying VOC content of joint compound. Use all purpose joint and texturing compound containing inert fillers and natural binders, including lime compound. Pre-mixed compounds must be free of antifreeze, vinyl adhesives, preservatives, biocides and other slow releasing compounds.

2.1.2.1 Embedding Compound

Specifically formulated and manufactured for use in embedding tape at gypsum board joints and compatible with tape, substrate and fasteners.

2.1.2.2 Finishing or Topping Compound

Specifically formulated and manufactured for use as a finishing compound.

2.1.2.3 All-Purpose Compound

Specifically formulated and manufactured to serve as both a taping and a finishing compound and compatible with tape, substrate and fasteners.

2.1.2.4 Setting or Hardening Type Compound

Specifically formulated and manufactured for use with fiber glass mesh tape.

2.1.2.5 Joint Tape

Use cross-laminated, tapered edge, reinforced paper, or fiber glass mesh tape recommended by the manufacturer.

2.1.3 Fasteners

2.1.3.1 Screws

ASTM C1002, Type "G", Type "S" or Type "W" steel drill screws for fastening gypsum board to gypsum board, wood framing members and steel framing members less than 0.033 inch thick. ASTM C954 steel drill screws for fastening gypsum board to steel framing members 0.033 to 0.112 inch thick. Provide cementitious backer unit screws with a polymer coating.

2.1.4 Accessories

ASTM C1047. Fabricate from corrosion protected steel designed for intended use. Accessories manufactured with paper flanges are not acceptable. Flanges must be free of dirt, grease, and other materials that may adversely affect bond of joint treatment. Provide prefinished or job decorated materials.

2.1.5 Water

Provide clean, fresh, and potable water.

PART 3 EXECUTION

3.1 EXAMINATION

3.1.1 Framing and Furring

Verify that framing and furring are securely attached and of sizes and spacing to provide a suitable substrate to receive gypsum board and cementitious backer units. Verify that all blocking, headers and supports are in place to support plumbing fixtures and to receive soap dishes, grab bars, towel racks, and similar items. Do not proceed with work until framing and furring are acceptable for application of gypsum board and cementitious backer units.

3.2 APPLICATION OF GYPSUM BOARD

Apply gypsum board to framing and furring members in accordance with ASTM C840 or GA 216 and the requirements specified. Apply gypsum board with separate panels in moderate contact; do not force in place. Stagger end joints of adjoining panels. Neatly fit abutting end and edge joints. Use gypsum board of maximum practical length; select panel sizes to minimize waste. Cut out gypsum board to make neat, close, and tight joints around openings. In vertical application of gypsum board, provide panels in lengths required to reach full height of vertical surfaces in one continuous piece. Lay out panels to minimize waste; reuse cutoffs whenever feasible. Surfaces of gypsum board and substrate members may be bonded together with an adhesive. Treat edges of cutouts for plumbing pipes, screwheads, and joints with water-resistant compound as recommended by the gypsum board

manufacturer. Provide type of gypsum board for use in each system specified herein as indicated.

3.2.1 Application of Gypsum Board to Steel Framing and Furring

Apply in accordance with ASTM C840, System VIII or GA 216.

3.3 FINISHING OF GYPSUM BOARD

Tape and finish gypsum board in accordance with ASTM C840, GA 214 and GA 216. Finish plenum areas above ceilings to Level 1 in accordance with GA 214. Finish water resistant gypsum backing board, ASTM C1396/C1396M, to receive ceramic tile to Level 2 in accordance with GA 214. Finish walls and ceilings to receive a heavy-grade wall covering or heave textured finish before painting to Level 3 in accordance with GA 214. Finish walls and ceilings without critical lighting to receive flat paints, light textures, or wall coverings to Level 4 in accordance with GA 214. Unless otherwise specified, finish all gypsum board walls, partitions and ceilings to Level 5 in accordance with GA 214. Provide joint, fastener depression, and corner treatment. Tool joints as smoothly as possible to minimize sanding and dust. Do not use self-adhering fiber glass mesh tape with conventional drying type joint compounds; use setting or hardening type compounds only. Provide treatment for water-resistant gypsum board as recommended by the gypsum board manufacturer. Protect workers, building occupants, and HVAC systems from gypsum dust.

3.3.1 Uniform Surface

Wherever gypsum board is to receive eggshell, semigloss or gloss paint finish, or where severe, up or down lighting conditions occur, finish gypsum wall surface in accordance to GA 214 Level 5. In accordance with GA 214 Level 5, apply a thin skim coat of joint compound to the entire gypsum board surface, after the two-coat joint and fastener treatment is complete and dry.

3.4 SEALING

Seal openings around pipes, fixtures, and other items projecting through gypsum board and cementitious backer units as specified in Section 07 92 00 JOINT SEALANTS. Apply material with exposed surface flush with gypsum board or cementitious backer units.

3.5 PATCHING

Patch surface defects in gypsum board to a smooth, uniform appearance, ready to receive finishes. All surfaces that receive fresh paint will require patching and repair.

-- End of Section --

SECTION 09 30 10

CERAMIC, QUARRY, AND GLASS TILING
08/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A136.1	(2008 Reaffirmed 2013) American National Standard Specifications for Organic Adhesives for Installation of Ceramic Tile
ANSI A137.1	(2012) American National Standards Specifications for Ceramic Tile

ASTM INTERNATIONAL (ASTM)

ASTM C33/C33M	(2018) Standard Specification for Concrete Aggregates
ASTM C144	(2018) Standard Specification for Aggregate for Masonry Mortar
ASTM C150/C150M	(2018) Standard Specification for Portland Cement
ASTM C206	(2014) Standard Specification for Finishing Hydrated Lime
ASTM C207	(2018) Standard Specification for Hydrated Lime for Masonry Purposes
ASTM C241/C241M	(2015) Standard Specification for Abrasion Resistance of Stone Subjected to Foot Traffic
ASTM C373	(2018) Standard Test Methods for Determination of Water Absorption and Associated Properties by Vacuum Method for Pressed Ceramic Tiles and Glass Tiles and Boil Method for Extruded Ceramic Tiles and Non-tile Fired Ceramic Whiteware Products
ASTM C648	(2004; R 2009) Breaking Strength of Ceramic Tile
ASTM C847	(2014a) Standard Specification for Metal Lath

ASTM C1026	(2013; R 2018) Standard Test Method for Measuring the Resistance of Ceramic and Glass Tile to Freeze-Thaw Cycling
ASTM C1027	(2009; R 2017) Standard Test Method for Determining Visible Abrasion Resistance of Glazed Ceramic Tile
ASTM C1178/C1178M	(2013) Standard Specification for Glass Mat Water-Resistant Gypsum Backing Panel
ASTM D226/D226M	(2017) Standard Specification for Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
ASTM D2103	(2015) Standard Specification for Polyethylene Film and Sheeting
ASTM F446	(2019) Standard Consumer Safety Specification for Grab Bars and Accessories Installed in the Bathing Area

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2017) Adhesive and Sealant Applications

TILE COUNCIL OF NORTH AMERICA (TCNA)

TCNA Hdbk	(2017) Handbook for Ceramic, Glass, and Stone Tile Installation

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191	Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines

UNDERWRITERS LABORATORIES (UL)

UL 2818

(2013) GREENGUARD Certification Program For
Chemical Emissions For Building Materials,
Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Porcelain Tile; G

Quarry Tile; G

Glazed Wall Tile; G

Setting-Bed; G

Mortar, Grout, and Adhesive; G

SD-04 Samples

Tile; G

Accessories; G

Transition Strips; G

Grout; G

SD-08 Manufacturer's Instructions

Maintenance Instructions

SD-10 Operation and Maintenance Data

Installation; G

1.3 CERTIFICATIONS

1.3.1 Indoor Air Quality Certifications

1.3.1.1 Adhesives and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have

certification, provide validation that product meets the indoor air quality product requirements cited in this Section.

1.4 QUALITY ASSURANCE

Provide installers having a minimum of two years experience with a company specializing in performing the type of work described. Each type and color of tile to be provided from a single source. Each type and color of mortar, adhesive, and grout to be provided from the same source.

1.5 DELIVERY, STORAGE, AND HANDLING

Ship tiles in sealed packages and clearly marked with the grade, type of tile, producer identification, and country of origin. Deliver materials to the project site in manufacturer's original unopened containers with seals unbroken and labels and hallmarks intact. Protect materials from weather, and store them under cover in accordance with manufacturer's printed instructions.

1.6 ENVIRONMENTAL REQUIREMENTS

Do not perform ceramic tile work unless the substrate and ambient temperature is at least 50 degrees F and rising. Maintain temperature above 50 degrees F while the work is being performed and for at least 7 days after completion of the work. When temporary heaters are used, ventilate the area to the outside to avoid carbon dioxide damage to new tilework.

1.7 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a 1-year period.

1.8 EXTRA MATERIALS

Supply an extra 2 percent of each type tile used in clean and marked cartons.

PART 2 PRODUCTS

2.1 TILE

Provide tiles that comply with ANSI A137.1 and are standard grade tiles. Provide a minimum breaking strength of 125 lbs. for wall tile and 250 lbs. for floor tile in accordance with ASTM C648. Provide exterior building tile for cold climate projects that is approved by the manufacturer for exterior use when tested in accordance with ASTM C1026. Provide floor tiles with a wet dynamic coefficient of friction (DCOF) value of 0.42 or greater when tested in accordance with ANSI A137.1 requirements. Provide glazed floor tile with a Class IV-Commercial V-Heavy Commercial classification as rated by the manufacturer when tested in accordance with ASTM C1027 for visible abrasion resistance as related to foot traffic. For materials like tile, accessories, and transition strips submit samples of sufficient size to show color range, pattern, type and joints. Submit manufacturer's catalog data.

2.1.1 Porcelain Tile

Provide glazed, porcelain tile, base and trim pieces with color extending uniformly through the body of the tile. Provide nominal tile size(s) of per manufacture's specs for each product selected. See schedule. Provide a 0.50 percent maximum water absorption in accordance with ASTM C373.

2.1.2 Quarry Tile

Furnish an unglazed quarry tile, cove bullnose base and trim pieces. Provide tile with coefficient of friction as specified surface. Provide nominal tile size(s) of per manufacture's specs for each product selected. See schedule. Provide a 0.30 percent maximum water absorption in accordance with ASTM C373.

Provide Quarry Tiling Materials that contain a minimum of 10 percent recycled content. Provide data identifying percentage of recycled content for quarry tile.

2.1.3 Accessories

Provide built-in type accessories of the same materials and finish as the wall tile. Provide accessories as follows:

	Quantity	Location
Recessed soap holders	NA	NA
Tumbler holders	NA	NA
Combination tumbler and toothbrush holders	NA	NA
Towel bars,	NA	NA
Robe hooks	NA	NA
Roll paper holder	NA	NA
Recessed soap holder and hand hold combination: support static load in compliance with ASTM F446	NA	NA

2.2 SETTING-BED

Submit manufacturer's catalog data. Compose the setting-bed of the following materials:

2.2.1 Aggregate for Concrete Fill

Conform to ASTM C33/C33M for aggregate fill. Do not exceed one-half the thickness of concrete fill for maximum size of coarse aggregate.

2.2.2 Portland Cement

Conform to ASTM C150/C150M for cement, Type I, white for wall mortar and gray for other uses.

2.2.3 Sand

Conform to ASTM C144 for sand.

2.2.4 Hydrated Lime

Conform to ASTM C206 for hydrated lime, Type S or ASTM C207, Type S.

2.2.5 Metal Lath

Conform to ASTM C847 for flat expanded type metal lath, and weighing a minimum 2.5 pound/square yard.

2.3 WATER

Provide potable water.

2.4 MORTAR, GROUT, AND ADHESIVE

Provide non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide aerosol adhesives used on the interior of the building meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of GS-36. Provide certification or validation of indoor air quality for adhesives.

2.4.1 Dry-Set Portland Cement Mortar

TCNA Hdbk.

2.4.2 Latex-Portland Cement Mortar

TCNA Hdbk.

2.4.3 Ceramic Tile Grout

TCNA Hdbk; petroleum-free and plastic-free sand portland cement grout latex-portland cement grout commercial portland cement grout.

2.4.4 Organic Adhesive

TCNA Hdbk, Type I. Water-resistant. Comply with ANSI A136.1.

2.4.5 Epoxy Resin Grout

TCNA Hdbk.

2.4.6 Furan Resin Grout

TCNA Hdbk and consist of an intimate mixture of furfuryl-alcohol resin with carbon filler and catalyst.

2.4.7 Sealants

Comply with applicable regulations regarding toxic and hazardous materials and as specified. Grout sealant must not change the color or alter the appearance of the grout. Refer to Section 07 92 00 JOINT SEALANTS.

2.5 SUBSTRATES

2.5.1 Cementitious Backer Board

Provide cementitious backer units, for use as tile substrate over wood sub-floors, in accordance with TCNA Hdbk. Furnish 1/2 inch thick cementitious backer units.

2.5.2 Glass Mat Gypsum Backer Panel

Provide glass mat water-resistant gypsum backer board, for use as tile substrate over wood subfloors, in accordance with ASTM C1178/C1178M. Provide 1/2 inch thick glass mat gypsum backer board.

2.6 TRANSITION STRIPS

Provide anodized aluminum transitions between tile and carpet or resilient flooring. Provide types as recommended by flooring manufacturer for both edges and transitions of flooring materials specified. Provide minimum 12.0 marble abrasion when tested in accordance with ASTM C241/C241M[solid surface transitions appropriate for conditions. Reference SECTION 06 61 16 SOLID SURFACING FABRICATIONS for specifications. Provide transition strips that comply with 36 CFR 1191 requirements.

2.7 MEMBRANE MATERIALS

Conform to ASTM D226/D226M, Type 1 for 15 pound waterproofing membrane, asphalt-saturated building felt. Conform to ASTM D2103 4 mil for polyethylene film.

2.8 COLOR, TEXTURE, AND PATTERN

Provide color, pattern and texture in accordance with Section 09 06 00 SCHEDULES FOR FINISHES. Provide floor patterns as specified on the drawings.

PART 3 EXECUTION

3.1 PREPARATORY WORK AND WORKMANSHIP

Inspect surface to receive tile in conformance to the requirements of TCNA Hdbk for surface conditions for the type setting bed specified and for workmanship. Provide variations of tiled surfaces that fall within maximum values shown below:

TYPE	WALLS	FLOORS
Dry-Set Mortar	1/8 inch in 8 ft.	1/8 inch in 10 ft.
Organic Adhesives	1/8 inch in 8 ft.	1/16 inch in 3 ft.
Latex Portland Cement Mortar	1/8 inch in 8 ft.	1/8 inch in 10 ft.
Epoxy	1/8 inch in 8 ft.	1/8 inch in 10 ft.

3.2 GENERAL INSTALLATION REQUIREMENTS

Do not start tile work until roughing in for mechanical and electrical work has been completed and tested, and built-in items requiring membrane waterproofing have been installed and tested. Close space, in which tile is being set, to traffic and other work. Keep closed until tile is firmly set. Do not start floor tile installation in spaces requiring wall tile until after wall tile has been installed. Apply tile in colors and patterns indicated in the area shown on the drawings. Install tile with the respective surfaces in true even planes to the elevations and grades shown. Provide special shapes as required for sills, jambs, recesses, offsets, external corners, and other conditions to provide a complete and neatly finished installation. Solidly back tile bases and coves with mortar. Do not walk or work on newly tiled floors without using kneeling boards or equivalent protection of the tiled surface. Keep traffic off horizontal portland cement mortar installations for at least 72 hours. Keep all traffic off epoxy installed floors for at least 40 hours after grouting, and heavy traffic off for at least 7 days, unless otherwise specifically authorized by manufacturer. Dimension and draw detail drawings at a minimum scale of 1/4 inch = 1 foot. Include drawings of pattern at inside corners, outside corners, termination points and location of all equipment items such as thermostats, switch plates, mirrors and toilet accessories mounted on surface. Submit drawings showing ceramic tile pattern elevations and floor plans. Submit manufacturer's preprinted installation instructions.

Do not install building construction materials that show visual evidence of biological growth.

3.3 INSTALLATION OF WALL TILE

Install wall tile in accordance with the TCNA Hdbk, method and with grout joints as recommended by the manufacturer for the type of tile. Install thinner wall tile flush with thicker wall tile applied on same wall and provide installation materials as recommended by the tile and setting materials manufacturer's to achieve flush installation.

3.3.1 Workable or Cured Mortar Bed

Install tile over workable mortar bed or a cured mortar bed at the option of the Contractor. Install a 4 mil polyethylene membrane, metal lath, and scratch coat. Conform to TCNA Hdbk for workable mortar bed, materials, and installation of tile. Conform to TCNA Hdbk for cured mortar bed and materials.

3.3.2 Dry-Set Mortar and Latex-Portland Cement Mortar

Use Latex-Portland Cement to install tile in accordance with TCNA Hdbk. Use Latex Portland Cement when installing porcelain ceramic tile.

3.3.3 Organic Adhesive

Conform to TCNA Hdbk for the organic adhesive installation of ceramic tile.

3.3.4 Furan Mortar and Grout

Conform to TCNA Hdbk for furan mortar and grout installation.

3.3.5 Ceramic Tile Grout

Prepare and install ceramic tile grout in accordance with TCNA Hdbk. Provide and apply manufacturer's standard product for sealing grout joints in accordance with manufacturer's recommendations.

3.4 INSTALLATION OF FLOOR TILE

Install floor tile in accordance with TCNA Hdbk method and with grout joints as recommended by the manufacturer for the type of tile.

3.4.1 Workable or Cured Mortar Bed

Install floor tile over a workable mortar bed or a cured mortar bed at the option of the Contractor. Conform to TCNA Hdbk for workable mortar bed materials and installation. Conform to TCNA Hdbk for cured mortar bed materials and installation. Provide minimum 1/4 inch to maximum 3/8 inch joints in uniformed width.

3.4.2 Dry-Set and Latex-Portland Cement

Use Latex-Portland cement mortar to install tile directly over properly cured, plane, clean concrete slabs in accordance with TCNA Hdbk. Use Latex Portland cement when installing porcelain ceramic tile.

3.4.3 Resinous Grout

When resinous grout is indicated, grout quarry tile with either furan or epoxy resin grout. Rake and clean joints to the full depth of the tile and neutralize when recommended by the resin manufacturer. Install epoxy resin grout in conformance with TCNA Hdbk. Install resin grout in accordance with manufacturer's printed installation instructions. Provide a coating of wax applied from the manufacturer on all tile installed and furan resin. Follow manufacturer's printed installation instructions of installed resin grout for proportioning, mixing, installing, and curing. Maintain the recommended temperature in the area and on the surface to be grouted. Protect finished grout of grout stain.

3.4.4 Ceramic Tile Grout

Prepare and install ceramic tile grout in accordance with TCNA Hdbk. Provide and apply manufacturer's standard product for sealing grout joints in accordance with manufacturer's recommendations.

3.4.5 Concrete Fill

Provide a 3500 psi concrete fill mix to dry as consistency as practicable. Spread, tamp, and screed concrete fill to a true plane, and pitch to drains or levels as shown. Thoroughly damp concrete fill before applying setting-bed material. Reinforce concrete fill with one layer of reinforcement, with the uncut edges lapped the width of one mesh and the cut ends and edges lapped a minimum 2 inch. Tie laps together with 18 gauge wire every 10 inch along the finished edges and every 6 inch along the cut ends and edges. Provide reinforcement with support and secure in the centers of concrete fills. Provide a continuous mesh; except where expansion joints occur, cut mesh and discontinue across such joints. Provide reinforced concrete fill under the setting-bed where the distance between the under-floor surface and the finished tiles floor surface is a minimum of 2 inches, and of the same thickness that the mortar setting-bed over the concrete fill with the thickness required in the specified TCNA Hdbk method.

3.5 INSTALLATION OF TRANSITION STRIPS

Install transition strips where indicated, in a manner similar to that of the ceramic tile floor and as recommended by the manufacturer. Provide thresholds full width of the opening. Install head joints at ends not exceeding 1/4 inch in width and grouted full.

3.6 CLEANING AND PROTECTING

Upon completion, thoroughly clean tile surfaces in accordance with manufacturer's approved cleaning instructions. Do not use acid for cleaning glazed tile. Clean floor tile with resinous grout or with factory mixed grout in accordance with printed instructions of the grout manufacturer. After the grout has set, provide a protective coat of a noncorrosive soap or other approved method of protection for tile wall surfaces. Cover tiled floor areas with building paper before foot traffic is permitted over the finished tile floors. Provide board walkways on tiled floors that are to be continuously used as passageways by workmen. Replace damaged or defective tiles. Submit copy of manufacturer's printed maintenance instructions.

-- End of Section --

SECTION 09 51 00

ACOUSTICAL CEILINGS

08/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A489	(2018; E 2018) Standard Specification for Carbon Steel Eyebolts
ASTM A580/A580M	(2018) Standard Specification for Stainless Steel Wire
ASTM A641/A641M	(2019) Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire
ASTM A653/A653M	(2019) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A1008/A1008M	(2016) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM B633	(2019) Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel
ASTM C635/C635M	(2017) Standard Specification for Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-In Panel Ceilings
ASTM C636/C636M	(2013) Standard Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels
ASTM C834	(2017) Standard Specification for Latex Sealants
ASTM E580/E580M	(2017) Standard Practice for Installation of Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels in Areas Subject to Earthquake Ground Motions

ASTM E1264 (2014) Acoustical Ceiling Products

ASTM E1414/E1414M (2011a; E 2014) Airborne Sound Attenuation Between Rooms Sharing a Common Ceiling Plenum

ASTM E1477 (1998a; R 2017; E 2018) Standard Test Method for Luminous Reflectance Factor of Acoustical Materials by Use of Integrating-Sphere Reflectometers

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350 (2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168 (2017) Adhesive and Sealant Applications

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-310-04 (2013; with Change 1, 2016) Seismic Design of Buildings

UNDERWRITERS LABORATORIES (UL)

UL 2818 (2013) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Approved Detail Drawings; G

SD-03 Product Data

Acoustical Ceiling Systems; G

SD-04 Samples

Acoustical Units; G

Acoustical Ceiling Tiles; G

SD-07 Certificates

Indoor Air Quality for Adhesives

Indoor Air Quality for Sealants

1.3 CERTIFICATIONS

1.3.1 Indoor Air Quality Certifications

1.3.1.1 Ceiling Tiles

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification by other third-party programs. Provide current product certification documentation from certification body.

1.3.1.2 Adhesives and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited in this Section.

1.4 DELIVERY, STORAGE. AND HANDLING

Deliver materials to the site in the manufacturer's original unopened containers with brand name and type clearly marked. Carefully handle and store materials in dry, watertight enclosures. Immediately before installation, store acoustical units for not less than 24 hours at the same temperature and relative humidity as the space where they will be installed in order to assure proper temperature and moisture acclimation.

1.5 ENVIRONMENTAL REQUIREMENTS

Maintain a uniform temperature of not less than 60 degrees F nor more than 85 degrees F and a relative humidity of not more than 70 percent for 24 hours before, during, and 24 hours after installation of acoustical units.

1.6 SCHEDULING

Complete and dry interior finish work such as plastering, concrete and terrazzo work before ceiling installation. Complete mechanical, electrical, and other work above the ceiling line; install and start operating heating, ventilating, and air conditioning systems in order to maintain temperature and humidity requirements.

1.7 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a one year period. Include an agreement to repair or replace acoustical panels that fail within the warranty period in the standard performance guarantee or warranty. Failures include, but are not limited to, sagging and warping of panels; rusting and manufacturers defects of grid system. Warrant Period, Acoustical Panels: (10) years from date of substantial completion, Suspension: (10) years from date of substantial completion, Ceiling System (30) years from date of substantial completion.

1.8 EXTRA MATERIALS

Furnish spare tiles, from the same lot as those installed, of each color at the rate of 5 tiles for each 1000 tiles installed.

1.9 OTHER SUBMITTAL REQUIREMENTS

Submit the following:

- a. Manufacturer's catalog showing UL classification of fire-rated ceilings giving materials, construction details, types of floor and roof constructions to be protected, and UL design number and fire protection time rating for each required floor or roof construction and acoustic ceiling assembly.
- b. Reports by an independent testing laboratory attesting that acoustical ceiling systems meet specified requirements. Data attesting to conformance of the proposed system to Underwriters Laboratories requirements for the fire endurance rating listed in UL Fire Resistance may be submitted in lieu of test reports.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide sound controlling units mechanically mounted on a ceiling suspension system for acoustical treatment. The unit size, texture, finish, and color must be as specified. The Contractor has the option to substitute inch-pound (I-P) Recessed Light Fixtures (RLF) for metric RLF. If the Contractor opts to furnish I-P RLF, other ceiling elements like acoustical ceiling tiles, air diffusers, air registers and grills, must also be I-P products. Coordinate the whole ceiling system with other details, like the location of access panels and ceiling penetrations, etc., shown on the drawings. The Contractor is responsible for all associated labor and materials and for the final assembly and performance of the specified work and products if I-P products are used. The location and extent of acoustical treatment must be as shown on the approved detail drawings. Submit drawings showing suspension system, method of anchoring and fastening, details, and reflected ceiling plan. Coordinate with paragraph RECLAMATION PROCEDURES for reclamation of mineral fiber acoustical ceiling panels to be removed from the job site. Manufacturer to be Armstrong or approved equal, see schedule.

2.1.1 Ceiling Attenuation Class and Test

Provide a ceiling system with an attenuation class (CAC) of 33 Min. for all areas and ceiling tile types when determined in accordance with ASTM

E1414/E1414M. Provide fixture attenuators over light fixtures and other ceiling penetrations, and provide acoustical blanket insulation adjacent to partitions, as required to achieve the specified CAC. Provide test ceiling continuous at the partition and assembled in the suspension system in the same manner that the ceiling will be installed on the project.

2.1.2 Ceiling Sound Absorption

Determine the Noise Reduction Coefficient (NRC) in accordance with ASTM C423 Test Method. Provide NRC of .55 min.

2.1.3 Light Reflectance

Determine light reflectance factor in accordance with ASTM E1477 Test Method. Provide Light Reflectance of .82 min.

2.2 ACOUSTICAL UNITS

Submit two samples of each type of acoustical unit and each type of suspension grid tee section showing texture, finish, and color. Conform acoustical units to ASTM E1264, Class A, and the following requirements:

2.2.1 Units for Exposed-Grid System A

2.2.1.1 Type

III (non-asbestos mineral fiber with painted finish). Provide Type III Acoustical Ceiling Tiles containing a minimum of 30 percent recycled content. Provide data identifying percentage of recycled content for Type III ceiling tiles. Provide certification of indoor air quality for Type III Ceiling Tiles.

2.2.1.2 Flame Spread

Class A, 25 or less

2.2.1.3 Pattern

See Reflected Ceiling Plan

2.2.1.4 Nominal Size

24 by 48 or 24 by 24 see drawings.

2.2.1.5 Finish

Factory-applied standard finish- Color White.

2.3 SUSPENSION SYSTEM

Provide Armstrong Prelude XL 15/16" Exposed Tee Grid suspension system conforming to ASTM C635/C635M or as directed on plans. Provide surfaces exposed to view of steel with a factory-applied white color baked-enamel finish. Provide wall molding having a flange of not less than 15/16 inch. Provide standard corners. Suspended ceiling framing system must have the capability to support the finished ceiling, light fixtures, air diffusers, and accessories, as shown. Provide a suspension system with a maximum

deflection of 1/360 of the span length. Conform seismic details to the guidance in UFC 3-310-04 and ASTM E580/E580M. At locations where GWB material is horizontally hung as soffits, use the suspension system method by Armstrong. Follow all manufacture's recommendations.

Provide Suspension System containing a minimum of 15 percent recycled content. Provide data identifying percentage of recycled content for suspension systems.

2.4 HANGERS

Provide hangers and attachment capable of supporting a minimum 300 pound ultimate vertical load without failure of supporting material or attachment.

2.4.1 Wires

Conform wires to ASTM A641/A641M, Class 1, 12 gauge ASTM A580/A580M, composition 302 or 304, condition annealed stainless steel, 0.08 inch (12 gauge) in diameter.

2.4.2 Straps

Provide straps of 1 by 3/16 inch galvanized steel conforming to ASTM A653/A653M, with a light commercial zinc coating or ASTM A1008/A1008M with an electrodeposited zinc coating conforming to ASTM B633, Type RS.

2.4.3 Rods

Provide 3/16 inch diameter threaded steel rods, zinc or cadmium coated.

2.4.4 Eyebolts

Provide eyebolts of weldless, forged-carbon-steel, with a straight-shank in accordance with ASTM A489. Eyebolt size must be a minimum 1/4 inch, zinc coated.

2.4.5 Anchorage Devices

Comply with ASTM C636/C636M for anchorage devices for eyebolts. Where aluminum is in contact with concrete, coat aluminum with bituminous paint or where exposed, with a chromatic primer and 2-coats of enamel paint.

2.5 ACCESS PANELS

Provide access panels that match adjacent acoustical units, designed and equipped with suitable framing and fastenings for removal and replacement without damage. Size panel to be not less than 12 by 12 inch or more than 12 by 24 inch.

- a. Attach an identification plate of 0.032 inch thick aluminum, 3/4 inch in diameter, stamped with the letters "AP" and finished the same as the unit, near one corner on the face of each access panel.
- b. Identify ceiling access panel by a number utilizing white identification plates or plastic buttons with contrasting numerals. Provide plates or buttons of minimum 1 inch diameter and securely attached to one corner of each access unit. Provide a typewritten card

framed under glass listing the code identification numbers and corresponding system descriptions listed above. Mount the framed card where directed and furnish a duplicate card to the Contracting Officer. Code identification system is as follows:

1. Fire detection/alarm system.
2. Air conditioning controls.
3. Plumbing system.
4. Heating and steam systems.
5. Air conditioning duct system.
6. Sprinkler system.
7. Intercommunication system.
8. Nurse's call system.
9. Pneumatic tube system.
10. Medical piping system.
11. Program entertainment.
12. Telephone junction boxes.
13. Detector X-ray.
14. Other.

2.6 ADHESIVE

Use adhesive as recommended by tile manufacturer.

2.7 FINISHES

Use manufacturer's standard textures, patterns and finishes as specified for acoustical units and suspension system members. Treat ceiling suspension system components to inhibit corrosion.

2.8 COLORS AND PATTERNS

Use colors and patterns for acoustical units and suspension system components as specified in Section 09 06 00 SCHEDULES FOR FINISHES

2.9 ACOUSTICAL SEALANT

Conform acoustical sealant to ASTM C834, nonstaining. Provide sealants used on the interior of the building (defined as inside of the weatherproofing system) that meet either emissions requirements of CDPH SECTION 01350 (use the office or classroom requirements, regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide certification of indoor air quality for Sealants.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

Examine surfaces to receive directly attached acoustical units for unevenness, irregularities, and dampness that would affect quality and execution of the work. Rid areas, where acoustical units will be cemented, of oils, form residue, or other materials that reduce bonding capabilities of the adhesive. Complete and dry interior finish work such as plastering, concrete, and terrazzo work before installation. Complete and approve mechanical, electrical, and other work above the ceiling line prior to the start of acoustical ceiling installation. Provide acoustical work complete with necessary fastenings, clips, and other accessories required for a complete installation. Do not expose mechanical fastenings in the finished work. Lay out hangers for each individual room or space. Provide hangers to support framing around beams, ducts, columns, grilles, and other penetrations through ceilings. Keep main runners and carrying channels clear of abutting walls and partitions. Provide at least two main runners for each ceiling span. Wherever required to bypass an object with the hanger wires, install a subsuspension system so that all hanger wires will be plumb.

3.1.1 Suspension System

Install suspension system in accordance with ASTM C636/C636M and as specified herein. Do not suspend hanger wires or other loads from underside of steel decking.

3.1.1.1 Plumb Hangers

Install hangers plumb and not pressing against insulation covering ducts and pipes. Where lighting fixtures are supported from the suspended ceiling system, provide hangers at a minimum of four hangers per fixture and located not more than 6 inch from each corner of each fixture.

3.1.1.2 Splayed Hangers

Where hangers must be splayed (sloped or slanted) around obstructions, offset the resulting horizontal force by bracing, countersplaying, or other acceptable means.

3.1.2 Wall Molding

Provide wall molding where ceilings abut vertical surfaces. Miter corners where wall moldings intersect or install corner caps. Secure wall molding not more than 3 inch from ends of each length and not more than 16 inch on centers between end fastenings. Provide wall molding springs at each acoustical unit in semi-exposed or concealed systems.

3.1.3 Acoustical Units

Install acoustical units in accordance with the approved installation instructions of the manufacturer. Ensure that edges of acoustical units are in close contact with metal supports, with each other, and in true

alignment. Arrange acoustical units so that units less than one-half width are minimized. Hold units in exposed-grid system in place with manufacturer's standard hold-down clips, if units weigh less than 1 psf or if required for fire resistance rating.

3.1.4 Caulking

Seal all joints around pipes, ducts or electrical outlets penetrating the ceiling. Apply a continuous ribbon of acoustical sealant on vertical web of wall or edge moldings.

3.1.5 Adhesive Application

Wipe back of tile to remove accumulated dust. Daub acoustical units on back side with four equal daubs of adhesive. Apply daubs near corners of tiles. Ensure that contact area of each daub is at least 2 inch diameter in final position. Press units into place, aligning joints and abutting units tight and uniform without differences in joint widths.

3.2 CEILING ACCESS PANELS

Locate ceiling access panels directly under the items which require access.

3.3 CLEANING

Following installation, clean dirty or discolored surfaces of acoustical units and leave them free from defects. Remove units that are damaged or improperly installed and provide new units as directed.

3.4 RECLAMATION PROCEDURES

Neatly stack ceiling tile, designated for recycling by the Contracting Officer, on 4 by 4 foot pallets not higher than 4 foot. Panels must be completely dry. Shrink wrap and symmetrically stack pallets on top of each other without falling over.

-- End of Section --

SECTION 09 65 00

RESILIENT FLOORING
08/10, CHG 3: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D4078	(2002; R 2015) Water Emulsion Floor Polish
ASTM E648	(2019a) Standard Test Method for Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source
ASTM F710	(2021) Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring
ASTM F1482	(2021) Standard Practice for Installation and Preparation of Panel Type Underlayments to Receive Resilient Flooring
ASTM F1861	(2021) Standard Specification for Resilient Wall Base
ASTM F1869	(2022) Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride
ASTM F2170	(2019a) Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168

(2017) Adhesive and Sealant Applications

UNDERWRITERS LABORATORIES (UL)

UL 2818

(2013) GREENGUARD Certification Program For
Chemical Emissions For Building Materials,
Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Resilient Flooring and Accessories; G

SD-03 Product Data

Resilient Flooring and Accessories; G

Adhesives

SD-04 Samples

Resilient Flooring and Accessories; G

SD-06 Test Reports

Moisture, Alkalinity and Bond Tests; G

SD-07 Certificates

SD-08 Manufacturer's Instructions

Surface Preparation; G

Installation; G

SD-10 Operation and Maintenance Data

Resilient Flooring and Accessories; G

1.3 CERTIFICATES

1.3.1 Indoor Air Quality

Submit required indoor air quality certifications and validations in one submittal package.

1.3.1.1 Floor Covering Materials

Provide Luxury Vinyl Tile, and wall base products certified to meet indoor air quality requirements by FLOORSCORE, UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification by other third-party programs. Provide current product certification documentation from certification body.

1.3.1.2 Adhesives, Caulking and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the building site in original unopened containers bearing the manufacturer's name, style name, pattern color name and number, production run, project identification, and handling instructions. Store materials in a clean, dry, secure, and well-ventilated area with ambient air temperature maintained above 68 degrees F and below 85 degrees F, stacked according to manufacturer's recommendations. Protect materials from the direct flow of heat from hot-air registers, radiators and other heating fixtures and appliances. Observe ventilation and safety procedures specified in the MSDS.

1.5 ENVIRONMENTAL REQUIREMENTS

Maintain areas to receive resilient flooring at a temperature above 68 degrees F and below 85 degrees F for 3 days before application, during application and 2 days after application, unless otherwise directed by the flooring manufacturer for the flooring being installed. Maintain a minimum temperature of 55 degrees F thereafter. Provide adequate ventilation to remove moisture from area and to comply with regulations limiting concentrations of hazardous vapors.

1.6 SCHEDULING

Schedule resilient flooring application after the completion of other work which would damage the finished surface of the flooring.

1.7 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a one year period.

1.8 EXTRA MATERIALS

Provide extra flooring material of each color and pattern at the rate of 5 tiles for each 1000 tiles installed. Provide extra wall base material composed of 20 linear feet of each type, color and pattern. Package all extra materials in original properly marked containers bearing the manufacturer's name, brand name, pattern color name and number, production

run, and handling instructions. Provide extra materials from the same lot as those installed. Leave extra stock at the site in location assigned by Contracting Officer.

PART 2 PRODUCTS

2.1 LUXURY VINYL TILE PROVIDE LVT AS NOTED ON DRAWINGS.

Provide certification of indoor air quality for Luxury Vinyl Tile.

2.2 WALL BASE

Conform to ASTM F1861, and as noted on plans.

2.3 NOT USED

2.4 ADHESIVES

Provide adhesives for flooring, base and accessories as recommended by the manufacturer and comply with local indoor air quality standards. Submit manufacturer's descriptive data, documentation stating physical characteristics, and mildew and germicidal characteristics.

Provide non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) that meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide aerosol adhesives used on the interior of the building that meet either emissions requirements of CDPH SECTION 01350 (use the office or classroom requirements, regardless of space type) or VOC content requirements of GS-36. Provide certification or validation of indoor air quality for adhesives.

2.5 SURFACE PREPARATION MATERIALS

Provide surface preparation materials, such as panel type underlayment, lining felt, and floor crack fillers as recommended by the flooring manufacturer for the subfloor conditions. Comply with ASTM F1482 for panel type underlayment products.

2.6 POLISH/FINISH

Provide polish finish as recommended by the manufacturer and conform to ASTM D4078 for polish.

2.7 CAULKING AND SEALANTS

Provide caulking and sealants in accordance with Section 07 92 00 JOINT SEALANTS.

2.8 MANUFACTURER'S COLOR, PATTERN AND TEXTURE

Provide color, pattern and texture for resilient flooring and accessories as indicated on the drawings. Provide floor patterns as specified on the drawings. Provide flooring in any one continuous area or replacement of damaged flooring in continuous area from same production run with same shade and pattern. Submit scaled drawings indicating patterns (including location

of patterns and colors) and dimensions. Submit manufacturer's descriptive data and three samples of each indicated color and type of flooring, base, moldings, and accessories sized a minimum 2-1/2 by 4 inch. Submit Data Package 1 in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

2.9 FIRE RESISTANCE TESTING REQUIREMENTS

Provide a minimum average critical radiant flux of [0.22][0.45] watts per square centimeter for flooring in corridors and exits when tested in accordance with ASTM E648.

PART 3 EXECUTION

3.1 EXAMINATION

Examine and verify that site conditions are in agreement with the design package. Report all conditions that will prevent a proper installation. Do not take any corrective action without written permission from the Government. Work will proceed only when conditions have been corrected and accepted by the installer. Submit manufacturer's printed installation instructions for all flooring materials and accessories, including preparation of substrate, seaming techniques, and recommended adhesives.

3.2 SURFACE PREPARATION

Provide a smooth, true, level plane for surface preparation of the flooring, except where indicated as sloped. Floor to be flat to within 3/16 inch in 10 feet. Prepare subfloor in accordance with flooring manufacturer's recommended instructions. Prepare the surfaces of lightweight concrete slabs (as defined by the flooring manufacturer) as recommended by the flooring manufacturer. Comply with ASTM F710 for concrete subfloor preparation. Floor fills or toppings may be required as recommended by the flooring manufacturer. Install underlayments, when required by the flooring manufacturer, in accordance with manufacturer's recommended printed installation instructions. Comply with ASTM F1482 for panel type underlayments. Before any work under this section is begun, correct all defects such as rough or scaling concrete, chalk and dust, cracks, low spots, high spots, and uneven surfaces. Repair all damaged portions of concrete slabs as recommended by the flooring manufacturer. Remove concrete curing and sealer compounds from the slabs, other than the type that does not adversely affect adhesion. Remove paint, varnish, oils, release agents, sealers, waxes, and adhesives, as required by the flooring product in accordance with manufacturer's printed installation instructions.

3.3 MOISTURE, ALKALINITY AND BOND TESTS

Determine the suitability of the concrete subfloor for receiving the resilient flooring with regard to moisture content and pH level by moisture and alkalinity tests. Conduct moisture testing in accordance with ASTM F1869 or ASTM F2170, unless otherwise recommended by the flooring manufacturer. Conduct alkalinity testing as recommended by the flooring manufacturer. Determine the compatibility of the resilient flooring adhesives to the concrete floors by a bond test in accordance with the flooring manufacturer's recommendations. Submit copy of test reports for moisture and alkalinity content of concrete slab, and bond test stating date of test, person conducting the test, and the area tested.

3.4 GENERAL INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

3.5 PLACING LUXURY VINYL TILES

Install luxury vinyl tile flooring using glue down installation. Install flooring and accessories in accordance with manufacturer's printed installation instructions. Prepare and apply adhesives in accordance with manufacturer's directions for installation method specified. Keep tile lines and joints square, symmetrical, tight, and even. Keep each floor in true, level plane, except where slope is indicated. Vary edge width as necessary to maintain full-size tiles in the field, no edge tile to be less than one-half the field tile size, except where irregular shaped rooms make it impossible. Cut flooring to fit around all permanent fixtures, built-in furniture and cabinets, pipes, and outlets. Cut, fit, and scribe edge tile to walls and partitions after field flooring has been applied.

3.6 PLACING MOULDING

Provide moulding where flooring termination is higher than the adjacent finished flooring and at transitions between different flooring materials. When required, locate moulding under door centerline. Moulding is not required at doorways where thresholds are provided.

3.7 CLEANING

Immediately upon completion of installation of flooring in a room or an area, dry and clean the flooring and adjacent surfaces to remove all surplus adhesive. Clean flooring as recommended in accordance with manufacturer's printed maintenance instructions and within the recommended time frame. As required by the manufacturer, apply the recommended number of coats and type of polish and finish in accordance with manufacturer's written instructions.

3.8 PROTECTION

From the time of installation until acceptance, protect flooring from damage as recommended by the flooring manufacturer. Remove and replace flooring which becomes damaged, loose, broken, or curled and wall base which is not tight to wall or securely adhered.

-- End of Section --

SECTION 09 68 00

CARPETING

11/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

CARPET AND RUG INSTITUTE (CRI)

CRI 104	(2015) Carpet Installation Standard for Commercial Carpet
CRI 105	(2015) Carpet Installation Standard for Residential Carpet
CRI GLP QM	(2017) Green Label Plus Quality Manual

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1113	(2016) Architectural Coatings
SCAQMD Rule 1168	(2017) Adhesive and Sealant Applications

UNDERWRITERS LABORATORIES (UL)

UL 2818	(2013) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that

will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Carpet; G

SD-04 Samples

Carpet; G

SD-06 Test Reports

Moisture and Alkalinity Tests; G

SD-08 Manufacturer's Instructions

Surface Preparation

SD-10 Operation and Maintenance Data

Cleaning and Protection

Maintenance Service

SD-11 Closeout Submittals

Warranty

1.3 CERTIFICATIONS

1.3.1 Indoor Air Quality Certifications

1.3.1.1 Floor Covering Materials

Provide carpet and cushion products certified to meet indoor air quality requirements by UL 2818 (GreenGuard) Gold, SCS Global Services Indoor Advantage Gold, CRI GLP QM or provide certification or validation by other third-party program that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the site in the manufacturer's original wrappings and packages clearly labeled with the manufacturer's name, brand name, size, dye lot number, and related information. Remove materials from packaging and store them in a clean, dry, well ventilated area protected from damage, soiling, and moisture, and maintain at a temperature above 60 degrees F for 2 days prior to installation. Do not store carpet near materials that may off gas or emit harmful fumes, such as kerosene heaters, fresh paint, or adhesives.

1.5 AMBIENT CONDITIONS

Maintain areas in which carpeting is to be installed at a temperature above 60 degrees F and below 90 degrees F for 2 days before installation, during installation, and for 2 days after installation. Provide temporary ventilation during work of this section. Maintain a minimum temperature of 55 degrees F thereafter for the duration of the contract.

1.6 WARRANTY

Provide manufacturer's standard performance guarantees or warranties including minimum ten year wear warranty, two year material and workmanship and ten year tuft bind and delamination.

PART 2 PRODUCTS

2.1 CARPET

Furnish first quality carpet that is free of visual blemishes, streaks, poorly dyed areas, fuzzing of pile yarn, spots or stains, and other physical and manufacturing defects. Provide carpet materials and treatments as reasonably nonallergenic and free of other recognized health hazards. Provide a static control construction on all grade carpets which gives adequate durability and performance. Submit manufacturer's catalog data and printed documentation stating physical characteristics, durability, resistance to fading, and flame resistance characteristics for each type of carpet material and installation accessory. Submit manufacturer's Product Data for 1) Carpet, 2) Moldings, and 3) Carpet Cushion. Also, submit Samples of the following:

- a. Carpet: Two "Production Quality" samples of a single unit measurement of each carpet proposed for use, showing quality, pattern, and color specified

2.1.1 Physical Characteristics for Modular Tile Carpet

2.1.1.1 Carpet Construction

See contract documents for carpet types.

2.1.1.2 Backing Materials

Provide primary backing materials of commercial grade quality at broadloom carpets. Carpet tile is self backed. Provide secondary backing to suit project requirements of those customarily used and accepted by the trade for each type of carpet.

2.2 ADHESIVES AND CONCRETE PRIMER

Comply with applicable regulations regarding toxic and hazardous materials. Provide water resistant, mildew resistant, nonflammable, and nonstaining adhesives and concrete primers for carpet installation as required by the carpet manufacturer. Non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) must meet either emissions requirements of CDPH SECTION 01350 (limit requirements for

either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) must meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of GS-36. Provide validation of indoor air quality for aerosol adhesives. Provide validation of indoor air quality for non-aerosol adhesives. Concrete primer products used on the interior of the building (defined as inside of the weatherproofing system) must meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1113. Provide validation of indoor air quality for concrete primer.

PART 3 EXECUTION

3.1 SURFACE PREPARATION

Do not install carpet on surfaces that are unsuitable and will prevent a proper installation. Prepare subfloor in accordance with flooring manufacturer's recommended instructions. Repair holes, cracks, depressions, or rough areas using material recommended by the carpet or adhesive manufacturer. Free floor of any foreign materials and sweep clean. Before beginning work, test subfloor with glue and carpet to determine "open time" and bond. Submit three copies of the manufacturer's printed Installation instructions for the carpet, including Surface Preparation, seaming techniques, and recommended adhesives and tapes.

3.2 MOISTURE AND ALKALINITY TESTS

Test concrete slab for moisture content and excessive alkalinity in accordance with CRI 104/CRI 105. Submit three copies of reports of Moisture and Alkalinity Tests including content of concrete slab stating date of test, person conducting the test, and the area tested.

3.3 PREPARATION OF CONCRETE SUBFLOOR

Do not commence installation of the carpeting until concrete substrate is at least 90 days old. Prepare the concrete surfaces in accordance with the carpet manufacturer's instructions. Match carpet, when required, and adhesives to prevent off-gassing to a type of curing compounds, leveling agents, and concrete sealer.

3.4 INSTALLATION

Perform all work by manufacturer's approved installers. Conduct installation in accordance with the manufacturer's printed instructions and CRI 104/CRI 105. Protect edges of carpet meeting hard surface flooring with molding and install in accordance with the molding manufacturer's printed instructions. Follow ventilation, personal protection, and other safety precautions recommended by the adhesive manufacturer. Continue ventilation during installation and for at least 72 hours following installation. Do not permit traffic or movement of furniture or equipment in carpeted area for 24 hours after installation. Complete other work which would damage the carpet prior to installation of carpet.

Do not install building construction materials that show visual evidence of biological growth.

3.5 CLEANING AND PROTECTION

Submit one digital copy of carpet manufacturer's maintenance instructions describing recommended type of cleaning equipment and material, spotting and cleaning methods, and cleaning cycles.

3.5.1 Cleaning

As specified in Section 01 78 00 CLOSEOUT SUBMITTALS. After installation of the carpet, remove debris, scraps, and other foreign matter. Remove soiled spots and adhesive from the face of the carpet with appropriate spot remover. Cut off and remove protruding face yarn. Vacuum carpet clean.

3.5.2 Protection

Protect the installed carpet from soiling and damage with heavy, reinforced, nonstaining kraft paper, plywood, or hardboard sheets. Lap and secure edges of kraft paper protection to provide a continuous cover. Restrict traffic for at least 48 hours. Remove protective covering when directed by the Contracting Officer.

3.6 REMNANTS

Manage waste as specified in the Waste Management Plan. Remove non-retained scraps from site and recycle appropriately.

3.7 MAINTENANCE

3.7.1 Extra Materials

Provide one box attic stock of carpet tile.

-- End of Section --

SECTION 09 90 00

PAINTS AND COATINGS

05/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

ACGIH 0100 (2015; Suppl 2002-2016) Documentation of the Threshold Limit Values and Biological Exposure Indices

ASTM INTERNATIONAL (ASTM)

ASTM D235 (2002; R 2012) Mineral Spirits (Petroleum Spirits) (Hydrocarbon Dry Cleaning Solvent)

ASTM D523 (2014; R 2018) Standard Test Method for Specular Gloss

ASTM D4214 (2007; R 2015) Standard Test Method for Evaluating the Degree of Chalking of Exterior Paint Films

MASTER PAINTERS INSTITUTE (MPI)

MPI 50 (2012) Primer Sealer, Latex, Interior

MPI 52 (2012) Latex, Interior, (MPI Gloss Level 3)

MPI 79 (2012) Primer, Alkyd, Anti-Corrosive for Metal

MPI 107 (2012) Primer, Rust-Inhibitive, Water Based

MPI 141 (2012) Latex, Interior, High Performance Architectural, Semi-Gloss (MPI Gloss Level 5)

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS SCS Global Services (SCS) Indoor Advantage

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC PA 1 (2016) Shop, Field, and Maintenance Coating of Metals

SSPC PA Guide 3 (1982; E 1995) A Guide to Safety in Paint Application

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1000

Air Contaminants

UNDERWRITERS LABORATORIES (UL)

UL 2818

(2013) GREENGUARD Certification Program For
Chemical Emissions For Building Materials,
Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

The current MPI, "Approved Product List" which lists paint by brand, label, product name and product code as of the date of contract award, will be used to determine compliance with the submittal requirements of this specification. The Contractor may choose to use a subsequent MPI "Approved Product List", however, only one list may be used for the entire contract and each coating system is to be from a single manufacturer. Provide all coats on a particular substrate from a single manufacturer. No variation from the MPI Approved Products List is acceptable.

Samples of specified materials may be taken and tested for compliance with specification requirements.

SD-03 Product Data

Coating; G

Sealant

SD-04 Samples

Color; G

SD-10 Operation and Maintenance Data

Coatings; G

1.3 CERTIFICATES

1.3.1 Indoor Air Quality

Submit required indoor air quality certifications in one submittal package.

1.3.1.1 Paints and Coatings

Provide paint and coating products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor

Advantage Gold or provide certification by other third-party programs.
Provide current product certification documentation from certification body.

1.4 QUALITY ASSURANCE

1.4.1 Field Samples and Tests

The Contracting Officer may choose up to two coatings that have been delivered to the site to be tested at no cost to the Government. Take samples of each chosen product as specified in the paragraph SAMPLING PROCEDURES. Test each chosen product as specified in the paragraph TESTING PROCEDURE. Remove products from the job site which do not conform, and replace with new products that conform to the referenced specification. Test replacement products that failed initial testing at no cost to the Government.

Another required testing is Batch Quality Conformance Testing to prove conformance of the manufacturer's paint to the specified MPI standard. This testing is accomplished before the materials are delivered to the job site. Test paint products as specified in the paragraph "Testing Procedure".

1.4.1.1 Sampling Procedure

The Contracting Officer, at their discretion, will select paint at random from the products that have been delivered to the job site for sample testing. The Contractor will provide one quart samples of the selected paint materials. Take samples in the presence of the Contracting Officer, and label, and identify each sample. Provide labels in accordance with the paragraph PACKAGING, LABELING, AND STORAGE of this specification.

1.4.1.2 Testing Procedure

Provide Batch Quality Conformance Testing for specified products, as defined by and performed by MPI. As an alternative to Batch Quality Conformance Testing, the Contractor may provide Qualification Testing for specified products above to the appropriate MPI product specification, using the third-party laboratory approved under the paragraph "Qualification Testing" laboratory for coatings. Include the backup data and summary of the test results within the qualification testing lab report. Provide a summary listing of all the reference specification requirements and the result of each test. Clearly indicate in the summary whether the tested paint meets each test requirement. Note that Qualification Testing may take 4 to 6 weeks to perform, due to the extent of testing required.

Submit name, address, telephone number, FAX number, and e-mail address of the independent third party laboratory selected to perform testing of coating samples for compliance with specification requirements. Submit documentation that laboratory is regularly engaged in testing of paint samples for conformance with specifications, and that employees performing testing are qualified. If MPI is chosen to perform the Batch Quality Conformance testing, the above submittal information is not required, only a letter is required from the Contractor stating that MPI will perform the testing.

1.5 SAFETY AND HEALTH

Apply coating materials using safety methods and equipment in accordance with the following:

Comply with applicable Federal, State, and local laws and regulations, and with the ACCIDENT PREVENTION PLAN, including the Activity Hazard Analysis as specified in Section 01 35 26 GOVERNMENT SAFETY REQUIREMENTS and in Appendix A of EM 385-1-1. Include in the Activity Hazard Analysis the potential impact of painting operations on painting personnel and on others involved in and adjacent to the work zone.

1.5.1 Safety Methods Used During Coating Application

Comply with the requirements of SSPC PA Guide 3.

1.5.2 Toxic Materials

To protect personnel from overexposure to toxic materials, conform to the most stringent guidance of:

- a. The applicable manufacturer's Safety Data Sheets (SDS) or local regulation.
- b. 29 CFR 1910.1000.
- c. ACGIH 0100, threshold limit values.

1.6 ENVIRONMENTAL CONDITIONS

Comply, at minimum, with manufacturer recommendations for space ventilation during and after installation.

1.6.1 Coatings

Do not apply coating when air or substrate conditions are:

- a. Less than 5 degrees F above dew point;
- b. Below 50 degrees F or over 95 degrees F, unless specifically pre-approved by the Contracting Officer and the product manufacturer. Do not, under any circumstances, violate the manufacturer's application recommendations.

1.7 COLOR SELECTION

Provide colors of finish coats as indicated or specified. Allow Contracting Officer or designer to select colors not indicated or specified. Manufacturers' names and color identification are used for the purpose of color identification only. Named products are acceptable for use only if they conform to specified requirements. Products of other manufacturers are acceptable if the colors match, colors indicated and the product conforms to specified requirements.

Tint each coat progressively darker to enable confirmation of the number of coats.

Provide color, texture, and pattern of wall coating systems in accordance with Section 09 06 00 SCHEDULES FOR FINISHES and on construction documents.

Submit manufacturer's samples of paint colors. Cross reference color samples to color scheme as indicated. Submit color stencil codes.

1.8 LOCATION AND SURFACE TYPE TO BE PAINTED

1.8.1 Painting Included

Where a space or surface is indicated to be painted, include the following unless indicated otherwise.

- a. Surfaces behind portable objects and surface mounted articles readily detachable by removal of fasteners, such as screws and bolts.
- b. New factory finished surfaces that require identification or color coding and factory finished surfaces that are damaged during performance of the work.
- c. Existing coated surfaces that are damaged during performance of the work.

1.8.1.1 Exterior Painting

Includes new surfaces, existing coated surfaces and as depicted on the construction drawings.

1.8.1.2 Interior Painting

Includes new surfaces, existing uncoated surfaces, existing coated surfaces] of the building and appurtenances as indicated and existing coated surfaces made bare by cleaning operations. Where a space or surface is indicated to be painted, include the following items, unless indicated otherwise.

- a. Exposed columns, girders, beams, joists, and metal deck; and
- b. Other contiguous surfaces.

1.8.2 Painting Excluded

Do not paint the following unless indicated otherwise.

- a. Surfaces concealed and made inaccessible by panelboards, fixed ductwork, machinery, and equipment fixed in place.
- b. Surfaces in concealed spaces. Concealed spaces are defined as enclosed spaces above suspended ceilings, furred spaces, attic spaces, crawl spaces, elevator shafts and chases.
- c. Steel to be embedded in concrete.
- d. Copper, stainless steel, aluminum, brass, and lead except existing coated surfaces.
- e. Hardware, fittings, and other factory finished items.
- f. Coatings installed per construction documents.

1.8.3 Exterior Painting of Site Work Items

Field coat the following items:

New and Existing Surfaces

- a. Repair of column(s) cracking requires repainting of column.

1.8.4 Definitions and Abbreviations

1.8.4.1 Qualification Testing

Qualification testing is the performance of all test requirements listed in the product specification. This testing is accomplished by MPI to qualify each product for the MPI Approved Product List, and may also be accomplished by Contractor's third party testing lab if an alternative to Batch Quality Conformance Testing by MPI is desired.

1.8.4.2 Batch Quality Conformance Testing

Batch quality conformance testing determines that the product provided is the same as the product qualified to the appropriate product specification. This testing must be accomplished by an MPI testing lab.

1.8.4.3 Coating

A film or thin layer applied to a base material called a substrate. A coating may be a metal, alloy, paint, or solid/liquid suspensions on various substrates (such as metals, plastics, wood, paper, leather, cloth). They may be applied by electrolysis, vapor deposition, vacuum, or mechanical means such as brushing, spraying, calendaring, and roller coating. A coating may be applied for aesthetic or protective purposes or both. The term "coating" as used herein includes emulsions, enamels, stains, varnishes, sealers, epoxies, and other coatings, whether used as primer, intermediate, or finish coat. The terms paint and coating are used interchangeably.

1.8.4.4 DFT or dft

Dry film thickness, the film thickness of the fully cured, dry paint or coating.

1.8.4.5 DSD

Degree of Surface Degradation, the MPI system of defining degree of surface degradation. Five (5) levels are generically defined under the Assessment sections in the MPI Maintenance Repainting Manual.

1.8.4.6 EPP

Environmentally Preferred Products, a standard for determining environmental preferability in support of Executive Order 13101.

1.8.4.7 EXT

MPI short term designation for an exterior coating system.

1.8.4.8 INT

MPI short term designation for an interior coating system.

1.8.4.9 micron / microns

The metric measurement for 0.001 mm or one/one-thousandth of a millimeter.

1.8.4.10 mil / mils

The English measurement for 0.001 in or one/one-thousandth of an inch, equal to 25.4 microns or 0.0254 mm.

1.8.4.11 mm

The metric measurement for millimeter, 0.001 meter or one/one-thousandth of a meter.

1.8.4.12 MPI Gloss Levels

MPI system of defining gloss. Seven (7) gloss levels (G1 to G7) are generically defined under the Evaluation sections of the MPI Manuals. Traditionally, Flat refers to G1/G2, Eggshell refers to G3, Semigloss refers to G5, and Gloss refers to G6.

Gloss levels are defined by MPI as follows:

Gloss Level	Description	Units at 60 degrees	Units at 85 degrees
G1	Matte or Flat	0 to 5	10 max
G2	Velvet	0 to 10	10 to 35
G3	Eggshell	10 to 25	10 to 35
G4	Satin	20 to 35	35 min
G5	Semi-Gloss	35 to 70	
G6	Gloss	70 to 85	
G7	High Gloss		

Gloss is tested in accordance with ASTM D523. Historically, the Government has used Flat (G1 / G2), Eggshell (G3), Semi-Gloss (G5), and Gloss (G6).

1.8.4.13 MPI System Number

The MPI coating system number in each Division found in either the MPI Architectural Painting Specification Manual or the Maintenance Repainting Manual and defined as an exterior (EXT/REX) or interior system (INT/RIN). The Division number follows the CSI Master Format.

1.8.4.14 Paint

See Coating definition.

1.8.4.15 REX

MPI short term designation for an exterior coating system used in repainting projects or over existing coating systems.

1.8.4.16 RIN

MPI short term designation for an interior coating system used in repainting projects or over existing coating systems.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to the coating specifications and standards referenced in PART 3. Submit product data sheets for specified coatings and solvents. Provide preprinted cleaning and maintenance instructions for all coating systems.

Submit Manufacturer's Instructions on Mixing: Detailed mixing instructions, minimum and maximum application temperature and humidity, potlife, and curing and drying times between coats.

PART 3 EXECUTION

3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED

Prior to surface preparation and coating applications, remove, mask, or otherwise protect hardware, hardware accessories, machined surfaces, radiator covers, plates, lighting fixtures, public and private property, and other such items not to be coated that are in contact with surfaces to be coated. Following completion of painting, reinstall removed items by workmen skilled in the trades. Restore surfaces contaminated by coating materials, to original condition and repair damaged items.

3.2 SURFACE PREPARATION

Remove dirt, splinters, loose particles, grease, oil, disintegrated coatings, and other foreign matter and substances deleterious to coating performance as specified for each substrate before application of paint or surface treatments. Remove oil and grease prior to mechanical cleaning. Schedule cleaning so that dust and other contaminants will not fall on wet, newly painted surfaces. Spot-prime exposed ferrous metals such as nail heads on or in contact with surfaces to be painted with water-thinned paints, with a suitable corrosion-inhibitive primer capable of preventing flash rusting and compatible with the coating specified for the adjacent areas.

3.2.1 Additional Requirements for Preparation of Surfaces With Existing Coatings

Before application of coatings, perform the following on surfaces covered by soundly-adhered coatings, defined as those which cannot be removed with a putty knife:

- a. Test existing finishes for lead before sanding, scraping, or removing. If lead is present, refer to paragraph Toxic Materials.
- b. Wipe previously painted surfaces to receive solvent-based coatings, except stucco and similarly rough surfaces clean with a clean, dry cloth saturated with mineral spirits, ASTM D235. Allow surface to dry. Wipe immediately preceding the application of the first coat of any coating, unless specified otherwise.

- c. Sand existing glossy surfaces to be painted to reduce gloss. Brush, and wipe clean with a damp cloth to remove dust.
- d. The requirements specified are minimum. Comply also with the application instructions of the paint manufacturer.
- e. Thoroughly clean previously painted surfaces specified to be repainted [damaged during construction] of all grease, dirt, dust or other foreign matter.
- f. Remove blistering, cracking, flaking and peeling or otherwise deteriorated coatings.
- g. Remove chalk so that when tested in accordance with ASTM D4214, the chalk resistance rating is no less than 8.
- h. Roughen slick surfaces. Repair damaged areas such as, but not limited to, nail holes, cracks, chips, and spalls with suitable material to match adjacent undamaged areas.
- i. Feather and sand smooth edges of chipped paint.
- j. Clean rusty metal surfaces as per SSPC requirements. Use solvent, mechanical, or chemical cleaning methods to provide surfaces suitable for painting.
- k. Provide new, proposed coatings that are compatible with existing coatings.

3.2.2 Existing Coated Surfaces with Minor Defects

Sand, spackle, and treat minor defects to render them smooth. Minor defects are defined as scratches, nicks, cracks, gouges, spalls, alligatoring, chalking, and irregularities due to partial peeling of previous coatings. Remove chalking by sanding so that when tested in accordance with ASTM D4214, the chalk rating is not less than 8.

3.3 APPLICATION

3.3.1 Coating Application

Comply with applicable federal, state and local laws enacted to insure compliance with Federal Clean Air Standards. Apply coating materials in accordance with SSPC PA 1. SSPC PA 1 methods are applicable to all substrates, except as modified herein.

At the time of application, paint must show no signs of deterioration. Maintain uniform suspension of pigments during application.

Unless otherwise specified or recommended by the paint manufacturer, paint may be applied by brush, roller, or spray. Use trigger operated spray nozzles for water hoses. Use rollers for applying paints and enamels of a type designed for the coating to be applied and the surface to be coated. Wear protective clothing and respirators when applying oil-based paints or using spray equipment with any paints.

Only apply paints, except water-thinned types to surfaces that are completely free of moisture as determined by sight or touch.

Thoroughly work coating materials into joints, crevices, and open spaces. Pay special attention to ensure that all edges, corners, crevices, welds, and rivets receive a film thickness equal to that of adjacent painted surfaces.

Apply each coat of paint so that dry film is of uniform thickness and free from runs, drops, ridges, waves, pinholes or other voids, laps, brush marks, and variations in color, texture, and finish. Completely hide all blemishes.

Touch up damaged coatings before applying subsequent coats. Broom clean and clear dust from interior areas before and during the application of coating material.

- a. Drying Time: Allow time between coats, as recommended by the coating manufacturer, to permit thorough drying, but not to present topcoat adhesion problems. Provide each coat in specified condition to receive next coat.
- b. Primers, and Intermediate Coats: Do not allow primers or intermediate coats to dry more than 30 days, or longer than recommended by manufacturer, before applying subsequent coats. Follow manufacturer's recommendations for surface preparation if primers or intermediate coats are allowed to dry longer than recommended by manufacturers of subsequent coatings. Cover each preceding coat or surface completely by ensuring visually perceptible difference in shades of successive coats.
- c. Finished Surfaces: Provide finished surfaces free from runs, drops, ridges, waves, laps, brush marks, and variations in colors.

3.3.2 Mixing and Thinning of Paints

Reduce paints to proper consistency by adding fresh paint, except when thinning is mandatory to suit surface, temperature, weather conditions, application methods, or for the type of paint being used. Obtain written permission from the Contracting Officer to use thinners. Verify that the written permission includes quantities and types of thinners to use.

When thinning is allowed, thin paints immediately prior to application with not more than 1 pin of suitable thinner per gallon. The use of thinner does not relieve the Contractor from obtaining complete hiding, full film thickness, or required gloss. Thinning cannot cause the paint to exceed limits on volatile organic compounds. Do not mix paints of different manufacturers.

3.3.3 Coating Systems

- a. Systems by Substrates: Apply coatings that conform to the respective specifications listed in the following Tables:

Table

Division 3. Exterior Concrete Paint Table
Division 4. Exterior Concrete Masonry Units Paint Table
Division 5. Exterior Metal, Ferrous and Non-Ferrous Paint Table
Division 6. Exterior Wood; Dressed Lumber, Paneling, Decking,
Shingles Paint Table
Division 9: Exterior Stucco Paint Table
Division 10. Exterior Cloth Coverings and Bituminous Coated
Surfaces Paint Table

Division 3. Interior Concrete Paint Table
Division 4. Interior Concrete Masonry Units Paint Table
Division 5. Interior Metal, Ferrous and Non-Ferrous Paint Table
Division 6. Interior Wood Paint Table
Division 9: Interior Plaster, Gypsum Board, Textured Surfaces
Paint Table

- b. Minimum Dry Film Thickness (DFT): Apply paints, primers, varnishes, enamels, undercoats, and other coatings to a minimum dry film thickness of 1.5 mil each coat unless specified otherwise in the Tables. Coating thickness where specified, refers to the minimum dry film thickness.
- c. Coatings for Surfaces Not Specified Otherwise: Coat surfaces which have not been specified, the same as surfaces having similar conditions of exposure.
- d. Existing Surfaces Damaged During Performance of the Work, Including New Patches In Existing Surfaces: Coat surfaces with the following:
 - (1) One coat of primer.
 - (2) One coat of undercoat or intermediate coat.
 - (3) One topcoat to match adjacent surfaces.
- e. Existing Coated Surfaces To Be Painted: Apply coatings conforming to the respective specifications listed in the Tables herein, except that pretreatments, sealers and fillers need not be provided on surfaces where existing coatings are soundly adhered and in good condition. Do not omit undercoats or primers.

3.4 COATING SYSTEMS FOR METAL

Apply coatings of Tables in Division 5 for Exterior and Interior.

- a. Apply specified ferrous metal primer on the same day that surface is cleaned, to surfaces that meet all specified surface preparation requirements at time of application.
- b. Inaccessible Surfaces: Prior to erection, use one coat of specified primer on metal surfaces that will be inaccessible after erection.
- c. Shop-primed Surfaces: Touch up exposed substrates and damaged coatings to protect from rusting prior to applying field primer.

- d. Surface Previously Coated with Epoxy or Urethane: Apply MPI 101, 1.5 mils DFT immediately prior to application of epoxy or urethane coatings.
- e. Pipes and Tubing: The semitransparent film applied to some pipes and tubing at the mill is not to be considered a shop coat. Overcoat these items with the specified ferrous-metal primer prior to application of finish coats.
- f. Exposed Nails, Screws, Fasteners, and Miscellaneous Ferrous Surfaces. On surfaces to be coated with water thinned coatings, spot prime exposed nails and other ferrous metal with latex primer MPI 107.

3.5 INSPECTION AND ACCEPTANCE

In addition to meeting previously specified requirements, demonstrate mobility of moving components, including swinging and sliding doors, cabinets, and windows with operable sash, for inspection by the Contracting Officer. Perform this demonstration after appropriate curing and drying times of coatings have elapsed and prior to invoicing for final payment.

3.6 WASTE MANAGEMENT

As specified in the Waste Management Plan and as follows. Do not use kerosene or any such organic solvents to clean up water based paints. Properly dispose of paints or solvents in designated containers. Close and seal partially used containers of paint to maintain quality as necessary for reuse. Store in protected, well-ventilated, fire-safe area at moderate temperature. Place materials defined as hazardous or toxic waste in designated containers.

3.7 PAINT TABLES

All DFT's are minimum values. Acceptable products are listed in the MPI Green Approved Products List, available at <http://www.specifygreen.com/APL/ProductIdxByMPInum.asp>.

3.7.1 Exterior Paint Tables

DIVISION 3: EXTERIOR CONCRETE PAINT TABLE

3.7.2 Interior Paint Tables

INTERIOR STEEL / FERROUS SURFACES

- A. Metal,
miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment: MPI INT 5.1R-G5 (Semigloss)
- | | | |
|---------|---------------|----------|
| Primer: | Intermediate: | Topcoat: |
| MPI 79 | MPI 141 | MPI 141 |
- System DFT: 5 mils for door frames and similar elements that are new or in area of new paint. See construction drawings.

DIVISION 9: INTERIOR PLASTER, GYPSUM BOARD, TEXTURED SURFACES PAINT TABLE

A. New and Existing, previously painted Wallboard not otherwise specified:

New; MPI INT 9.2A-G3 (Eggshell) / Existing; RIN 9.2A-G3 (Eggshell)
Primer: Intermediate: Topcoat:
MPI 50 MPI 52 MPI 52
System DFT: 4 mils]

-- End of Section --

SECTION 10 11 00

VISUAL DISPLAY UNITS

08/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B221	(2014) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM E84	(2018a) Standard Test Method for Surface Burning Characteristics of Building Materials

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

UNDERWRITERS LABORATORIES (UL)

UL 2818	(2013) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 DEFINITIONS OR ADMINISTRATIVE REQUIREMENTS

The term visual display board when used herein includes presentation boards, marker boards, tackboards, board cases, display track system and horizontal sliding units; submit manufacturer's descriptive data and catalog cuts plus manufacturer's installation instructions, and cleaning and maintenance instructions. Visual display boards must be from manufacturer's standard product line. Submit certificate of compliance signed by Contractor attesting that visual display boards conform to the requirements specified.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that

will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Visual Display Board; G

SD-04 Samples

Aluminum; G

Porcelain Enamel; G

Materials; G

1.4 CERTIFICATIONS

1.4.1 Indoor Air Quality

1.4.1.1 Indoor Air Quality for Visual Display Products

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party program that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the building site in the manufacturer's original unopened containers and store them in a clean dry area with temperature maintained above 50 degrees F. Stack materials according to manufacturer's recommendations. Visual display boards must be allowed to acclimate to the building temperature for 24 hours prior to installation.

1.6 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a one year period.

PART 2 PRODUCTS

2.1 MATERIALS

Submit section of core material showing the lamination of colored cork, natural cork, woven fabric, non-woven fabric, and vinyl wall covering. Submit sample of hardwood and plastic laminate finish, and glass type. Samples must be minimum 4 by 4 inches and show range of color.

2.1.1 Woven Fabric

Provide plain weave fabric. Fiber content must be 100 percent polyester. Minimum total weight must be 16 oz. plus or minus 0.5 oz. per lineal yard.

Fabric must have a Class A flame spread rating of 0-50 and smoke development rating of 0-450 in accordance with ASTM E84.

2.1.2 Aluminum

Aluminum frame extrusions must be alloy 6063-T5 or 6063-T6, conform to ASTM B221, and be a minimum 0.06 inches thick. Exposed aluminum must have an anodized, satin finish. Straight, single lengths must be used wherever possible. Joints must be kept to a minimum. Corners must be mitered and must have a hairline closure. Submit sections of frame, map rail, and chalktray.

2.1.3 Hardwood

Exposed hardwood for frames, cabinets, and cases must be oak, walnut or mahogany. Provide hardwood with a durable factory-applied stain and lacquer finish of a type standard with the manufacturer.

2.2 PRESENTATION BOARD

The presentation board must be a wall hung cabinet with lockable double doors. The doors must be attached to cabinet with piano hinges and have a catch or closure to keep doors closed when not in use. The interior of the cabinet must contain a porcelain enamel markerboard writing surface with chalk tray, a flip chart that can be hung on an interior door panel, and fabric covered tacksurface on the interior door panels. The cabinet must be as specified in the plans. The edge detailing must be rectilinear. Dry erase markings must be removable with a felt eraser or dry cloth without ghosting. Each unit must come complete with an eraser and four different color compatible dry erase markers. Two keys must be provided for each unit.

2.3 TACKBOARDS

Provide tackboards that meet the emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type). Provide certification or validation of indoor air quality for tackboards.

2.3.1 Vinyl Covered

Tackboard must have a vinyl wall covering laminated to a minimum 1/8 inch thick cork laminated to a minimum 3/8 inch thick insulation board or fiberboard, 1/4 inch thick cork laminated to a minimum 1/4 inch thick hardboard or particleboard 1/2 inch thick insulation board or fiberboard, and must have an aluminum frame.

2.3.2 Fabric Covered

Tackboard must have a woven fabric covering laminated to a minimum to a minimum 3/8 inch thick insulation board or fiberboard, and must have a frame as specified in the plans.

2.4 CASE FOR BOARD UNIT

The case for the board unit must be surface mounted and have hinged minimum 3/16 inch thick tempered glass doors that are lockable. Case must be

finished as specified in drawings. Mitered corners must be reinforced for rigidity. Doors must be equipped with continuous piano hinges. Door glass must be framed with the case material, and be reinforced at all corners. Door framing must not depend upon the glass for rigidity. Multiple door cases must have an elbow catch. The interior side of the back panel must be tackable and must be composed of a minimum 1/4 inch colored cork. Two keys must be provided for each unit.

2.5 COLOR

Finish colors for required items must be as specified in Section 09 06 00 SCHEDULES FOR FINISHES.

2.6 MENU BOARDS

Menu boards are flat screen TV boards with electrical and data wiring. See Drawing A301 for locations and installation instructions, including pertinent details. Provide required mounting brackets. When requiring Unistrut bracing at trusses, see Structural S901.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install items that show visual evidence of biological growth. Perform installation and assembly in accordance with manufacturer's printed instructions. Use concealed fasteners. Visual display boards must be attached to the walls with suitable devices to anchor each unit. furnish and install trim items, accessories and miscellaneous items in total, including but not limited to hardware, grounds, clips, backing materials, adhesives, brackets, and anchorages incidental to or necessary for a sound, secure, complete and finished installation. Installation must not be initiated until completion of room painting and finishing operations. Visual display boards must be installed in locations and at mounting heights indicated. Visual display boards must be installed level and plumb, and if applicable doors must be aligned and hardware must be adjusted. Damaged units must be repaired or replaced as directed by the Contracting Officer.

3.2 CLEANING

Writing surfaces must be cleaned in accordance with manufacturer's instructions.

-- End of Section --

SECTION 10 21 13

TOILET COMPARTMENTS

08/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M	(2017) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A167	(2011) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A336/A336M	(2018) Standard Specification for Alloy Steel Forgings for Pressure and High-Temperature Parts
ASTM A385/A385M	(2017) Standard Practice for Providing High-Quality Zinc Coatings (Hot-Dip)
ASTM A653/A653M	(2019) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B36/B36M	(2018) Standard Specification for Brass Plate, Sheet, Strip, and Rolled Bar
ASTM B86	(2018) Standard Specification for Zinc and Zinc-Aluminum (ZA) Alloy Foundry and Die Castings
ASTM B221	(2014) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes

INTERNATIONAL CODE COUNCIL (ICC)

ICC A117.1 COMM	(2017) Standard And Commentary Accessible and Usable Buildings and Facilities

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE AMS2460	(2013; Rev A) Plating, Chromium

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-60003

(Basic) Partitions, Toilet, Complete

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191

Americans with Disabilities Act (ADA)
Accessibility Guidelines for Buildings and
Facilities; Architectural Barriers Act (ABA)
Accessibility Guidelines

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Fabrication Drawings

Installation Drawings; G

SD-03 Product Data

Cleaning and Maintenance Instructions

Colors And Finishes

Anchoring Devices and Fasteners

Hardware and Fittings

Brackets

Door Hardware

Pilaster Shoes

Finishes; G

SD-04 Samples

Colors and Finishes; G

Hardware and Fittings

Anchoring Devices and Fasteners

SD-10 Operation And Maintenance Date

Plastic Identification; GSD-11 Closeout Submittals

1.3 CERTIFICATIONS

1.4 REGULATORY REQUIREMENTS

Conform to ICC A117.1 COMM code for access for the handicapped operation of toilet compartment door and hardware.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver materials in the manufacturer's original unopened packages with the brand, item identification, and project reference clearly marked. Store components in a dry location that is adequately ventilated; free from dust, water, other contaminants, and damage during delivery, storage, and construction.

1.6 WARRANTY

Provide certification or warranties that toilet partitions will be free of defects in materials, fabrication, finish, and installation and will remain so for a period of not less than one year after completion.

PART 2 PRODUCTS

2.1 SYSTEM REQUIREMENTS

Provide a complete and usable toilet partition system, including toilet enclosures, urinal screens, system of panels, hardware, and support components. Furnish the partition system from a single manufacturer, with a standard product as shown in the most recent catalog data. Submit Fabrication Drawings for metal toilet partitions and urinal screens consisting of fabrication and assembly details to be performed in the factory. Submit manufacturer's Cleaning and Maintenance Instructions with Fabrication Drawings for review. Refer to Architectural Drawings for manufacturer.

2.2 MATERIALS

2.2.1 Galvanized Steel Sheet

Provide galvanized steel sheet cold-rolled, stretcher-level, commercial quality material, conforming to ASTM A653/A653M. Conform surface preparation of material for painting to ASTM D6386, Method A.

2.2.2 Sound-Deadening Cores

Provide sound deadening consisting of treated kraft paper honeycomb cores with a cell size of not more than 1 inch. Resin-material content must weigh not less than 11 percent of the finished core weight. Expanded cores must be faced on both sides with kraft paper.

2.2.3 Anchoring Devices and Fasteners

Provide steel anchoring devices and fasteners hot-dipped galvanized after fabrication, in conformance with ASTM A385/A385M and ASTM A123/A123M. Conceal all galvanized anchoring devices.

2.2.4 Brackets

Wall brackets must be two-ear panel brackets, T-style, 1-inch stock. Provide stirrup style panel-to-pilaster brackets.

2.2.5 Hardware and Fittings

2.2.5.1 General Requirements

Conform hardware for the toilet partition system to CID A-A-60003 for the specified type and style of partitions. Provide hardware finish highly resistant to alkalis, urine, and other common toilet room acids. Comply latching devices and hinges for handicap compartments with 36 CFR 1191; provide stainless steel devices and hinges with door latches that operate without either tight grasping or twisting of the wrist of the operator. Submit three samples of each item, including anchoring devices and fasteners. Approved hardware samples may be installed in the work if properly identified.

Material	Conformance Standard
Cold-rolled sheet steel	ASTM A336/A336M, commercial quality
Zinc-base alloy	ASTM B86, Alloy AC41-A
Brass	ASTM B36/B36M, Alloy C26800
Aluminum	ASTM B221
Corrosion-resistant steel	ASTM A167, Type 302, 304

2.2.5.2 Finishes

- b. Finish must conform to SAE AMS2460, Class I, Type I.
- d. Corrosion-resistant steel must have a No. 4 finish.
- e. Exposed fasteners must match the hardware and fittings.

2.2.6 Door Hardware

2.2.6.1 Hinges

Hinges must be adjustable to hold in-swinging doors open at any angle up to 90 degrees and out swinging doors to 10 degrees. Provide self-lubricating hinges with the indicated swing. Hinges must be concealed with the thickness of the door, top and bottom and have the following type of return movement:

- c. Torsion-rod return movement

2.2.6.2 Latch and Pull

Latch and pull must be a combination rubber-faced door strike and keeper equipped with emergency access.

2.2.6.3 Coat Hooks

Coat hooks must be combination units with hooks and rubber tipped pins.

2.3 PARTITION PANELS AND DOORS

Fabricate partition panels and doors not less than 1 inch thick with face sheets not less than 0.0396 inch thick.

Provide painted steel toilet partitions and screens with recycled content of 27 percent minimum. Provide data identifying percentage of recycled content for painted steel partitions and screens.

2.3.1 Toilet Enclosures

Provide and conform toilet enclosures to CID A-A-60003, Type I, Style D, floor to ceiling hung. Furnish width, length, and height of toilet enclosures as shown. Provide a width of 1 inch. Finish surface of panels must be painted metal, Finish 1; 1/4 inch radius beveled edges. Reinforce panels indicated to receive toilet paper holders or grab bars for mounting of the items required. Provide grab bars to withstand a bending stress, shear stress, shear force, and a tensile force induced by 250 lbf. Grab bars must not rotate within their fittings.

2.3.2 Urinal Screens

Provide and conform urinal screens to CID A-A-60003, Type III, Style D, floor to ceiling hung. Provide finish for surface of screens as painted metal, Finish 1; 1/4 inch radius beveled edges. Furnish width and height of urinal screens as shown. Provide thickness of 1 inch. Secure wall hung urinal screens with a minimum of three wall stirrup brackets. 42 inch long, continuous flanges. Fabricate screens from the same types of panels and pilasters as the toilet partitions. Use corrosion-resistant stainless steel fittings and fasteners.

2.4 PILASTER SHOES

Provide shoes at pilasters to conceal floor-mounted anchorage. Pilaster shoes must be stainless steel. Height must be 3 inches.

2.5 HARDWARE

Provide hardware for the toilet partition system that conforms to CID A-A-60003 for the specified type and style of partitions. Provide hardware pre-drilled by manufacturer. Use a hardware finish that is highly resistant to alkalis, urine, and other common toilet room acids. Hardware includes: chrome plated non ferrous cast pivot hinges, gravity type, adjustable for door close positioning; nylon bearings; chrome plated door latch; door strike and keeper with rubber bumper; and cast alloy chrome plated coat hook and bumper. Provide latching devices and hinges for handicap compartments complying with 36 CFR 1191 and stainless steel door latches that operate without either tight grasping or twisting of the wrist of the operator. Use stainless steel, tamper proof type screws and bolts. Wall mounting brackets

must be continuous, full height, stainless steel, in accordance with toilet compartment manufacturer's instructions.

2.6 COLORS AND FINISHES

2.6.1 Colors

Provide manufacturer's standard color charts for color of finishes for toilet partition system components. Submit three samples showing a finished edge on two adjacent sides and core construction, each not less than 12-inch square. See finish schedule.

2.6.2 Finishes No. 1 Through No. 3

Conform partitions, panels, screen, and door finishes to CID A-A-60003 finished with Finish No. 1, baked enamel

PART 3 EXECUTION

3.1 PREPARATION

Take field measurements prior to the preparation of drawing and fabrication to ensure proper fits. Verify that field measurements, surfaces, substrates and conditions are as required, and ready to receive work. Verify correct spacing of plumbing fixtures. Verify correct location of built in framing, anchorage, and bracing. Report in writing to Contracting Officer prevailing conditions that will adversely affect satisfactory execution of the work of this section. Do not proceed with work until unsatisfactory conditions have been corrected.

3.2 METAL PARTITION FABRICATION

- a. Fabricate metal Partition Panels, doors, screens, and pilasters required for the project from galvanized-steel face sheets with formed edges. Face sheets must be pressure-laminated to the sound-deadening core with edges sealed with a continuous locking strip and corners mitered and welded. Ground all welds smooth. Provide concealed reinforcement for installation of hardware, fittings, and accessories. Surface of face sheets must be smooth and free from wave, warp, or buckle.
- b. Before application of an enamel coating system, solvent-clean galvanized-steel surfaces to remove processing compounds, oils, and other contaminants harmful to coating-system adhesion. After cleaning, coat the surfaces with a metal-pretreatment phosphate coating. After pretreatment, finish exposed galvanized-steel surfaces with a baked-enamel coating system as specified.
- c. Provide an enamel coating system consisting of a factory-applied baked acrylic enamel coating system. Coating system must be a durable, washable, stain-resistant, mar-resistant finish.

3.3 INSTALLATION

Do not install items that show visual evidence of biological growth. Install partitions rigid, straight, plumb, and level, with the panels centered between the fixtures. Provide a panel clearance of not more than

1/2 inch and secure the panels to walls and pilasters with not less than two wall brackets attached near the top and bottom of the panel. Locate wall brackets so that holes for wall bolts occur in masonry or tile joints. Secure Panels to pilasters with brackets matching the wall brackets. Provide for adjustment due to minor floor variations. Locate head rail joints at pilaster center lines. Install adjacent components for consistency of line and plane. Equip each door with hinges, one door latch, and one coat hook and bumper. Align hardware to uniform clearance at vertical edges of doors.

- a. Secure panels to hollow plastered walls with toggle bolts using not less than 1/4-20 screws of the length required for the wall thickness. Toggle bolts must have a load-carrying strength of not less than 600 pounds per anchor.
- b. Secure panels to ceramic tile on hollow plastered walls or hollow concrete-masonry walls with toggle bolts using not less than 1/4-20 screws of the length required for the wall thickness. Toggle bolts must have a load-carrying strength of not less than 600 pounds per anchor.
- c. Secure panels to solid masonry or concrete with lead or brass expansion shields designed for use with not less than 1/4-20 screws, with a shield length of not less than 1-1/2 inch. Expansion shields must have a load-carrying strength of not less than 600 pounds per anchor.
- d. Submit Installation Drawings for metal toilet partitions and urinal screens showing plans, elevations, details of construction, hardware, reinforcing and blocking, fittings, mountings and escutcheons. Indicate on drawings the type of partition, location, mounting height, cutouts, and reinforcement required for toilet-room accessories.

3.4 FINAL ADJUSTMENT

After completion of the installation, make final adjustments to the pilaster-leveling devices, door hardware, and other working parts of the partition assembly. Doors must have a uniform vertical edge clearance of approximately 3/16 inch and must rest open at approximately 30 degrees when unlatched.

3.5 CLEANING

Baked enamel finish must be touched up with the same color of paint that was used for the finish. Clean all surfaces of the work, and adjacent surfaces soiled as a result of the work, in an approved manner compliant with the manufacturer's recommended cleaning and protection from damage procedures until accepted. Remove all equipment, tools, surplus materials, and work debris from the site.

-- End of Section --

SECTION 10 28 13

TOILET ACCESSORIES

08/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C1036 (2016) Standard Specification for Flat Glass

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Finishes; G

Accessory Items; G

SD-10 Operation and Maintenance Data

1.3 CERTIFICATIONS

1.4 DELIVERY, STORAGE, AND HANDLING

Wrap toilet accessories for shipment and storage, then deliver to the jobsite in manufacturer's original packaging, and store in a clean, dry area protected from construction damage and vandalism.

1.5 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a 1 year period.

PART 2 PRODUCTS

2.1 MANUFACTURED UNITS

Provide toilet accessories where indicated in accordance with paragraph SCHEDULE. Porcelain type, tile-wall accessories are specified in Section 09 30 10 CEMENT TILING, QUARRY TILING, AND PAVER TILING. Provide each

accessory item complete with the necessary mounting plates of sturdy construction with corrosion resistant surface.

Provide stainless steel products listed herein manufactured from materials containing a minimum of 50 percent recycled content. Provide data identifying percentage of recycled content for stainless steel toilet accessories.

2.1.1 Anchors and Fasteners

Provide anchors and fasteners capable of developing a restraining force commensurate with the strength of the accessory to be mounted and suited for use with the supporting construction. Provide tamperproof design exposed fasteners with finish to match the accessory.

2.1.2 Finishes

Except where noted otherwise, provide the following finishes on metal:

Metal	Finish
Stainless steel	No. 4 satin finish
Carbon steel, copper alloy, and brass	Chromium plated, bright

2.2 ACCESSORY ITEMS

Conform to the requirements for accessory items specified below. Submit fasteners proposed for use for each type of wall construction, mounting, operation, and cleaning instructions and one sample of each other accessory proposed for use. Incorporate approved samples into the finished work, provided they are identified and their locations noted. Submit certificate for each type of accessory specified, attesting that the items meet the specified requirements.

2.2.1 Grab Bar (GB)

Provide an 18 gauge, 1-1/4 inch grab bar OD Type 304 stainless steel. Provide form and length for grab bar as indicated. Provide concealed mounting flange. Provide grab with satin finish. Furnish installed bars capable of withstanding a 500 pound vertical load without coming loose from the fastenings and without obvious permanent deformation. Allow 1-1/2 inch space between wall and grab bar. Manufacturer to be Bobrick, or approved equal.

2.2.2 Mirrors, Glass (MG)

Provide Type I transparent flat type, Class 1-clear glass for mirrors. Glazing Quality q1 1/4 inch thick conforming to ASTM C1036. Coat glass on one surface with silver coating, copper protective coating, and mirror backing paint. Provide highly adhesive pure silver coating of a thickness which provides reflectivity of 83 percent or more of incident light when viewed through 1/4 inch thick glass, free of pinholes or other defects. Provide copper protective coating with pure bright reflective copper,

homogeneous without sludge, pinholes or other defects, of proper thickness to prevent "adhesion pull" by mirror backing paint. Provide mirror backing paint with two coats of special scratch and abrasion-resistant paint and baked in uniform thickness to provide a protection for silver and copper coatings which will permit normal cutting and edge fabrication. Provide 1/2" stainless steel edge, top and bottom of mirror at vanity and 1/2" stainless steel edge at all four sides for full height mirrors.

2.2.3 Paper Towel Dispenser (PTD)

Refer to Section 2.2.4. To be part of Combination Electric Hand Dryer, Paper Towel Dispenser, Waste Receptacle.

2.2.4 Combination Paper Towel Dispenser/Waste Receptacle (PTDWR)

Provide recessed 3-in-1 Electric Handryer, Paper Towel Dispenser, and Waste Receptacle with a capacity of 400 sheets of C-fold towel. Design waste receptacle to be locked in unit and removable for service. Provide tumbler key locking mechanism. Provide waste receptacle capacity of 6.8 gallons. Fabricate a minimum 0.03 inch stainless steel welded construction unit with all exposed surfaces having a satin finish. Provide waste receptacle that accepts reusable liner standard for unit manufacturer. Manufacturer, American Specialties, Inc., simplicity 3-in-1 Model 64672-2 Stainless Steel.

2.2.5 Sanitary Napkin Disposer (SND)

Refer to Section 2.2.11, To be part of Combination Toilette Seat Cover Dispenser, Toilette Tissue Dispenser and Sanitary Napkin Disposal.

2.2.6 Sanitary Napkin and Tampon Dispenser (SNTD)

Provide sanitary napkin and tampon dispenser semi-recessed. Dispenser, including door of Type 304 stainless steel that dispense both napkins and tampons with a minimum capacity of 20 each. Furnish dispensing mechanism for complimentary operation. Hang doors with a full-length corrosion-resistant steel piano hinge and secure with a tumbler lock. Provide keys for coin box different from the door keys. Manufacture, Bobrick b-0864 or approved equal. See Accessory schedule and note that dispenser is surface mounted.

2.2.7 Waste Receptacle (WR)

Refer to Section 2.2.4. To be part of Combination Electric Hand Dryer, Paper Towel Dispenser, Waste Receptacle. See Accessory schedule and note that dispenser is surface mounted.

2.2.8 Toilet Seat Cover Dispenser (TSCD)

Refer to Section 2.2.11 To be part of Combination Toilette Seat Cover Dispenser, Toilette Tissue Dispenser and Sanitary Napkin Disposal.

2.2.9 Toilet Seat Cover/Tissue Dispenser/Waste Receptacle (TSCTDWR)

Provide stainless steel recessed mounted ADA stall, surface mounted (standard stall), toilet seat cover, tissue dispenser, and waste receptacle combination for sanitary napkin disposal (women's restroom only). Provide a

minimum of 500 seat covers and 2 standard tissue rolls for each dispenser. Provide fifty waste receptacle liners liner of type standard with the receptacle manufacturer. Furnish tumbler key lock locking mechanism. Manufacturer, Bobrick B3574 or approved equal for ADA Stall and B3579 for standard stall.

2.2.10 Electric Hand Dryer (EHD)

Refer to Section 2.2.4. To be part of Combination Electric Hand Dryer, Paper Towel Dispenser, Waste Receptacle.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install items that show visual evidence of biological growth. Provide the same finish for the surfaces of fastening devices exposed after installation as the attached accessory. Provide oval exposed screw heads. Install accessories at the location and height indicated. Protect exposed surfaces of accessories with strippable plastic or by other means until the installation is accepted. After acceptance of accessories, remove and dispose of strippable plastic protection. Coordinate accessory manufacturer's mounting details with other trades as their work progresses. After installation, thoroughly clean exposed surfaces and restore damaged work to its original condition or replace with new work.

3.1.1 Recessed Accessories

Fasten accessories with wood screws to studs, blocking or rough frame in wood construction. Set anchors in mortar in masonry construction. Fasten to metal studs or framing with sheet metal screws in metal construction.

3.1.2 Surface Mounted Accessories

Mount on concealed backplates, unless specified otherwise. Conceal fasteners on accessories without backplates. Install accessories with sheet metal screws or wood screws in lead-lined braided jute, PTFE or neoprene sleeves, or lead expansion shields, or with toggle bolts or other approved fasteners as required by the construction. Install backplates in the same manner, or provide with lugs or anchors set in mortar, as required by the construction. Fasten accessories mounted on gypsum board and plaster walls without solid backing into the metal or wood studs or to solid wood blocking secured between wood studs, or to metal backplates secured to metal studs.

3.2 CLEANING

Clean material in accordance with manufacturer's recommendations. Do not use alkaline or abrasive agents. Take precautions to avoid scratching or marring exposed surfaces.

-- End of Section --

SECTION 10 51 13

METAL LOCKERS

05/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A1008/A1008M	(2016) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-PRF-22750	(2014; Rev G; Notice 1 2019) Coating, Epoxy, High Solids
MIL-PRF-23377	(2012; Rev K) Primer Coatings: Epoxy, High Solids

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS AA-L-00486	(Rev J) Lockers, Clothing, Steel

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Types; G

Location; G

Installation

Numbering system

SD-03 Product Data

Material

Locking Devices

Lock Control Chart

Handles

Finish

Locker components

Assembly instructions

SD-04 Samples

Color chips; G

1.3 DELIVERY, HANDLING, AND STORAGE

Deliver lockers and associated materials in their original packages, containers, or bundles bearing the manufacturer's name and the name of the material. Protect from weather, soil, and damage during delivery, storage, and construction.

1.4 FIELD MEASUREMENTS

To ensure proper fits, make field measurements prior to the preparation of drawings and fabrication. Verify correct location.

1.5 QUALITY ASSURANCE

1.5.1 Color Chips

Provide a minimum of three color chips, not less than 3 inches square, of each color scheduled.

Government may request performance-characteristic tests on assembled lockers. Tests and results must conform to FS AA-L-00486. Lockers not conforming will be rejected.

PART 2 PRODUCTS

2.1 TYPES

Locker must have the following type and size in the location and quantities indicated. Locker finish colors will be as scheduled.

2.1.1 Double-Tier

Double-tier lockers must be as follows:

Type DTC-2: Double-tier locker 15 inches wide, 18 inches deep, and 72 inches high, attached to a 6-inch high closed base, Manufacturer Hadrian, Powder Coated series lockers. Two of the bottom lockers to be designated as ADA.

2.2 MATERIAL

2.2.1 Steel Sheet (Cold Rolled)

ASTM A1008/A1008M, commercial quality, minimized spangle material. Prepare material surfaces for powder coating finishing in accordance with FS AA-L-00486. Fabricate locker bodies from not less than 0.0239-inch thick steel sheet.

2.2.2 Finish

FS AA-L-00486.

Primer, MIL-PRF-23377; topcoat, MIL-PRF-22750 Powder Coating

2.2.2.1 Color

As selected.

2.3 COMPONENTS

2.3.1 Built-In Locks

FS AA-L-00486. Provide locking devices as a padlock eye in the door latching mechanism. 2 lockers are ADA compliant. They will be left unlocked.

2.3.2 Coat Hooks

FS AA-L-00486, chromium plated.

2.3.3 Hanger Rods

FS AA-L-00486.

2.3.4 Door Handles

FS AA-L-00486. Provide zinc alloy or steel handles with a chromium coating.

2.3.5 Doors

FS AA-L-00486, not less than 0.0598 inch thick steel sheet.

2.3.5.1 Hinges

In addition to the requirements of FS AA-L-00486, provide 5-knuckle hinges, minimum 2 inches high. Fabricate knuckle hinges from not less than 0.0787 inch thick steel sheet. Weld or bolt hinges to the door frame. Weld, bolt, or rivet hinges to the door.

2.3.5.2 Latching Mechanisms

FS AA-L-00486.

2.3.6 Latch Strikes

FS AA-L-00486. Fabricate from not less than 0.0787 inch thick steel sheet, except latch strike may be continuous from top to bottom and fabricated as part of the door framing.

2.3.7 Silencers

FS AA-L-00486.

2.3.8 Back and Side Panels, Tops, and Bottoms

FS AA-L-00486, not less than 0.0474 inch thick steel sheet.

2.3.9 Sloping Locker Tops

Provide sloping locker tops in addition to the locker-section flat tops. Sloping tops must be continuous in length. Provide fillers or closures at the exposed end of sloping tops. Fabricate sloping tops from not less than 0.0478-inch thick steel sheet.

2.3.10 Shelves

FS AA-L-00486. Fabricate from not less than 0.0598 inch thick steel sheet.

2.3.11 Legs

FS AA-L-00486.

2.3.12 Number Plates

FS AA-L-00486. Aluminum. Provide consecutive numbers from left with odd numbers on top and even numbers on bottom.

2.3.13 Label Holders

FS AA-L-00486.

2.3.14 Fastening Devices

Provide bolts, nuts, and rivets as specified in FS AA-L-00486.

PART 3 EXECUTION

3.1 ASSEMBLY AND INSTALLATION

Assemble lockers according to the locker manufacturer's instructions. Align lockers horizontally and vertically. Secure lockers to wall and base with screws as indicated. Bolt adjacent lockers together. Adjust doors to operate freely without sticking or binding and to ensure they close tightly.

3.2 NUMBERING SYSTEM

Install number plates on lockers consecutively with odd numbers on top and even numbers on bottom.

3.3 FIELD QUALITY CONTROL

3.3.1 Testing

Government may request performance-characteristic tests on assembled lockers in accordance with FS AA-L-00486. Lockers not conforming will be rejected.

3.3.2 Repairing

Remove and replace damaged and unacceptable portions of completed work with new.

3.3.3 Cleaning

Clean surfaces of the work, and adjacent surfaces soiled as a result of the work, in an approved manner. Remove equipment, surplus materials, and rubbish from the site.

-- End of Section --

SECTION 114000
FOODSERVICE EQUIPMENT

PART 1 - GENERAL

1.1 SECTION INCLUDES

- A. Foodservice equipment.

1.2 SCOPE OF WORK

- A. Furnish all labor, materials and services necessary for the procurement and installation of the equipment included in this section.
- B. Supervise and provide required instructions for work to be performed by other contractors in connection with requirements for all equipment included in this section.
- C. Specifications and drawings have been prepared to form the basis for coordination with the other trades on this Project, procurement, erection, start-up and adjustment of all equipment in this section. Plans and specifications are to be considered as mutually required by both. Work to be accomplished as called for in specifications and shown on drawings, so that all items of equipment are completely functional for purpose for which they were designed. When/if there is any discrepancy between drawings and specifications, bidders should seek clarification of any discrepancies from the Consultant prior to bidding.
- D. Should the drawings disagree between themselves, or the specifications with the drawings, the better quality, and more stringent, and greater quantity of work or materials is to be completed without any additional costs to the Owner.
- E. Secure and pay fees for all permits and licenses as required by all authorities having jurisdiction. Give all notices and comply with all laws, ordinances, rules, regulations and contract requirements bearing on the work.

1.3 RELATED DIVISIONS/SECTIONS

- A. Refer to General Conditions, Supplementary Conditions, and applicable provisions of Division 1 for additional instructions.
- B. Refer to Interior Design Divisions for applicable provisions and sections regarding décor finishes, applications, details, and special instructions relating to items specified in this Section. Applicable to Projects with items specified in this Section, with décor finishes and/or construction.

- C. Refer to Mechanical/Plumbing Divisions for applicable provisions and sections regarding mechanical services, including, but not limited to: floor sinks and floor drains, water gas and steam rough-ins, grease traps, steam traps, drain traps, atmospheric vents, valves, pipes and pipe fittings, ductwork, and other materials necessary to complete final connections to individual items as specified in the Section. Not work of this Section. Also included:
1. Piping and Insulation for fryer oil systems.
 2. Piping for remote pulping systems.
 3. All hood or ventilatory duct work and fans upstream from the connection position.
- D. Refer to Electrical Divisions for applicable provisions and sections regarding electrical services, including, but not limited to, rough-ins, standard voltage and low-voltage wiring, conduit, drop-cords, ceiling-mounted cord reel assemblies, disconnects and other materials necessary to complete final connections to individual items as specified in this Section. Not work of this Section. Also includes:
1. Installation of light fixtures furnished loose at cold storage rooms.
 2. Connection of cold storage room temperature alarm system to the building security system.
 3. Connection of hood fire suppression system to the building security system.
- E. Work included in other Divisions - Provision of all walls, floor, and/or ceiling/roof openings, and sealing thereof, as necessary for installation of items included in this section. Not work of this Section. Also includes:
1. Slab depressions reinforced concrete wearing bed and interior finished floor with coved base at prefabricated cold storage assemblies.
 2. Concrete or masonry platforms with finished top and coved base at perimeter, for raised setting of foodservice equipment: Divisions 03/09.
 3. Slab depressions to receive stainless steel drain trench liner/grate assemblies provided under this Section.
 4. Wall backing to support all wall mounted equipment.
 5. Conduit and piping sleeves for soda, beer/liquor, refrigeration, CO2 and drain lines through building ceilings and floors.
- F. Seismic Restraint of Equipment - Section XX XX XX, Seismic Restraint Requirements for Non-structural Components, as required by location.

1.4 DEFINITIONS

- A. Furnish - Supply and deliver to Project Site, ready for unloading, unpacking, assembly, installation, and similar operations.

- B. Install (set in place) - Operations at Project Site including actual unloading, unpacking, assembly, erecting, placing, anchoring, applying, finishing, curing, protecting, cleaning and similar operations, ready for final utility connections by other Divisions as appropriate.
- C. Provide - Furnish and install complete, ready for intended use, including any necessary initial training.
- D. Contractor - Refers to the Kitchen Equipment (Sub) Contractor in this Section. References to any other Contractor or Division will be specific, such as General Contractor, Plumbing (Sub) Contractor/Division, Electrical (Sub) Contractor / Division, Architect designated, etc.

1.5 LAWS, ORDINANCES, REGULATIONS AND STANDARDS

- A. Comply with the following in their current published form.
 - 1. Air Conditioning and Refrigeration Institute (A.R.I.): applicable regulations and references of the latest edition of standards for remote refrigeration system(s), components, and installation.
 - 2. American Gas Association (A.G.A.): standards for gas heated equipment and provide equipment with the A.G.A. seal. Automatic safety pilots to be provided on all equipment, where available.
 - 3. American National Standards Institute (A.N.S.I.): Z21-Series for gas-burning equipment. Provide labels indicating name of testing agency.
 - 4. American National Standards Institute (A.N.S.I.): B57.1 for compressed gas cylinder connections, and with applicable standards of the Compressed Gas Association for compressed gas piping.
 - 5. American National Standards Institute (A.N.S.I.): A40.4 and A40.6 for water connection air gaps and vacuum breakers. American Society of Heating, Refrigeration and Air Conditioning Engineers (A.S.H.R.A.E.): applicable regulations and references of the latest edition of standards for remote refrigeration system(s), components and installation.
 - 6. American Society of Mechanical Engineers (A.S.M.E.): Boiler Code requirements for steam generating and steam heated equipment and provide A.S.M.E. inspection stamp and registration with National Board.
 - 7. American Society for Testing and Materials (A.S.T.M.): C1036 for flat glass.
 - 8. American Society for Testing and Materials (A.S.T.M.): C1048 for heat-treated flat glass - Kind HS, Kind FT coated and uncoated glass.
 - 9. American Society for Testing and Materials (A.S.T.M.): F232-03 for pre-rinse spray units, and in compliance with Energy Policy Act of 2005 (EPAAct).
 - 10. American Welding Society (A.W.S.): D1.1 structural welding code.
 - 11. Energy Policy Act of 2005 (EPAAct 20005): water savings pre-rinse spray valves.

12. National Electric Code (N.E.C.): N.F.P.A. Volume 5 for electrical wiring and devices included with foodservice equipment, A.N.S.I. C2 and C73, and applicable NE.M.A. and N.E.C.A. standards.
13. National Electrical Manufacturers Association (N.E.M.A.): LD3 for high-pressure decorative laminates.
14. National Fire Protection Association (N.F.P.A.): applicable sections for exhaust hoods, ventilators, duct and fan materials, hoods fire suppression systems, wheel placement systems, construction, and installation; in addition to local codes and standards.
15. National Sanitation Foundation (NSF): latest Standards and Revisions, and as accredited by ANSI, IAS, NELAC, ISO, OSHA and SCC. Provide NSF Seal of Approval on all standard manufactured items included in this Project and listed in any NSF Certified Food Equipment Products Category, and on all items of custom fabricated work included in this Project. (UL Sanitation approval and seal accepted if acceptable to local code jurisdictions.
16. Sheet Metal and Air Conditioning Contractor's National Association (S.M.A.C.N.A.): latest edition of guidelines for seismic restraint of kitchen equipment, as applicable to project location. All seismic requirements shall be shown on all submittals. Submit requested information to the agencies and authorities having jurisdiction.
17. Underwriters Laboratories (U>L>): as applicable for electrical components and assemblies. Provide either U.L. labeled products or, where no labeling service is available, "recognized markings" to indicate listing in the U.L. "Recognized Component Index". (Canadian Standards Association or alternate testing lab's seals accepted if acceptable to local code jurisdictions.)
18. UL300 Standard: for wet chemical fire suppression systems for exhaust hoods/ventilators.
19. American with Disabilities Act (ADA): as applicable to this Project.
20. Refrigeration Service Engineers Society (R.S.E.S.): applicable regulations and references for the latest edition of standards for remote refrigeration system(s), components, and installation.
21. All refrigerants used for any purpose is to comply with the current Corp of Engineer requirement, and subsequent revisions and amendments. No CFC or HCFC refrigerants will be permitted on this Project.
22. All refrigeration components installation, repairs, and/or associated work on any refrigeration system, is to be performed by a Certified Refrigeration Mechanic thoroughly familiar with this type of commercial foodservice installation. ETL and other national and international recognized Testing and Listing Agency labels and certifications are acceptable in lieu of Listing Agencies indicated in these documents, if acceptable to the local code jurisdictions.
23. All applicable local codes, standards, and regulations.
24. All special local codes, standard, and regulations: such as (examples only) California Energy Commissions Regulations, Dade County requirements for walk-in cooler(s) and/or freezer(s).

25. For detention facilities projects (as applicable): applicable Correctional Standards. Verify the level of security and construction required with the Architect and provide all items in compliance.
- B. The Contract Documents shall prevail whenever they require larger sized or higher standards than are required by regulations.
- C. The above regulations shall govern whenever the Contract Documents require something that is deemed to violate the above regulations.
- D. No extra charge will be paid by Owner for furnishing items required by the regulations, but not specified and/or shown on the drawings.
- E. Rulings and interpretations of the enforcing agencies shall be considered a part of the regulations.

1.6 CONTRACTOR'S QUALIFICATIONS

- A. In addition to requirements of Related Sections 1.2.A
 1. Five (5) years minimum continuous operation under the same company name and ownership.
 2. Financial stability and ability to complete this Project.
 3. Comparable size and scope projects completed in the last five (5) years.
 4. Contractor to provide letter that states they can purchase, distribute, and install all items specified.
- B. Any sub-contractor or fabricator employed by Contractor:
 1. Is to comply with the same qualifications.
 2. Their name, address, and a summary of their experience and qualifications is to be submitted with the bid proposal.
 3. Fabrication sub-contractor shall be NSF, NEC, and UL approved at a minimum for fabrication of all items detailed within this specification and attending drawing set. Moreover, fabrication shop shall have the means and expertise to fully engineer and fabricate all counters, tables, quartz counter tops, food shields, etc. all in one manufacturing facility where specified as part of this document set.

1.7 BIDDING AND SUBSTITUTIONS

- A. Unless otherwise instructed by Division 1 bidding instructions, the Bidder shall provide pricing on primary manufacturer and model specified. These Contract Documents were designed and engineered using the primary manufacturer and model and are intended to be the Basis of Bid. Provide itemized prices for each item, along with

- cited accessories with separate total prices for delivery and installation. All city, state, occupational and government taxes which are included in a grand total package bid proposal. Bids shall be valid for thirty (30) days after bid deadline date and shall indicate same. Failure to comply with the above may be cause for rejection of the bid.
- B. Unless otherwise noted, substitutions may be submitted for consideration, but must be itemized at the end of the bid proposal.
 - C. Substitutions must be approved in writing by the Architect and/or Owner, prior to utilization in this Contract. A copy of the approval must be included with any submittals by Contractor.
 - D. Contractor shall provide all design/engineering services required to adjust in space, systems, utilities, etc. and pay all additional costs of utilities, construction or professional services that may be incurred due to the acceptance of any substitution.
 - E. Application for Substitution of Specified Food Service Equipment. This form shall be submitted in support of each suggestion of request to substitute an alternate manufacturer and/or model of equipment that is not included in the Division 114000 (Food Service Equipment) specifications.
 - F. Products not available for substitution. Products and specific manufacturers have been carefully chosen to support the Air Force's 2.0 Program and are not available for substitution.

APPLICATION FOR SUBSTITUTION OF SPECIFIED FOOD SERVICE EQUIPMENT

The decision to accept an unnamed alternate will be based exclusively on the information provided hereon and the Owner's or their designee's research and verifications of claims, which shall include sharing the information with manufacturer(s) of the originally specified equipment. Accordingly, any proprietary information regarding the proposed substitution should be so identified and submitted as an addendum to this form.

By submitting this application, the contractor guarantees the information is correct and accepts total responsibility for all additional costs that may directly or indirectly result from acceptance of the proposed substitution. It is the interest of the Contractor to declare in this form all benefits they will accrue to the Owner. Include the proposed manufacturer's data sheets, drawings and any other supporting information.

The original specifications describe the minimum standards of the equipment - proposed substitutions that do not meet or exceed this minimum standard or otherwise benefit the Owner will not be considered except in the case of an originally specified item that is no longer available. The Owner or their designee will be the sole authority regarding identifying specific features, capacities, etc. that are operationally critical. Acceptance of a proposed

substitution does not relieve the Contractor of responsibility for all direct or indirect costs associated with the substitution.

1. Date Submitted: _____
2. Item Number: _____ Description: _____ Quantity: _____
3. Specified Manufacturer: _____
Specified Model Number: _____
4. Proposed Manufacturer: _____
Proposed Model Number: _____

5. Does the proposed equipment incorporate all features and options expressed or implied by the specifications, including features and options that are provided as standard by the specified item?

☐☐

Yes No - describe (attach additional sheets as required):

6. Compare Utilities (attach additional sheets as required):

Specified: HW _____ CW _____ Gas (BTU) _____

Steam (BHP) _____ Electrical _____

Exhaust (cfm) _____ Duct size _____ Supply (cfm) _____

Duct size _____

Proposed: HW _____ CW _____ Gas (BTU) _____ Steam (BHP) _____

Electrical _____

Exhaust (cfm) _____ Duct size _____ Supply (cfm) _____ Duct size _____

7. Compare Dimension:

Specified: Left to Right _____ Front to Rear _____
Height _____

8. Does the proposed substitution require changes to the work to be provided by other trades?

☐☐

No Yes - describe (attach additional sheets as required):

9. Does the proposed substitution require changes or create any issues regarding adjacent or associated equipment (for instance: door swing interference; service access; air circulation)?

☐

No

☐

Yes - describe (attach additional sheets as required):

10. What benefits will the Owner realize as a result of this substitution (for instance: capital expense; energy savings, flexibility)? Provide specific information.

☐

There are no benefits to the Owner.

☐

The following will benefit the Owner - (attach additional sheets as required):

11. Are there any other considerations that should be evaluated?

12. Signature of Contractor's Representative:

Printed name of Contractor's Representative:

Certain Products and manufacturers have been tested and specifically chosen to support the Air Force Food 2.0 program are not available for substitution. Below are listed the manufacturer not available for substitution:

BSI	Sneeze Guards - XGuard
Turbo Chef	Double Batch Oven model HHD-9500 and High-Speed Oven
Traulsen	Up right and undercounter refrigeration
Structural Concepts	Cold grab n Go Cases

Rational/Alto Shaam	Combi ovens
Nu-Vu	Proofer/baking ovens
Hobart	Dishwasher, food prep equipment
Price Castle	Upright toaster
Cook Tec	Induction cookers
Vulcan	Cooking equipment
Hatco	Heated grab n go displays, toaster
Duke	Heated/holding bins
Nichols	Fabrication and counters
Randell	Refrigerated Prep tables with plexi covers
Turbo Air	Refrigerated Prep tables with plexi covers
Aerowerks	Dish room conveyor equipment
Vollrath	Cooking equipment
Viverau	Sparkling Water Dispenser
Advance Tabco	Handsinks
Metro	Shelving
Bally	Walk-in Cooler/Freezers
Captive Aire	Exhaust Hoods
Salvajor	Dishroom Disposal Equipment

Any substitutions must be submitted and approved ten (10) days prior to close of bids.

1.8 APPROVED SUBSTITUTIONS AND LISTED ALTERNATES

A. Substitutions approved as noted in Article 1.7, and/or any Listed Alternate manufacturers included in the Itemized Specifications Article 3.12, or added by Addendum, may be utilized, in lieu of the primary specified manufacturer with the following conditions:

1. These Contract Documents are designed and engineered using the primary specified manufacturer and model and are intended to be the Basis of Design and Bid. Contractor assumes complete responsibility for any deviations required due to utilization of a substitution/alternate manufacturer or model; including, but not limited to, fitting alternates into available space, providing directions for required changes, and assuming any associated cost for utility, building, architectural, or engineering changes.

2. Contractor is responsible for supplying the model which is as close as possible to the primary specified model in regard to general function, features, options, sizes, utility requirements, finish, operation, internal system engineering and listing approvals. If it is determined by the owner or their appointed representative at any time during the construction and installation process, and prior to the final acceptance of the Project, that the substitution/alternate model submitted is not equivalent to the primary specified model, the Contractor will assume all associated cost and implications required to replace the model submitted, with the correct model.
3. The bid proposal is to clearly state any proposed substitutions/alternates that are being offered for review, by including the manufacturer and model number, along with a current data sheet for each substitution/alternate, with any and all deviations between the primary specified manufacturer and the substitution/alternate manufacturer clearly defined. Technical brochures from manufacturers may not be acceptable as adequate information required for comparison. Complex alternates such as utility distribution systems, exhaust hoods, ventilators, refrigeration systems, etc. shall include a shop drawing specific to this Project.
4. Inclusion of an alternate manufacturer in Itemized Specifications Article 3.12 is not intended to indicate that there is an equal alternate unit to match every primary specified unit. It is the responsibility of the Contractor to ensure that the alternate unit submitted matches or exceeds the primary specified unit and meets the conditions as stated above.
5. Manufacturers not approved as substitutions or included as a Listed Alternates will not be permitted.

1.9 DISCREPANCIES

- A. Where discrepancies are discovered between the drawings and the specifications, regarding quality or quantity, the higher quality or the greater quantity is to be included in the Bid Proposal.
- B. Contractor to notify the Architect, in writing, of any discrepancies discovered, and await written clarification prior to proceeding with the items or areas in question.
- C. Contractor is responsible for verifying and coordinating all items provided in this Section with the drawings, specifications, manufacturer's requirements, submittals, actual site conditions, adjacent items, and associated (Sub-) Contractors to assure that there are no discrepancies or conflicts. This is to include, but not be limited to, quantities, dimensions, clearances required, direction of operation, door swings, utilities, fabrication details and methods, installation requirements, etc.

1.10 SUBMITTALS

- A. Provide one (1) digital (PDF) of all Submittals for review by the Design Team. After review process this set will be returned for copying and distribution.
- B. Substitutions must be approved in writing by the Architect and/or Owner prior to utilization in this contract. Substitutions must be submitted and approved ten (10) days prior to Bid. A copy of the approval must be included with any submittals.
- C. Contractor to review all submittals for compliance with the Contract Documents prior to submitting to the Design Team for review and is responsible for the accuracy of the information within their submittals.
- D. Contractor's use of any Design Team's digital contract drawings for basis of producing their submittal drawings is with the following conditions and understanding:
 - 1. Contractor shall assume complete liability and responsibility for accuracy, and for conformance and verification with the latest Architectural and Engineering drawings, actual field conditions, and all equipment provided.
 - 2. Contractor further assumes responsibility for coordination of their submittals with those of other Contractors and Sub-Contractors, as required.
 - 3. Submittals shall contain Contractor's notes, symbols, details, title block and information.
- E. Equipment Plan and Rough-In Drawings
 - 1. Submit ¼" (1:50) scale drawings in PDF format. These drawings are to include complete information on the work included in this Contract, with references to equipment as provided by others, and are to provide sufficient information for associated trades, contractors, and/or sub-contractors to complete their division of work associated with food service equipment included in this Contract. Include any additional information pertinent to the installation of this equipment.
 - 2. Special Conditions Drawings, dimensioned, sizing and locating the following conditions:
 - a. Slab depressions, cores, sleeves or block-outs (cold storage assemblies, drain trenches, piping, etc.).
 - b. Concrete or masonry platforms.
 - c. Pipe sleeves or roof jacks.
 - d. Wall openings or block-outs for pass-through equipment, recessed control panels, in-wall fire-protection system components, etc.
 - e. Blocking grounds or anchor plates required in walls for equipment support/attachment.
 - f. Above-ceiling hanger assemblies for support of exhaust hoods, utensil racks, etc.
 - g. Access panels in walls or ceiling for service of equipment.

- h. Ceiling pockets or recesses for unusually high equipment.
 - i. In-wall carriers for wall-hung or cantilevered equipment.
 - j. Ventilation for exhaust hoods, condensate hoods, ice machines, compressors.
 - k. Beverage conduit and sleeves.
 - l. Any other additional information pertinent to the installation of this equipment, including seismic bracing.
- 3. Electrical Rough-in Drawings dimensioned and providing the following information, but not limited to:
 - a. Electrical utility schedule.
 - b. Locations of rough-ins.
 - c. Locations of control panels.
 - d. Interwiring of walk-in freezer compressors to compressor rack control panel for defrost cycle.
 - e. Interwiring of control panels to equipment.
- 4. Plumbing Rough-In Drawings dimensioned, and providing the following information, but not limited to:
 - a. Plumbing utility schedule.
 - b. Locations of rough-ins.
 - c. Interconnection water filters assemblies to ice machine, beverage equipment, combi-ovens, steamers, etc.

F. Shop Drawings

- 1. Submit shop drawings for items of custom fabrication included in this contract in PDF format. Shop drawings are to be submitted a 3/4" (1:20) and/or 1-1/2" (1:10) scale and are to show dimensions, materials of construction, installation and relation of adjoining work requiring cutting or close fitting. Shop drawings are to also indicate reinforcements, anchorage and related work required for the complete installation of fixtures.
- 2. Submit shop drawings for any equipment requiring field assembly, including but not limited to, Waldorf cooking assemblies, pulper/extractor assemblies, remote refrigeration systems, walk-in coolers and/or freezers, exhaust hoods/ventilators, fire suppression system, utility distribution systems, pot/utility/cart/tray/ware washing assemblies/machines, conveyors, floor troughs, seismic anchoring details (as required) and fresh oil supply/waste oil recovery systems in PDF format.
- 3. Before proceeding with the fabrication or manufacture of any item, Contractor is responsible for verifying and coordinating all dimensions and details, with site dimensions, conditions, and adjacent equipment.
- 4. The Contractor is to clearly identify on drawings all differences between the bid documents and what is being provided. If any electrical, plumbing, gas or steam requirements are different than what the bid documents show, the Contractor will make a note on the drawings, identifying what is different.
- 5. Provide calculations and details for the support and anchorage of all kitchen equipment that is to be permanently fastened to the

building or utilities. Alternatively, show a note on the plans requiring that the kitchen equipment be supported and anchored per the SMACNA's "Guidelines for Seismic Restraints of Kitchen Equipment". Note the SMACNA Guideline page number that applies to each piece of equipment being anchored.

G. Product Data Submittal Manuals

1. Submit product data brochure(s) with a cover sheet, complete with detailed information on every item included in this section in PDF format. Detailed information is to include, but not be limited to, item number, description, quantity, model numbers, options and accessories provided, N.E.M.A. plug and receptacle configuration for applicable items, exact utility requirements, manufacturer's cut-sheets, reference to specific shop drawings, etc. Distribute one additional copy of installation and start-up instructions to the Installer. Every cover sheet and associated detailed submittal is to provide sufficient and complete information for the Design Team to verify that the Contractor understands the Contract requirements and is providing each item in compliance with the Contract documents. Cover sheets to also include associated items as listed on the Equipment Plan, but provided by others, and are to be noted as "Not in Section 114000 Contract Division".
2. Reproduction of any part of the Contract Specifications will not be acceptable as part or total of Contractor's Product Data Submittal Manuals. These Manuals are to be produced and assembled entirely by the Contractor, in numerical order according to Item numbers.
3. The cover sheet to clearly identify all differences between the bid documents and what is being provided. If any electrical, plumbing, gas or steam requirements are different than what the bid documents show, the Contractor will make a note on the cover sheet identifying what is different and why. If a model has been discontinued, the Contractor will make a note on the cover sheet and offer a replacement model.
4. The cover sheet to clearly identify all differences between the bid documents and what is being provided. If any electrical, plumbing, gas or steam requirements are different than what the bid documents show, the contractor will make a note on the cover sheet and offer a replacement model.

H. Design Team's review of submittal drawings, shop details, product data brochures, and operation and maintenance manuals is for general conformance with the design concept and contract documents. Review markings or comments are not to be construed as relieving Contractor from compliance with the contract documents, or departures there from. Contractor remains responsible for details and accuracy, confirming and correlating all quantities and dimensions, selecting fabrication processes, techniques of assembly, and performing their work in a safe, satisfactory, code-compliant and professional manner.

I. Commencement of purchasing or fabrication by the Contractor of any item(s) included in this Contract, prior to receipt of reviewed Submittals from the Design Team, shall be at the Contractor's own risk,

unless specifically instructed to do so in writing by the Owner, including the specific item numbers requested.

- J. Food Service Equipment Contractor shall verify requirements and equipment sizes or other characteristics necessary to represent Owner/Purveyor items completely on the shop drawing submittals even though they may be listed as "NIC/Not in Contract" in the Equipment Schedule/Item Specification sections of this document.

1.11 OPERATION AND MAINTENANCE DATA MANUALS

- A. Two (2) bound sets of manuals are to be furnished for items of standard manufacture on/or before the date of the first event to occur of the following: demo/start-up, start-up for intended use by the Owner/Operator, completion of Installation of kitchen equipment contract package, or final acceptance of installation by Owner. Manuals are to be in alphabetical order, according to manufacturer. Manufacturer's info is to include Tech Service's telephone number, email, and website address, where available.
- B. Provide a complete list of local service agencies for included manufacturers, complete with address and telephone numbers. Also, provide email and website addresses, where available.
- C. Provide electronic/digital media for maintenance, training, operation, etc., where available from the manufacturer.
- D. Manual shall also include a leak testing report for each, and every remote refrigerated system included under this Foodservice Equipment Section, as required in Article 2.6.A.6 Refrigeration Equipment of this Section.

1.12 AS BUILT/RECORD DOCUMENTS

- A. Time is of the essence, and acceptance constitutes assurance that the Contractor can, and will, obtain materials, equipment, and manpower to permit installation of the items included in this Section, on schedule. Contractor is to coordinate their work with the progress schedule, as prepared and updated periodically by the General Contractor or Construction Manager.
- B. Anticipated delays, not within the control of the Contractor, are to be noted in a written notification to the Architect immediately upon the Contractor's realization that delays are imminent.
- C. Failure of manufacturers to meet promised delivery dates will not grant relief to the Contractor for failure to meet schedules unless the

Contractor can establish, in writing, that orders were received by the manufacturer with reasonable lead times.

- D. Extra charges resulting from special handling or air shipment in order to meet the schedule will be paid by the Contractor if insufficient time was allowed in placing factory orders.

1.13 SCHEDULE

- A. Time is of the essence and acceptance constitutes assurance that the Contractor can and will obtain materials, equipment, and manpower, to permit installation of the items included in this Section, on schedule. Contractor is to coordinate their work with the progress schedule, as prepared and updated periodically by the General Contractor or Construction Manager.
- B. Anticipated delays, not withing the control of the Contractor, are to be noted in a written notification to the Architect, immediately upon the Contractor's realization that delays are imminent.
- C. Failure of manufacturers to meet promised delivery dates will not grant relief to the Contractor for failure to meet schedules, unless the Contractor can establish, in writing, that orders were received by the manufacturer, with reasonable lead times.
- D. Extra charges resulting from special handling or air shipment in order to meet the schedule will be paid by the Contractor if sufficient time was allowed in placing factory orders.

1.14 WARRANTY

- A. Unless otherwise noted in Related Divisions / Sections 1.2.A, items furnished are to be fully guaranteed against defects in workmanship, materials, and functionality for one (1) full year from the date of the first event to occur of the following: date of issue of Certificate of Occupancy (or the equivalent), start-up for intended use by the Owner/Operator, completion of installation of kitchen equipment contract package, or final acceptance of installation by Owner. Should a Temporary Certificate of Occupancy be issued for partial completion of work, the items furnished within that designated area are to be under warranty from the date of issue of that Certificate. Contractor or their service agent will make necessary repairs and replacements without charge to the Owner, and within a reasonable time.
- B. Additional Refrigeration Warranty: In addition to the one-year warranty requirements, as stated above, provide start-up and parts and labor for the first year, plus additional four-year extended warranty on compressors. Extended warranty is for provision of replacement compressor, determined to be defective by a certified refrigeration mechanic. However, verification of defective compressor, installation

of replacement compressor, recharging and repairs of system, will be the responsibility of the Owner. This includes all items with built-in or remote refrigeration systems.

- C. Periodic routine maintenance, servicing, adjustments, cleaning, etc., as required by the manufacturers included in this Project, are the responsibility of the Owner.
- D. Any and all parts or requirements for manufacturer's warranties to be in effect, whether noted in the itemized specifications, are to be provided or complied with by the Contractor. This is to include, but not be limited to: particular parts, accessories, or installation; installation supervision, start-up, and/or follow-up inspections required by factory trained, Certified, and/or authorized personnel. Factory training, Certification, and/or authorization is to be in effect at the time of bidding, installation, start-up, and warranty period of this Project.
- E. Unless otherwise noted in Related Divisions, manufacturer's warranties which comply with the requirements of this Warranty Article 1.17, are to be provided in lieu of Contractor's own warranties, where available. Copies of the written warranties are to be included in the O & M Manuals.

PART 2 - PRODUCTS

2.1 EQUIPMENT

- A. Refer to schedule on Foodservice Drawings and Section 3.12 Itemized Specifications for equipment included in this Section.

2.2 MATERIALS

A. Metals:

1. Stainless Steel AISI Type 201 or 301/304, hardest workable temper, and No. 4 directional polish. Unless otherwise noted or specified, or required by the manufacturer, 201 may be used wherever 302/304 is listed.
2. Galvanized Steel Sheet: ASTM A526, except ASTM A527 for extensive forming; ASTM A525, G90 zinc coating, chemical treatment.
 - a. Where painted finish is indicated, provide mill phosphatized treatment in lieu of chemical treatment.
3. Steel Sheet: ASTM A569 hot-rolled carbon steel.
4. Galvanized Steel Pipe: ASTM A53 or ASTM A120, welded or seamless, schedule 40, galvanized.
5. Steel Structural Members: Hot rolled or cold formed, carbon steel unless stainless steel is indicated.
 - a. Galvanized Finish (G.I.): ASTM A123 Hot-dipped zinc coating, applied after fabrication.
6. Aluminum: ASTM B209/B221 sheet, plate and extrusions (as indicated), alloy, temper and finish as determined by manufacturer/fabricator, except 0.40 mil natural anodized finish on exposed work, unless another finish is indicated.

- B. Plastic Laminate: NEMA LD3, Type 2, 0.050" (1.27mm) thick except Type 3, 0.042" (1.07mm) for post-forming smooth (non-textured). Color and texture as selected by Architect/Interior Designer.
1. Comply with N.S.F. Standard No. 35.
 2. Veneered with approved waterproof and heat proof cement. Rubber base adhesives are not acceptable.
 3. Applied directly over close grained plywood, such as solid Mahogany or solid Birch, of select, smooth, sanded stock to ensure a smooth ripple-free laminated surface, or commercial grade furniture particle board, Cortron or equal.
 4. Exposed faces and edges are to be faced with 1/16" (1.6mm) thick material. Corresponding backs are to be covered with approved backing and balancing sheet material.
- C. Millwork: No unfinished millwork, plywood, no particle board or wood framing (including backs, undersides, and all surfaces concealed from view) will be permitted. All unfinished surfaces or openings cut through finished surfaces are to be sealed to be water resistant, with excess plastic laminate material, Cortron (Melamine) material, backing materials, sealers, primers, finish paint, etc., to blend with specified finish materials.
- D. Hardwood Work Surfaces: Laminated edge grained hard maple (*Acer saccharum*), NHLA First Grade with knots, holes and other blemishes culled out, kiln dried at 8 percent or less moisture, waterproof glue, machined, sanded, and finished with N.S.F. approved oil-sealer.
- E. Simulated/Engineered Stone
1. Single-Source Responsibility for Simulated/Engineered Stone: Obtain each color, grade, finish, type, and variety of material or stone from a supplier with resources to provide materials of consistent quality in appearance and physical properties, including the capacity to cut and finish material without delaying the progress of the work.
 2. Single-Source Responsibility for Other Materials: Obtain each type of solid surface material and simulated/engineered stone accessory, sealant, and other materials from one manufacturer for each product.
 3. Installer Qualifications: Trained and approved by countertop manufacturer who has completed countertops similar in material, design, and extent to that indicated for project that has resulted in construction with a record of successful in-service performance.
 4. The Contractor is responsible for verification of delivered stone materials for quantities, defects, or damage within ten (10) days after delivery. No compensation will be allowed to the contractor for materials and labor that may be required to replace materials after this time period.
 5. Allowable Tolerances:
 - a. Variation in component size +/- 1/8 inch in 8 feet.
 - b. Maximum height of abrupt irregularities: 1/32 inch.
 - c. Location of openings: +/- 1/8 inch from indicated location.

6. Do not deliver countertop materials until painting and similar operations that could damage engineered stone materials have been completed in installation areas. If engineered stone materials must be stored in other than installation areas, store in only areas where environmental conditions comply with requirements specified in "Project Conditions" Article.
7. Handle materials to prevent damage to finished surfaces. Provide protective coverings to prevent physical damage or staining following installation for duration of project.
8. Environmental Limitations: Do not deliver or install simulated stone materials until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature and relative humidity at occupancy levels during the remainder of the construction period.
 - a. Maintain ambient temperature between 50 and 95-degrees F for 48 hours before, during, and for minimum of 7 days after installation.
9. Field Measurements: Where simulated stone materials are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements of Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
 - a. Locate concealed framing, blocking, and reinforcements that support simulated stonework by field measurements before being enclosed and indicate measurements on Shop Drawings.
10. Anchors: Select material, type, size and finish required for each substrate for secure anchorage. Provide nonferrous-metal or hot-dip galvanized anchors and inserts on inside face of exterior walls and elsewhere as required for corrosion resistance. Provide toothed-steel or lead expansion sleeves for drilled-in-place anchors.
11. Adhesive and sealant as recommended by engineered stone manufacturers.
12. Sink/bowl mounting hardware:
 - a. Manufacturer's approved bowl clips, brass inserts and fasteners for attachment of under mount sinks/bowls.
13. Fabrication
 - a. Fabricate components to greatest extent practical to sizes and shaped indicated in accordance with approved shop drawings and manufacturer's printed instructions.
 - b. Clean surfaces to remove loose and foreign matter that could impair adhesion.
 - c. Remove ridges and projections. Fill voids and depressions with patching compound compatible with setting materials.
 - d. Shop cut openings to maximum extent possible, to receive hardware, appliances, plumbing fixtures, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings.

- e. Rout and finish component edges with clean, sharp returns. Rout cutouts, radii and contours to template. Smooth edges. Repair or reject defective and inaccurate work.
- f. When necessary to cut and fit on site, provide materials with ample allowance for cutting. Provide trip for scribing and site cutting.
- g. Thickness: Provide thickness indicated, but not less than the following:
 - i. Countertop: [3/4] [1-1/4] inch[es]
 - ii. Back and End Splashes: 3/4 inch, unless shown otherwise.

F. Stone

1. Single-Source Responsibility for Stone: Obtain each color, grade, finish, type, and variety of stone from a supplier with resources to provide materials of consistent quality in appearance and physical properties, including the capacity to cut and finish material without delaying the progress of work.
2. Single-Source Responsibility for Other Materials: Obtain each type of stone accessory, sealant, and other materials from one manufacturer for each product.
3. Installer Qualifications: Engage an experienced installer who have completed quartz countertops similar in material, design, and extent to that indicated for project that has resulted in construction with a record of successful in-service performance.
4. The Contractor is responsible for verification of delivered stone materials for quantities, defects, or damage within ten (10) days after delivery. No compensation will be allowed from the contractor for materials and labor that may be required to replace materials after this time period.
5. Allowable Tolerances:
 - a. Variation in component size +/- 1/8 inch in 8 feet.
 - b. Maximum height of abrupt irregularities: 1/32 inch.
 - c. Location of openings: +/- 1/8 inch from indicated location.
6. Do not deliver countertop materials until painting and similar operations that could damage stone materials have been completed in installation areas. If stone materials must be stored in other than installation areas, store only in areas where environmental conditions comply with requirements specified in "Project Conditions" Article.
7. Deliver materials to project site in undamaged condition.
8. Store and handle stone and related materials to prevent their deterioration or damage due to moisture, temperature changes, contaminants, corrosion, breakage, chipping, or other causes.
 - a. Do not use pinch or wrecking bars.
 - b. Lift with wide-belt-type slings where possible. Do not use wire rope or ropes containing tar or other substances that

- might cause staining. If required to move stone, use wood rollers with cushions at end of wood slides.
 - c. Store stone on wood skids or pallets covered with non-staining, waterproof membrane.
 - d. Place and stack skids and stones to distribute weight evenly and to prevent breakage or cracking of stones.
 - e. Protect stored stone from weather with waterproof, non-staining covers or enclosures, but allow air to circulate around stones.
 - f. Store cementitious materials off the ground, under cover, and in dry location.
9. Environmental Limitations: Do not deliver or install stone materials until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature and relative humidity at occupancy levels during the remainder of the construction period.
- a. Maintain ambient temperature between 50- and 95-degrees F for 48 hours before, during and for minimum 7 days after installation.
10. Field Measurements: Verify dimensions of construction to receive stone countertops by field measurements before fabrication and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the work.
- a. Established Dimensions: Where field measurements cannot be made without delaying the work, establish dimensions and proceed with fabricating countertops without field measurements. Provide allowance for trimming at site and coordinate construction to ensure actual dimensions correspond to established dimensions.
11. Comply with referenced standards and other requirements indicated applicable to each type of material required.
12. Provide matched slabs, coordinated for each type, variety, color, and quality of stone required.
13. The use of colored tints, dyes, or waxes applied to stone shall NOT be permitted.
14. Adhesives
- a. Stone seam adhesive, 2-part epoxy or polyester stone adhesive formulated specifically for bonding stone to stone, with an initial set time of not more than 2 hours at 70 deg F
 - b. Water-cleanable epoxy adhesives, ANSI A118.3, water cleanable, tile-setting epoxy adhesive.
 - c. Color to match stone or clear.
 - d. Use installation adhesives that have a VOC content 65 g/l or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24) or listed in VOC limit tables in Section 01 81 19 "Indoor Air Quality Requirements". Products furnished shall comply with whichever content requirement is more stringent.
15. Stone Sealants
- a. Sealant for countertops, clear silicone sealant complying with requirements of Section 07 92 00 "Joint Sealants".
 - b. For sealants used inside of vapor barrier, provide sealants that have a VOC content of 250 g/l or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24) or listed in

VOC limit tables in Section 01 81 18 "Indoor Air Quality Requirements". Products furnished shall comply with whichever is more stringent.

16. Stone sealers
 - a. Penetrating sealer: Penetrating sealer that protects the exposed faces of stone and grout from staining. Sealer shall be UV transparent, non-yellowing, VOC compliant, mold and mildew resistant and USDA approved as safe food handling surfaces. Material shall exceed ADA standards for slip resistance at traffic areas.
 - b. For sealers used inside of the vapor barrier, provide sealers that have a VOC content of 250 g/l or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24) or listed in VOC limit tables in Section 01 81 19 "Indoor Quality Requirements". Products furnished shall comply with whichever is the more stringent.
17. Only quartz is accepted no granite or marble are allowed unless in non-food areas.
18. Cutouts and holes for lavatory sinks and fittings
 - a. Undercounter lavatories: Make cutouts for undercounter lavatories in shop using template or pattern furnished by lavatory manufacturer. Form cutouts to smooth even curves with edges at right angles to the top. Ease juncture of cutout edges with tops and finish edges to match tops.
19. Fittings: Drill countertops in shop for plumbing fittings, undercounter soap dispensers and similar items.

G. Insulation

1. For low temperature applications, such as ice bins, cold pans or fabricated under counter freezers, use urethan rigid foam board or foamed in place, not less than 2" (50 MM) thick, except that vertical surface of cold pans and ice bins may be 1" (25MM) thick. Insulation to be bonded at joints to prevent condensation on exterior.
2. For refrigerated applications such as fabricated undercounter refrigerators use urethan rigid foam or foamed in place or Styrofoam rigid foam board 2" (50MM) thick bonded at joints. No fiberglass insulation will be permitted.
3. For heated type applications, such as plate warmers, use block type rock wool, minimum 1" (25MM) or Marinite I as noted in #4 below.
4. At corners subject to direct or indirect heat from heating and cooking equipment use 1" (25MM) thick BNZ Materials, Inc. (303-978-1199) Marinite I or equal to insulate between counter and heat source. In addition, provide a 1" (25MM) minimum air space between the heat source and the insulation.
5. All insulation is to be fully or enclosed in 16 gauge (1.6MM) stainless steel.

H. Joint Materials

1. Sealants: waterproof and mildew resistant silicone sealant with Shore A hardness of 30 except for 45 if subject to traffic and minimum service temperature range of -60 to 400°F. Sealant to be NSF Standard #51 Listed, FDA and USDA approved for use in food zones. Surfaces cleaning and sealants installation to comply with applicable requirements of FDA, USDA and NSF Standards and accepted foodservice installation practices.
2. Backer rod: For 3/8" (9.5MM) or larger joints to be polyurethane rod stock larger than joint width.
3. Gaskets to be solid or hollow (but not cellular) neoprene or polyvinyl chloride, light grey with a minimum of 40 hardness, self-adhesive or prepared for either adhesive application or mechanical anchorage.

I. Paint and coatings

1. Provide the types of painting and coating materials which after drying or curing are suitable for use in conjunction with foodservice and which are durable, non-toxic, non-dusting, non-flaking, mildew resistant and comply with NSF Standards and governing regulation for foodservice.
2. Galvanize repair paint - MIL-P-21035.
3. Sound deadener: NSF listed sound deadening material such as latex sound deadener for internal surfaces or metal work and underside of metal counters and tables between work top and underbracing. Verify sound deadening requirements or restrictions with current local requirements.
4. Pretreatment: SSPC-PT2 or PT3 or FS TT-C490.
5. Primer coating for metals: FS TT-P-86, type suitable for baking where indicated.
6. Enamel for metal: Synthetic type FA TT-P-491, type suitable for baking where indicated.

2.3 FABRICATED PRODUCTS

- A. Hardware (also refer to article 2.4 Fabrication of Metal Works in general and paragraphs O. Doors 1-3 and P. Drawer assemblies 1-6 specifically for additional requirements.

1. General: Manufacturer's standard but not less than ANSI 156.9 Type 2 (Institutional) satin finish stainless steel or dull chrome finish on brass, bronze, or steel.
2. Hinged door hardware: Stainless steel hinged doors to be mounted with heavy duty or equal NSF heavy duty hinges with Component Hardware Group Model No. P62-1010 pulls or equal, or full length pulls as per individual itemized specifications and shown on standard detail FSD1-24. Catches to be heavy-duty magnetic type except as otherwise indicated. Millwork cabinet hinged doors to be mounted with Blum 95 CLIP top thick door all metal hinges,

nickel plated with 3-dimensional adjustment or equal, or as per individual itemized specifications.

3. Drawer hardware: Slides to be 200 lbs. (90 kilograms) minimum capacity per pair, 201 or 300 series stainless steel, full extension, side-mounting, self-closing type with stainless steel ball bearings and positive stops. Component Hardware Group Series S52 or equal. Pulls to be Component Hardware Group Model P62-1012 or equal, or full length pulls as per individual itemized specifications and shown on Standard Detail FSD1-24.
4. Sliding door hardware: Sliding doors to be mounted on large, quiet ball bearing rollers in 14 gauge (2MM) stainless steel guide pins and not channel tracks for doors.
5. All hardware to be with manufacturers name and number so that broken or worn parts may be replaced.

B. Casters

1. Type and size as recommended by caster manufacturer, NSF approved for type and weight of equipment supported, normally 5" (127MM) diameter heavy duty, ball bearing, solid or disc wheel with non-marking grease proof rubber, neoprene or polyurethane tires, unless otherwise specified. Minimum width of tread to be 1-3/16" (30MM). Minimum capacity per caster or be 250 lbs. (113 KG) unless otherwise noted in itemized specifications.
2. Solid material wheels to be provided with stainless steel rotating wheel guard.
3. To be sanitary, have sealed wheel and swivel bearings and polished plated finish per NSF.
4. Unless otherwise indicated, equip each item with two (2) swivel type casters and two (2) fixed casters with footbrakes on two (2) casters.
5. Unless item is equipped with another form of all all-round protective bumper, provide circular rotating bumper above each caster, 5" (127 MM) diameter tire or light grey synthetic rubber (hollow or closed cell) on cadmium-plated disc.

C. Plumbing fittings, trim and accessories

1. General: Where exposed or semi-exposed, provide bright chrome plated brass or polished stainless-steel units. Provide copper or brass where not exposed.
2. Vacuum breakers: provide with foodservice equipment as listed in the itemized specifications.
3. Water outlets: at sinks and at other locations where water is supplied (by manual or remote control) furnish commercial quality faucets, valves, dispenser or fill devices of type and size indicated and as required to operate as indicated.
4. Waste fittings: except as otherwise indicated, furnish 2" (50 MM) remote-lever ball valve type waste valve and 3-1/2" (89MM) flat strainer.
5. Also refer to article 2.4K for additional information.

D. Electrical materials

1. General: provide standard materials, devices and components as recommended by the manufacturer or fabricator, selected and installed in accordance with NEMA standards and recommendations and as required for safe and efficient use and operation of the food service equipment without sanitation problems.
2. Components to bear UL label or be approved by the prevailing authority.
3. Custom fabricated refrigeration/freezer to be provided with vapor type might, receptacles, shatterproof lamps and automatic switches. Wiring to be concealed.
4. Where light fixtures are specified or detailed as part of the counters, cases and fixtures. Light fixtures with lamps to be furnished and installed. Warm white lamps to be provided unless otherwise specified. If fluorescent light fixtures are specified, ballast and tubes to be provided. Shields to be provided for all light fixtures.
5. Convenience and power outlets: make cutouts and install appropriate boxes or outlets in fabricated fixtures, complete with wiring, conduit, outlet and stainless-steel cover plate. Outlets and plugs to conform NEMA standards. Electrical outlets and devices to be first quality "Specification Grade". GFCI outlets to be furnished where adjacent to sink compartments as per the National Electrical Code.
6. Plugs and cords: where cords and plugs are provided, they are to comply with National Electrical Manufacturers Association (NEMA) requirements. Indicate NEMA configuration for each applicable item.
7. Power characteristics: refer to Electrical Divisions specifications for project power characteristics. Also refer to individual equipment requirements for loads and ratings.
8. All electrical components (J-boxes, conduit, outlets, switches, cover plates, light fixtures, panels, etc) built into or on any equipment provided by the KEC, other than standard buy-out factory manufactured equipment with vapor or watertight electrical components wherever available.

2.4 FABRICATION OF METALWORK

A. General fabrication requirements

1. Remove burrs from sheared edges of metalwork, ease the corners and smooth to eliminate cutting hazard. Bend sheets of metal, at not less than the minimum radius required to avoid grain separation in the metal. Maintain flat smooth surfaces without damage to finish.
2. Reinforce metal at locations of hardware, anchorages and accessory attachments wherever metal is less than 14 gauge (2MM) or requires mortised application. Conceal reinforcements to the greatest extent possible. Weld in place on concealed faces.
3. Exposed screws or bolt heads, rivets and butt joints made by riveting straps under seams and then filled with solder will not be accepted. Where fasteners are permitted, provide Phillips's head,

flat or oval head machine screws. Cap threads with acorn nuts, unless fully concealed in inaccessible construction and provide nuts and lock washers unless metal for tapping is at least 12 gauge (2.5MM), match fastener head finish with finish of metal fastened.

4. Where components of fabricated metal work are indicated to be galvanized and involve welding or machining of metal heavier than 16 gauge (1.6MM) complete the fabrication and provide hot-dip galvanizing of each component after fabrication to the greatest extent possible (depending upon available dip-tank sizes) comply with ASTM A123.
5. Welding and soldering
 - a. Materials 18 gauge (1.3MM) or heavier to be welded.
 - b. Seams and joints to be shop welded or soldered as the nature of the material may require.
 - c. Welds to be ground and polished to match original finish
 - d. Where galvanizing has been burned off the weld is to be cleaned and touched up with high grade aluminum paint.

B. Metal and Gauges

1. Except as otherwise indicated, fabricate exposed metalwork of stainless steel and fabricate the following components from gauge of metal indicated and other components from not less than 20 gauge (1MM) metal:
 - a. Table and counter tops: 14 gauge (2MM)
 - b. Sinks and drain boards: 14 gauge (2MM)
 - c. Shelves: 16 gauge (1.6MM)
 - d. Front drawer and door panels 18 gauge (1.3MM) double pan type
 - e. Single pan doors and drawer fronts: 16 gauge (1.6MM)
 - f. Enclosed base cabinets: 18 gauge (1.3MM)
 - g. Enclosed wall cabinets: 18 gauge (1.3MM)
 - h. Exhaust hoods and ventilators: 18 gauge (1.3MM)
 - i. Pan-type insets and trays: 16 gauge (1.6MM)
 - j. Removable covers and panels 18 gauge (1.3MM)
 - k. Skirts and enclosure panels: 18 gauge (1.3MM)
 - l. Closure/trim strips over 4" (102MM) 18 gauge (1.3MM)
 - m. Hardware reinforcement: 12 gauge (2.5MM)
 - n. Gusset plates: 10 gauge (3.4MM)

C. Work Surface Fabrication

1. Fabricate metal work surfaces by forming and welding to provide seamless construction using welding rods matching sheet metal, grinding, and polishing. Where necessary for disassembly, provide waterproof gasketed draw-type joints. With concealed bolting.
2. Reinforce work surfaces 30" (762MM) on center both ways with galvanized or stainless steel concealed structural members. Reinforce edges which are not self-reinforced by formed edges.

D. Metal Top Construction

1. Metal tops to be one piece welded construction including field joints. Secure to a full perimeter galvanized steel channel frame cross braced not farther than 30" (762MM) on center. Fasten top with stud bolts or tack weld. If hat sections are used in lieu of channels, close ends.
2. Properly designed draw fastening, trim strip, or commercial joint material to suit requirement is to be used, only if specified.

E. Structural Framing

1. Except as otherwise indicated, provide framing of minimum 1" (25mm) pipe-size round pipe or tube members, with mitered and welded joints and gusset plates, ground smooth. Provide 14 gauge (2mm) stainless steel tube for exposed framing, and galvanized steel pipe for concealed framing.
2. Where indicated, flange rear and end edges up to form splashes integrally with top, with vertical and horizontal corners coved of not less than ¼" (6mm) radius, die formed. Turn back splashes 1" (25mm) to wall across top and ends with rounded edge on break, unless otherwise specified.
3. For die-crimped edges, use inverted "V" ½" (13mm) deep inside and 2" (50mm) deep on outside, unless otherwise shown. For straight down flanges, make 1-3-4" (45mm) deep on outside. For bullnose edges, roll down 1-3/4 (45mm).
4. Edges: die-formed, integral with top. For rounded corners, form to 1" (25mm) radius, weld, and polish to original finish.

F. Field Joints: For any field joint required because of size of fixture, butt-joint, reinforce on underside with angles of same material, bolt together with non-corrosive bolts and nuts, field weld, grind and polish.

G. Pipe Bases: Construct pipe bases of 1-5/8" (41mm) diameter 18 gauge (1.3mm) stainless steel tubing. Fit legs with polished stainless steel sanitary adjustable bullet feet to provide for adjustment of approximately 1-1/2" (37mm), without exposing threads. Space legs to provide ample support for tops, precluding any possibility of buckling or sagging and in no case more than 6'-0" (1829mm) centers.

H. Legs and Cross rails

1. Equipment legs and cross rails to be 1-5/8" (41mm), 16 gauge (1.6mm) stainless steel tubing.
2. Welds at cross rails to be continuous and ground smooth. Tack welds will not be acceptable.
3. Bottom of legs to be swedged inward and fitted with a stainless steel bullet-type foot with not less than 2" (50mm) adjustment.
4. Free standing legs to be pegged to floor with ¼" (6mm) stainless steel rod or provided with bolt down type flanged feet anchored to the floor, depending on expected severity of use and/or abuse.
5. Components

- a. Steel Gusset: Stainless steel exterior to fit 1-5/8" (41mm) tubing, with Allen screw for fastening and adjustment. Not less than 3" (76mm) diameter at top and 3-3/4" (95mm) long. Outer shell 16 gauge (1.6mm) stainless steel, reinforced with 12 gauge (2.5mm) mild steel insert welded interior shell, or approved equal.
 - b. Stainless Steel Low Counter Legs: Stainless steel exterior 5-3/4" (146mm) minimum, 7" (178mm) maximum length with stainless steel 3-1/2" (89mm) square plate with four counter-sunk holes, welded to top for fastening.
 - c. Stainless Steel Adjustable Foot: Stainless steel 1-1/2" (37mm) diameter tapered at bottom to 1" (25mm) diameter, fitted with threaded cold rolled rod for minimum 1-1/2" (37mm) diameter, fitted with threaded cold rolled rod for minimum 1-1/2" (37mm) diameter x 3/4" (19mm) threaded bushing plug welded to legs, or approved equal. Push-in foot not acceptable.
6. Legs to be fastened to equipment with gussets as follows:
- a. Sinks: Reinforced with bushings and set screw.
 - b. Metal Top Tables and Dish Tables: Welded to galvanized steel channels, 14 gauge (2mm) or heavier, anchored to top with screws through slotted holes.
 - c. Wood Top Tables: Welded to stainless steel channels, 14 gauge (2mm) or heavier, anchored to top with screws through slotted holes.

I. Shelves

1. Construct solid shelves under pipe base tables of 16 gauge (1.6mm) stainless steel, with 1-1/2" (37mm) turned down and under edges on exposed sides, and 2" (50mm) turn up against walls or equipment. Fully weld to pipe legs.
2. In fixtures with enclosed bases, turn up shelves on back and sides with 1/4" (6mm) (minimum) radius and feather slightly to ensure a tight fit to enclosure panels.

J. Sinks

1. Construct sinks of 14 gauge (2mm) stainless steel with No. 4 finish inside and outside.
2. Form back, bottom and front of one piece, with ends and partitions welded into place. Partitions: double thickness, 2" (51mm) minimum space between walls. Multiple compartments to be continuous on the exterior, without applied facing strips or panels.
3. Cove interior vertical and horizontal corners of each tub not less than 1/4" (6mm) radius, die formed. Outer ends of drainboards to have roll rim risers not less than 3" (76mm) high.
4. Drill faucet holes in splashes 2-1/2" (63.5mm) below top edge. Verify center spacing with faucet specified.
5. Sink insets to be deep drawn of 16 gauge (1.6mm), or heavier, polished stainless steel. Weld into sink drainboards with 1-1/2" (37mm) x 1-1/2" (37mm) x 14 gauge (2mm) stainless steel angle brackets, securely welded to sinks and galvanized cross angles spot

welded to underside of drainboards to form an integral part of the installation.

6. The bottom of each compartment is to be creased such as to ensure complete drainage to waste opening. Slope bottom of sink bowls toward outlet.

K. Drains and Wastes and Faucets

1. Furnish and install Fisher model 28940, or equal, ball valve type rotary drain assembly with flat strainer and connected overflow assembly, with chrome finish, in die-drawn inset type sinks and Bain Marie sinks.
2. Other custom fabricated sinks to be furnished with Fisher model 28932, or equal, ball valve type rotary drain assembly, with flat strainer and chrome finish. Waste connection to have 2" (50mm) external thread size, with 1-1/2" (37mm) internal thread size.
3. Rotary Handle: Of sufficient length to extend to front edge of sink. No riveting, screws or soldering permitted to fit drains to sinks, with all parts of drains easily removable for servicing and replacement.
4. All faucets furnished with equipment included in this Section to be lead free and comply with N.S.F. Standard #61, Section #9, such as manufactured by Fisher, Chicago, or T&S.
5. Faucets and pre-rinse spray assemblies furnished with equipment included in this Section are to have a maximum GPM flow rate in compliance with the Energy Policy Act of 2005 (EPAct) and later updates, or local requirements, whichever is lower. EPAct/local requirements are to be applicable to all faucets and pre-rinses, except for pre-rinse type assemblies used at glass icing/fill stations, fill hose/faucet assemblies at high water usage cooking equipment such as kettles, tilt fry pans, etc., and fill faucets at high volume/usage sinks such as pot and prep sinks, etc. are to have flow rates of approximately 5 gpm flow minimum.
6. All flex hose type faucet assemblies, such as pre-rinses, kettle fill hoses, etc., to have an inline pressure type back flow preventer in the hose assembly, as required by local codes.
7. All equipment provided by this Contractor, which discharges liquid waste exceeding 140°F (60°C), is to be provided with a cold water drain tempering assembly per local codes.

L. Workmanship

1. Best quality in the trade. Field-verify dimensions before fabricating, conform all items to dimensions of building; neatly fit around pipes, offsets and other obstructions.
2. Fabricate only in accordance with approved shop drawings, showing pipes, obstructions to be built around, and location of utilities and services.

M. Casework

1. Enclosure: except as otherwise indicated, provide each unit of casework (base, wall, overhead and free-standing) with a complete-

- enclosure metal cabinet, including fronts, backs, tops, bottoms, and sides.
2. Bases to be made of 18 gauge (1.3mm) stainless steel sheets reinforced by forming the metal.
 3. Ends, partitions and shelves to be stainless steel.
 4. Unexposed backs and structural members may be galvanized, unless otherwise noted.
 5. Vertical ends and partitions to be single wall, with a 2" (50mm) face.
 6. Sides and through partitions are flush with bottom rail, welded at intersections.
 7. Shelves: Provide adjustable standards for positioning and support of shelves in casework, except bottom shelf of cabinet mounted on legs or as specified. Turn back of shelf units up 2" (50mm) and hem. Turn other edges down to form open channel. Reinforce shelf units to support 40 pounds per square foot (195 kgs/sq meter) loading, plus 100 percent impact loading.
 8. Bottom front rail of bases set on masonry platform to be continuously closed and sealed to platform.

N. Doors

1. Metal doors to be double-cased stainless steel. Outer pans to be 18 gauge (1.3mm) stainless steel with corners welded, ground smooth and polished. Inner pan to be 20 gauge (1mm) stainless steel fitted tightly into outer pan with a sound deadening material such as Celotex or Styrofoam used as a core. The two pans to be tack welded together and joints solder filled. Doors to finish approximately $\frac{3}{4}$ " (10mm) thick and be fitted with flush recessed type stainless steel door pulls, or full length pulls as per individual itemized specifications and shown on Standard Detail FSD1-24.
2. Wood doors to be fabricated as detailed.
3. Hinged doors to be mounted on heavy-duty N.S.F. approved hinges, or as noted on plans or specifications.

O. Drawer Assemblies

1. Assemblies to consist of removable drawer body mounted in a ball bearing slide assembly with fully enclosed housing.
2. Slide assembly consists of one pair of 200-pound (90 kilograms) capacity stainless steel roller bearing full extension slides, with side and back enclosure panels, front spacer angle, two drawer carrier angles, secured to slides and stainless steel front.
3. Drawers intended for tools and general non-food products storage are to have 20" x 20" x 6" deep (508mm x 508mm x 152mm), 18 gauge (1.3mm) minimum stainless steel drawer pans.
4. Drawers intended to hold food products are to have 12" x 20" x 6" deep; (305mm x 508mm x 152mm) stainless steel food pans.
5. All drawer pans to be easily removable without tools or disassembly of any drawer assembly components.
6. Drawer fronts are double cased, $\frac{3}{4}$ " (19mm) thick, with 18 gauge (1.3mm) stainless steel welded and polished front pan. Steel back pan is tightly fitted, and tack welded.

7. Provide drawers with replaceable soft neoprene bumpers or for refrigerated drawers, a full perimeter replaceable refrigerator gasket.

P. Closed Base: Where casework is indicated to be located on a raised-floor base, prepare casework for support without legs, and for anchorage and sealant application, as required for a completely enclosed and concealed base.

Q. Support from Floor: Equip floor supported mobile units with casters, and equip items indicated as roll-out units, with manufacturer's standard one-directional rollers. Otherwise, and except for closed-base units, provide pipe or tube legs, with adjustable bullet-design feet for floor supported items of fabricated metalwork. Provide 1-1/2" (37mm) adjustment of feet (concealed threading).

R. Shop Painting

1. Clean and prepare metal surfaces to be painted, remove rust and dirt. Apply treatment to zinc coated surfaces, which have not been mill phosphatized. Coat welded and abraded areas of zinc coated surfaces, with galvanize repair paint.
2. Apply 1.5 mil (dry film thickness metal primer coating, followed by 2, 1.0 mil (dry film thickness) metal enamel finish coatings.
3. Bake primer and finish coatings in accordance with paint manufacturer's instructions for a baked enamel finish.

S. Sound Deadening

1. Sound deaden underside of metal tops, drainboards, undershelves, cabinet interior shelves, etc., above the underbracing/reinforcing/framing only.

T. Comply with requirements in Section XX XX XX, Seismic Restraint Requirements for Non-Structural Components. Comply with applicable guidelines for seismic restraint of kitchen equipment contained in SMACNA's "Kitchen Ventilation Systems and Food Service Equipment Guidelines", Publication 1767, Appendix A.

1. Metal Butt joints, Equipment edges, and Backsplashes.
2. Anchored feet.

2.5 FABRICATION OF METALWORK

A. The following general requirement shall govern the construction of millwork-built fixtures, except where otherwise noted. Work shall be performed by skilled mechanics of the trade and shall be of the highest quality throughout, in such a manner as to fulfill the intent of the Contract Documents. Perform architectural woodwork in accordance with "Architectural Woodwork Quality Standards" published by the Architectural Woodwork Institute (AWI). Fabricator shall have a

demonstrated ability in fabricating woodwork items similar in type and quality to those required for this project.

1. All fixtures shall be made by one manufacturer and assembled in single and complete units as the dimensions will permit shipment to and installation of at the building. Large pieces requiring sectional construction shall have their parts accurately fitted and aligned with all others, and provided with ample screws, glue and bolt blocks, tongues, grooves and splines, dowels, mortises and tenons, screws, bolts or suitable means of concealed fastening, as required to render the work substantial, rigid and permanently secured in proper position to each related section.
2. Sufficient additional material shall be allowed to permit accurate scribing to walls, floor and related work, and due allowance made whenever possible for such shrinkage as may develop after installation. Single and sectional units shall be provided with adequate cleating, blocking, crating and other forms of protection as required precluding damage during shipping and handling.
3. Framing and blocking members shall be assembled with bolted and screwed connections and should be secured to the structural backing with cinch, expansion screws or toggle bolts as required, spaced and installed to insure ample strength and rigidity. Rails and stiles shall be mortised and tenoned, work neatly mitered and membered, all butt joints made flush and smooth and permanent joints made up with water resistant glue. All fixtures shall be assembled without face screws or nails except where it may be necessary to attach items. All face screws or nails which are necessary shall be counter sunk and plastic or wood plugs used to cover head and plug neatly touched up. the heads of all screws used in any assembly shall be counter sunk below the surface.
4. The core material shall be marine grade, 7 ply substrate or MEDEX exterior resin medium density fiberboard substrate, conform to ANSI A208.2.3.3.4. All substrate material shall be LEED certified and meet LEED requirements for the project.
5. Back sheet shall be NEMA LD .020" thick, Type V, Grade 91 plastic laminate, apply on all surfaces not covered with plastic laminate. Coordinate color with exposed surface color, comply with NSF Standard 35.

B. Construction joints

1. Follow AWI Premium Grade Standards, factory assembled parts and prefinished, flush type fronts and over lapping ends. ¾" core material base cabinet, end and dividers with corner joints between framed members fully lock-jointed, glued and screwed. Dado and glue cabinet backs into slides and bottom. Scribe countertop and back splashes, secure countertops to base cabinet from underside, fully secure surfaces prior to installation. Mortise and tenon, spline, dowel and/or pin lock and glue work to avoid use of nails wherever practical. Make butt joints with an approved device for prevention of separation of members. Blind nail and conceal.

C. Plastic laminate

1. Plastic laminate shall be bonded to all exposed surfaces with Urac 185 adhesive or equal to minimum $\frac{3}{4}$ " fir faced, close grain marine grade plywood applied under high pressure. In accordance with AWI 1600A-G-1, use horizontal grade on all exposed surfaces. Reject plastic or plastic backing shall be carefully sanded to smooth finish, removing burns, nicks and cur marks. Plastic laminate joints shall be finished without any wavy and unsightly joints. Joints need not be mitered except as specified. Hand sand edges to a slight chamfer.
2. Top sheet shall be placed on and over finished edge. Ease exposed edge to overlap sheet. Use largest sheet possible to minimize seams.
3. Coved backsplashes shall be a minimum of $\frac{1}{4}$ ". End splashes may have a square intersection with tabletops unless specified otherwise.
4. Plastic laminate shelves shall be laminated with horizontal grade laminate on the side and vertical grade at all edges.

D. Doors/hinged

1. Hinged doors shall be fabricated of $\frac{3}{4}$ " marine grade plywood with hardwood full perimeter edge with plastic laminate on face and self-edging on exposed sides unless indicated otherwise in drawings and details. Door hinges, pulls and catches shall be supplied and detailed. Provide Grass 1200, 176 degree opening concealed casework hinges or equal by Blum or Amerock. Door catches shall be Component Hardware Model M22-2420 for non-magnetic and model M30-2400, heavy duty, self-aligning for magnetic.
2. Utilize EPCO Model MC 4032.5 or as specified in item Specifications.
3. Door Locks shall be Component Hardware Model P30 Series, stainless faced, master keyed as specified.

E. Doors / Sliding

1. Sliding doors shall be fabricated of solid core marine grade plywood with hardwood edges and constructed similar to hinged doors. Doors shall be mounted on E-Z Glides track. Doors shall be removable without the use of tools. Rubber stops shall be provided concealed in end stile or mullion

- F. Access panels shall be fabricated of $\frac{3}{4}$ " nominal thick hardwood and shall be fabricated as a door. Each access panel shall be provided with 2 (two) magnetic catches at the top and 2 (two) $\frac{3}{16}$ " positioning pins at the bottom.

G. Drawers

1. Drawers shall have dovetail construction, well glued and blocked. Fronts shall be not less than $\frac{3}{4}$ " thick hardwood. Sides and back shall be $\frac{1}{2}$ " thick fabricated of birch, maple or sycamore except where extension slides are used, in which the side shall be $\frac{5}{8}$ " thick. Bottom shall be milled into front and sides.
2. Drawers shall be provided with suitable stops. Provide pulls as detailed or specified. The inside surfaces of all drawers shall

receive one coat of penetrating primer and one coat of glass lacquer.

H. Painted Finishes

1. Painted finishes shall have exposed surfaces free from defects and blemishes that would show after being finished, regardless of grade specified. All surfaces specified to receive paint or enamel finish shall receive one cross coat of lacquer type undercoat. The undercoat shall be appreciably different color from that of the finished coat and of proper ground color with relation to finish coat. After the undercoat has been dried the surface shall be sanded smooth and two coats of enamel shall be applied. Back painting shall be provided for all cabinet and woodwork prior to installation.

I. Interior and Wall Shelves

1. Interior shelves shall be adjustable with flush routed-in shelf standards. Wall shelves to be fabricated as specified and as per "Standard Detail".

J. Fire Retarding

1. Where required by code, all materials are to be treated with fire retardant chemicals to achieve the required flame spread performance rating. Retardant chemicals must be a type approved by local authorities.

2.6 FILTER EXHAUST HOODS FABRICATION

- A. 18-gauge (1.3MM) type 201 or 304 stainless steel external welded construction in accordance with the latest edition of the NFPA no 96 and International Mechanical Code, including all applicable appendices. Exposed welds to be ground and polished. Exhaust hoods to be UL Listed as available for length specified.
- B. Furnish type of fixture specified. Fixtures to be UL listed for cooking equipment exhaust hoods, NSF approved and with sealed safety lenses.
- C. Furnish welded stainless steel formed duct collars at ceiling or wall connections. Verify size and location of duct connections required in this contract before fabrication.
- D. Pre-piped liquid chemical or water fire suppressant system as specified, complying with applicable local and NFPA regulations. Wet chemical fire suppression systems to comply with UL 300 Standards. Water fire suppression systems to comply with UL Category Subject 199E. Each pull station is to be clearly identified with a permanent type of label as to which exhaust hood(s) it is for. Each exhaust hood is to have a matching permanent type of label identifying which pull station activates its fire system.
- E. All cooking equipment below exhaust hoods/ventilators on casters are to be provided with positive wheel placement systems for rear casters similar to Posi-Set units in compliance with NFPA-17A 5.6.4 and NFPA-96 12.1.2.3.
- F. Water wash of ultraviolet control panel to be the same manufacturer as ventilator with time clock control for automatic operation. Provide stainless steel trim strips recessed control cabinet applications.

Provide stainless steel chase for surface mounted control panel from top of panel to ceiling full width and depth of panel.

- G. comply with applicable guidelines for seismic restraint of kitchen equipment contained in SMACNA's Kitchen ventilation Systems and Food Service Equipment Guidelines, Appendix A. (Note: Where applicable)

2.7 REFRIGERATION EQUIPMENT

A. General

1. Furnish either single or multiple compressor units as specified or recommended by the manufacturer for the sizes and variations between connected evaporator loads as indicated.
2. Furnish units of the capacities indicated arranged to respond to multiple evaporator thermostats and defrosting timers. Include coils, receivers, compressors, motor and motor starters, mounting bases, vibration isolation units, fans, dryers, valves, piping, insulation, gauges, winter control equipment and complete automatic control systems.
3. Refrigerant: Pre-charge units with type or types recommended by manufacturer for services indicated with quick disconnect type connections only where specified, ready to receive refrigerant piping runs to evaporators and (where remote) to condensers. All refrigerant and associated components to comply with the requirements of the Montreal Protocol Agreement. No CFC or HCFC refrigerants or associated components will be permitted on this project. HFC refrigerants and components are to be used. Contractor is responsible for coordinating these requirements with manufacturers.
4. Foodservice equipment items included in this section with remote refrigerated systems are to include interconnecting refrigeration lines, sizing, and insulation between components as per manufacturers installation instructions and as determined by this Contractors Certified Refrigeration Sub-Contractor, and only after a thorough examination of the site conditions and obstacles which might affect the routing. Routing should be as direct and short as possible and practical. Refer to additional requirements listed in this section 114000, 1.5 Laws, Ordinances and Standards.
5. The minimum outdoor operating ambient temperature for design of units is -10 degrees Fahrenheit (-23 Centigrade) or lower as applicable for extreme low local conditions. The maximum indoor design temperature for operation of compressor units is 95 degrees Fahrenheit (35 Centigrade). The maximum outdoor ambient temperature is to be determined by contractor with prevailing conditions at mounting location of compressor such as sun exposure, limited ventilation, high fences/walls, roof color and materials, local climatic extremes, etc. but in no case is it to be less than 100 degrees Fahrenheit 93.8 Centigrade).
6. All refrigeration systems with remote condensing units and jobsite installed interconnecting refrigeration lines shall be tested to verify that there are no leaks. Leak testing shall be equal to or better than a professionally recognized 48-hour minimum pressure

holding test. If any leaks are detected, they shall be repaired, and another leak test performed until there are zero leaks detected. A written report of the type test performed, and a step-by-step record of the procedure and readings shall be submitted to the KEC for inclusion in the Operations and Maintenance Manuals.

B. Components

1. Coils for fabricated refrigerators to have vinyl plastic coatings, stainless steel housings and be installed in such a manner as to be replaceable.
2. Provide guards for all refrigeration/freezer fans with maximum ½" mesh.
3. Remote refrigeration system to be complete with thermostatic expansion valves at the evaporator.
4. Fabricated refrigerated compartments to be fitted with flush dial thermometers with chrome plated bezels. Thermometers to be adjustable and shall be calibrated after installation. Thermometers to have an accuracy or +/- 2 degrees Fahrenheit (1 Centigrade).
5. Hardware
 - a. Refrigerator hardware for fabricated refrigerator compartments to be heavy duty components.
 - b. Self-Closing
 - c. Latches to be magnetic edge mount type, unless specified or detailed otherwise.
6. Doors and drawers for walk-in coolers/freezers and reach-in refrigerated compartments, both fabricated and standard to be fitted with cylinder locking type latches and provided with master keys.
7. Provide and install shut-off valves and service port for each compressor, manifold or header and refrigerated fixtures for multiplex and parallel installation to enable service personnel to service one (1) fixture while other fixture (s) connected to the same compressor can continue to operate. Isolation valves for individual fixtures based upon the sizes of the individual pieces.
8. Drawers for refrigerated fabricated compartments shall be complete with heated surround at closing perimeter.

C. Cold Pans: Ice pans, refrigerated pans and cabinets to be provide with breaker strips where adjoining top or cabinet face materials to prevent transfer of cold.

D. All mechanically cooled custom fabricated or standard buy-out refrigerators with openings in the top for cooling pans and/or all built-in or drop-in mechanically cooled cold pans are to comply with and be listed by NSF Standard #7. Contractor is to verify that the specified unit complies with this requirement.

E. Ventilation of refrigerated equipment

1. Adequate ventilation to be provided for custom fabricated equipment with integral refrigeration condensing units, both built-in and

drop-in. if flow through ventilation. If flow through ventilation cannot be provided, provide flow direction partitions and an additional fan capable of cooling the condensing unit.

2. If, in the opinion of the contractor, additional room ventilation is required to ensure correct operating temperatures of standard buy-out, custom fabricated or remote refrigeration condensing units or compressor rack assemblies, they are to so state in a letter to the architect for evaluation and decision.

2.8 REMOTE REFRIGERATION SYSTEMS

- A. All remote refrigeration systems shall be furnished with installed by one contractor unless otherwise specified. Provide all components necessary for a complete and operable system. System to be fully capable of satisfying the refrigeration requirements for each fixture as defined by the manufacturer of each fixture.

- B. Compressor and condensing units

1. Units shall be factory assemblies complete with hermetic units below 1 HP, semi-hermetic units 1 HP and larger, air- or water-cooled condenser depending on building conditions and speciation's, high-low pressure controls, suction accumulator on low temperature system, sight glass, liquid line dryer, suction and discharge service valves, liquid receiver, motor started, defrost timer clock and contractors in accordance with Refrigeration Institute (ARI) Standards. The refrigerant for medium and low temperature fixtures to be CFC free and conform to the Montreal Protocol Agreement.
2. Capacities shall be based on the following:
 - a. compartment temperature and evaporating temperature greater than 32oF (0oC) 18 - 20 hours operations.
 - b. Compartment temperature greater than 32 degrees (0c) and evaporating temperature less than 32 degrees (oc) 16 hours operation.
 - c. Compartment temperature and evaporating temperature less than 32 degrees (0c) 18 hours operation.
3. Condensing units shall be mounted on a steel base to affect a quiet operation. All rotating parts to be carefully balanced for minimum vibration and lubricated with forced or splash oil system. Receiver shall be sized for a complete pump down of the system and shall be shell type with fusible plug.
4. Compressor units to be provided with suction and discharge back setting type service valves and standard machinery finish.
5. Motors shall be single speed, maximum 1750 RPM, compound wound ball bearings or sleeve bearing. Double squirrel cage motors with high starting torque set and low starting current to be used in a 3-phase application.
6. All machines to be equipped with quick acting type high-low pressure control switches having adjustable range and differential and high-pressure cut-out. Cut-out to be automatic reset type.

7. For air-cooled units the condenser shall be a standard manufactured part of the equipment. Condensing temperatures shall be based upon (100 degrees 38C) ambient air.
8. Other components and accessories such as suction filter and crank case heater shall be furnished when specified in the itemized specifications.

C. Motor starters-contactors

1. All single-phase motors shall be provided with mounted and internally wired contactors except where pre-wired units are furnished without contactors. Single phase compressors shall be provided with built-in thermal and electrical overload protection.
2. All three phase motors shall be provided with magnetic type starters with quick trip overload elements matched for motor amperage except where overload protection is built into the compressor motor and the manufacturer supplies a contactor instead of a starter. Overload heater element shall be sized according to manufacturer's recommendation. Compressor motor starters shall be definite purpose starters with manual reset.
3. Starters shall be installed upon surfaces free from excessive vibrations.
4. Where starters are required for installation in a motor control center, make and model of control center shall be verified, and starters provided to match.

D. Oil Separator

1. Provide oil separators except when compressor manufacturer requires otherwise, 34oF, (1oC) and below and install as near as possible to the compressor. The return line shall be connected to the top of the crank case above the oil level. Where compressor does not have connection for oil return from separator, connect to a tee in the suction line adjacent to the compressor. Exposed oil return line to be provided with shut-off valve of the pack-less stem type.

E. Compressor Racks

1. Racks shall be of the number of tiers and quantity to accommodate the number of condensing units specified for each rack assembly and allow for service clearance and ventilation. Review and confirm access into building or housing requirements to roof top locations.
2. Racks shall be fabricated with structural steel of size and quantity to properly support the equipment to be installed on the rack. In special applications where building access is limited, construct rack framing with Dexion of Unistrut material.
3. Racks shall be all welded construction with welds ground smooth.
4. After completion of the fabrication the complete rack shall be cleaned, primed, and painted with top quality oil-based enamel.
5. Each rack shall be equipped with prewired duplex outlet.
6. Racks shall be prewired to circuit breaker panel and pre-plumbed to a header (when specified water cooled) requiring a single point electrical and plumbing connection.

7. Racks shall have UL or equivalent approval.
8. Special Conditions: For custom built racks for individual condensing units provide Dixon Angle Iron.
9. Comply with applicable guidelines for seismic restraint of kitchen equipment in SMACNA's "Kitchen Ventilation Systems and Food Service Equipment Guidelines" Appendix A. as required by location.

F. Coils and Cooling Units

1. Units shall be direct expansion type of size and design to effect required temperature humidity and to suit application intent.
2. Units shall be hung from ceiling with ½" nylon rods with plated steel nuts and washers. Rods shall extend through ceiling to bracing adequate for the suspended weight. Bracing shall be furnished as require. Penetrations shall be sealed and trimmed with escutcheon plates.
3. Units shall be installed tight to ceiling. All installations adjacent to walls shall be set out a minimum distance conforming to manufacturer's directions to ensure proper air circulation and performance.
4. Units with fan or blower and motor shall have thermal overload protection and be wired as indicated in "Refrigeration Schedule".
5. Defrost cycle shall be based on the following:
 - a. Coils for 32oF (0oC) and lower shall have as electric defrost controlled by time clock mounted on compressor rack or at evaporators locations inter-wired by Division 26 - Electrical.
 - b. Coils for 33-degree F (0.6C) and 34-degree F (1C) shall have an air defrost controlled by a time clock mounted on the compressor rack or at evaporators location inter-wired by Division 26 - Electrical.
6. Coils for temperature above 34F (1C) shall have an air defrost in off cycle controlled by proper sizing of the coil and compressor.
7. Location of the coils shall be coordinated with shelving and floor sink locations.
8. All coils for fabricated refrigerators and/or freezers shall be installed for accessibly and replacement

G. Penetration Sleeves and Plates

1. Service line penetrations of insulation to accommodate electrical conduit, refrigerant and drain shall be limited to a minimum with service stubbed through insulation locations predetermined by respective divisions.
2. Where service lines penetrate insulated walls, the opening shall be packed with caulking before trimming with escutcheon plate.
3. Where service lines penetrate building walls outside of foodservice areas, the opening shall be packed with "Perma-Gum" and foam caulking.
4. All exposed ends of sleeves, both inside and outside of compartments are to be trimmed with 24-gauge stainless steel escutcheon plates,

furnished as blanks in which respective work divisions shall cut as required line holes and install.

H. Refrigerant Piping

1. copper tubing for refrigerant piping shall conform to ASTM standard specifications, serial designation B-88. All piping shall be type "L" ACR hard copper or cleaned and sealed soft type "L" tubing, dry seal or equal as indicated. Forged or wrought copper fitting with sweat or soldered joints shall be used.
2. Tubing shall be cut only with tube cutter and sized with sizing tool.
3. Piping shall be exposed to view as required by standard safety code for mechanical refrigeration.
4. The liquid suction lines from condensing units to coil shall be sized and run as shown on the "Refrigeration Schedule" and Refrigeration Drawings.
5. Piping run within cold storage rooms shall be finished with aluminum paint.
6. For exposed areas accessible furred ceiling spaces and in walls or excavated trench type installations, hard copper tubing shall be used. Exposed tubing shall be run in a manner to preclude damage by activities in the area or shall be protected by conduit furnished and installed as part of the contract. conduit shall have water evacuated and both ends completely sealed.
7. For piping run in conduit through inaccessible areas such as under slab or grade continuous one-piece soft copper tubing shall be used with no joints. In lieu of large piping in conduit, especially vertical runs, random lines may be used, carefully fabricated and assembled to ensure equal pressure drop.
8. Ends of lines shall be capped to prevent contamination and opened only at time of final connection.
9. Suction lines shall be sized for a maximum pressure drop from evaporator to compressor 2 lbs. (0.9kg). for high and medium temperature systems and 1 lb. (0.45 kg) for low temperature systems and shall allow gas velocities of not less than 750 FPM (3.8 M/sec) in horizontal runs and 1500 FPM (91.4 M/sec) in vertical risers. Liquid lines shall be sized for a maximum pressure drop of 3 lbs. (1.36kg) from receiver to evaporator.
10. Tubing runs shall be graded or pitched to prevent trapping of oil. Suction lines shall pitch 1/8"/10"-0 minimum.

I. Joints and Connections

1. Fittings shall be long radius wrought copper only as manufactured by Mueller Brass Company or equal.
2. Vertically run suction lines shall have one piece of manufactured oil "P" traps. Line to be sized for proper velocity for oil return to compressor.
3. 1/8" NPT by 1/4 fl. Half union for all suction and discharge service valves with 1/4 fl. Cap.
4. Reduction in piping size shall be made with a manufactured reducer coupling.

5. Flare nuts shall be short forged or frost proof.
6. All surfaces to be joined must be prepared and cleaned. When soldering stop or solenoid valves, wrap valves, with moist fabric to absorb excessive heat. Stop valves shall be partly open. When soldering expansion valves or pressure regulating, remove power assembly, if necessary to prevent damage by excessive heat.
7. Copper joints shall be made with Handy & Harmon "Sil-Fos" brazing alloy, "Phoson15", Silvaloy 15" or equal, melting point of 1185-1350 degrees F; (640 C - 732C) Silver content not less than 15%.
8. Copper to be brass joints shall be made with Handy & Harmon (Easy Flo 45" brazing alloy (Silvaloy 45", Mueller 122" or equal, melting point of 1125-1145 F, (607C-618C) silver content not less than 45%.

J. Hangers and Supports

1. For all piping not run-in conduit provide adjustable hangers, anchors or straps as required. Hanger spacing shall not exceed 8'-0").
2. Insulated copper piping shall be provided with approved type sleeves at hanger points.
3. All insulated copper piping shall be isolated from supports by means of felt wrapping or with "Trisolater" by Semco or approved equal.
4. Vertical piping shall be supported at intervals with spring type hangers or a substantial pipe at case of the pipe. All horizontal pipe runs connected to vertical risers must be adequately supported.
5. For suspended conduit, support shall be by means of hanger permitting screw adjustments. Sufficient hangers shall be used to provide support, allow expansion and limit vibration.

K. Piping Sleeves

1. Coordinate sleeves provided by the General Contractor through walls which allow for fully insulated lines. Extend sleeves entirely through wall and dress each end with chromium plated wall plate neatly fitted against wall. Securely fastened and sealed in place. All sleeves through wall shall be of standard weight steel pipe.
2. piping lines and sleeves at wall or floor penetrations shall be caulked and made vermin-proof at all locations.

L. Piping Insulation

1. Suction lines run in conduit shall be insulated according to ambient and humidity conditions to prevent condensation and freezing.
2. Refrigeration suction lines outside of refrigerated compartments not run-in conduit shall be insulated back to compressors with Armstrong Armaflex AP foamed plastic insulation or as determined by code. Thickness of material shall suit service, ambient and humidity conditions to prevent condensation, minimum thickness ½" (15MM).
3. Cold Storage Room freezer drain lines extended through adjacent cooler compartments shall be insulated with ½" (15MM) minimum thickness or Armstrong Armaflex AP foamed plastic insulation to prevent condensation. Carefully seal end of insulation tight against cooler wall surface.

4. Piping for cooling water services or refrigerant piping exposed to freezing ambient temperatures shall be insulated with ½" (15MM) minimum thickness of Armstrong Armaflex AP foamed plastic insulation. Paint exterior installation with Armaflex paint.
5. Thickness of material shall suit service, ambient and humidity conditions to prevent condensation.
6. Joints shall be sealed with Armstrong 520 Adhesive. Insulation shall be continuous through clamps. Provide additional insulation where suction lines must be run within 12" or less of water or underground waste lines.
7. Exterior-run piping shall be insulated as per above and covered with stainless steel channels secured to structure, sealed to be weather-proof.

M. Heat Interchangers

1. All blower controls, unit coolers, plate type evaporators and other evaporators where specified to be provided with heat interchangers with a capacity to match the condensing unit.

N. Temperature Control

1. Temperature control of cold storage rooms shall be by line voltage thermostats operating liquid line solenoids.
2. Temperature control for remote normal temperature refrigerator shall be by low pressure switch setting.
3. Temperature in each cold storage room compartment shall be controlled by electric thermostat, Ranco No 010-1408, located within compartment and sensing element positioned to avoid fan discharge air stream.
4. Contractor to coordinate any additional specified temperature control/monitoring/alarm system within this document set including assisting with coordination of home-run control wiring, wireless assembly coordination and HACCP requirements in terms of reporting.

O. Valves and Accessories

1. All valves and controls shall be standard weight and suitable for service purpose intended and subject to approval by Designer.
2. Provide shut-off valves and service port for each refrigerated fixture for multiplex installations to enable service personnel to service one fixture while the other fixture(s) connected to same compressor can continue to operate.
3. Each system shall include condensing unit with standard valving, refrigerant piping, refrigerant, evaporator(s), liquid and suction line isolation valves with-in 5' (1500MM) of evaporators, thermostatic expansion valve for evaporator, heat exchanger, filter-dryer, liquid line solenoids for Cold Storage Rooms and liquid indicator.
4. Vibration eliminators on compressor suction and discharge lines, size same as piping as manufactured by Anaconda.

5. Refrigerant shut-off valves shall be as manufactured by Henry or Superior Valve Company. Valves shall be placed and in liquid line for each condensing unit and in each liquid line to each evaporator.
6. Expansion valves shall be Sporlan or approved equal, furnished, and installed in the liquid line at the evaporator unless provided with manufactured equipment. External equalizer expansion valves shall be provided for coils fitted with refrigerant distributor.
7. A Sporlan or approved equal drier shall be provide at compressor. Up to 3HP shall be a catch-all series, larger than 3HP shall be angle replaceable cartridge series or approved equal.
8. Each liquid line sight glass shall be Sporlan (See All) moisture and liquid indicator and shall be full line size or approved equal.
9. Solenoid valves shall be Sporlan or approved equal, line voltage, manual lift stem type to operate at a maximum of 2 lbs. (0.9kg) pressure drop across the valve. Valves shall be full line size, using silver solder connection as applicable. A liquid line solenoid, normally closed, shall be used with temperature controller for each Cold Storage Room compartment coil on a system.
10. Include a suction line filter with access valve adjacent to compressor. Filter shall be a Superior "F" Series or equal.
11. EPR, CTR, and/or CDA valves shall be Alco or Sporlan or approved equal.
12. Suction accumulators shall be Refrigeration Research 3700 series or Virginia VA series or approved equal.
13. Discharge line mufflers shall be Refrigeration Research M-10 and M-15 or AC and RSS-6300 series or approved equal.
14. Time clocks shall be Paragon or approved equal.

P. Drain Lines

1. Type "L" copper coil drain lines extended to exterior of refrigerated compartments over floor sinks (drain) with "S" traps at termination ends.
2. Provide clean out "T" and cap at each change of direction in the lines. Provide individual drain lines for each coil unless otherwise specified. Drain lines shall be run tight to refrigeration compartment walls with minimum pitch of 2" per foot.
3. Drain lines inside low temperature compartments shall be equipped with drain-line heaters wired y electrical division. Drain lines in low-temperature compartments shall be extended into adjacent, medium, or high temperature compartments to reduce length of drain line heater required. (Drain line in low temp compartment to be insulated with Armaflex ½" - insulation and wall fastening by the foodservice equipment contractor).
4. Drain lines on the exterior of refrigerated compartment shall be painted with chrome tone paint and shall be trapped to disallow ambient air infiltration into refrigerated cavity.

Q. Refrigerant/Compressor Oil Reclaim

1. For existing refrigeration systems which may be reused, abandoned or where site conditions warrant, the system(s) refrigerant, oil and/or other components shall be reclaimed and contained by certified

personnel in conformance to Refrigerants and Hazardous Waste criterion as specified by the Environmental Protection Agency and/or Montreal Protocol Guidelines & Requirements.

2.9 MISCELLANEOUS MATERIALS AND FABRICATION

- A. Nameplates: Whenever possible, locate nameplates and labels on manufactured items, in accessible position, but not within customer's normal view. Do not apply name plates or labels on custom fabricated work, except as required for compliance with governing regulations, insurance requirements, or operator performance.
- B. Manufactured Equipment Items: Furnish items as scheduled or herein specified. Verify dimensions, spaces, rough-in and service requirements, and electrical characteristics, before ordering. Provide trim, accessories and miscellaneous items for complete installation.
- C. Insert Pans
 - 1. General: cut-outs, openings, drawers, or equipment specified or detailed to hold stainless steel insert pans to be provided with a full complement of pans as follows:
 - a. One (1) stainless steel, 20-gauge (1mm) minimum, solid insert pan - in US pan size of gastronome configuration as specified for each space, sized per plans, details, or specifications.
 - b. Where pan sizes are not indicated in plans, details, or specifications, provide one full-size pan for each opening.
 - c. Provide maximum depth to suit application and space.
 - d. Provide 18-gauge (1.3mm) NSF-approved removable stainless steel adapter bars where applicable.
 - 2. All cut-outs and openings, or equipment specified or detailed to hold stainless steel insert pans, shall be provided with a hinged stainless steel removable right cover.
- D. Tray Slides: Before fabrication of counters with tray slides, verify.
 - 1. Size and shape of tray with Owner/Operator. Edge of tray should not overhang outer support/slider by more than 2" (50mm). If the edge of tray exceeds this dimension, notify the Architect, in writing, for evaluation and adjustment, if necessary.
 - 2. Configuration of corners, turns, and shape of tray slides for proper support and safe guidance of trays.
 - 3. Tray slide to be capable of supporting 200 pounds per linear foot (298 kgs/meter), live load.
 - 4. All tray slides shall be fabricated with a 15 degree turn down 2" in from end of slide to disallow scraping of trays and poly racks
- E. Self-level dispensers: Verify type, make dimensions and weight of ware with Owner/Operator, and submit to the dispenser manufacturer, for proper sizing and calibration of dispensers.

- F. Carbon dioxide (CO2) equipment: Where equipment requires connection with compressed CO2 cylinder for operation, provide 2-cylinder manifold and control system (integral with equipment) with proper connectors for Department of Transportation (DOT) approved type cylinders, complete with cylinder safety devices and supports. Applicable to projects with CO2 equipment included in Contractor's specified equipment.
- G. Reasonable quietness of operation of equipment is a requirement, and Contractor will be required to replace or repair any equipment producing out-of-the-ordinary intolerable noise. This also includes providing and installing bumpers and gaskets for doors and drawers on fabricated and standard manufactured items and sound insulation where feasible.
- H. Gas pressure regulator: All gas fired equipment included with this Section is to be provided with a gas pressure regulating valve with a built-in vent limiting device sized per WC pressure rating of this project. Contractors are responsible for coordinating this requirement with their manufacturers and suppliers.

PART 3 - EXECUTION

3.1 SUPERVISION

- A. A competent supervisor, representing the Contractor, is to always be present during progress of the Contractor's work.
- B. Contractor is responsible for coordinating with all applicable Design Team members, Key Ownership Stakeholders Assigned, General Contractor, other Contractors and/or Sub-Contractors and Trades involved in this Project and associated with any items or work provided under this Section, as required for the successful provision, installation, completion, and functioning of these items and/or work, and the Project in general. This is to include, but not be limited to, exchange of shop drawings, details, and manufacturer's information, supplying templates or actual components to be installed in or on items provided by other Sections, for coordination; and coordinating with and between their own internal staff, sub-contractors, trades, manufacturers, fabricators and installers, for compliance with the Contract Documents.
- C. The contractor is responsible for obtaining any documents referenced in this Section and on any associated drawings, which contain information related to the performance of this Contract and disseminating and coordinating the pertinent information contained in them, with the appropriate sub-contractors, manufacturers, fabricators, and/or installers.
- D. The contractor is to take every precaution against injuries to persons or damage to property.

- E. The contractor is to store his apparatus, materials, supplies and equipment in an orderly fashion at the site of the work so it will not unduly interfere with the progress of his work or the work of any other contractors.

3.2 SITE EXAMINATION

- A. Verify site conditions under the provisions of the General Conditions, Supplementary Conditions, and applicable provisions of Division 1 Sections. Notify the Architect, in writing, of unsatisfactory conditions for the proper installation of foodservice equipment.
- B. Verify wall, column, door, window, and ceiling locations and dimensions. Fabrication and installation should not proceed until dimensions and conditions have been verified and coordinated with fabrication details.
- C. Verify that wall reinforcement or backing has been provided and is correct for wall supported equipment. Coordinate placement dimensions with wall construction Section.
- D. Verify that ventilation ducts are of the correct characteristics, and in the required locations.
- E. Verify that utilities are available, of the correct characteristics, and in the required locations.

3.3 DELIVERY AND INSTALLATION

A. Delivery

- 1. The equipment shall be delivered and installed on schedule. Coordinate all work with the General Contractor and other divisions as required.
- 2. Deliver materials (except bulk materials) in manufacturer's containers, fully identified with manufacturer's name, trade name, type, class, grade, size, color, item number, area, etc.
- 3. Contractor is responsible for receiving and warehousing equipment and fixtures, until ready for installation. Store materials, equipment and fixtures in sealed containers, where possible. Store off the ground and under cover, protected from damage.
- 4. Contractor to verify and coordinate conditions at the building site, particularly door and/or wall openings, and passages, to assure access for all equipment. Pieces too bulky for existing facilities are to be hoisted or otherwise handles with apparatus as required.

5. Extra charges resulting from special handling or shipment to be paid by the Kitchen Equipment Contractor if insufficient time was allowed in placing factory orders to ensure normal shipment.
- B. The work to be accomplished so as not to delay the project construction schedule, interfere or conflict with the work being performed by other contractors. Work to be coordinated and integrated to prevent conflict of work necessitating changes to work already completed. Sequence installation and erection to ensure correct mechanical and electrical utility connections are achieved.
- C. Verify all field dimensions before fabrication.
- D. Install items in accordance with manufacturer's instructions.
- E. Set each item of non-mobile and non-portable equipment securely in place, leveled and adjusted to correct height. Anchor to supporting substrate where indicated, and where required for sustained operation and use without shifting or dislocation. Conceal anchorages, wherever possible. Adjust counter tops and other work surfaces to a level tolerance of 1/16" (1.6mm), (maximum offset, and plus or minus on dimension, and maximum variation in 24" (610mm) run from level or indicated slope). Provide anchors, supports, bracing, clips, attachments, etc., as required to comply with the local seismic restraint requirements. The Guidelines for Seismic and Restraint of Kitchen Equipment, as prepared for the Sheet Metal Industry Fund of Los Angeles and endorsed by S.M.A.C.N.A., is to be followed. Install seismic restraints for food service equipment.
- F. Complete field assembly joints in the work (joints which cannot be completed in the shop) by welding, bolting-and-gasketing, or similar methods as indicated and specified. Grind welds smooth and restore finish. Set or trim flush, except for "T" gaskets as indicated. Field joints shall not be visible to the untrained eye.
- G. Provide closure plates and strips where required, with joints coordinated with units of equipment.
- H. Provide sealants and gaskets all around equipment to wall, ceiling, floors, masonry pads, and adjoining units not portable and with enclosed bodies to make joints airtight, waterproof, vermin-proof, and sanitary for cleaning purposes. Space between all equipment to wall, ceiling, floors, masonry pads, and adjoining units not portable and with enclosed bodies shall be completely sealed against entrance of food particles or vermin by means of trim strips, welding, soldering or mastic. Mastic to be General Electric Silicone Construction Sealant Series SE1200 or equal in appropriate color.
- I. Joints up to 3/8" (9.5mm) wide, to be stuffed with backer rod, to shape sealant bead properly, at 1/4" (6mm) depth.
- J. At internal corner joints, apply sealant or gaskets to form a sanitary cove, of not less than 3/8" (9.5mm) radius.

- K. Shape exposed surfaces of sealant slightly concave, with edges flush with faces of materials at joint.
- L. Provide sealant filled or gasketed joints up to 3/8" (9.5mm) joint width. Wider than 3/8" (9.5mm), provide matching metal closure strips, with sealant application each side of strips. Anchor gaskets mechanically, or with adhesives to prevent displacement.
- M. Treat enclosed spaces, inaccessible after equipment installation, by covering horizontal surfaces with powdered borax at a rate of 4 ounces per square foot (1.2 kg/m2).
- N. Insulate to prevent electrolysis between dissimilar metals.
- O. Cut and drill components for service outlets, fixtures, piping, conduit, fittings, etc. as required. Grind and polish penetrations to safe tolerance. Work to include welded sleeves, collars, ferrules or escutcheons.
- P. Verify and coordinate the mounting heights of all wall shelves and equipment, with equipment located below them, for proper clearances.
- Q. Walk-In Cooler/Freezers
 - 1. The cold storage rooms shall be delivered and installed on schedule by factory supervised and approved installers. Coordinate the work with the General Contractor and other trades as necessary.
 - 2. Provide the necessary job site coordination with the various trades to ensure job site conditions will meet the requirements of the cold storage rooms.
 - 3. During curing and cleaning of the wearing floors inside the cold storage rooms, the cold storage room doors shall be left open and well ventilated to prevent damage to the interior. "Keep Out" signs to be posted at each open door.
 - 4. After the installation of the cold storage rooms and prior to the installation of the wearing floor has cured, the cold storage room doors are to be closed and locked.
- R. Coordinate with the Plumbing and Electrical Divisions and provide penetrations in food service equipment for plumbing and electrical service to and to the fixtures, as required. This includes welded sleeves, collars, ferrules, or escutcheons. These services are to be located so that they do not interfere with intended use and/or servicing of the fixture.
- S. All equipment provided by this Section, that requires light bulb(s), are to be provided with heavy-duty, energy efficient, extra-long-life bulbs with a minimum life expectancy of 5000 hours, and as required by the local Jurisdictions. All light bulbs in and/or above foodservice equipment and/or areas are to be coated or provided with shields in compliance with local health codes.

- T. All equipment provided by this Section shall include any and all parts, components, options, accessories, etc. necessary to provide a completely functional item for its intended use under normal conditions and, if appropriate, after the final utility connections are completed by other Divisions. This shall generally apply to equipment such as soda systems, beer systems, and remote refrigeration systems, any type of remote system or equipment, or ice machines, but shall also apply to any equipment provided by this Section.

3.4 COUNTERTOP INSTALLATION

- A. General: Install countertops, except for vanities, over plywood sub-tops with a full spread of water-cleanable epoxy adhesive.
- B. Install components plumb. Level and rigid, scribes to adjacent finishes, in accordance with approved shop drawings and product data.
1. Tops:
- a. Flat and true to within 1/8" of a flat surface over a 10' length.
 - b. Allow a minimum of 1/16" to a maximum of 1/8" clearance between surface and each wall.
2. Fit countertops around projections and to adjacent construction. Smooth and clean field cut edges. Ensure that trim will completely cover cut edges.
- C. Bond seams with stone seam adhesive and draw tight as countertops are set. Mask areas of countertops adjacent to seams to prevent adhesive smears. Use clamps to ensure countertop units are properly aligned and seams are minimum width.
- D. Complete cutouts not finished in shop. Mask areas of countertops adjacent to cutouts while cutting to prevent damage.
- E. Install backsplash and end splash by adhering to wall with water-cleanable epoxy adhesive.
- F. Leave 1/16-inch gap between countertop and splash for filling with sealant. Use temporary shims to ensure uniform spacing.
- G. Heat isolation for hot food wells, heated deck and other drop-in heated equipment.
- 1. Three (3) layers of Nomex insulation held in place with aluminum tape.
 - 2. 16-gauge stainless steel collar.

3. Heat resistant, food safe silicone caulking.

H. Apply sealant to seams and to gap between countertops and splashes; comply with Section 07 92 00 (07920) "Joint Sealants".

I. Countertop Adjusting and Cleaning

1. Remove and replace or repair stonework of the following description:
 - a. Broken, chipped, stained, or otherwise damaged stones: Broken, chipped, stained or otherwise damaged stone may be repaired, providing the methods and results are acceptable to Owner's Representative.
 - b. Defective joints.
 - c. Stones and joints not matching approved samples.
 - d. Stonework not complying with other requirements indicated.
2. Replace in manner that results in stonework matching approved samples and field-constructed mock-ups, complying with other requirements, and showing no evidence of replacement.
3. The contractor is to clean the stone countertops not less than six days after completion of work, using clean water and stiff and soft rags. Do not use wire brushes, acid-type cleanings agents, cleaning compounds with caustic or harsh filler, or other materials or methods that could damage the stone.

J. Countertop Sealer Application

1. All surfaces must be clean and free from all loose grit and debris, stains, dirt, and wax coatings. Surfaces shall remain dry for a minimum of 24 hours before the application of sealer and remain dry for 24 hours after the application of sealer.
2. Floor surface temperature must be above 50°F and below 90°F.
3. Test on a small area before using to determine if the product is acceptable with type of stone.
4. Two (2) uniform coatings of sealer shall be applied before or after installation of stone materials. If prior to installation, adequate documentation shall be included with the material confirming it has been sealed. If after installation, install in strict accordance with Sealer manufacturer's recommendations.

3.5 PROTECTION OF WORK

- A. Use all means reasonable to protect the materials of this Section against theft and damage before, during, and after installation, and to protect the associated work and materials of the other trades.
- B. Fabricated fixtures: cardboard, fiberboard or plywood taped to tops and exposed body panels/components.
- C. Manufactured Equipment: cardboard, fiberboard or plywood taped as required by equipment shape and installation-access requirements.

- D. Prohibited use of equipment includes tool and materials storage, workbench, scaffolding and stacking of construction materials.
- E. Damaged Equipment: immediately document and submit to Owner with Contractor's recommendation of action for repair or replacement and its impact on the Project Schedule and Contract Amount.
- F. Prefabricated walk-in coolers/freezers are not to be used as general storage and should be locked before leaving the site daily. Damage and theft resulting from failure to secure units will be repaired or replaced at Contractor's expense.

3.6 ADJUSTING

- A. Equipment to be tested for leaks, poor connections, inadequate or faulty performance.
 - 1. Thermostatically controlled equipment and equipment with automatic features shall be operated for 14 days to prove controls are functioning as intended. Walk-in refrigerators and freezers shall be turned on and run for a minimum of fourteen days.
- B. Refrigeration equipment to run a minimum of three days durations before acceptance.
- C. Lubricate and adjust drawer slides, hinges, casters.
- D. Adjust pressure regulating valves, time-delay relays, thermostatic controls, temperature sensors, exhaust hood grills, etc.
- E. Clean or replace faucet aerators, line strainers.
- F. Repair, adjust or replace equipment, which is found to be defective in its operation, including units which are below capacity or operating with excessive noise or vibration

3.7 CLEANING, RESTORING AND REPAIRING

- A. After completion of installation, and completion of other major work in foodservice areas, remove protective coverings and clean foodservice equipment internally and externally. Repair all damage as a result of this installation.
- B. Restore exposed and semi-exposed finishes removing abrasions and other damages, polish exposed metal surfaces and touch-up painted surfaces. Replace work which cannot be successfully restored.
- C. Polish glass, plastic, hardware and accessories, fixtures and fittings.
- D. Wash and clean equipment and leave in a condition ready for the Owner to sanitize and use.

3.8 TESTING

- A. Delay the start-up of equipment until service lines have been tested, balanced, and adjusted for pressure, voltage and similar considerations, and until water and steam lines have been cleaned and treated for sanitation.
- B. Kitchen Equipment Contractor (K.E.C.) with assistance from a factory-certified representative from the exhaust hood manufacturer shall conduct an exhaust hood performance test for each exhaust hood in the K.E.C.'S scope of work at the conclusion of the project when all hoods and related cooking equipment are in operation. K.E.C. shall have manufacturer's factory authorized representative test and measure exhaust airflow rates, dampers, switches, and sequence of operation, with all appliances at operating temperatures. K.E.C. shall furnish a written report within ten (10) working days of substantial completion and acceptance of the project by the Owner, indicating the design requirements for each hood and the actual operating parameters as tested and measured.
- C. Refrigeration Piping Testing
 - 1. Each system shall be pressure tested for leaks. Tests are to be on the high side and the low side. All valves shall be fully open during last test.
 - 2. Tests are to be accomplished as follows:
 - a. Charge the systems with refrigerant through the port of liquid shut-off valves of the receivers to a pressure of 10 to 20 p.s.i.
 - b. Add dry nitrogen, the supply of which shall be equipped with a pressure regulating valve to provide the specified pressure.
 - c. Carefully test all joints for leaks using either a Halide torch or an electronic Halogen leak detector.
 - 3. Precautions to be taken to disconnect the low-pressure controls for protection of the bellows during testing.
 - 4. Refrigeration System Evacuation
 - a. Evacuation shall be with a vacuum pump with an indicating gauge registering pressure in microns. Pump shall be connected to the system with a 5/8" (15mm) O.D. line or larger.
 - b. Evacuate both high and low sides to 500 microns. Break the vacuum with refrigerant to 0 p.s.i. evacuate high and low sides to 100 microns, and then break vacuum to 0 p.s.i. with the refrigerant to be used in the system.

3.9 START-UP AND INSTRUCTIONS

- A. Make arrangements for demonstration of foodservice equipment operation and maintenance, in advance, with the Owner/Operator.

- B. Demonstrate foodservice equipment to familiarize the Owner and the Operator on operation and maintenance procedures, including periodic preventative maintenance measures required. Include an explanation of service requirements and simple on-site service procedures, as well as information concerning the name, address and telephone number of qualified local sources of service. The individual(s) performing the demonstration are to be knowledgeable of operating and service aspects of the equipment.
- C. Provide a written report of the demonstration to the Owner, outlining the equipment demonstrated and malfunctions or deficiencies noted. Indicate individuals present at demonstration
- D. Final Cleaning: After testing and start-up, clean the foodservice equipment and leave in a condition ready for the Owner to sanitize and use.
- E. All keys for all locks provided with equipment provided under this Section are to be gathered up, individually tagged with the equipment they belong to, put into a single box, and handed over to the Owner's authorized representative. A list of the keys and their associated equipment item numbers are to be provided with the O&M Manuals, along with a copy of the list, signed by the Owner's representative, acknowledging receipt of the keys.

3.10 CLEAR AWAY

- A. Throughout the progress of their work, Contractor is to keep the working area free from debris and remove rubbish from the premises resulting from work being done by them. At the completion of their work, Contractor is to leave the premises in a clean and finished condition.

3.11 SEISMIC RESTRAINTS

- A. Install equipment according to the SMACNA's "Kitchen Ventilation Systems and Food Service Equipment Guidelines Publication 1767", Appendix A, as necessary for acceptance. This shall include:
 - 1. Identifying items on submittal drawings, plans, elevations, and sections.
 - 2. Showing required SMACNA methods of restraint on submittal drawings.
 - 3. Referencing the appropriate details
 - 4. Obtain regulatory approval for all seismic engineering details.
- B. If no SMACNA detail exists for a particular equipment/situation, prepare and obtain approval for a special attachment details:

1. Detail must be prepared by an engineer licensed by the State having jurisdiction over the project and accompanied by the supporting calculations used in the design.
2. Verify that the restrain design is appropriate to the building's structural conditions and the surfaces to which the equipment will be secured.

3.12 DESIGN SUBMITTAL REQUIREMENTS

A. Kitchen Equipment Contractor to submit detailed and fully coordinated drawings for all foodservice equipment produced in Autodesk Revit 2020. Revit 2020 drawings must be 1/4-inch scale minimum. Submit complete Foodservice Equipment Itemized Floor Plans, Full MEP Itemized Equipment Schedules, Electrical Rough-In Drawings, Plumbing Rough-In Drawings, Exhaust Hood Rough-In Drawings, Exhaust Manufacture Shop Drawings, Special Conditions Drawings (Noting all ceiling, wall, floor changes and dimensioned wall backing required for the project), Refrigeration System Manufacture Shop Drawings, Walk-In Box Manufacture Shop Drawings, Tray Return System Manufacture Shop Drawings, Dish Machine Manufacture Shop Drawings, Power Sink Manufacture Shop Drawings, Fabricated Serving Counter Manufacture Shop Drawings, Sneeze Guard Manufacture Shop Drawings, Foodservice Fixture and Equipment Elevations, Foodservice Fixture and Equipment Sections and Foodservice Fixture and Equipment Standard Details. Provide detail drawings showing complete wiring, piping, and schematic diagrams, and any other details required to demonstrate that the major foodservice systems are fully coordinated and will properly function as complete unit(s) once installed. Drawings must show proposed layout and anchorage of equipment and appurtenances, and equipment relationship to other parts of the scope of work, including clearances for maintenance, operation, ADA clearances and proper aisle spaces. All rough-in drawings noted above shall be full dimensioned from face of finished walls. Kitchen Equipment Contractor to provide field verify architectural background within Revit model to ensure dimensional accuracy on rough-in plans prior to submittal review and completion to ensure proper dimensions for construction.

1. Detail drawings by Kitchen Equipment Contractor must be separate drawings and be on the Governments standard sheet size, but not smaller than the contract drawings, indicating foodservice equipment and cold storage assemblies with itemized schedule, special conditions drawings indicating size and location of slab depressions, cores, wall openings, block-outs, ceiling pockets, blocking grounds, ceiling details, wall, access panels, rough-in plumbing/mechanical systems and rough-in electrical systems.
2. Prepare and submit detailed drawings that show the size, type, and location of equipment drain lines, and floor drains / sinks. Indicate drain lines from equipment, distances of drain lines and floor drain or floor sink receptacles from equipment and aisles, and elevation views of drain piping and floor drains or floor sink locations.

3. Detail drawings by manufacturers must be separate drawings; manufacturer's standard size and indicate item number, name, and quantity, construction details, sections, and elevations, adjacent walls, columns, and equipment, plumbing and electrical schematics, and fabricated fixtures with single electrical or plumbing connection, and service access panels required for maintenance or replacement of mechanical or electrical components.
4. Detail drawings of the custom fabricated serving counters shall include all sneeze guard placement fully dimensioned (height, reach and all NSF conforming dimensions are to be shown) on the serving counter drawings. Serving counter detail drawings shall include fully dimensioned floor plan views, fully dimensioned elevation views, fully dimensioned sections views and fully dimensioned critical expanded views of the hot / cold drop-in isolation detail, mounting method of the sneeze guard details, quartz manufacture fabrication details and drop-in control panel mounting details on the service side of the serving counters. The detail drawings also include full load center balancing schedules that shall be coordinated with the General Contractor and Electrical Contractor prior to final rough-in to ensure proper building floor power is being supplied by the General Contractor and Electrical Contractor.
5. The kitchen equipment contractor shall provide laser cut plywood templates to be used for jobsite coordination during construction and for the General Contractors use locating all load center power stub-ups and floor sink locations. The kitchen equipment contractor shall personally supervise and install the plywood templates. Once plywood templates are installed, Kitchen Equipment Contractor shall spray paint the edges of the custom fabricated serving counter templates, spray paint and location all floor sink locations and load center locations. Once spray painting is complete, Kitchen Equipment Contractor is to gain final sign off from the General Contractor, Electrical Contractor and Plumbing Contractor that all rough-in locations have been fully coordinated and agreed upon. Kitchen Equipment Contractor is to leave plywood templates in place onsite and remove at a later date when requested by the General Contractor.

3.14 SUBMITTALS

A. Government, Architect of Record and Foodservice Consultant of Record approval is required for all foodservice equipment detail drawings, manufacture shop drawings and manufacture cut-sheet book submittals prior to release and fabrication.

SD-01 Preconstruction Submittals and Field Dimensioned; Kitchen Equipment Contractor's Field Verification Report of Architectural Data and Manufacturer's Qualifications

SD-02 Detailed Revit Drawing Package

SD-03 Manufacture Shop Drawing Package

SD-04 Product Data Sheets for Foodservice Equipment

SD-05 Samples for Serving Counter Materials, Sample of Stainless-Steel Materials (All Gauges) and Sample of Exposed Exterior Walk-In Box Finish

SD-06 Design Data Manufacturer's Descriptive and Technical Literature

SD-07 Test Reports Manufacturer's Test Data Field Test Reports and Existing Exhaust Hood Air Balancing Test

SD-08 Certificates National Sanitation Foundation Standards Underwriters Laboratories Standards Energy Star

SD-09 Manufacturer's Instructions Manufacturer's Instructions for shipping, handling, storage, installation, and start-up. Kitchen Equipment Contractor Equipment Demonstration for All Manufactures

SD-10 Operation and Maintenance Data Operation and Maintenance Manuals List of Authorized Local Service and Repair Entities

SD-11 Closeout Submittals Manufacturer's Warranty Contractor's Warranty for Installation As-Built Revit Drawings and Model Submission

3.13 ITEMIZED SPECIFICATIONS-LUKE DFAC

ITEM #1 TRASH DROP COUNTER

Quantity: One (1)
Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED TRASH DROP COUNTER
2. To measure per drawing. 34" High.
Standard grade quartz top with a 4" backsplash. Counter to accommodate 4 trash cans. Counter base to be stainless steel construction with walls, flooring and shelving as required. Refer to fabrication details.
3. Counter exterior to have 3/4" plywood panels and hinged doors covered with a standard grade laminate.
4. Counter to sit on 6" high stainless steel legs with adjustable feet and have a toe kick as required.
5. No utilities included.
6. Provide 4 equally spaced doors.

ITEM #2 DISHWASHER CONVEYOR

Quantity: One (1)
Manufacturer: Aerowerks
Model: FABRICATED

1. Model FABRICATED DISHWASHER CONVEYOR
Refer to manuf. drawings for additional information

ITEM #3 RACK CONVEYOR DISHWASHER

Quantity: One (1)
Manufacturer: Custom
Model: EXISTING TO REMAIN

2. Model EXISTING TO REMAIN RACK CONVEYOR DISHWASHER

ITEM #4 CONVEYOR DISHMACHINE

Quantity: One (1)
Manufacturer: Custom
Model: VERIFY

1. Model VERIFY CONVEYOR DISHMACHINE

ITEM #5 VENT DUCT

Quantity: Two (2)
Manufacturer: Custom
Model: FABRICATED

1. Model FABRICATED VENT DUCT

ITEM #6 CONVEYOR

Quantity: One (1)
Manufacturer: Custom

1. CONVEYOR

ITEM #7 PRE-RINSE FAUCET ASSEMBLY, WITH ADD ON FAUCET

Quantity: One (1)
Manufacturer: T&S Brass
Model: B-0133-12-CR-B

1. Model B-0133-12-CR-B EasyInstall Pre-Rinse Unit, spring action gooseneck, 8" wall mount, spray valve (B-0107), 12" add-on faucet, wall bracket, quarter-turn Cerama cartridges, low lead

ITEM #8 WASTE COLLECTOR

Dimensions: 35.88(h) x 36.5(w) x 22.25(d)
Quantity: One (1)
Manufacturer: Salvajor
Model: P914

1. Model P914 Pot/Pan Scrap Collector™, scrapping, pre-flushing & collecting system (widely accepted in areas where disposers are restricted), NEMA 4 HYDROLOGIC® control panel with patented operator sensor, two water saving modes (timed run & auto start/stop), safety line disconnect, LCD readout, salvage basin & silverware trap, scrap basket, 3/4 HP corrosion-resistant pump, pump intake screen, stainless steel construction, UL, CSA, CE, NSF
2. Collector top is available to ship to the fabricator in advance of unit (additional shipping charges will apply). Please provide instructions on order
3. 208v/60/1-ph, 5.5 amps

ITEM #9-10 SPARE NO.

ITEM #11 WALL / SPLASH MOUNT FAUCET

Quantity: Two (2)
Manufacturer: T&S Brass
Model: B-0231

1. Model B-0231 Sink Mixing Faucet, wall mount, 8" centers, 12" swing nozzle, lever handles, quarter-turn Eterna cartridges, 1/2" NPT female inlets, low lead, ADA Compliant

ITEM #12 SPARE NO.

ITEM #15-20 SPARE NO.

ITEM #23 DISPLAY CASE, NON-REFRIGERATED COUNTERTOP

Dimensions: 30.63(h) x 28.13(w) x 25(d)
Quantity: One (1)
Manufacturer: Structural Concepts
Model: CGS2830

1. Model CGS2830 Impulse® Service/Self-Service Non-Refrigerated Display Case, countertop, 28-1/8"W, straight

- front glass & ends, (3) lighted metal shelves, top light, clear glass rear swinging doors, black interior & exterior, cETLus, ETL-Sanitation
2. NOTE: If GFCI is required, a GFCI breaker MUST be used in lieu of a GFCI receptacle
 3. Warranty: 1 year parts & labor warranty, standard
 4. Electrical: 110-120v/60/1ph, 0.40 amp, standard
 5. Electrical Connection: 6' Straight blade power cord with NEMA 5-15P, standard
 6. Model Finish: Powder coated SCC Standard Silversand Black (FDA compliant)

ITEM #24 CONVEYOR TOASTER

Dimensions: 13.75(h) x 14.5(w) x 17.71(d)
Quantity: One (1)
Manufacturer: Hatco
Model: TQ-10

1. Model TQ-10 Toast-Qwik® Conveyor Toaster, horizontal conveyor, countertop design, all bread types toaster, approximately 5 slices/min capacity, painted steel top & aluminized steel construction, 4" legs, 1.8kW, CE, cULus, UL EPH Classified, Made in USA
2. NOTE: Sale of this product must comply with Hatco's Minimum Resale Price Policy; consult order acknowledgement for details
3. NOTE: Includes 24/7 parts & service assistance, call 414-671-6350
4. One year on-site parts & labor warranty, plus one additional year parts only warranty on all Toast-Qwik metal sheathed elements
5. 120v/60/1-ph, 1800 watts, 15.0 amps, NEMA 5-15P (domestic voltage), standard

ITEM #25 JUICE DISPENSER, ELECTRIC

Dimensions: 33.1(h) x 15.7(w) x 25.5(d)
Quantity: One (1)
Manufacturer: BUNN
Model: 37300.0004

1. Model 37300.0004 37300.0004 JDF-4S Silver Series® 4-Flavor Cold Beverage System, Push and Hold, Lighted Door,, (3) 12 oz. drinks/min capacity, 2-modular dispense decks, 18 lb. ice bank, 7" cup clearance, dispense 1.0 to 1.5 ounces per second flow rate, pumps & mixes 2+1 to 11+1 concentrated beverages, 4+1 high viscosity & 5+1 juices, dispenses frozen and ambient products, High Intensity™ mixing technology, push button and portion control, LED lighted door graphics, door lock, juice display, 120v/60/1-ph, 6amps, NEMA 5-15P, ETLus, NSF

ITEM #26 BEVERAGE COUNTER

Quantity: One (1)
Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED BEVERAGE COUNTER
2. One (1) Beverage Counter - To measure per site conditions. 34" High.
3. Standard grade quartz top with a 4" backsplash.
4. Counter to accommodate Beverage Equipment and Buyout Equipment.
5. Counter base to be stainless steel construction with walls, flooring and shelving as required. Refer to fabrication details.
6. Counter exterior to have 3/4" plywood panels and hinged doors covered with a standard grade laminate.
7. Counter to sit on 6" high stainless steel legs with adjustable feet and have a toe kick as required. No utilities included.

ITEM #27 ESPRESSO MACHINE

Quantity: One (1)
Manufacturer: VENDOR FURNISHED
Model: BEAN-TO-CUP

1. Model BEAN-TO-CUP ESPRESSO MACHINE

ITEM #28 SMOOTHIE MAKER

Quantity: One (1)
Manufacturer: VENDOR FURNISHED
Model: VERIFY

1. Model VERIFY SMOOTHIE MAKER

ITEM #29-30 SPARE NO.**ITEM #31 TRASH RECEPTACLE, INDOOR**

Dimensions: 30(h) x 22(w) x 11(d)
Quantity: One (1)
Manufacturer: Rubbermaid Commercial Products
Model: FG354060BLA

1. Model FG354060BLA Slim Jim® Container,
2. 23 gallon, 22"W x 11"D x 30"H, with venting channels

3. Molded-in handles, general purpose waste, open type without lid, high-impact plastic construction, black,
4. Made in USA

ITEM #32 CONDIMENT DISPENSER

Quantity: One (1)
Manufacturer: Star (Middleby)
Model: CD3S

1. Model CD3S CONDIMENT DISPENSER

ITEM #33 CO2 TANK

Quantity: Two (2)
Manufacturer: VENDOR FURNISHED
Model: BY VENDOR

1. Model BY VENDOR CO2 TANK

ITEM #34 SODA SYSTEM W/ RACK

Quantity: One (1)
Manufacturer: VENDOR FURNISHED
Model: BY VENDOR

1. Model BY VENDOR SODA SYSTEM W/ RACK

ITEM #35 B-N-B CABINET

Quantity: One (1)
Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED B-N-B CABINET

ITEM #37 COFFEE BREWER

Quantity: One (1)
Manufacturer: VENDOR FURNISHED
Model: BY VENDOR

1. Model BY VENDOR COFFEE BREWER

ITEM #41 ICED TEA BREWER / DISPENSER

Quantity: One (1)
Manufacturer: VENDOR FURNISHED
Model: BY VENDOR

1. Model BY VENDOR ICED TEA BREWER / DISPENSER

ITEM #42 WATER DISPENSING SYSTEM

Dimensions: 52.88(h) x 23.38(w) x 21.63(d)
Quantity: One (1)
Manufacturer: Vivreau Advanced Water Systems
Model: V3-202

1. Model V3-202 (1045954) Vivreau High Volume Water Bottling System,
2. Dual tap, undercounter cabinet, self-contained ice bank refrigeration system, micro-filtered, chilled still and sparkling water, twin tap with removable nozzles & stainless steel drip tray,
3. Accommodates 20 lb CO2 cylinder (cylinder not included), front feet, rear rollers, 120v/60/1-ph, 11.0 amps, NEMA 5-15P, ETL, NSF (for indoor use only)
4. Annual Maintenance Program, includes: (2) filter changes per year, routine maintenance, reactive service, (1) year warranty on parts & service, training materials, marketing & promotional services (priced per year) (NET)
5. Installation (NET)
6. Shipping (NET)
7. Model ZZVIVRE008 100 Bottles (cases of 20) mix of sparkling and still Vivreau Bottles comes standard with equipment. Contact factory for selection. Additional artwork charges may apply for custom logo
8. Model TRAY-16 (1046000) Wash Rack, (16) 4.4" x 4.4" compartments, use with Designer, Classic or Twist bottles, fits standard commercial dishwasher

ITEM #43 TRASH RECEPTACLE, INDOOR

Dimensions: 30(h) x 22(w) x 11(d)
Quantity: One (1)
Manufacturer: Rubbermaid Commercial Products
Model: FG354060BLA

1. Model FG354060BLA Slim Jim® Container, 23 gallon, 22"W x 11"D x 30"H, with venting channels, molded-in handles, general purpose waste, open type without lid, high-impact plastic construction, black, Made in USA

ITEM #44 BEVERAGE COUNTER

Quantity: One (1)

Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED BEVERAGE COUNTER
2. One (1) Beverage Counter - To measure per site conditions. 34" High.
3. Standard grade quartz top with a 4" backsplash.
4. Counter to accommodate Beverage Equipment and Buyout Equipment (Provided by others).
5. Counter base to be stainless steel construction with walls, flooring and shelving as required.
6. Refer to fabrication details.
7. Counter exterior to have 3/4" plywood panels and hinged doors covered with a standard grade laminate. Counter to sit on 6" high stainless steel legs with adjustable feet and have a toe kick as required. No utilities included.

ITEM #45 POS SYSTEM

Quantity: Two (2)
Manufacturer: OWNER
Model: BY OWNER

1. Model BY OWNER POS SYSTEM

ITEM #46 POS COUNTER

Quantity: One (1)
Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED POS STATION
2. One (1) Serving Counter - To measure per site conditions. 34" High.
3. Standard grade quartz top. Counter to accommodate 2 POS Stations (Provided by others).
4. Counter base to be stainless steel frame construction with flooring and shelving as required.
5. Counter to have to be able to house (2) roll-in items. Counter to have 18 gauge stainless steel walls, hinged doors and hinged louvered doors as required.
6. Counter exterior to have 3/4" plywood panels covered with a standard grade laminate.
7. Counter to sit on 6" high stainless steel legs with adjustable feet and have a toe kick as required. Counters to have (2) Vertical sneeze shields- one on each side.

ITEM #47 RACK DISPENSERS

Dimensions: 36.13(h) x 23.75(w) x 25.69(d)
Quantity: Two (2)

Manufacturer: Lakeside Manufacturing
Model: 998

1. Model 998 Tray & Glass Rack Dispenser, cabinet style, enclosed base, mobile, for 10" x 20" or 14" x 20" or 20" x 20" racks, stainless steel construction, 4" swivel casters (2) with brakes, NSF, Made in USA

ITEM #48 POS SYSTEM

Quantity: Two (2)
Manufacturer: OWNER
Model: BY OWNER

1. Model BY OWNER POS SYSTEM

ITEM #49-50 SPARE NO.

ITEM #51 POS COUNTER

Quantity: One (1)
Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED POS STATION
2. One (1) Serving Counter - To measure per site conditions. 34" High.
3. Standard grade quartz top. Counter to accommodate 2 POS Stations(Provided by others).
4. Counter base to be stainless steel frame construction with flooring and shelving as required.
5. Counter to have to able to house (2) roll-in items. Counter to have 18 gauge stainless steel walls, hinged doors and hinged louvered doors as required.
6. Counter exterior to have 3/4" plywood panels covered with a standard grade laminate.
7. Counter to sit on 6" high stainless steel legs with adjustable feet and have a toe kick as required.
8. Counters to have (2) Vertical sneeze shields- one on each side.

ITEM #52 RACK DISPENSERS

Dimensions: 36.13(h) x 23.75(w) x 25.69(d)
Quantity: Two (2)
Manufacturer: Lakeside Manufacturing
Model: 998

1. Model 998 Tray & Glass Rack Dispenser, cabinet style, enclosed base, mobile, for 10" x 20" or 14" x 20" or 20" x 20" racks, stainless steel construction, 4" swivel casters (2) with brakes, NSF, Made in USA

ITEM #53 LIGHT FIXTURE

Quantity: One (1)
Manufacturer: BSI
Model: 2580

1. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
2. Lamp type to be specified
3. Remote Infinite, standard
4. Wiring exit point to be specified
5. Lighting frame finish to be specified

ITEM #54 FROST TOP / COLD SLAB, DROP IN

Dimensions: 27.13(h) x 42.25(w) x 21.75(d)
Quantity: One (1)
Manufacturer: Randell
Model: RFT-3

1. Model RFT-3 Drop-In Frost Top, refrigerated, 43" L, (3) 18" x 13" pan capacity, stainless steel top, corrosion resistant steel exterior, self-contained refrigeration system, R290 Hydrocarbon refrigerant, 1/4 HP, 115v/60/1-ph, 3.5 amps, NEMA 5-15P, cUL, UL, NSF, Made in USA
2. (1) year parts, labor, and compressor warranty, standard

ITEM #55 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified
5. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
6. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
7. Remote Infinite, standard
8. Wiring exit point to be specified

9. Lighting frame finish to be specified
10. Housing length to be specified

ITEM #56 LIGHT FIXTURE

Quantity: One (1)
Manufacturer: BSI
Model: 2580

1. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
2. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
3. Housing length to be specified
4. Remote Infinite, standard
5. Wiring exit point to be specified
6. Lighting frame finish to be specified

ITEM #57 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified

ITEM #58 INDUCTION RETHERMALIZER, BUILT-IN / DROP-IN

Dimensions: 12.31(h) x 13.88(w)
Quantity: Two (2)
Manufacturer: Vollrath
Model: 741101D

1. Model 741101D Mirage® Induction Rethermalizer, drop-in, dry operation, 11 quart, inset with hinged cover, (4) soup presets, stir indicator LED, solid state controls with locking function, temperature control in °F or °C, cabinet mount controls with leads, includes: induction ready inset, inset cover, mounting hardware & cord with NEMA 5-15P, 800 watts, 6.7 amps, 120v/60/1-ph, cULus, NSF, FCC (cover not NSF) (Refer to vollrathfoodservice.com for full warranty policy)
2. Requires use of included Vollrath induction-ready inset - failure to use these insets may damage the unit & will void the warranty

3. Model 88204 Inset, 11 quart, induction ready, for Mirage induction rethermalizer, NSF (Refer to vollrathfoodservice.com for full warranty policy)
4. Model 47490 Kool-Touch Hinged Cover, stainless with black phenolic knob, fits 78204 Inset & 77110 Double Boiler, imported (Refer to vollrathfoodservice.com for full warranty policy)

ITEM #59-60 SPARE NO.**ITEM #61 DROP-IN FREEZER**

Dimensions: 28.38(w) x 17.19(d)
Quantity: One (1)
Manufacturer: Randell
Model: 9550-290

1. Model 9550-290 Drop-In Freezer/Plate Chiller, 6 gallon, top opening with 2 insulated hinged covers, stainless steel interior & top, corrosion resistant steel exterior, self-contained refrigeration system, bottom mount, R290 Hydrocarbon refrigerant, 1/4 HP, UL, cUL, NSF, Made in USA
2. (1) year parts, labor, and compressor warranty, standard
3. 115v/60/1-ph, 2.0 amps, 8' cord, NEMA 5-15P, standard

ITEM #62 HOT / COLD FOOD WELL UNIT, DROP-IN, ELECTRIC

Dimensions: 27.75(h) x 70.06(w) x 26.13(d)
Quantity: One (1)
Manufacturer: Randell
Model: RCHB-5-208

1. Model RCHB-5-208 Drop-In Hot/Cold Food Unit, electric, (5) 12" x 20" pan size, common waterbath, switch for hot or cold operation, thermostatic controls, 1" drain & gate valve, 18 gauge stainless steel top & interior, corrosion resistant steel exterior, R290a, 1/4 HP, 4.4kW, cUL, UL, NSF, Made in USA (unit cutout size: 68-1/2"W x 25"D)
2. (1) year parts, labor, and compressor warranty, standard
3. 120/208v/60/1-ph, hardwired connection, standard

ITEM #63 HEAT LAMP

Quantity: One (1)
Manufacturer: BSI
Model: 705

1. Model 705 Stealth™ Warmer & Light Combo, (specify voltage & length), cULus, NSF

2. Voltage & Length to be specified
3. Lamp type to be specified
4. Remote Infinite, standard
5. Wiring exit point to be specified

ITEM #64 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified
5. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
6. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
7. Remote Infinite, standard
8. Wiring exit point to be specified
9. Lighting frame finish to be specified
10. Housing length to be specified

ITEM #65 COLD FOOD WELL UNIT, DROP-IN, REFRIGERATED

Quantity: One (1)
Manufacturer: BSI
Model: CP-500N-30

1. Model CP-500N-30 BSI, LLC Drop-In Rotating Cold Pan, refrigerated, 30" inner dia., round, 10" unit depth, 3" below countertop interior, holds (12) bain maries or (5) triangle bowls, utilizing 404 refrigerant, pressure foamed insulation, 1/2" drain with ball valve, 304 stainless steel, 14-gauge brushed finish interior, 18-gauge brushed finish exterior, 1/4 HP, 120v/60/1-ph, 10.7 amp, 700 BTU, NEMA 5-15, ETL
2. Built-in Unit
3. Serving Pan, triangular, single wall, stainless steel
4. Self-Contained refrigeration, standard

ITEM #66 LIGHT FIXTURE

Quantity: One (1)
Manufacturer: BSI
Model: 2580

1. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
2. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
3. Housing length to be specified
4. Remote Infinite, standard
5. Wiring exit point to be specified
6. Lighting frame finish to be specified

ITEM #67 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified
5. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
6. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
7. Remote Infinite, standard
8. Wiring exit point to be specified
9. Lighting frame finish to be specified
10. Housing length to be specified

ITEM #68 LIGHT FIXTURE

Quantity: One (1)
Manufacturer: BSI
Model: 2580

1. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
2. Lamp type to be specified
3. Remote Infinite, standard
4. Wiring exit point to be specified
5. Lighting frame finish to be specified

ITEM #69 SPARE NO.**ITEM #70 SERVING COUNTER**

Quantity: One (1)
Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED SERVING COUNTER

ITEM #71 HOT / COLD FOOD WELL UNIT, DROP-IN, ELECTRIC

Dimensions: 27.75(h) x 44.06(w) x 26.13(d)
Quantity: One (1)
Manufacturer: Randell
Model: RCHB-3-208

1. Model RCHB-3-208 Drop-In Hot/Cold Food Unit, electric, (3) 12" x 20" pan size, common waterbath, switch for hot or cold operation, thermostatic controls, 1" drain & gate valve, 18 gauge stainless steel top & interior, corrosion resistant steel exterior, R290a, 1/4 HP, 2.2kW, cUL, UL, NSF, Made in USA (unit cutout size: 42-1/2"W x 25"D)
2. (1) year parts, labor, and compressor warranty, standard
3. 120/208v/60/1-ph, hardwired connection, standard

ITEM #72 LIGHT FIXTURE

Quantity: One (1)
Manufacturer: BSI
Model: 2580

1. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
2. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
3. Housing length to be specified
4. Remote Infinite, standard
5. Wiring exit point to be specified
6. Lighting frame finish to be specified

ITEM #73-74 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified
5. Model 705 Stealth™ Warmer & Light Combo, (specify voltage & length), cULus, NSF
6. Voltage & Length to be specified
7. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
8. Remote Infinite, standard
9. Wiring exit point to be specified
10. Warmer finish to be specified

ITEM #75 HEATED SHELF FOOD WARMER

Dimensions: 2.16(h) x 49.63(w) x 19.63(d)
Quantity: One (1)
Manufacturer: Hatco
Model: HBGB-4818

1. Model HBGB-4818 Heated Base Glass Shelf, built-in, 48"L, ceramic glass surface, uniform heat, 100° - 200°F thermostatic control with lighted on/off rocker switch, choice of frame finish, cULus, UL EPH Classified
2. NOTE: Sale of this product must comply with Hatco's Minimum Resale Price Policy; consult order acknowledgement for details
3. NOTE: Includes 24/7 parts & service assistance, call 414-671-6350
4. 1-Yr Warranty on Blanket Heating Elements against burnout, standard
5. 120v/60/1-ph, 850 watts, 7.1 amps, NEMA 5-15P (domestic voltage), standard
6. NOTE: Recommended for use in metallic countertop, verify that the material is suitable for temperatures up to 200°F
7. Model HBGB-GLASS-BLK Black finished ceramic glass, standard
8. Stainless steel trim ring (standard)
9. Flat top surface, standard
10. Thermostat control with lighted rocker switch, standard
11. Stainless steel bezel only (standard)

ITEM #76 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified
5. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
6. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
7. Remote Infinite, standard
8. Wiring exit point to be specified
9. Lighting frame finish to be specified
10. Housing length to be specified

ITEM #77 GRIDDLE, ELECTRIC, FLOOR MODEL

Dimensions: 36(h) x 59.14(w) x 39.5(d)
Quantity: One (1)
Manufacturer: Evo America, LLC (Middleby)
Model: 10-0600-EVT

1. Model 10-0600-EVT Evo® EEvent® 48E PLUS Full Metal Surround Cooking Station, electric, 48"W x 24"D rectangular steel cooktop surrounded with black granite, self-contained ventilation, multi-stage filtration system, integrated fire suppression system, 100° F to 425° F (38° C to 218° C) temperature range, touch panel display, includes: cleaning kit, (2) stainless steel spatulas, (1) stainless steel scraper, UL, UL EPH Classified, Made in USA
2. OWNER RESPONSIBILITY: Before any Evo EEvent Electric Cooktop with Ventless Recirculating Ventilation System can be powered up for the first time, the factory installed UL300 Buckeye fire suppression system must be armed, commissioned, and tagged by a certified and locally licensed BUCKEYE Fire Suppression contractor. This commissioning is also the commencement of an agreement between the Buckeye agent and the owner and cannot be altered by Evo, Inc., its agents, dealers, or service agencies. Cost will vary by individual Buckeye agent and are paid by the customer, not by Evo.
3. NOTE: Before purchasing and installing this equipment, Evo, Inc. recommends that operators apply for permits as required by local jurisdictional authorities. Required permits vary by jurisdiction and may include Electrical, Fire, Mechanical and Food Service. Permits are the responsibility of the operator and/ or its contractors.
4. 1 year parts & labor warranty (contact factory for details)
5. 208v/60/3-ph, 32.0 amps, 6.7 kW, 8-foot cord, NEMA 15-50P
6. Model 10-0150-EVT-FMS Customization for 10-0148-EVT: Metal surround, stainless steel enclosure
7. Model 10-0150-EVT-34 Caster Kit, for 34" working height, ADA Compliant
8. Model 13-0237-EVT Replaceable Charcoal Filter (6 pack)

ITEM #78 SNEEZE GUARD, STATIONARY

Quantity: Three (3)
Manufacturer: BSI
Model: ZG9500-4

1. Model ZG9500-4 ZGuard® Food Shield, single, full-service/vertical partition, fully adjustable, 27" height, 24-1/2" wide tempered glass, 1" diameter tubing single supports
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. Frame finish to be specified
4. 1" radius corner, standard

ITEM #79-80 SPARE NO.**ITEM #81 LIGHT FIXTURE**

Quantity: One (1)
Manufacturer: BSI
Model: 2580

1. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
2. Lamp type to be specified
3. Remote Infinite, standard
4. Wiring exit point to be specified
5. Lighting frame finish to be specified

ITEM #82 COMPACT PREP TABLE REFRIGERATOR

Dimensions: 36(h) x 27(w) x 34.5(d)
Quantity: One (1)
Manufacturer: Traulsen
Model: UST279-D

1. Model UST279-D Dealer's Choice Compact Prep Table Refrigerator with low profile flat cover, (2) drawers, one-section, 27" wide, top rail holds (9) 1/6 pans 4" deep (included), drawers hold (6) 1/6 pans per drawer (not included), top rail & drawers can accommodate up to 6" deep pans. Full length reversible cutting board, stainless steel exterior top, sides & drawers, anodized aluminum interior, galvanized exterior back & bottom, rear mounted, self-contained refrigeration, R290 Hydrocarbon refrigerant, (4) 4" casters, 1/4 HP, cETLus, ETL-Sanitation
2. 6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
3. 115v/60/1-ph, 7.2 amps, 8' cord, NEMA 5-15P

ITEM #83 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified

5. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
6. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
7. Remote Infinite, standard
8. Wiring exit point to be specified
9. Lighting frame finish to be specified
10. Housing length to be specified

ITEM #84 PIZZA SERVING COUNTER

Quantity: One (1)
 Manufacturer: Stainless Fabricating
 Model: FABRICATED

1. Model FABRICATED PIZZA SERVING COUNTER-
2. One (1) Serving Counter - To measure per plans. 34" High. Standard grade quartz top.
3. Counter to accommodate Drop-in Equipment and Buyout Equipment.
4. Counter base to be stainless steel frame construction with flooring and shelving as required.
5. Counter to have 18 gauge stainless steel walls, hinged doors and hinged louvered doors as required.
6. Counter exterior to have 3/4" plywood panels covered with a standard grade laminate.
7. Counter to be recessed to accommodate Roll-In Equipment, drop in and under counter equipment (Provided by others).
8. Counter to sit on 6" high stainless steel legs with adjustable feet and have a removable toe kick as required. Counter to be pre-wired to a load center with final connections by others.
9. Sneeze guards to be provided by others.

Refer to Fabrication details for additional information.

ITEM #85 HEATED SHELF FOOD WARMER

Dimensions: 3.92(h) x 16.75(d)
 Quantity: Three (3)
 Manufacturer: Hatco
 Model: GRSR-15

1. Model GRSR-15 Heated Shelf, Free-standing, 15" round, counter top or drop-in, designer colors, 250 watts, CE, cUL, UL, UL EPH Classified
2. NOTE: Sale of this product must comply with Hatco's Minimum Resale Price Policy; consult order acknowledgement for details
3. NOTE: Includes 24/7 parts & service assistance, call 414-671-6350
4. 1-Yr Warranty on Blanket Heating Elements against burnout, standard

5. 120v/60/1-ph, 250 watts, 2.1 amps, NEMA 5-15P (domestic voltage), standard
6. Model STANDARD Black designer color, standard (available at time of purchase only)

ITEM #86 HEATED SHELF FOOD WARMER

Dimensions: 2.16(h) x 49.63(w) x 19.63(d)
Quantity: One (1)
Manufacturer: Hatco
Model: HBGB-4818

1. Model HBGB-4818 Heated Base Glass Shelf, built-in, 48"L, ceramic glass surface, uniform heat, 100° - 200°F thermostatic control with lighted on/off rocker switch, choice of frame finish, cULus, UL EPH Classified
2. NOTE: Sale of this product must comply with Hatco's Minimum Resale Price Policy; consult order acknowledgement for details
3. NOTE: Includes 24/7 parts & service assistance, call 414-671-6350
4. 1-Yr Warranty on Blanket Heating Elements against burnout, standard
5. 120v/60/1-ph, 850 watts, 7.1 amps, NEMA 5-15P (domestic voltage), standard
6. NOTE: Recommended for use in metallic countertop, verify that the material is suitable for temperatures up to 200°F
7. Model HBGB-GLASS-BLK Black finished ceramic glass, standard
8. Stainless steel trim ring (standard)
9. Flat top surface, standard
10. Thermostat control with lighted rocker switch, standard
11. Stainless steel bezel only (standard)

ITEM #87 LIGHT FIXTURE

Quantity: One (1)
Manufacturer: BSI
Model: 2580

1. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
2. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
3. Housing length to be specified
4. Remote Infinite, standard
5. Wiring exit point to be specified
6. Lighting frame finish to be specified

ITEM #88 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified
5. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
6. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
7. Remote Infinite, standard
8. Wiring exit point to be specified
9. Lighting frame finish to be specified
10. Housing length to be specified

ITEM #89-90 SPARE NO.**ITEM #91 CUTTING BOARD**

Dimensions: 0.38(h) x 76(w) x 6.25(d)
Quantity: One (1)
Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED Poly Cutting Board, for (5) well, 68"W x 6-1/4"D x 3/8" thick

ITEM #93 PIZZA PREPARATION REFRIGERATOR

Dimensions: 44(h) x 60(w) x 33(d)
Quantity: One (1)
Manufacturer: Randell
Model: 8260N-290

1. Model 8260N-290 Refrigerated Raised Rail Prep Table, two-section, 60" W, 14.67 cu. ft. capacity, side-mounted self-contained refrigeration, (2) solid hinged doors, stainless steel front, top, & sides, cold wall refrigeration pan rail (includes divider bars), accommodates (8) 1/3 size pans (pans not included), separate controls, automatic adaptive defrost, aluminum interior, R290 Hydrocarbon refrigerant, 6" casters, 1/3 HP, NSF, cUL, UL, Made in USA
2. (1) year parts and labor warranty, standard
3. CW5 (5) year compressor warranty, standard
4. 115v/60/1-ph, 6.0 amps, NEMA 5-15P, standard
5. Self-contained refrigeration standard
6. 6" Casters, standard

ITEM #94 MOBILE PLATE AND DISH DISPENSER

Dimensions: 39.13(h) x 35.13(w) x 19.5(d)
Quantity: One (1)
Manufacturer: Lakeside Manufacturing
Model: 935

1. Model 935 Adjust-a Fit® Dish Dispenser, non-heated, cabinet style, enclosed base, mobile, (2) self-leveling dish dispensing tubes, maximum dish size 12" diameter, stainless steel construction, 4" swivel casters (2) with brakes, NSF, UL, Made in USA

ITEM #95 UNIVERSAL PAN RACK

Dimensions: 69.75(h) x 20.38(w) x 26.38(d)
Quantity: One (1)
Manufacturer: New Age
Model: 1305

1. Model 1305 Rack, mobile, universal, open frame design, square tube construction, (12) universal slides, 5" centers, all-welded aluminum construction, end loading, slides for 12" x 20", 18" x 26" & 13" x 18" pans, 3-1/4" wide runners, (4) 5" platform casters, NSF, Made in USA, (standard factory lead time)
2. Lifetime warranty against rust & corrosion, 5 year workmanship and material defects warranty, standard

ITEM #96 ROLL-IN REFRIGERATOR

Dimensions: 89.13(h) x 35.5(w) x 35.56(d)
Quantity: One (1)
Manufacturer: Traulsen
Model: RRI132HUT-FHS

1. Model RRI132HUT-FHS Spec-Line Refrigerator, Roll-in, one-section, self-contained refrigeration, StayClear™ Condenser, stainless steel exterior & interior, standard depth cabinet, full-height doors, accepts 72" high racks (by others) with microprocessor controls, 1/2 HP, cETLus, ETL-Sanitation
2. Oversized units with crated shipping dimensions greater or equal to 72" in length and/or 90" in height. If delivery is to a facility without a standard height dock, additional shipping charges will apply, depending on the service requested (consult factory for details)
3. 6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
4. 115v/60/1-ph, 7.6 amps, cord with NEMA 5-15P, standard
5. Door hinged on right, standard

ITEM #97 HEATED HOLDING CABINET

Dimensions: 75.81(h) x 26.44(w) x 32.19(d)
Quantity: One (1)
Manufacturer: Alto-Shaam
Model: 1200-UP

1. Model 1200-UP Halo Heat® Low Temperature Holding Cabinet, double compartment, on/off simple controller with adjustable thermostats, indicator light, (2) sets of chrome plated universal side rails, (4) sets of pan slides, (16) 20" x 12" x 2-1/2" full size pan capacity, heavy stainless steel exterior, 5" casters; 2 rigid, 2 swivel with brakes, EcoSmart®, cULus, UL EPH Classified, CE, IPX4, TUV NORD, EAC, ENERGY STAR®
2. NOTE: Subject to Manufacturer's Terms & Conditions. See Documents Section
3. 120v/50/60/1-ph, 1.9 kW, 16.0 amps, NEMA 5-20P, standard
4. Reach-in design, standard
5. Solid door, hinged on right, standard
6. Model 1775 Water Reservoir Pan, for proofing
7. Model 1774 Water Reservoir Pan Cover

ITEM #98 HAND SINK

Dimensions: 12.75(h) x 17.25(w) x 15.25(d)
Quantity: One (1)
Manufacturer: Advance Tabco
Model: 7-PS-40

1. Model 7-PS-40 Hand Sink, wall mounted, 14" wide x 10" front-to-back x 5" deep bowl, 20 gauge 304 stainless steel, 7-3/4" high side splashes, with heavy duty splash mounted faucet, lever drain with overflow, P-trap, wall bracket, NSF, cCSAus

ITEM #99-100 SPARE NO.**ITEM #101 SOAP & TOWEL DISPENSER**

Quantity: One (1)
Manufacturer: OWNER
Model: G.F.G.I

1. Model G.F.G.I SOAP & TOWEL DISPENSER

ITEM #102 BACK SERVICE COUNTER

Quantity: One (1)
Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED BACK SERVICE COUNTER
2. One (1) Serving Counter - To measure per site conditions. 34" High.
3. Standard Stainless top, 14 ga, Counter base to be stainless steel frame construction with flooring and shelving as required.
4. Counter to have 18 gauge stainless steel walls, hinged doors and hinged louvered doors as required.
5. Counter to sit on 6" high stainless steel legs with adjustable feet and have a toe kick as required. Counter to have convenience outlets as required.
6. Refer to fabrication details for additional specifications and details.

ITEM #103 UNDERCOUNTER REFRIGERATOR

Dimensions: 33.5(h) x 48(w) x 32(d)
Quantity: One (1)
Manufacturer: Traulsen
Model: UHT48-LR

1. Model UHT48-LR Dealer's Choice Compact Undercounter Refrigerator, Reach-in, two-section, 48" wide, stainless steel exterior top, sides & door, hinged left/right, anodized aluminum interior, galvanized exterior back & bottom, rear mounted, self-contained refrigeration, R290 Hydrocarbon refrigerant, (4) 4" casters, 1/5 hp, cETLus, ETL-Sanitation
2. 6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
3. 115v/60/1-ph, 7.2 amps, 8' cord, NEMA 5-15P

ITEM #104 CONVECTION OVEN, ELECTRIC

Dimensions: 23.2(h) x 27.7(w) x 31.7(d)
Quantity: One (1)
Manufacturer: TurboChef (Middleby)
Model: DOUBLE BATCH, 1P

1. Model DOUBLE BATCH, 1P HHD-9500-801 Double Batch™ Oven, electric, 1-phase ventless, countertop, stackable, (2) independent decks, store up to 800 recipes (400 per cavity), smart voltage sensor technology (North America only), internal catalytic converters, 16" pizza capacity per deck, (1) oven cleaner, (1) oven guard, (1) aluminum paddle, (2) trigger sprayers, (2) standard racks, (2) top &

- bottom jetplates, stainless steel front, top & sides, rubber seal for surface mounting, cULus, UL EPH Classified, TÜV, CE
2. Model MDD-1001 Open Kitchen bundle, includes - 1 x ConnectWare module, 1 x Secure Access Point (SAP), 3 year subscription for Open Kitchen (NET price displays when item is added to quote)
 3. One year parts and labor warranty
 4. (DOUBLE BATCH, 1P-1) 208/240v/60/1-ph, 50.0 amps, 8.32/9.6 kW, 6 ft. cord & plug (nominal), NEMA 6-50P, standard

ITEM #105 SOAP & TOWEL DISPENSER

Quantity: One (1)
Manufacturer: OWNER
Model: G.F.G.I

1. Model G.F.G.I SOAP & TOWEL DISPENSER

ITEM #106 HAND SINK

Dimensions: 12.75(h) x 17.25(w) x 15.25(d)
Quantity: One (1)
Manufacturer: Advance Tabco
Model: 7-PS-40

1. Model 7-PS-40 Hand Sink, wall mounted, 14" wide x 10" front-to-back x 5" deep bowl, 20 gauge 304 stainless steel, 7-3/4" high side splashes, with heavy duty splash mounted faucet, lever drain with overflow, P-trap, wall bracket, NSF, cCSAus

ITEM #107 REACH-IN REFRIGERATOR

Dimensions: 83.25(h) x 58(w) x 35(d)
Quantity: One (1)
Manufacturer: Traulsen
Model: RHT232WUT-FHS

1. Model RHT232WUT-FHS Spec-Line Refrigerator, Reach-in, two-section, 51.6 cu. ft., self-contained refrigeration, StayClear™ Condenser, variable speed compressor, stainless steel exterior and interior, standard depth, wide full-height door or doors with EZ-Clean Gaskets, (3) adjustable wire shelves per section, microprocessor controls, 6" adjustable stainless steel legs, R-290 Hydrocarbon refrigerant, 1/2 HP, cETLus, ETL-Sanitation, ENERGY STAR®
2. 6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
3. 115v/60/1-ph, 7.6 amps, cord with NEMA 5-15P, standard
4. Full height solid door, standard

5. Full height solid door, standard
6. Left door hinged left/right hinged right, standard

ITEM #108 RAPID COOK OVEN

Dimensions: 61.16(h) x 48.88(w) x 32.81(d)
Quantity: One (1)
Manufacturer: TurboChef (Middleby)
Model: PLE-9500-1-DL-ICI

1. Model PLE-9500-1-DL-ICI TurboChef Plexor A3 - PLE-9500-1-DL-ICI Combination Oven, 3 decks, impinged air / convection / impinged air combination type, ventless, electric, 48.88" wide, right load, touch screen, Middleby Connect wifi ready, store over 1,000 recipes via USB or wifi, digital timer, autoload/unload, variable speed blower motor, internal catalytic converter, stainless steel exterior finish, includes open stand with castors, TurboChef Cleaner and Guard Starter Kit, includes (1) cleaner packet, (1) 24oz bottle, (1) Guard bottle and (2) foamer trigger, 208-240v/60/3-ph, 50 amps, NEMA 15-50P
2. Model MDD-1001 Open Kitchen bundle, includes - 1 x ConnectWare module, 1 x Secure Access Point (SAP), 3 year subscription for Open Kitchen (NET price displays when item is added to quote)
3. All items FOB: Carrollton, Texas: Consumable/accessory orders less than \$5,000 will incur a handling fee. Orders shipping standard ground will incur a \$15.00 handling fee. Orders shipping other than standard ground will incur \$25.00 handling fee
4. Model PLEXOR-INSTALL Installation Program for PLEXOR Ovens, includes: delivery to customer from Taylor distributor, shipping damage protection, contact site location to confirm site is ready, (2) Taylor distributors will deliver, remove packaging, and install the oven in customer location, oven testing, end-user operational testing, creating and loading menus via USB, overview of troubleshooting and best practices (priced per oven) (NET)

ITEM #111 MOBILE PLATE AND DISH DISPENSER

Dimensions: 39.13(h) x 35.13(w) x 19.5(d)
Quantity: One (1)
Manufacturer: Lakeside Manufacturing
Model: 935

1. Model 935 Adjust-a Fit® Dish Dispenser, non-heated, cabinet style, enclosed base, mobile, (2) self-leveling dish dispensing tubes, maximum dish size 12" diameter, stainless steel construction, 4" swivel casters (2) with brakes, NSF, UL, Made in USA

ITEM #112 BACK SERVICE COUNTER W/ SINK

Quantity: One (1)
Manufacturer: Custom
Model: FABRICATED

1. Model FABRICATED BACK SERVICE COUNTER W/HANDSINK
2. One (1) Serving Counter - To measure per site conditions. 34" High.
Standard Stainless top, 14 ga,
3. Counter base to be stainless steel frame construction with flooring and shelving as required.
4. Counter to have 18 gauge stainless steel walls, hinged doors and hinged louvered doors as required.
5. Counter to sit on 6" high stainless steel legs with adjustable feet and have a toe kick as required.
6. Counter to have (1) one 10"x14 handsink with faucet and splash guard,
7. Counter to have convenience outlets as required.

Refer to fabrication details for additional specifications and details.

ITEM #112.1 DECK MOUNT FAUCET

Quantity: One (1)
Manufacturer: T&S Brass
Model: B-0221

1. Model B-0221 Mixing Faucet, deck mount, 12" swing nozzle, 8" centers on deck faucet with 1/2" IPS eccentric flanged female inlets, quarter-turn Eterna cartridges with spring checks, lever handles, low lead, ADA Compliant

ITEM #113 INDUCTION RETHERMALIZER, BUILT-IN / DROP-IN

Dimensions: 12.31(h) x 13.88(w)
Quantity: Two (2)
Manufacturer: Vollrath
Model: 741101D

1. Model 741101D Mirage® Induction Rethermalizer, drop-in, dry operation, 11 quart, inset with hinged cover, (4) soup presets, stir indicator LED, solid state controls with locking function, temperature control in °F or °C, cabinet mount controls with leads, includes: induction ready inset, inset cover, mounting hardware & cord with NEMA 5-15P, 800 watts, 6.7 amps, 120v/60/1-ph, cULus, NSF, FCC (cover not NSF) (Refer to vollrathfoodservice.com for full warranty policy)

2. Requires use of included Vollrath induction-ready inset - failure to use these insets may damage the unit & will void the warranty
3. Model 88204 Inset, 11 quart, induction ready, for Mirage induction rethermalizer, NSF (Refer to vollrathfoodservice.com for full warranty policy)
4. Model 47490 Kool-Touch Hinged Cover, stainless with black phenolic knob, fits 78204 Inset & 77110 Double Boiler, imported (Refer to vollrathfoodservice.com for full warranty policy)

ITEM #114 SPARE NO.**ITEM #115 HEATED HOLDING CABINET**

Dimensions: 75.81(h) x 26.44(w) x 32.19(d)
Quantity: One (1)
Manufacturer: Alto-Shaam
Model: 1200-UP

1. Model 1200-UP Halo Heat® Low Temperature Holding Cabinet, double compartment, on/off simple controller with adjustable thermostats, indicator light, (2) sets of chrome plated universal side rails, (4) sets of pan slides, (16) 20" x 12" x 2-1/2" full size pan capacity, heavy stainless steel exterior, 5" casters; 2 rigid, 2 swivel with brakes, EcoSmart®, cULus, UL EPH Classified, CE, IPX4, TUV NORD, EAC, ENERGY STAR®
2. NOTE: Subject to Manufacturer's Terms & Conditions. See Documents Section
3. 120v/50/60/1-ph, 1.9 kW, 16.0 amps, NEMA 5-20P, standard
4. Reach-in design, standard
5. Solid door, hinged on right, standard

ITEM #116 MOBILE PLATE AND DISH DISPENSER

Dimensions: 39.13(h) x 35.13(w) x 19.5(d)
Quantity: One (1)
Manufacturer: Lakeside Manufacturing
Model: 935

1. Model 935 Adjust-a Fit® Dish Dispenser, non-heated, cabinet style, enclosed base, mobile, (2) self-leveling dish dispensing tubes, maximum dish size 12" diameter, stainless steel construction, 4" swivel casters (2) with brakes, NSF, UL, Made in USA

ITEM #117-118 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified
5. Model 705 Stealth™ Warmer & Light Combo, (specify voltage & length), cULus, NSF
6. Voltage & Length to be specified
7. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
8. Remote Infinite, standard
9. Wiring exit point to be specified
10. Warmer finish to be specified

ITEM #120 SPARE NO.**ITEM #122 HOT / COLD FOOD WELL UNIT, DROP-IN, ELECTRIC**

Dimensions: 27.75(h) x 72.69(w) x 26.13(d)
Quantity: Two (2)
Manufacturer: Randell
Model: RCHB-5-208-AF

1. Model RCHB-5-208-AF Drop-In Hot/Cold Food Unit, electric, (5) 12" x 20" pan size, common waterbath, switch for hot or cold operation, thermostatic controls, auto water fill, 1" drain & gate valve, 18 gauge stainless steel top & interior, corrosion resistant steel exterior, R290a, 1/4 HP, 4.4kW, cUL, UL, NSF, Made in USA (unit cutout size: 71-1/4"W x 25"D)
2. (1) year parts, labor, and compressor warranty, standard
3. 120/208v/60/1-ph, hardwired connection, standard

ITEM #124 COMPACT PREP TABLE REFRIGERATOR

Dimensions: 36(h) x 27(w) x 34.5(d)
Quantity: One (1)
Manufacturer: Traulsen
Model: UST279-D

1. Model UST279-D Dealer's Choice Compact Prep Table Refrigerator with low profile flat cover, (2) drawers, one-section, 27" wide, top rail holds (9) 1/6 pans 4" deep

- (included), drawers hold (6) 1/6 pans per drawer (not included), top rail & drawers can accommodate up to 6" deep pans. Full length reversible cutting board, stainless steel exterior top, sides & drawers, anodized aluminum interior, galvanized exterior back & bottom, rear mounted, self-contained refrigeration, R290 Hydrocarbon refrigerant, (4) 4" casters, 1/4 HP, cETLus, ETL-Sanitation
2. 6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
 3. 115v/60/1-ph, 7.2 amps, 8' cord, NEMA 5-15P

ITEM #128 INDUCTION RANGE, WOK, COUNTERTOP

Dimensions: 7.41(h) x 15.6(w) x 17.25(d)
 Quantity: One (1)
 Manufacturer: CookTek (Middleby)
 Model: HTF-9500-WK35-1

1. Model HTF-9500-WK35-1 (MW3500G - formerly 621501) Induction Wok, countertop, 4.3" capacitive touch display, power percentage display options, temperature range from 85°F-425°F, portable design with stainless steel housing, 3500 watts, 240V

ITEM #129-130 SPARE NO.**ITEM #131 EQUIPMENT STAND, REFRIGERATED BASE**

Dimensions: 26(h) x 48(w) x 34.13(d)
 Quantity: One (1)
 Manufacturer: Traulsen
 Model: TE048HT

1. Model TE048HT Spec-Line Refrigerated Equipment Stand, 48"W, (4) 12' x 20' x 6' deep pan capacity, side by side, (2) drawers, self-contained refrigeration, stainless steel marine top, stainless steel interior & exterior, 4' casters, microprocessor controls, R290 Hydrocarbon refrigerant, 1/4 HP, cETLus, ETL-Sanitation
2. Oversized units with crated shipping dimensions greater or equal to 72" in length and/or 90" in height. If delivery is to a facility without a standard height dock, additional shipping charges will apply, depending on the service requested (consult factory for details)
3. 6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
4. 115v/60/1-ph, 4.5 amps, cord with NEMA 5-15P plug
5. Compressor located on left side, standard
6. Casters, 4"H (set of 4), standard

ITEM #132 GRIDDLE, GAS, COUNTERTOP

Dimensions: 18.8(h) x 48(w) x 33.1(d)
Quantity: One (1)
Manufacturer: Vulcan
Model: VCCG48-AC

1. Model VCCG48-AC Heavy Duty Griddle, countertop, gas, 48" W x 24" D cooking surface, 3/4" thick Rapid Recovery™ composite plate, (4) burners, solid state thermostat every 12", atmospheric type "U" shaped aluminized steel burners, electronic spark ignition & pilot protection, wire knob guards, (1) drawer, stainless steel front, sides, front top ledge, front grease trough, 4" back & tapered side splashes, 4" adjustable legs, 120,000 BTU, CSA, NSF
2. 1 year limited parts & labor warranty, standard
3. Gas type to be specified
4. 120v/50/60/1-ph, 2 amp, NEMA 5-15P

ITEM #133 SNEEZE GUARD, STATIONARY

Quantity: One (1)
Manufacturer: BSI
Model: ZG9500-4

1. Model ZG9500-4 ZGuard® Food Shield, single, full-service/vertical partition, fully adjustable, 27" height, 24-1/2" wide tempered glass, 1" diameter tubing single supports
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. Frame finish to be specified
4. 1" radius corner, standard

ITEM #134 MOBILE PLATE AND DISH DISPENSER

Dimensions: 39.13(h) x 35.13(w) x 19.5(d)
Quantity: One (1)
Manufacturer: Lakeside Manufacturing
Model: 935

1. Model 935 Adjust-a Fit® Dish Dispenser, non-heated, cabinet style, enclosed base, mobile, (2) self-leveling dish dispensing tubes, maximum dish size 12" diameter, stainless steel construction, 4" swivel casters (2) with brakes, NSF, UL, Made in USA

ITEM #135 PANINI GRILL

Dimensions: 22(h) x 17(w) x 17(d)
Quantity: One (1)
Manufacturer: Equipex LLC
Model: PANINI

1. Model PANINI Roller Grill Panini Grill, cast iron grooved top & grooved bottom griddle plates, 14"W x 9-1/2"D grill area, adjustable spring counterbalanced top, front drip tray & scraper, grills with stainless steel construction, 570°F thermostatic controls, cULus, cULus Classified
2. Limited 1 year parts & labor warranty
3. 208/240v/60/1-ph, 12.0/14.0 amps, 3.0 kW, cord, NEMA 6-15P
4. Grooved top & grooved bottom plates, standard

ITEM #136 BACK SERVICE COUNTER

Quantity: One (1)
Manufacturer: Custom
Model: FABRICATED

1. Model FABRICATED BACK SERVICE COUNTER
2. One (1) Serving Counter - To measure per site conditions. 34" High.
Standard Stainless top, 14 ga,
3. Counter base to be stainless steel frame construction with flooring and shelving as required.
4. Counter to have 18 gauge stainless steel walls, hinged doors and hinged louvered doors as required.
5. Counter to sit on 6" high stainless steel legs with adjustable feet and have a toe kick as required.
6. Counter to have convenience outlets as required.

Refer to fabrication details for additional specifications and details.

ITEM #137 UNDERCOUNTER REFRIGERATOR

Dimensions: 33.5(h) x 48(w) x 32(d)
Quantity: One (1)
Manufacturer: Traulsen
Model: UHT48-LR

1. Model UHT48-LR Dealer's Choice Compact Undercounter Refrigerator, Reach-in, two-section, 48" wide, stainless steel exterior top, sides & door, hinged left/right, anodized aluminum interior, galvanized exterior back & bottom, rear mounted, self-contained refrigeration, R290 Hydrocarbon refrigerant, (4) 4" casters, 1/5 hp, cETLus, ETL-Sanitation

2. 6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
3. 115v/60/1-ph, 7.2 amps, 8' cord, NEMA 5-15P

ITEM #138 UNIVERSAL PAN RACK

Dimensions: 69.75(h) x 20.38(w) x 26.38(d)
Quantity: One (1)
Manufacturer: New Age
Model: 1305

1. Model 1305 Rack, mobile, universal, open frame design, square tube construction, (12) universal slides, 5" centers, all-welded aluminum construction, end loading, slides for 12" x 20", 18" x 26" & 13" x 18" pans, 3-1/4" wide runners, (4) 5" platform casters, NSF, Made in USA, (standard factory lead time)
2. Lifetime warranty against rust & corrosion, 5 year workmanship and material defects warranty, standard

ITEM #139-140 SPARE NO.**ITEM #141 HAND SINK**

Dimensions: 12.75(h) x 17.25(w) x 15.25(d)
Quantity: One (1)
Manufacturer: Advance Tabco
Model: 7-PS-40

1. Model 7-PS-40 Hand Sink, wall mounted, 14" wide x 10" front-to-back x 5" deep bowl, 20 gauge 304 stainless steel, 7-3/4" high side splashes, with heavy duty splash mounted faucet, lever drain with overflow, P-trap, wall bracket, NSF, cCSAus

ITEM #142 SOAP & TOWEL DISPENSER

Quantity: One (1)
Manufacturer: OWNER
Model: G.F.G.I

1. Model G.F.G.I SOAP & TOWEL DISPENSER

ITEM #143 ROLL-IN FREEZER

Dimensions: 89.13(h) x 68(w) x 35.56(d)
Quantity: One (1)
Manufacturer: Traulsen

Model: RIF232H-FHS

1. Model RIF232H-FHS Spec-Line Freezer, (REMOTE MODEL), Roll-in, Two-Section, remote refrigeration, stainless steel exterior & interior, standard depth cabinet, full-height doors, for 72" high racks (by others) with microprocessor controls, unit can be programmed to operate at -10°F, cETLus, ETL-Sanitation
2. 6-year parts & labor, standard. Visit www.traulsen.com for details
3. 115v/60/1-ph, 7.0 amps, cord with NEMA 5-15P, standard
4. R407A TXV, standard
5. Left door hinged left/right hinged right, standard

ITEM #144 CONVECTION OVEN / PROOFER, ELECTRIC

Dimensions: 77.75(h) x 38.5(w) x 30.75(d)
Quantity: One (1)
Manufacturer: NU-VU (Middleby)
Model: QBT-3/9

1. Model QBT-3/9 Oven/Proofer, electric, oven (3) 18 "x 26" or (6) 13 " x 18", proofer (9) 18 "x 26" or (18) 13 " x 18" pan capacities, touch screen programmable controls, AUTOMIST™ proofer, (2) dual pane cool-to-the touch glass doors, V-Air® technology, separate heat & humidity controls for proofer, stainless steel construction, heavy duty casters, 6.7kW, cETLus, NSF, Made in USA
2. Doyon & NU-VU requires all equipment purchased for shipment outside the countries of US & Canada must complete an Electrical Questionnaire form. This form helps ensure that all equipment is to the correct spec of the site & country. You can download the form at <https://doyonnuvubaking.com/Sales/Forms/ElectricalQuestionnaire.pdf>. Any questions please contact our factory by phone 800-338-9886 or email sales@nu-vu.com. Thank you.
3. Note: Accessories must be ordered with equipment in order to qualify for any additional discounts or special freight pricing. Any questions please contact Doyon/NU-VU.
4. Factory Note: This unit is engineered, designed, and built to be used in specific foodservice applications. It is intended for on-site premise batch baking of a single dough product with specific profiles and baking parameters. This unit is not recommended for general market use, unless confirmed by NU-VU Culinary Support. By quoting this product, you are acknowledging NU-VU's recommended use of the unit.
5. Two year parts and one year labor warranty, standard
6. NOTE: Installation and startup are not included in the pricing for any item. Startup and installation are the responsibility of the buyer, its agent, contractor, as the case may be.
7. 208v/60/1-ph, 32.0 amps, 2-wire system with ground
8. Door hinged on left

ITEM #146 FRYMATE HOLDING STATION

Dimensions: 36.25(h) x 15.5(w) x 30.13(d)
Quantity: One (1)
Manufacturer: Vulcan
Model: FRYMATE VX15

1. Model FRYMATE VX15 Frymate™ Holding Station, free standing or add-on unit, 15-1/2" wide, 30-1/8" depth, stainless steel cabinet base, stainless steel top drain section with removable grease collector, set of 4 casters (2 locking), connecting strip & hardware included, (for 35-65 lb capacity gas or electric fryers)
2. 1 year limited parts & labor warranty, standard

ITEM #147 GAS FLOOR FRYER

Dimensions: 47.25(h) x 15.5(w) x 30.13(d)
Quantity: One (1)
Manufacturer: Vulcan
Model: 1TR45D

1. Model 1TR45D PowerFry3™ Fryer, gas, high efficiency, 15-1/2" W, free-standing, 45-50 lbs. capacity, solid state digital control with melt cycles, ThreePass™ heat transfer system, electronic ignition, twin baskets, stainless steel cabinet & fry tank, adjustable casters (2 swivel locking & 2 non-locking), 70,000 BTU, CSA, CSA STAR, NSF, ENERGY STAR®
2. 1 year limited parts & labor warranty, standard
3. 10 year limited tank warranty, standard.
4. Gas type to be specified
5. 120v/60/1-ph, with cord & plug, standard

ITEM #148 GRIDDLE, GAS, COUNTERTOP

Dimensions: 18.8(h) x 48(w) x 33.1(d)
Quantity: One (1)
Manufacturer: Vulcan
Model: VCCG48-AC

1. Model VCCG48-AC Heavy Duty Griddle, countertop, gas, 48" W x 24" D cooking surface, 3/4" thick Rapid Recovery™ composite plate, (4) burners, solid state thermostat every 12", atmospheric type "U" shaped aluminized steel burners, electronic spark ignition & pilot protection, wire knob guards, (1) drawer, stainless steel front, sides, front top ledge, front grease trough, 4" back & tapered side splashes, 4" adjustable legs, 120,000 BTU, CSA, NSF
2. 1 year limited parts & labor warranty, standard

3. Gas type to be specified
4. 120v/50/60/1-ph, 2 amp, NEMA 5-15P

ITEM #149-150 SPARE NO.**ITEM #151 EQUIPMENT STAND, REFRIGERATED BASE**

Dimensions: 26(h) x 48(w) x 34.13(d)
Quantity: One (1)
Manufacturer: Traulsen
Model: TE048HT

1. Model TE048HT Spec-Line Refrigerated Equipment Stand, 48'W, (4) 12' x 20' x 6' deep pan capacity, side by side, (2) drawers, self-contained refrigeration, stainless steel marine top, stainless steel interior & exterior, 4' casters, microprocessor controls, R290 Hydrocarbon refrigerant, 1/4 HP, cETLus, ETL-Sanitation
2. Oversized units with crated shipping dimensions greater or equal to 72" in length and/or 90" in height. If delivery is to a facility without a standard height dock, additional shipping charges will apply, depending on the service requested (consult factory for details)
3. 6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
4. 115v/60/1-ph, 4.5 amps, cord with NEMA 5-15P plug
5. Compressor located on left side, standard
6. Casters, 4"H (set of 4), standard

ITEM #152 CHARBROILER, GAS, COUNTERTOP

Dimensions: 15.5(h) x 46.88(w) x 31(d)
Quantity: One (1)
Manufacturer: Vulcan
Model: VACB47

1. Model VACB47 Achiever Charbroiler, countertop, 46-7/8", (8) 17,000 BTU cast iron burners, infinite heat control valves, fully welded chassis, (2) drip trays, stainless steel front, sides & top trim, backsplash & grease trough, 4" adjustable legs, 136,000 BTU, CSA, NSF
2. 1 year limited parts & labor warranty, standard
3. Gas type to be specified
4. Model 3/4QD HOSE-4 3/4" x 4' long gas flex hose & quick disconnect with restraining device

ITEM #153 EQUIPMENT STAND, REFRIGERATED BASE

Dimensions: 26(h) x 48(w) x 34.13(d)
Quantity: One (1)

Manufacturer: Traulsen
Model: TE048HT

1. Model TE048HT Spec-Line Refrigerated Equipment Stand, 48'W, (4) 12' x 20' x 6' deep pan capacity, side by side, (2) drawers, self-contained refrigeration, stainless steel marine top, stainless steel interior & exterior, 4' casters, microprocessor controls, R290 Hydrocarbon refrigerant, 1/4 HP, cETLus, ETL-Sanitation
2. Oversized units with crated shipping dimensions greater or equal to 72" in length and/or 90" in height. If delivery is to a facility without a standard height dock, additional shipping charges will apply, depending on the service requested (consult factory for details)
3. 6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
4. 115v/60/1-ph, 4.5 amps, cord with NEMA 5-15P plug
5. Compressor located on left side, standard
6. Casters, 4"H (set of 4), standard

ITEM #157 HEATED HOLDING / WARMING BIN

Dimensions: 11.8(h) x 26(w) x 14.13(d)
Quantity: One (1)
Manufacturer: Duke Manufacturing
Model: R FHU-23

1. Model RFHU-23 ReadyFlex™ Hot Holding Cabinet, (2) compartment high, (3) compartment wide, 26"W x 14-1/8"D x 11-4/5"H, holds 2.5" deep pans, pans are not included, full color touchscreen control, independent top and bottom zoned heat, individual & interchangeable pan lids, includes 3 solid and 3 vented lids, audible alarm, stainless steel construction, CE, cULus, UL EPH Classified
2. 120v/60/1-ph, 10.0 amps, NEMA 5-15P

ITEM #158 BACK SERVICE COUNTER

Quantity: One (1)
Manufacturer: Stainless Fabricating
Model: FABRICATED

1. Model FABRICATED BACK SERVICE COUNTER
2. One (1) Serving Counter - To measure per site conditions. 34" High.
Standard Stainless top, 14 ga,
3. Counter base to be stainless steel frame construction with flooring and shelving as required.
4. Counter to have 18 gauge stainless steel walls, hinged doors and hinged louvered doors as required.
5. Counter to sit on 6" high stainless steel legs with adjustable feet and have a toe kick as required.

6. Counter to have convenience outlets as required.

Refer to fabrication details for additional specifications and details.

ITEM #159-160 SPARE NO.

ITEM #162 MOBILE PLATE AND DISH DISPENSER

Dimensions: 39.13(h) x 35.13(w) x 19.5(d)
Quantity: Two (2)
Manufacturer: Lakeside Manufacturing
Model: 935

1. Model 935 Adjust-a Fit® Dish Dispenser, non-heated, cabinet style, enclosed base, mobile, (2) self-leveling dish dispensing tubes, maximum dish size 12" diameter, stainless steel construction, 4" swivel casters (2) with brakes, NSF, UL, Made in USA

ITEM #163 HEAT LAMP

Quantity: One (1)
Manufacturer: BSI
Model: 705

1. Model 705 Stealth™ Warmer & Light Combo, (specify voltage & length), cULus, NSF
2. Voltage & Length to be specified
3. Lamp type to be specified
4. Remote Infinite, standard
5. Wiring exit point to be specified

ITEM #164 HEATED SHELF FOOD WARMER

Dimensions: 2.16(h) x 37.63(w) x 19.63(d)
Quantity: One (1)
Manufacturer: Hatco
Model: HBGB-3618

1. Model HBGB-3618 Heated Base Glass Shelf, built-in, 36"L, ceramic glass surface, uniform heat, 100° - 200°F thermostatic control with lighted on/off rocker switch, choice of frame finish, cULus, UL EPH Classified
2. NOTE: Sale of this product must comply with Hatco's Minimum Resale Price Policy; consult order acknowledgement for details
3. NOTE: Includes 24/7 parts & service assistance, call 414-671-6350

4. 1-Yr Warranty on Blanket Heating Elements against burnout, standard
5. 120v/60/1-ph, 630 watts, 5.3 amps, NEMA 5-15P (domestic voltage), standard
6. NOTE: Recommended for use in metallic countertop, verify that the material is suitable for temperatures up to 200°F
7. Model HBGB-GLASS-BLK Black finished ceramic glass, standard
8. Stainless steel trim ring (standard)
9. Flat top surface, standard
10. Thermostat control with lighted rocker switch, standard
11. Stainless steel bezel only (standard)

ITEM #165 SNEEZE GUARD, STATIONARY

Quantity: One (1)
 Manufacturer: BSI
 Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified
5. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
6. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
7. Remote Infinite, standard
8. Wiring exit point to be specified
9. Lighting frame finish to be specified
10. Housing length to be specified

ITEM #167 MEGA TOP SANDWICH / SALAD PREPARATION REFRIGERATOR

Dimensions: 31.63(h) x 48.25(w) x 35.75(d)
 Quantity: One (1)
 Manufacturer: Turbo Air
 Model: PST-48-18-N-GL

1. Model PST-48-18-N-GL PRO Series Mega Top Sandwich/Salad Prep Table with Glass Lid, two-section, rear mount self-contained compressor, 15.0 cu. ft., 48-1/4"W x 36-3/4"D x 31-3/4"H, (18) 1/6 size 4"deep pans, (2) solid hinged swing doors with locks, aluminum door liner, (2) stainless steel shelves, 6-1/4" deep cutting board with side rail, digital temperature control & monitor system, cold bunker system, stainless steel interior & exterior (galvanized bottom), LED interior lighting & fan control, self-cleaning condenser, R290 Hydrocarbon refrigerant, 1/5 HP, 115v/60/1-ph, 6.5 amps, NEMA 5-15P, cETLus, ETL-Sanitation, Made in USA (contact sales for lead time)

2. Note: Contact factory representative for parts & accessories discounts
3. 5 year parts & labor warranty, standard
4. 7 year compressor warranty (self-contained only)
5. 1/6 size, 4" deep condiment pan & pan dividers included, standard
6. Non-Standard mounting options below:

ITEM #168 DISPLAY MERCHANDISER, HEATED, FOR MULTI-PRODUCT

Dimensions: 32.4(h) x 36(w) x 24.29(d)
Quantity: One (1)
Manufacturer: Hatco
Model: GRSDS-36D

1. Model GRSDS-36D Glo-Ray® Merchandising Warmer, countertop, 36" long, (14) rods, pass thru design, with (2) shelves, forward-slanted shelves, pre-focused infrared top heat, tempered glass sides, stainless steel & aluminum construction, 4" legs, 1810 watts, cULus, UL EPH Classified, Made in USA
2. NOTE: Sale of this product must comply with Hatco's Minimum Resale Price Policy; consult order acknowledgement for details
3. NOTE: Includes 24/7 parts & service assistance, call 414-671-6350
4. One year on-site parts & labor warranty, plus one additional year parts only warranty on all Glo-Ray metal sheathed elements
5. 120v/60/1-ph, 1810 watts, 15.1 amps, NEMA 5-20P (domestic voltage), standard
6. Model GGRAY Glossy gray, gloss finish, (available at time of purchase only)
7. Open Customer Side, upper, standard
8. Open Customer Side, lower, standard

ITEM #169-170 SPARE NO.**ITEM #172 MEGA TOP SANDWICH / SALAD PREPARATION REFRIGERATOR**

Dimensions: 32.12(h) x 60.25(w) x 34.62(d)
Quantity: One (1)
Manufacturer: Turbo Air
Model: PST-60-24-N-GL

1. Model PST-60-24-N-GL PRO Series Mega Top Sandwich/Salad Prep Table with Glass Lid, two-section, rear mount self-contained compressor, 19.0 cu. ft., 60-1/4"W x 36-3/4"D x 31-3/4"H, (24) 1/6 size 4" deep pans, (2) solid hinged swing doors with locks, aluminum door liner, (2) stainless steel shelves, 6-1/4" deep cutting board with side rail,

- digital temperature control & monitor system, cold bunker system, stainless steel interior & exterior (galvanized bottom), LED interior lighting & fan control, self-cleaning condenser, R290 Hydrocarbon refrigerant, 1/5 HP, 115v/60/1-ph, 8.9 amps, NEMA 5-15P, cETLus, ETL-Sanitation, Made in USA (contact sales for lead time)
2. Note: Contact factory representative for parts & accessories discounts
 3. 5 year parts & labor warranty, standard
 4. 7 year compressor warranty (self-contained only)
 5. 1/6 size, 4" deep condiment pan & pan dividers included, standard
 6. Non-Standard mounting options below:

ITEM #173-174 SNEEZE GUARD, STATIONARY

Quantity: One (1)
 Manufacturer: BSI
 Model: XG3930

1. Model XG3930 XGuard™ Food Shield, single, self service, fully adjustable, 20-1/2" height, 14" wide tempered glass top & lower sneeze guard, 1" diameter tubing double supports, NSF-Component, cULus
2. Tubing to be specified (NOTE: aluminum may be used only on above counter mounts)
3. 1" radius corner, standard
4. Frame finish to be specified
5. Model 2580 Slimline Light, 1-1/2" x 1-3/8", (specify length), cULus, NSF
6. Model 3000K 3000K LED Lamp, 110v/50/60/1-ph, cULus, NSF
7. Remote Infinite, standard
8. Wiring exit point to be specified
9. Lighting frame finish to be specified
10. Housing length to be specified

ITEM #175-179 SPARE NO.**ITEM #182 CONDIMENT DISPENSER-PUMP STYLE**

Quantity: One (1)
 Manufacturer: Star (Middleby)
 Model: CD3S

ITEM #183 NAPKIN DISPENSER

Quantity: Four (4)
 Manufacturer: Stainless Fabricating
 Model: FABRICATED

1. Model FABRICATED NAPKIN DISPENSER

ITEM #184 PUMP CONDIMENTS

Quantity: (10)
Manufacturer: Custom

1. PUMP CONDIMENTS

ITEM #185 FLATWARE HOLDER, CYLINDER HOLDER / DISPENSER

Dimensions: 12.63(h) x 10.13(w) x 16(d)
Quantity: Two (2)
Manufacturer: Vollrath
Model: CTFWH-6B

1. Model CTFWH-6B Flatware Holder, countertop, 10-1/8"W x 16"D x 12-5/8"H, (6) compartments (3 high x 2 wide), includes (6) 52633 flatware cylinders, black ABS & smoked acrylic construction (Refer to vollrathfoodservice.com for full warranty policy)

ITEM #186 TRASH RECEPTACLE, INDOOR

Dimensions: 30(h) x 22(w) x 11(d)
Quantity: One (1)
Manufacturer: Rubbermaid Commercial Products
Model: FG354060BLA

1. Model FG354060BLA Slim Jim® Container, 23 gallon, 22"W x 11"D x 30"H, with venting channels, molded-in handles, general purpose waste, open type without lid, high-impact plastic construction, black, Made in USA

ITEM #187-200 SPARE NO.

END OF SECTION

SECTION 12 34 00

MANUFACTURED PLASTIC CASEWORK

08/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASME INTERNATIONAL (ASME)

ASME B18.6.1 (2016) Wood Screws (Inch Series)

ASTM INTERNATIONAL (ASTM)

ASTM A240/A240M (2018) Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications

ASTM D4000 (2016) Standard Classification System for Specifying Plastic Materials

ASTM D4689 (2012) Standard Specification for Adhesive, Casein-Type

ASTM D4690 (2012) Standard Specification for Urea Formaldehyde Resin Adhesives

ASTM F594 (2009; E 2015) Standard Specification for Stainless Steel Nuts

ASTM F3125/F3125M (2015a) Standard Specification for High Strength Structural Bolts, Steel and Alloy Steel, Heat Treated, 120 ksi (830 MPa) and 150 ksi (1040 MPa) Minimum Tensile Strength, Inch and Metric Dimensions

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.9 (2015) Cabinet Hardware

KITCHEN CABINET MANUFACTURERS ASSOCIATION (KCMA)

KCMA A161.1 (2017) Performance & Construction Standards for Kitchen and Vanity Cabinets

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI/NEMA LD 3 (2005) Standard for High-Pressure Decorative Laminates

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS FF-B-588	(Rev E; Notice 1) Bolt, Toggle: and Expansion Sleeve, Screw
FS FF-S-325	(Basic; Int Amd 3; Notices 3, 4) Shield, Expansion; Nail, Expansion; and Nail, Drive Screw (Devices, Anchoring, Masonry)
FS TT-F-336	(Rev E; Notice 1) Filler, Wood, Paste

1.2 ADMINISTRATIVE REQUIREMENTS

1.2.1 Pre-Installation Meeting

Within 30 calendar days after date of award, submit for the approval of the Contracting Officer copies of outline drawings (number to be determined) of all casework to be furnished under this contract, together with weights, overall dimensions, and required samples. Ensure that drawings show the general arrangement and overall dimensions of the casework, details of any casework supports, and provisions for electrical outlets., special provisions for external cables and cords. Submit the following for review and approval:

- a. Fabrication Drawings
- b. Installation Drawings
- c. Casework Finish Samples
- d. Manufacturer's Standard Color Charts
- e. Accessories and Hardware Samples
- f. Certificates of Conformance

Submit installation drawings for manufactured plastic casework. Include in drawings location of cabinets, details of cabinets related and their dimensional positions.

Submit casework samples in accordance with ASTM D4000, and include accessories and hardware, one each.

Submit manufacturer's standard color charts for plastic cabinets, showing the manufacturer's recommended color and finish selections.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Fabrication Drawings; G

Installation Drawings; G

SD-04 Samples

Casework Samples; G

SD-07 Certificates

Certificates of Conformance

1.4 QUALITY CONTROL

Submit certificates of conformance for the following items, showing conformance with the standards cited in this section:

- a. Corrosion-resistant steel
- b. Glass
- c. Adhesives
- d. Filler material
- e. Fasteners
- g. Accessories and hardware

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver, handle, and store cabinets in a manner that will prevent damage or deformity. Provide temporary skids under units.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Furnish plastic laminate cabinets, factory-fabricated and finished as specified in drawings in the manufacturer's standard finishes, of the type, design, and configuration indicated. Construct cabinets as specified and meet the requirements of KCMA A161.1. Submit fabrication drawings for review and approval before commencement of fabrication. Provide wall and base cabinet assemblies consisting of individual units joined into continuous sections. Provide removable drawers equipped with position stops to prevent accidental complete withdrawals. Fix or adjust shelves as indicated.

2.2 COMPONENTS

Submit manufacturer's catalog data for the following items:

- a. Cabinets
- b. Glass
- c. Adhesives

- d. Filler material
- e. Fasteners
- g. Accessories and hardware
- h. Plastic laminate

Submit the manufacturer's instructions for plastic cabinet systems, including special provisions required to install equipment components and system packages, and any special notices detailing impedances, hazards and safety precautions, and casework maintenance.

Provide the manufacturer's cabinets with the type and design indicated. For both wall and base cabinets, join individual units into continuous sections as indicated.

2.2.1 Cabinets

Provide new factory-finished kitchen/server wall and base cabinets with high-pressure decorative laminate (HPDL) countertops and bathroom vanity cabinets. Provide cabinets that conform to KCMA A161.1 and requirements specified herein, and that bear the "KCMA Certified Cabinet" seal of the Kitchen Cabinet Manufacturers Association. Provide countertops that conform to ANSI/NEMA LD 3 and requirements specified herein.

2.2.2 Miscellaneous Cabinets

2.3 MATERIALS

Provide corrosion-resistant steel conforming to ASTM A240/A240M, Type 302304.

Provide thermosetting urea-resin Type II adhesives for application of plastic laminate, conforming to ASTM D4690 as recommended by the manufacturer of the laminate. Provide adhesive for wood members, conforming to ASTM D4689.

Provide filler material conforming to FS TT-F-336.

Provide plastic laminates conforming to ANSI/NEMA LD 3, Style and Finish per Plans.

Provide accessories and hardware conforming to the following requirements, as applicable:

- a. Extension drawer slides: ANSI/BHMA A156.9, Type B85071
- b. Semiconcealed hinges: ANSI/BHMA A156.9, Type B81201, 1 1/2 inches
- c. Full surface hinges: ANSI/BHMA A156.9, Type B81131, 1 1/2 inches
- d. Knob pulls: ANSI/BHMA A156.9, Type B12132 1-inch diameter
- e. Bar pulls: ANSI/BHMA A156.9, Type B12012 4-inch overall length
- f. Locks, keying, and keys: As directed

- g. Catches: Magnetic, 5-pound pull
- h. Sliding door set: Nylon glides

Provide fasteners conforming to the following:

- a. Screws: ASME B18.6.1, Group, Type and Class as applicable
- b. Anchoring devices: FS FF-S-325, Group, Type, and Class as applicable
- c. Toggle bolts: FS FF-B-588, Type I, Class A, Style 2
- d. Nuts: ASTM F594, corrosion-resistant steel
- e. Bolts: ASTM F3125/F3125M heavy, hexagon head bolts, corrosion-resistant steel

2.3.1 Finish

2.3.1.1 Cabinet Finish

Provide cabinets of a type standard with the manufacturer, with a durable factory-applied finish and in accordance with KCMA A161.1.

2.3.1.2 Backer Sheets

Provide backer sheets of high pressure plastic laminate conforming to ANSI/NEMA LD 3, with Grade BK20 applied to the underside of all core material.

2.3.2 Color, Texture, and Pattern

Provide color in accordance with Section 09 06 00 SCHEDULES FOR FINISHES. as indicated on the drawings The color listed is not intended to limit the selection of equal colors from other manufacturers.

PART 3 EXECUTION

3.1 INSTALLATION

Install the casework plumb with countertops level to within 1/16 inch in 10 feet. Level base cabinets by adjusting leveling screws. Scribe and fit scribe strips to irregularities of adjacent surfaces. Ensure the gap openings do not to exceed 0.025 inch.

Secure cases permanently to floor and wall construction using 1/4-inch-diameter masonry anchors, spaced 30 inches maximum on center, with a minimum of two anchors for each case, where indicated.

Install fastenings to permit removal and replacement of individual units without affecting the remainder of the installation.

Support wall cases on continuous 18-gauge galvanized-steel hanging brackets. Secure wall cases in position with screws to blocking, where indicated. Bolt adjoining cases together. Ensure that joint widths do not exceed 1/32 inch,

where indicated. Provide closer strips, filler strips, and finish moldings as required. Align doors, adjust hardware, and clean and wax surfaces.

3.2 FIELD QUALITY CONTROL

Examine casework grounds and supports for adequate anchorage, foreign material, moisture, and unevenness that could prevent casework installation from meeting the requirements specified.

Ensure that electrical and plumbing rough-ins for casework are complete. Do not proceed with installation until defects are corrected.

3.3 ADJUSTING AND CLEANING

On completion of cabinet installation, clean surfaces and surrounding area. Remove crating and packing materials from premises. Wipe down surfaces to remove fingerprints and markings and leave in clean condition.

-- End of Section --

SECTION 12 36 00

COUNTERTOPS

08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A161.2 (1998) Decorative Laminate Countertops,
Performance Standards for Fabricated High
Pressure

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350 (2010; Version 1.1) Standard Method for the
Testing and Evaluation of Volatile Organic
Chemical Emissions from Indoor Sources using
Environmental Chambers

INTERNATIONAL CODE COUNCIL (ICC)

ICC IPC (2018) International Plumbing Code

KITCHEN CABINET MANUFACTURERS ASSOCIATION (KCMA)

KCMA A161.1 (2017) Performance & Construction Standards
for Kitchen and Vanity Cabinets

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168 (2017) Adhesive and Sealant Applications

UNDERWRITERS LABORATORIES (UL)

UL 2818 (2013) GREENGUARD Certification Program For
Chemical Emissions For Building Materials,
Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Fabrication; G

Installation Drawings; G

SD-03 Product Data

Synthetic Resin; G

Adhesives; G

Filler Material; G

Fasteners; G

Service Fixtures; G

Joint Sealants; G

SD-04 Samples

Countertop; G

Backsplash; G

Manufacturer's Standard Color Charts, if finish not selected and on plans.; G

1.3 CERTIFICATIONS

1.3.1 Indoor Air Quality Certification

Submit required indoor air quality certifications in one submittal package.

1.3.1.1 Countertop Products

Provide countertop products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party program that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver, store, and handle countertops and backsplash in a manner that will prevent damage and disfigurement.

Provide temporary skids under units.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide the manufacturer's standard type countertops or as indicated on the drawings. Accomplish fastenings to permit removal and replacement of individual countertops without affecting the remainder of the installation.

Submit manufacturer's instructions for countertops including special provisions required to install equipment components and system packages. Include all special notices detailing impedances, hazards and safety precautions.

Submit manufacturer's standard color charts for countertops showing the manufacturer's recommended color and finish selections.

Provide countertop products certified to meet the emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type). Provide certification or validation of indoor air quality for countertop products.

2.1.1 Design

Provide factory fabricated, prefinished quartz countertops in the manufacturer's standard finishes of the type, design, and configuration indicated. Provide countertops as specified and meet the requirements of KCMA A161.1. Accomplish fastenings to permit removal and replacement of individual units without affecting the remainder of the installation. Provide counters with watertight sink rim when indicated. Include removable drawers equipped with position stops to avoid accidental complete withdrawals.

2.2 FABRICATION

2.2.1 Countertop And Backsplash

Provide countertops and backsplash where indicated on plans) of quartz and according to ANSI A161.2.

Provide a water-resistant type plywood substrate as required, Grade B-D Douglas fir plywood, with a minimum thickness of 3/4-inch. Provide Quartz backsplash 3/4-inch thick by the height indicated, according to ANSI A161.2.

Provide steel no lighter than 22-gage stainless steel for backed construction and not lighter than 18-gage stainless steel for integral construction. Make joints between sink, countertop, and backsplash watertight. Provide backsplash of the same material as countertop and form with square edges, and height as indicated.

Provide sink that is undercounter mounted where indicated in plans.

2.2.2 Color, Texture, and Pattern

Select color in accordance with Section 09 06 00 SCHEDULES FOR FINISHES as indicated on the drawings. from manufacturers standard colors. Color listed is not intended to limit the selection of equal colors from other manufacturers.

2.3 MATERIALS

Provide Douglas-fir plywood conforming to ICC IPC, exterior type, fully waterproof bond.

2.4 MIXES

2.4.1 Adhesives

Provide mounting and stone adhesives meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide validation of indoor air quality for mounting and stone adhesives.

2.4.1.1 Mounting Adhesives

Provide structural-grade silicone or epoxy adhesives of type recommended by manufacturer for application and conditions of use.

Provide spacers, if required, of type recommended by adhesive manufacturer.

2.4.2 Joint Sealants

Use clear silicone sealant of type recommended by manufacturer for application and conditions of use. Provide joint sealant products meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide validation of indoor air quality for joint sealants.

Provide anti-bacterial type in toilet rooms, and food preparation areas.

PART 3 EXECUTION

3.1 INSTALLATION

Inspect material for defects prior to installation. Ensure materials throughout bear labels with the same batch number. Visually inspect materials used for adjacent pieces to assure acceptable color match. Inspect in lighting conditions similar to those on the project. Repair or replace damaged materials.

Install countertops plumb with cabinetry level to within 1/16-inch in 10-feet. Level base cabinets by adjusting leveling screws. Scribe and fit scribe strips to irregularities of adjacent surfaces. Gap openings exceeding 0.025-inch are not acceptable.

Submit installation drawings for countertops. Ensure drawings include location of cabinets, details of cabinets related and dimensional positions, and locations for roughing in plumbing, including sinks, faucets, strainers and cocks.

3.1.1 Preliminary Installation and Adjustment

Install materials in accordance to manufacturer's recommendations. Lift and place to avoid breakage.

Position materials to verify that materials are correctly sized and prepared. Make necessary adjustments.

If jobsite cutting, grinding, or polishing is required, use water-cooled tools. Protect jobsite and surfaces against dust and water. Perform work away from installation site if possible.

Gypsum drywall back walls which are not fire or acoustically rated may be routed up to half the thickness of the drywall to allow countertop to fit.

Shim countertop drainage adjacent to sinks and where drainage is required, slightly to insure positive drainage.

3.1.2 Surfacing

3.1.3 Permanent Installation

After verifying fit, remove quartz surfacing from position, clean substrates of dust and contamination, and clean quartz surfacing back side and joints with solvent.

Apply sufficient quantity of mounting adhesive in accordance with adhesive manufacturer's recommendations to provide permanent, secure installation.

Install surfacing plumb, level, and square and flat to within 1/6-inch in 10-feet.

3.1.4 Joints

Ensure joints between adjacent pieces of quartz surfacing are:

- a. Flush, tight fitting, level, and neat.
- b. Securely joined with stone adhesive. Fill joints level with quartz surfacing.

Clamp or brace quartz surfacing in position until adhesive sets.

Seal joints between backsplashes and countertops with silicone sealer.

3.2 FIELD QUALITY CONTROL

Examine casework grounds and supports for adequate anchorage, foreign material, moisture, and unevenness that could prevent quality casework installation.

Ensure that electrical and plumbing rough-ins for casework are complete. Do not proceed with installation until defects are corrected.

3.3 ADJUSTING AND CLEANING

3.3.1 Solvent

Use a product recommended by adhesive manufacturer to clean surface of quartz surfacing to assure adhesion of adhesives and sealants.

3.3.2 Cleaning Agents

Use non-abrasive, soft-scrub type kitchen cleaners.

3.3.3 Cleaning

On completion of cabinet installation, touch up marred or abraded finished surfaces. Remove crating and packing materials from premises. Wipe down surfaces to remove fingerprints and markings and leave in clean condition.

-- End of Section --

SECTION 21 13 13

WET PIPE SPRINKLER SYSTEMS, FIRE PROTECTION
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.1	(2020) Gray Iron Pipe Flanges and Flanged Fittings Classes 25, 125, and 250
ASME B16.3	(2016) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.4	(2016) Standard for Gray Iron Threaded Fittings; Classes 125 and 250
ASME B16.21	(2016) Nonmetallic Flat Gaskets for Pipe Flanges

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C104/A21.4	(2016) Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water
AWWA C110/A21.10	(2012) Ductile-Iron and Gray-Iron Fittings for Water
AWWA C111/A21.11	(2017) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings

ASTM INTERNATIONAL (ASTM)

ASTM A47/A47M	(1999; R 2018; E 2018) Standard Specification for Ferritic Malleable Iron Castings
ASTM A53/A53M	(2020) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A135/A135M	(2021) Standard Specification for Electric-Resistance-Welded Steel Pipe
ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A183	(2014; R 2020) Standard Specification for Carbon Steel Track Bolts and Nuts

ASTM A536 (1984; R 2019; E 2019) Standard
Specification for Ductile Iron Castings

FM GLOBAL (FM)

FM 1637 (2010) Flexible Sprinkler Hose with
Threaded End Fittings

FM APP GUIDE (updated on-line) Approval Guide
<http://www.approvalguide.com/>

INTELLIGENCE COMMUNITY STANDARD (ICS)

ICS 705-1 (2010) Physical and Technical Security
Standard for Sensitive Compartmented
Information Facilities

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS
INDUSTRY (MSS)

MSS SP-71 (2018) Gray Iron Swing Check Valves,
Flanged and Threaded Ends

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 13 (2022) Standard for the Installation of
Sprinkler Systems

NFPA 13R (2022) Standard for the Installation of
Sprinkler Systems in Low-Rise Residential
Occupancies

NFPA 24 (2022) Standard for the Installation of
Private Fire Service Mains and Their
Appurtenances

NFPA 101 (2021) Life Safety Code

NFPA 291 (2022) Recommended Practice for Fire Flow
Testing and Marking of Hydrants

NATIONAL INSTITUTE FOR CERTIFICATION IN ENGINEERING TECHNOLOGIES
(NICET)

NICET 1014-7 (2012) Program Detail Manual for
Certification in the Field of Fire
Protection Engineering Technology (Field
Code 003) Subfield of Automatic Sprinkler
System Layout

UNDERWRITERS LABORATORIES (UL)

UL 199 (2020) UL Standard for Safety Automatic
Sprinklers for Fire-Protection Service

UL 262 (2004; Reprint Oct 2011) Gate Valves for
Fire-Protection Service

UL 312	(2010; Reprint Mar 2018) UL Standard for Safety Check Valves for Fire-Protection Service
UL 405	(2013; Bul. 2020) UL Standard for Safety Fire Department Connection Devices
UL 668	(2004; Reprint Oct 2021) UL Standard for Safety Hose Valves for Fire-Protection Service
UL 2443	(2015; Reprint May 2020) UL Standard for Safety Flexible Sprinkler Hose with Fittings for Fire Protection Service
UL Fire Prot Dir	(2012) Fire Protection Equipment Directory

1.2 SYSTEM DESCRIPTION

Provide wet pipe sprinkler system(s) in areas indicated on the drawings . Except as modified herein, the system must meet the requirements of NFPA 13. Pipe sizes which are not indicated on the Contract drawings must be determined by hydraulic calculations.

1.2.1 Hydraulic Design

1.2.1.1 Basis for Calculations

A waterflow test was performed on at and resulted in a static pressure of with a residual pressure of while flowing . Perform a fire hydrant flow test prior to shop drawing submittal in accordance with NFPA 291. Results must include hydrant elevations relative to the building and hydrant number/identifiers for the tested hydrants, including which were flowed, which had a gauge. This information must be presented in a tabular form if multiple hydrants were flowed. The results must be included with the hydraulic calculations. Hydraulic calculations must be based on flow test noted in this paragraph, unless approved by Contracting Officer. Hydraulic calculations must be based upon the Hazen-Williams formula with a "C" value noted in NFPA 13 for piping, . The minimum residual pressure in a service lateral (lead-in) at the design flow rate must be 20 psi at the inlet to the backflow preventer.

1.2.1.2 Hydraulic Calculations

- a. Water supply curves and system requirements must be plotted on semi-logarithmic graph ($N^{1.85}$) paper so as to present a summary of the complete hydraulic calculation.
- b. Provide a summary sheet listing sprinklers in the design area and their respective hydraulic reference points, elevations, minimum discharge pressures and minimum flows. Elevations of hydraulic reference points (nodes) must be indicated.
- c. Documentation must identify each pipe individually and the nodes connected thereto. Indicate the diameter, length, flow, velocity, friction loss, number and type fittings, total friction loss in the pipe, equivalent pipe length and Hazen-Williams coefficient for each pipe.

- d. Where the sprinkler system is supplied by interconnected risers, the sprinkler system must be hydraulically calculated using the hydraulically most demanding single riser. The calculations must not assume the simultaneous use of more than one riser.
- e. All calculations must include the backflow preventer manufacturer's stated friction loss at the design flow or 8 psi for double check backflow preventer, whichever is greater.
- f. All calculations must be performed back to the actual location of the flow test, taking into account the direction of flow in the service main at the test location.
- g. For gridded systems, calculations must show peaking of demand area friction loss to verify that the hydraulically most demanding area is being used. A flow diagram indicating the quantity and direction of flows must be included.

1.2.1.3 Design Criteria

Hydraulically design the system to discharge a minimum density as per NFPA 13. Hydraulic calculations must be in accordance with the Area/Density Method of NFPA 13. Add an allowance for exterior hose streams of 100/250 gpm to the sprinkler system demand at the fire hydrant shown on the drawings closest to the point where the water service enters the building .

1.2.2 Sprinkler Coverage

Sprinklers must be uniformly spaced on branch lines. Provide coverage throughout 100 percent of the area noted on the Contract drawings. This includes, but is not limited to, telephone rooms, electrical equipment rooms (regardless of the fire resistance rating of the enclosure), boiler rooms, switchgear rooms, transformer rooms, attached electrical vaults and other electrical and mechanical spaces. Coverage per sprinkler must be in accordance with NFPA 13. Provide sprinklers below all obstructions in accordance with NFPA 13. Exceptions are as follows:

- a. Sprinklers may be omitted from small rooms which are exempted for specific occupancies in accordance with NFPA 101.
- b. Facilities that are designed in accordance with NFPA 13R.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Partial submittals and submittals not fully complying with NFPA 13 and this specification section must be returned disapproved without review. SD-02, SD-03 and SD-05 must be submitted simultaneously.

Shop drawings (SD-02), product data (SD-03) and calculations (SD-05) must be prepared by the designer and combined and submitted as one complete package. The QFPE must review the SD-02/SD-03/SD-05 submittal package for completeness and compliance with the Contract provisions prior to submission to the Government. The QFPE must provide a Letter of Confirmation that they have reviewed the submittal package for compliance with the contract provisions. This letter must include their professional

engineer stamp and signature. Partial submittals and submittals not reviewed by the QFPE must be returned disapproved without review.

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualified Fire Protection Engineer (QFPE); G

Sprinkler System Designer; G

Sprinkler System Installer; G

SD-02 Shop Drawings

Shop Drawing; G

SD-03 Product Data

Pipe; G

Fittings; G

Valves, including gate, check, butterfly, and globe; G

Alarm Valves; G

Relief Valves; G

Sprinklers ; G

Pipe Hangers and Supports ; G

Sprinkler Alarm Switch; G

Valve Supervisory (Tamper) Switch; G

Fire Department Connection; G

Backflow Prevention Assembly; G

Air Vent; G

Hose Valve; G

Nameplates; G

SD-05 Design Data

Hydraulic Calculations; G

SD-06 Test Reports

Test Procedures; G

SD-07 Certificates

Verification of Compliant Installation; G

Request for Government Final Test; G

SD-10 Operation and Maintenance Data

Operating and Maintenance (O&M) Instructions; G

Spare Parts Data; G

SD-11 Closeout Submittals

As-built drawings

1.4 QUALITY ASSURANCE

1.4.1 Preconstruction Submittals

Within 36 days of contract award but no less than 14 days prior to commencing work on site, the prime Contractor must submit the following for review and approval. SD-02, SD-03 and SD-05 submittals received prior to the review and approval of the qualifications will be returned Disapproved Without Review.

1.4.1.1 Shop Drawing

3 copies of the shop drawings, no later than 28 days prior to the start of system installation. Working drawings conforming to the requirements prescribed in NFPA 13 and must be no smaller than the Contract Drawings. Each set of drawings must include the following:

- a. A descriptive index with drawings listed in sequence by number. A legend sheet identifying device symbols, nomenclature, and conventions used in the package.
- b. Floor plans drawn to a scale not less than 1/8-inch equals 1-foot clearly showing locations of devices, equipment, risers, and other details required to clearly describe the proposed arrangement.
- c. Actual center-to-center dimensions between sprinklers on branch lines and between branch lines; from end sprinklers to adjacent walls; from walls to branch lines; from sprinkler feed mains, cross mains and branch lines to finished floor and roof or ceiling. A detail must show the dimension from the sprinkler and sprinkler deflector to the ceiling in finished areas.
- d. Longitudinal and transverse building sections showing typical branch line and cross main pipe routing, elevation of each typical sprinkler above finished floor and elevation of "cloud" or false ceilings in relation to the building ceilings.
- e. Plan and elevation views which establish that the equipment will fit the allotted spaces with clearance for installation and maintenance.
- f. Riser layout drawings drawn to a scale of not less than 1/2-inch equals 1-foot to show details of each system component, clearances between each other and from other equipment and construction in the room.
- g. Details of each type of riser assembly, pipe hanger, and restraint of underground water main at point-of-entry into the building, and

electrical devices and interconnecting wiring. The dimension from the edge of vertical piping to the nearest adjacent wall(s) must be indicated on the drawings when vertical piping is located in stairs or other portions of the means of egress.

h. Details of each type of pipe hanger and related components.

1.4.1.2 Product Data

3 copies of annotated catalog data to show the specific model, type, and size of each item. Catalog cuts must also indicate the NRTL listing. The data must be highlighted to show model, size, options, and other pertinent information, that are intended for consideration. Data must be adequate to demonstrate compliance with all contract requirements. Product data for all equipment must be combined into a single submittal.

1.4.1.3 Hydraulic Calculations

Calculations must be as outlined in NFPA 13 except that calculations must be performed by computer using software intended specifically for fire protection system design using the design data shown on the drawings. Calculations must include isometric diagram indicating hydraulic nodes and pipe segments.

1.4.1.4 Operating and Maintenance (O&M) Instructions

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA as supplemented and modified by this specification section.

Provide six manuals and one pdf version on electronic media. The manuals must include the manufacturer's name, model number, parts list, list of parts and tools that should be kept in stock by the owner for routine maintenance, troubleshooting guide, and recommended service organization (including address and telephone number) for each item of equipment. Each service organization submitted must be capable of providing 4-hour on-site response to a service call on an emergency basis.

Submit spare parts data for each different item of material and equipment specified. The data must include a complete list of parts and supplies, and a list of parts recommended by the manufacturer to be replaced after 1-year and 3 years of service. Include a list of special tools and test equipment required for maintenance and testing of the products supplied.

1.4.2 Qualifications

1.4.2.1 Sprinkler System Designer

The sprinkler system designer must be certified as a Level IIIIV Technician by National Institute for Certification in Engineering Technologies (NICET) in the Water-Based Systems Layout subfield of Fire Protection Engineering Technology in accordance with NICET 1014-7.

1.4.2.2 Sprinkler System Installer

The sprinkler system installer must be regularly engaged in the installation of the type and complexity of system specified in the contract documents, and must have served in a similar capacity for at least three systems that have performed in the manner intended for a period of not less than 6 months.

1.4.3 Regulatory Requirements

Equipment and material must be listed or approved. Listed or approved, as used in this Section, means listed, labeled or approved by a Nationally Recognized Testing Laboratory (NRTL) such as UL Fire Prot Dir or FM APP GUIDE. The omission of these terms under the description of an item or equipment described must not be construed as waiving this requirement. All listings or approvals by testing laboratories must be from an existing ANSI or UL published standard. The recommended practices stated in the manufacturer's literature or documentation are mandatory requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

Protect all equipment delivered and placed in storage from the weather, excessive humidity and temperature variations, dirt and dust, or other contaminants. All pipes must be either capped or plugged until installed.

1.6 EXTRA MATERIALS

Spare sprinklers and wrench(es) must be provided as spare parts in accordance with NFPA 13.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

2.1.1 Standard Products

Provide materials, equipment, and devices listed for fire protection service when so required by NFPA 13 or this specification. Select material from one manufacturer, where possible, and not a combination of manufacturers, for a classification of material. Material and equipment must be standard products of a manufacturer regularly engaged in the manufacture of the products for at least 2 years prior to bid.

2.1.2 Nameplates

Major components of equipment must have the manufacturer's name, address, type or style, model or serial number, catalog number, date of installation, installing Contractor's name and address, and the contract number provided on a new name plate permanently affixed to the item or equipment. Nameplates must be etched metal or plastic, permanently attached by screws to control units, panels or adjacent walls.

2.1.3 Identification and Marking

Pipe and fitting markings must include name or identifying symbol of manufacturer and nominal size. Pipe must be marked with ASTM designation. Valves and equipment markings must have name or identifying symbol of manufacturer, specific model number, nominal size, name of device, arrow indicating direction of flow, and position of installation (horizontal or vertical), except if valve can be installed in either position. Markings must be included on the body casting or on an etched or stamped metal nameplate permanently on the valve or cover plate.

2.1.4 Pressure Ratings

Valves, fittings, couplings, alarm switches, and similar devices must be

rated for the maximum working pressures that can be experienced in the system, but in no case less than 175 psi.

2.2 UNDERGROUND PIPING COMPONENTS

2.2.1 Pipe

Pipe must comply with NFPA 24. Minimum pipe size is 4 inches. Piping more than 5 feet outside the building walls must comply with Section 33 11 00 WATER UTILITY DISTRIBUTION PIPING. A continuous section of welded stainless steel fire water service piping from a point outside the building perimeter to a flanged fitting at least 1-foot above the finished floor within the building is acceptable.

2.2.2 Fittings and Gaskets

Fittings must be ductile-iron conforming to AWWA C110/A21.10 with cement mortar lining conforming to AWWA C104/A21.4. Gaskets must be suitable in design and size for the pipe with which such gaskets are to be used. Gaskets for ductile-iron pipe joints must conform to AWWA C111/A21.11.

2.2.3 Gate Valve

Installation must comply with NFPA 24. Gate valves for use with indicator post must conform to UL 262.

2.2.4 Buried Utility Warning and Identification Tape

Provide detectable aluminum foil plastic backed tape or detectable magnetic plastic tape manufactured specifically for warning and identification of buried piping. Tape must be detectable by an electronic detection instrument. Provide tape, 3 inches minimum width, color coded for the utility involved with warning and identification imprinted in bold block letters continuously and repeatedly over the entire tape length. Warning and identification must read "CAUTION BURIED WATER PIPING BELOW" or similar wording. Use permanent code and letter coloring unaffected by moisture and other substances contained in trench backfill material.

2.3 ABOVEGROUND PIPING COMPONENTS

2.3.1 Steel Piping Components

2.3.1.1 Steel Pipe

Except as modified herein, steel pipe must be black as permitted by NFPA 13 and conform to the applicable provisions of ASTM A53/A53M, ASTM A135/A135M or ASTM A153/A153M.

Steel pipe must be minimum Schedule 40 for sizes 2 inches and less; and minimum Schedule 10 for sizes larger than 2 inches. Steel piping with wall thickness less than Schedule 40 must not be threaded. Grooved pipe must be cut-grooved.

2.3.1.2 Fittings

Fittings must be welded, threaded, or grooved-end type. Threaded fittings must be cast-iron conforming to ASME B16.4, malleable-iron conforming to ASME B16.3 or ductile-iron conforming to ASTM A536. Plain-end fittings with mechanical couplings, fittings that use steel gripping devices to bite

into the pipe, steel press fittings and field welded fittings are not permitted. Fittings, mechanical couplings, and rubber gaskets must be supplied by the same manufacturer. Threaded fittings must use Teflon tape or manufacturer's approved joint compound. Saddle tees using rubber gasketed fittings are permitted only when connecting to existing piping for additions or modifications. Saddle tees must use a connection method that completely wraps around the pipe. Reducing couplings are not permitted except as allowed by NFPA 13.

2.3.1.3 Grooved Mechanical Joints and Fittings

Joints and fittings must be designed for not less than 175 psi service and the product of the same manufacturer. Field welded fittings must not be used. Fitting and coupling housing must be malleable-iron conforming to ASTM A47/A47M, Grade 32510; ductile-iron conforming to ASTM A536, Grade 65-45-12. Rubber gasketed grooved-end pipe and fittings with mechanical couplings are permitted in pipe sizes 2 inches and larger. Gasket must be the flush type that fills the entire cavity between the fitting and the pipe. Nuts and bolts must be heat-treated steel conforming to ASTM A183 and must be cadmium-plated or zinc-electroplated.

2.3.1.4 Flanges

Flanges must conform to NFPA 13 and ASME B16.1. Gaskets must be non-asbestos compressed material in accordance with ASME B16.21, 1/16-inch thick, and full face or self-centering flat ring type.

2.3.2 Flexible Sprinkler Hose

Flexible sprinkler hose must comply with UL 2443 and FM 1637.

2.3.3 Pipe Hangers and Supports

Provide galvanized pipe hangers and supports in accordance with NFPA 13..

2.3.4 Valves

Provide valves of types approved for fire service. Valves must open by counterclockwise rotation.

2.3.4.1 Control Valve

Manually operated sprinkler control/gate valve must be outside stem and yoke (OS&Y) type or butterfly type and must be listed.

2.3.4.2 Check Valves

Check valves must comply with UL 312. Check valves 4 inches and larger must be of the swing type, have a clear waterway and meet the requirements of MSS SP-71, for Type 3 or 4. Inspection plate must be provided on valves larger than 6 inches.

2.3.4.3 Hose Valve

Valve must comply with UL 668.

2.3.5 Riser Check Valves

Riser check valves shall be existing to remain. Inspect for damage and

proper operation.

2.4 ALARM INITIATING AND SUPERVISORY DEVICES

2.4.1 Sprinkler Alarm Switch

Vane or pressure-type flow switch(es). Connection of switch must be by the fire alarm installer. Vane type alarm actuating devices must have mechanical diaphragm controlled retard device adjustable from 10 to 60 seconds and must instantly recycle.

2.4.2 Valve Supervisory (Tamper) Switch

Switch must be integral to the control valve or suitable for mounting to the type of control valve to be supervised open. The switch must be tamper resistant and contain SPDT (Form C) contacts arranged to transfer upon removal of the housing cover or closure of the valve of more than two rotations of the valve stem.

2.5 FIRE DEPARTMENT CONNECTION

Fire department connection must be existing to remain. type with cast-brass body, matching escutcheon lettered "Auto Spkr" with a existing finish. Female inlets must have existing diameter existing. Comply with UL 405.

2.6 SPRINKLERS

Sprinklers must comply with UL 199 and NFPA 13. Sprinklers with internal O-rings are not acceptable. Sprinklers in high heat areas including attic spaces or in close proximity to unit heaters must have temperature classification in accordance with NFPA 13. Extended coverage sprinklers are permitted for loading docks, residential occupancies and high-piled storage applications only.

2.6.1 Pendent Sprinkler

Pendent sprinkler must be recessed quick-response type with nominal K-factor of 5.68.0. Pendent sprinklers must have a polished chrome stainless steelwhite polyester finish. Assembly must include an integral escutcheon.

2.6.2 Upright Sprinkler

Upright sprinkler must be brasschrome-platedstainless steelwhite polyester quick-response type and have a nominal K-factor of 5.68.0.

2.7 ACCESSORIES

2.7.1 Sprinkler Cabinet

Provide spare sprinklers in accordance with NFPA 13 and must be placed in a suitable metal or plastic cabinet of sufficient size to accommodate all the spare sprinklers and wrenches in designated locations. Spare sprinklers must be representative of, and in proportion to, the number of each type and temperature rating of the sprinklers installed as required by NFPA 13. At least one wrench of each type required must be provided.

2.7.2 Pendent Sprinkler Escutcheon

Escutcheon must be one-piece metallic type with a depth of less than 3/4-inch and suitable for installation on pendent sprinklers. The escutcheon must have a factory finish that matches the pendent sprinkler.

2.7.3 Pipe Escutcheon

Provide split hinge metal plates for piping entering walls, floors, and ceilings in exposed spaces. Provide polished stainless steel plates or chromium-plated finish on copper alloy plates in finished spaces. Provide paint finish on metal plates in unfinished spaces.

2.7.4 Sprinkler Guard

Listed guard must be a steel wire cage designed to encase the sprinkler and protect it from mechanical damage. Guards must be provided on sprinklers located as indicated.

2.7.5 Relief Valve

Relief valves must be listed and installed at the riser in accordance with NFPA 13.

2.7.6 Air Vent

Air vents must be of the automatic type and piped to drain to the building exterior.

2.7.7 Identification Sign

Valve identification sign must be minimum 6 inches wide by 2 inches high with enamel baked finish on minimum 18 gage steel or 0.024-inch aluminum with red letters on a white background or white letters on red background. Wording of sign must include, but not be limited to "main drain", "auxiliary drain", "inspector's test", "alarm test", "alarm line", and similar wording as required to identify operational components. Where there is more than one sprinkler system, signage must include specific details as to the respective system.

PART 3 EXECUTION

3.1 VERIFYING ACTUAL FIELD CONDITIONS

Before commencing work, examine all adjoining work on which the contractor's work that is dependent for perfect workmanship according to the intent of this specification section, and report to the Contracting Officer's Representative a condition that prevents performance of first class work. No "waiver of responsibility" for incomplete, inadequate or defective adjoining work will be considered unless notice has been filed before submittal of a proposal.

3.2 INSTALLATION

The installation must be in accordance with the applicable provisions of NFPA 13, NFPA 24 and publications referenced therein. Locate sprinklers in a consistent pattern with ceiling grid, lights, and air supply diffusers. Install sprinkler system over and under ducts, piping and platforms when such equipment can negatively affect or disrupt the sprinkler discharge

pattern and coverage.

- a. Piping offsets, fittings, and other accessories required must be furnished to provide a complete installation and to eliminate interference with other construction.
- b. Wherever the contractor's work interconnects with work of other trades the Contractor must coordinate with other Contractors to insure all Contractors have the information necessary so that they may properly install all necessary connections and equipment. Identify all work items needing access (dampers and similar equipment) that are concealed above hung ceilings by permanent color coded pins/tabs in the ceiling directly below the item.
- c. Provide required supports and hangers for piping, conduit, and equipment so that loading will not exceed allowable loadings of structure. Submittal of a bid must be a deemed representation that the contractor submitting such bid has ascertained allowable loadings and has included in his estimates the costs associated in furnishing required supports.

3.2.1 Waste Removal

At the conclusion of each day's work, clean up and stockpile on site all waste, debris, and trash which may have accumulated during the day as a result of work by the contractor and of his presence on the job. Sidewalks and streets adjoining the property must be kept broom clean and free of waste, debris, trash and obstructions caused by work of the contractor, which will affect the condition and safety of streets, walks, utilities, and property.

3.3 ABOVEGROUND PIPING INSTALLATION

The methods of fabrication and installation of the aboveground piping must fully comply with the requirements and recommended practices of NFPA 13 and this specification section.

3.3.1 Protection of Piping Against Earthquake Damage

Seismic restraint is not required.

3.3.2 Piping in Exposed Areas

Install exposed piping without diminishing exit access widths, corridors or equipment access. Exposed horizontal piping, including drain piping, must be installed to provide maximum headroom.

3.3.3 Piping in Finished Areas

In areas with suspended or dropped ceilings and in areas with concealed spaces above the ceiling, piping must be concealed above ceilings. Piping must be inspected, hydrostatically tested and approved before being concealed. Risers and similar vertical runs of piping in finished areas must be concealed.

3.3.4 Pendent Sprinklers

- a. Drop nipples to pendent sprinklers must consist of minimum 1-inch pipe with a reducing coupling into which the sprinkler must be threaded.

- b. Where sprinklers are installed below suspended or dropped ceilings, drop nipples must be cut such that sprinkler ceiling plates or escutcheons are of a uniform depth throughout the finished space. The outlet of the reducing coupling must not extend below the underside of the ceiling.
- c. Recessed pendent sprinklers must be installed such that the distance from the sprinkler deflector to the underside of the ceiling must not exceed the manufacturer's listed range and must be of uniform depth throughout the finished area.
- d. Pendent sprinklers in suspended ceilings must be located in the center of the tile (plus or minus 2 inches).
- g. Where the maximum static or flowing pressure, whichever is greater at the sprinkler, applied other than through the fire department connection, exceeds 100 psi and a branch line above the ceiling supplies sprinklers in a pendent position below the ceiling, the cumulative horizontal length of an unsupported armover to a sprinkler or sprinkler drop must not exceed 12 inches for steel pipe and 6 inches for copper tube.

3.3.5 Upright Sprinklers

Riser nipples or "sprigs" to upright sprinklers must contain no fittings between the branch line tee and the reducing coupling at the sprinkler.

3.3.6 Pipe Joints

Pipe joints must conform to NFPA 13, except as modified herein. Not more than four threads must show after joint is made up. Welded joints will be permitted, only if welding operations are performed as required by NFPA 13 at the Contractor's fabrication shop, not at the project construction site. Flanged joints must be provided where indicated or required by NFPA 13. Grooved pipe and fittings must be prepared in accordance with the manufacturer's latest published specification according to pipe material, wall thickness and size. Grooved couplings, fittings and grooving tools must be products of the same manufacturer. For copper tubing, pipe and groove dimensions must comply with the tolerances specified by the coupling manufacturer. The diameter of grooves made in the field must be measured using a "go/no-go" gauge, vernier or dial caliper, narrow-land micrometer, or other method specifically approved by the coupling manufacturer for the intended application. Groove width and dimension of groove from end of pipe must be measured and recorded for each change in grooving tool setup to verify compliance with coupling manufacturer's tolerances.

3.3.7 Reducers

Reductions in pipe sizes must be made with one-piece tapered reducing fittings. When standard fittings of the required size are not manufactured, single bushings of the face or hex type will be permitted. Where used, face bushings must be installed with the outer face flush with the face of the fitting opening being reduced. Bushings cannot be used in elbow fittings, in more than one outlet of a tee, in more than two outlets of a cross, or where the reduction in size is less than 1/2-inch.

3.3.8 Pipe Penetrations

- a. Cutting structural members for passage of pipes or for pipe-hanger fastenings will not be permitted. Pipes that must penetrate concrete or masonry walls or concrete floors must be core-drilled and provided with pipe sleeves. Each sleeve must be Schedule 40 galvanized steel, ductile-iron or cast-iron pipe and extend through its respective wall or floor and be cut flush with each wall surface. Sleeves must provide required clearance between the pipe and the sleeve per NFPA 13. The space between the sleeve and the pipe must be firmly packed with mineral wool insulation.
- b. Where pipes and sleeves penetrate fire walls, fire partitions, or floors, pipes/sleeves must be firestopped in accordance with Section 07 84 00 FIRESTOPPING.
- c. In penetrations that are not fire-rated or not a floor penetration, the space between the sleeve and the pipe must be sealed at both ends with plastic waterproof cement that will dry to a firm but pliable mass or with a mechanically adjustable segmented elastomer seal.
- d. All penetrations through the boundary of rooms/areas identified as secure space area must meet ICS 705-1.

3.3.9 Escutcheons

Escutcheons must be provided for pipe penetration in finished areas of ceilings, floors and walls. Escutcheons must be securely fastened to the pipe at surfaces through which piping passes.

3.3.10 Inspector's Test Connection

Unless otherwise indicated, the test connection must consist of 1-inch pipe connected where existing; a test valve located approximately 7 feet above the floor; a smooth bore brass outlet equivalent to the smallest orifice sprinkler used in the system; and a painted metal identification sign affixed to the valve with the words "Inspector's Test". All test connection piping must be inside of the building and penetrate the exterior wall at the location of the discharge orifice only. The discharge orifice must be located outside the building wall no more than 2 feet above finished grade, directed so as not to cause damage to adjacent construction or landscaping during full flow discharge, or to the sanitary sewer. Discharge to the exterior must not interfere with exiting from the facility. Water discharge or runoff must not cross the path of egress from the building. Do not discharge to the roof. Discharge to floor drains, janitor sinks or similar fixtures is not permitted.

Provide concrete splash blocks at all drain and inspector's test connection discharge locations if not discharging to a concrete surface. Splash blocks must be large enough to mitigate erosion and not become dislodged during a full flow of the drain. Ensure all discharged water drains away from the facility and does not cause property damage.

3.3.11 Backflow Preventer

Locate within the building or in a heated enclosure in locations subject to freezing. For heated enclosures, provide a low temperature supervisory alarm connected to the facility fire alarm system. Heat trace is not permitted to be used.

Install backflow preventers so that the bottom of the assembly is a minimum of 6 inches above the finished floor/grade. Install horizontal backflow preventers so that the bottom of the assembly is no greater than 24 inches above the finished floor/grade. Install vertical backflow preventers so that the upper operating handwheel is no more than 6 feet above the finished floor/grade. Clearance around control valve handles must be minimum 6 inches above grade/finished floor and away from walls.

3.3.12 Drains

- a. Main drain piping must be provided to discharge at a safe point outside the building, no more than 2 feet above finished grade. Provide a concrete splash block at drain outlet. Discharge to the exterior must not interfere with exiting from the facility. Water discharge or runoff must not cross the path of egress from the building.
- b. Auxiliary drains must be provided as required by NFPA 13. Auxiliary drains are permitted to discharge to a floor drain if the drain is sized to accommodate full flow (min 40 gpm). Discharge to service sinks or similar plumbing fixtures is not permitted.

3.3.13 Installation of Fire Department Connection

Connection must be mounted as existing.. The piping between the connection and the check valve must be provided with an automatic drip in accordance with NFPA 13 and piped to drain to the outside or a floor drain within the same room.

3.3.14 Identification Signs

Signs must be affixed to each control valve, inspector test valve, main drain, auxiliary drain, test valve, and similar valves as appropriate or as required by NFPA 13. Main drain test results must be etched into main drain identification sign. Hydraulic design data must be etched into the nameplates and permanently affixed to each sprinkler riser as specified in NFPA 13. Provide labeling on the surfaces of all feed and cross mains to show the pipe function (e.g., "Sprinkler System", "Fire Department Connection", "Standpipe") and normal valve position (e.g. "Normally Open", "Normally Closed"). For pipe sizes 4-inch and larger provide white painted stenciled letters and arrows, a minimum of 2 inches in height and visible from at least two sides when viewed from the floor. For pipe sizes less than 4-inch, provide white painted stenciled letters and arrows, a minimum of 0.75-inch in height and visible from the floor.

3.4 ELECTRICAL

Except as modified herein, electric equipment and wiring must be in accordance with Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Alarm signal wiring connected to the building fire alarm control system must be by the fire alarm installer.

3.5 PAINTING

Color code mark piping red.

3.6 FIELD QUALITY CONTROL

3.6.1 Test Procedures

Submit detailed test procedures, prepared and signed by the NICET Level III or IV Fire Sprinkler Technician, and the representative of the installing company, 60 days prior to performing system tests. Detailed test procedures must list all components of the installed system. Test procedures must include sequence of testing, time estimate for each test, and sample test data forms. The test data forms must be in a check-off format (pass/fail with space to add applicable test data; similar to the forms in NFPA 13). The test procedures and accompanying test data forms must be used for the pre-Government testing and the Government final testing.

- a. Provide space to identify the date and time of each test. Provide space to identify the names and signatures of the individuals conducting and witnessing each test.

3.6.2 Pre-Government Testing

3.6.2.1 Verification of Compliant Installation

Conduct inspections and tests to ensure that equipment is functioning properly. Tests must meet the requirements of paragraph entitled "Minimum System Tests" and "System Acceptance" as noted in NFPA 13. The Contractor must be in attendance at the pre-Government testing to make necessary adjustments. After inspection and testing is complete, provide a signed Verification of Compliant Installation letter by the QFPE that the installation is complete, compliant with the specification and fully operable. The letter must include the names and titles of the witnesses to the pre-Government tests. Provide all completion documentation as required by NFPA 13 and the test reports noted below.

- a. NFPA 13 Aboveground Material and Test Certificate
- b. NFPA 13 Underground Material and Test Certificate

3.6.2.2 Request for Government Final Test

When the verification of compliant installation has been completed, submit a formal request for Government final test to the Contracting Officers Designated Representative (COR). Government final testing will not be scheduled until the DFPE has received copies of the request for Government final testing and Verification of Compliant Installation letter with all required reports. Government final testing will not be performed until after the connections to the building fire alarm system have been completed and tested to confirm communications are fully functional. Submit request for test at least 15 calendar days prior to the requested test date.

3.6.3 Correction of Deficiencies

If equipment was found to be defective or non-compliant with contract requirements, perform corrective actions and repeat the tests. Tests must be conducted and repeated if necessary until the system has been demonstrated to comply with all contract requirements.

3.6.4 Government Final Tests

The tests must be performed in accordance with the approved test procedures in the presence of the DFPE. Furnish instruments and personnel required for the tests. The following must be provided at the job site for Government Final Testing:

- a. The manufacturer's technical representative.
- c. Marked-up red line drawings of the system as actually installed.

Government Final Tests will be witnessed by the , Contracting Officer. At this time, all required tests noted in the paragraph "Minimum System Tests" must be repeated at their discretion.

3.7 MINIMUM SYSTEM TESTS

The system, including the underground water mains, and the aboveground piping and system components, must be tested to ensure that equipment and components function as intended. The underground and aboveground interior piping systems and attached appurtenances subjected to system working pressure must be tested in accordance with NFPA 13 and NFPA 24.

3.7.1 Underground Piping

3.7.1.1 Flushing

Underground piping must be flushed at a minimum of 10 fps in accordance with NFPA 24.

3.7.1.2 Hydrostatic Test

New underground piping must be hydrostatically tested in accordance with NFPA 24.

3.7.2 Aboveground Piping

3.7.2.1 Hydrostatic Test

Aboveground piping must be hydrostatically tested in accordance with NFPA 13. There must be no drop in gauge pressure or visible leakage when the system is subjected to the hydrostatic test. The test pressure must be read from a gauge located at the low elevation point of the system or portion being tested.

3.7.2.2 Backflow Prevention Assembly Forward Flow Test

Each backflow prevention assembly must be tested at system flow demand, including all applicable hose streams, as specified in NFPA 13. The Contractor must provide all equipment and instruments necessary to conduct a complete forward flow test, including 2.5-inch diameter hoses, playpipe nozzles or flow diffusers, calibrated pressure gauges, and pitot tube gauge. The Contractor must provide all necessary supports to safely secure hoses and nozzles during the test. At the system demand flow, the pressure readings and pressure drop (friction loss) across the assembly must be recorded. A metal placard must be provided on the backflow prevention assembly that lists the pressure readings both upstream and downstream of the assembly, total pressure drop, and the system test flow rate determined during the preliminary testing. The pressure drop must be compared to the

manufacturer's data and the readings observed during the final inspections and tests.

3.7.3 Main Drain Flow Test

Following flushing of the underground piping, a main drain test must be made to verify the adequacy of the water supply. Static and residual pressures must be recorded on the certificate specified in paragraph SUBMITTALS.

3.8 SYSTEM ACCEPTANCE

Following acceptance of the system, as-built drawings and O&M manuals must be delivered to the Contracting Officer for review and acceptance. Submit six sets of detailed as-built drawings. The drawings must show the system as installed, including deviations from both the project drawings and the approved shop drawings. These drawings must be submitted within two weeks after the final acceptance test of the system. At least one set of as-built (marked-up) drawings must be provided at the time of, or prior to the final acceptance test.

- a. Provide one set of full size paper as-built drawings and schematics. The drawings must be prepared electronically and sized no less than the contract drawings.
- b. Provide operating and maintenance (O&M) instructions.

3.9 ONSITE TRAINING

Conduct a training course for the responding fire department and operating and maintenance personnel as designated by the Contracting Officer. Training must be performed on two separate days (to accommodate different shifts of Fire Department personnel) for a period of 4 hours of normal working time and must start after the system is functionally complete and after the final acceptance test. The on-site training must cover all of the items contained in the approved Operating and Maintenance Instructions.

-- End of Section --

SECTION 22 00 00

PLUMBING, GENERAL PURPOSE
11/15

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z21.10.3/CSA 4.3 (2017) Gas-Fired Water Heaters Vol.III, Storage Water Heaters With Input Ratings Above 75,000 Btu Per Hour, Circulating and Instantaneous

ANSI Z21.22/CSA 4.4 (2015) Relief Valves for Hot Water Supply Systems

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 146 (2011) Method of Testing and Rating Pool Heaters

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME A112.1.2 (2012; R 2017) Air Gaps in Plumbing Systems (For Plumbing Fixtures and Water-Connected Receptors)

ASME A112.6.1M (1997; R 2017) Floor Affixed Supports for Off-the-Floor Plumbing Fixtures for Public Use

ASME A112.19.2/CSA B45.1 (2018; ERTA 2018) Standard for Vitreous China Plumbing Fixtures and Hydraulic Requirements for Water Closets and Urinals

ASME A112.19.3/CSA B45.4 (2017; Errata 2017) Stainless Steel Plumbing Fixtures

ASME A112.36.2M (1991; R 2017) Cleanouts

ASME B1.20.1 (2013; R 2018) Pipe Threads, General Purpose (Inch)

ASME B16.4 (2016) Standard for Gray Iron Threaded Fittings; Classes 125 and 250

ASME B16.5 (2017) Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard

ASME B16.12 (2019) Cast Iron Threaded Drainage Fittings

ASME B16.15	(2018) Cast Copper Alloy Threaded Fittings Classes 125 and 250
ASME B16.18	(2018) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.23	(2011) Cast Copper Alloy Solder Joint Drainage Fittings - DWV
ASME B16.24	(2011) Cast Copper Alloy Pipe Flanges and Flanged Fittings: Classes 150, 300, 600, 900, 1500, and 2500
ASME B16.29	(2017) Wrought Copper and Wrought Copper Alloy Solder-Joint Drainage Fittings - DWV
ASME B16.34	(2017) Valves - Flanged, Threaded and Welding End
ASME B16.50	(2013) Wrought Copper and Copper Alloy Braze-Joint Pressure Fittings
ASME B16.51	(2013) Copper and Copper Alloy Press-Connect Pressure Fittings
ASME B31.1	(2018) Power Piping
ASME B31.5	(2016) Refrigeration Piping and Heat Transfer Components
ASME B40.100	(2013) Pressure Gauges and Gauge Attachments
ASME BPVC SEC IX	(2017; Errata 2018) BPVC Section IX-Welding, Brazing and Fusing Qualifications

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)

ASSE 1001	(2016) Performance Requirements for Atmospheric Type Vacuum Breakers
ASSE 1003	(2009) Performance Requirements for Water Pressure Reducing Valves for Domestic Water Distribution Systems - (ANSI approved 2010)
ASSE 1010	(2004) Performance Requirements for Water Hammer Arresters (ANSI approved 2004)
ASSE 1011	(2004; Errata 2004) Performance Requirements for Hose Connection Vacuum Breakers (ANSI approved 2004)
ASSE 1012	(2009) Performance Requirements for Backflow Preventer with an Intermediate Atmospheric Vent - (ANSI approved 2009)

ASSE 1013	(2011) Performance Requirements for Reduced Pressure Principle Backflow Preventers and Reduced Pressure Fire Protection Principle Backflow Preventers - (ANSI approved 2010)
ASSE 1020	(2004; Errata 2004; Errata 2004) Performance Requirements for Pressure Vacuum Breaker Assembly (ANSI Approved 2004)
ASSE 1037	(2015; Reprint Sep 2017) Performance Requirements for Pressurized Flushing Devices for Plumbing Fixtures

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA 10084	(2017) Standard Methods for the Examination of Water and Wastewater
AWWA B300	(2010; Addenda 2011) Hypochlorites
AWWA B301	(2010) Liquid Chlorine
AWWA C203	(2008) Coal-Tar Protective Coatings and Linings for Steel Water Pipelines - Enamel and Tape - Hot-Applied
AWWA C651	(2014) Standard for Disinfecting Water Mains
AWWA C652	(2011) Disinfection of Water-Storage Facilities

AMERICAN WELDING SOCIETY (AWS)

AWS A5.8/A5.8M	(2019) Specification for Filler Metals for Brazing and Braze Welding
AWS B2.2/B2.2M	(2016) Specification for Brazing Procedure and Performance Qualification

ASTM INTERNATIONAL (ASTM)

ASTM A47/A47M	(1999; R 2018; E 2018) Standard Specification for Ferritic Malleable Iron Castings
ASTM A53/A53M	(2018) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A105/A105M	(2018) Standard Specification for Carbon Steel Forgings for Piping Applications
ASTM A183	(2014) Standard Specification for Carbon Steel Track Bolts and Nuts
ASTM A193/A193M	(2019) Standard Specification for

	Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service and Other Special Purpose Applications
ASTM A515/A515M	(2017) Standard Specification for Pressure Vessel Plates, Carbon Steel, for Intermediate- and Higher-Temperature Service
ASTM A516/A516M	(2017) Standard Specification for Pressure Vessel Plates, Carbon Steel, for Moderate- and Lower-Temperature Service
ASTM A536	(1984; R 2014) Standard Specification for Ductile Iron Castings
ASTM A733	(2016) Standard Specification for Welded and Seamless Carbon Steel and Austenitic Stainless Steel Pipe Nipples
ASTM A888	(2018) Standard Specification for Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications
ASTM B32	(2008; R 2014) Standard Specification for Solder Metal
ASTM B42	(2015a) Standard Specification for Seamless Copper Pipe, Standard Sizes
ASTM B88	(2016) Standard Specification for Seamless Copper Water Tube
ASTM B88M	(2018) Standard Specification for Seamless Copper Water Tube (Metric)
ASTM B117	(2016) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM B306	(2013) Standard Specification for Copper Drainage Tube (DWV)
ASTM B370	(2012; R 2019) Standard Specification for Copper Sheet and Strip for Building Construction
ASTM B584	(2014) Standard Specification for Copper Alloy Sand Castings for General Applications
ASTM B813	(2016) Standard Specification for Liquid and Paste Fluxes for Soldering of Copper and Copper Alloy Tube
ASTM B828	(2016) Standard Practice for Making Capillary Joints by Soldering of Copper and Copper Alloy Tube and Fittings

ASTM C564	(2014) Standard Specification for Rubber Gaskets for Cast Iron Soil Pipe and Fittings
ASTM C920	(2018) Standard Specification for Elastomeric Joint Sealants
ASTM D2000	(2018) Standard Classification System for Rubber Products in Automotive Applications
ASTM D2235	(2004; R 2016) Standard Specification for Solvent Cement for Acrylonitrile-Butadiene-Styrene (ABS) Plastic Pipe and Fittings
ASTM D2564	(2012) Standard Specification for Solvent Cements for Poly(Vinyl Chloride) (PVC) Plastic Piping Systems
ASTM D2822/D2822M	(2005; R 2011; E 2011) Standard Specification for Asphalt Roof Cement, Asbestos-Containing
ASTM D2855	(2015) Standard Practice for Making Solvent-Cemented Joints with Poly(Vinyl Chloride) (PVC) Pipe and Fittings
ASTM D3138	(2004; R 2016) Standard Specification for Solvent Cements for Transition Joints Between Acrylonitrile-Butadiene-Styrene (ABS) and Poly(Vinyl Chloride) (PVC) Non-Pressure Piping Components
ASTM D3139	(1998; R 2011) Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals
ASTM D3212	(2007; R 2013) Standard Specification for Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals
ASTM D3311	(2017) Standard Specification for Drain, Waste, and Vent (DWV) Plastic Fittings Patterns
ASTM E1	(2014) Standard Specification for ASTM Liquid-in-Glass Thermometers
ASTM F477	(2014) Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe
ASTM F493	(2014) Solvent Cements for Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe and Fittings
ASTM F2389	(2017a) Standard Specification for Pressure-rated Polypropylene (PP) Piping Systems

CAST IRON SOIL PIPE INSTITUTE (CISPI)

- CISPI 301 (2012) Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications
- CISPI 310 (2012) Coupling for Use in Connection with Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications

COPPER DEVELOPMENT ASSOCIATION (CDA)

- CDA A4015 (2016; 14/17) Copper Tube Handbook

INTERNATIONAL ASSOCIATION OF PLUMBING AND MECHANICAL OFFICIALS (IAPMO)

- IAPMO PS 117 (2005b) Press Type Or Plain End Rub Gasketed W/ Nail CU & CU Alloy Fittings 4 Install On CU Tubing

INTERNATIONAL CODE COUNCIL (ICC)

- ICC A117.1 COMM (2017) Standard And Commentary Accessible and Usable Buildings and Facilities
- ICC IPC (2018) International Plumbing Code

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

- MSS SP-25 (2018) Standard Marking System for Valves, Fittings, Flanges and Unions
- MSS SP-44 (2017) Steel Pipeline Flanges
- MSS SP-58 (2018) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation
- MSS SP-72 (2010a) Ball Valves with Flanged or Butt-Welding Ends for General Service
- MSS SP-80 (2013) Bronze Gate, Globe, Angle and Check Valves
- MSS SP-85 (2011) Gray Iron Globe & Angle Valves Flanged and Threaded Ends
- MSS SP-110 (2010) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

- NFPA 90A (2021) Standard for the Installation of Air Conditioning and Ventilating Systems

NSF INTERNATIONAL (NSF)

NSF 372	(2016) Drinking Water System Components - Lead Content
NSF/ANSI 14	(2018) Plastics Piping System Components and Related Materials
NSF/ANSI 61	(2019) Drinking Water System Components - Health Effects

PLASTIC PIPE AND FITTINGS ASSOCIATION (PPFA)

PPFA Fire Man	(2016) Firestopping: Plastic Pipe in Fire Resistive Construction

PLUMBING AND DRAINAGE INSTITUTE (PDI)

PDI WH 201	(2010) Water Hammer Arresters Standard

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE J1508	(2009) Hose Clamp Specifications

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

PL 93-523	(1974; A 1999) Safe Drinking Water Act

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

10 CFR 430	Energy Conservation Program for Consumer Products
40 CFR 141.80	National Primary Drinking Water Regulations; Control of Lead and Copper; General Requirements

UNDERWRITERS LABORATORIES (UL)

UL 1951	(2011; Reprint Aug 2017) UL Standard for Safety Electric Plumbing Accessories

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Fixtures

List of installed fixtures with manufacturer, model, and flow rate.

Kitchen Sinks

Service Sinks

Backflow Prevention Assemblies

Welding

A copy of qualified procedures and a list of names and identification symbols of qualified welders and welding operators.

Plumbing System

Diagrams, instructions, and other sheets proposed for posting. Manufacturer's recommendations for the installation of bell and spigot and hubless joints for cast iron soil pipe.

SD-06 Test Reports

Tests, Flushing and Disinfection

Test reports in booklet form showing all field tests performed to adjust each component and all field tests performed to prove compliance with the specified performance criteria, completion and testing of the installed system. Each test report shall indicate the final position of controls.

Test of Backflow Prevention Assemblies.

Certification of proper operation shall be as accomplished in accordance with state regulations by an individual certified by the state to perform such tests. If no state requirement exists, the Contractor shall have the manufacturer's representative test the device, to ensure the unit is properly installed and performing as intended. The Contractor shall provide written documentation of the tests performed and signed by the individual performing the tests.

SD-07 Certificates

Materials and Equipment

Where equipment is specified to conform to requirements of the ASME Boiler and Pressure Vessel Code, the design, fabrication, and installation shall conform to the code.

Bolts

Written certification by the bolt manufacturer that the bolts furnished comply with the specified requirements.

SD-10 Operation and Maintenance Data

Plumbing System

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.3 STANDARD PRODUCTS

Specified materials and equipment shall be standard products of a

manufacturer regularly engaged in the manufacture of such products. Specified equipment shall essentially duplicate equipment that has performed satisfactorily at least two years prior to bid opening. Standard products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year use shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2 year period.

1.3.1 Alternative Qualifications

Products having less than a two-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturer's factory or laboratory tests, can be shown.

1.3.2 Service Support

The equipment items shall be supported by service organizations. Submit a certified list of qualified permanent service organizations for support of the equipment which includes their addresses and qualifications. These service organizations shall be reasonably convenient to the equipment installation and able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.3.3 Manufacturer's Nameplate

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

1.3.4 Modification of References

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction", or words of similar meaning, to mean the Contracting Officer.

1.3.4.1 Definitions

For the International Code Council (ICC) Codes referenced in the contract documents, advisory provisions shall be considered mandatory, the word "should" shall be interpreted as "shall." Reference to the "code official" shall be interpreted to mean the "Contracting Officer." For leased facilities, references to the "owner" shall be interpreted to mean the "lessor." References to the "permit holder" shall be interpreted to mean the "Contractor."

1.3.4.2 Administrative Interpretations

For ICC Codes referenced in the contract documents, the provisions of Chapter 1, "Administrator," do not apply. These administrative requirements are covered by the applicable Federal Acquisition Regulations (FAR) included in this contract and by the authority granted to the Officer in Charge of Construction to administer the construction of this project. References in the ICC Codes to sections of Chapter 1, shall be

applied appropriately by the Contracting Officer as authorized by his administrative cognizance and the FAR.

1.4 DELIVERY, STORAGE, AND HANDLING

Handle, store, and protect equipment and materials to prevent damage before and during installation in accordance with the manufacturer's recommendations, and as approved by the Contracting Officer. Replace damaged or defective items.

1.5 PERFORMANCE REQUIREMENTS

1.5.1 Welding

Piping shall be welded in accordance with qualified procedures using performance-qualified welders and welding operators. Procedures and welders shall be qualified in accordance with ASME BPVC SEC IX. Welding procedures qualified by others, and welders and welding operators qualified by another employer, may be accepted as permitted by ASME B31.1. The Contracting Officer shall be notified 24 hours in advance of tests, and the tests shall be performed at the work site if practicable. Welders or welding operators shall apply their assigned symbols near each weld they make as a permanent record.

1.6 REGULATORY REQUIREMENTS

Unless otherwise required herein, plumbing work shall be in accordance with ICC IPC.

1.7 PROJECT/SITE CONDITIONS

The Contractor shall become familiar with details of the work, verify dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

1.8 INSTRUCTION TO GOVERNMENT PERSONNEL

When specified in other sections, furnish the services of competent instructors to give full instruction to the designated Government personnel in the adjustment, operation, and maintenance, including pertinent safety requirements, of the specified equipment or system. Instructors shall be thoroughly familiar with all parts of the installation and shall be trained in operating theory as well as practical operation and maintenance work.

Instruction shall be given during the first regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. The number of man-days (8 hours per day) of instruction furnished shall be as specified in the individual section. When more than 4 man-days of instruction are specified, use approximately half of the time for classroom instruction. Use other time for instruction with the equipment or system.

When significant changes or modifications in the equipment or system are made under the terms of the contract, provide additional instruction to acquaint the operating personnel with the changes or modifications.

1.9 ACCESSIBILITY OF EQUIPMENT

Install all work so that parts requiring periodic inspection, operation, maintenance, and repair are readily accessible. Install concealed valves, expansion joints, controls, dampers, and equipment requiring access, in locations freely accessible through access doors.

PART 2 PRODUCTS

2.1 MATERIALS

Materials for various services shall be in accordance with TABLES I and II. Pipe schedules shall be selected based on service requirements. Pipe fittings shall be compatible with the applicable pipe materials. Plastic pipe, fittings, and solvent cement shall meet NSF/ANSI 14 and shall be NSF listed for the service intended. Plastic pipe, fittings, and solvent cement used for potable hot and cold water service shall bear the NSF seal "NSF-PW." Polypropylene pipe and fittings shall conform to dimensional requirements of Schedule 40, Iron Pipe size and shall comply with NSF/ANSI 14, NSF/ANSI 61 and ASTM F2389. Polypropylene piping that will be exposed to UV light shall be provided with a Factory applied UV resistant coating. Pipe threads (except dry seal) shall conform to ASME B1.20.1. Grooved pipe couplings and fittings shall be from the same manufacturer. Material or equipment containing a weighted average of greater than 0.25 percent lead shall not be used in any potable water system intended for human consumption, and shall be certified in accordance with NSF/ANSI 61, Annex G or NSF 372. In line devices such as water meters, building valves, check valves, meter stops, valves, fittings and back flow preventers shall comply with PL 93-523 and NSF/ANSI 61, Section 8. End point devices such as drinking water fountains, lavatory faucets, kitchen and bar faucets, residential ice makers, supply stops and end point control valves used to dispense water for drinking must meet the requirements of NSF/ANSI 61, Section 9. Hubless cast-iron soil pipe shall not be installed underground, under concrete floor slabs, or in crawl spaces below kitchen floors. Plastic pipe shall not be installed in air plenums. Plastic pipe shall not be installed in a pressure piping system in buildings greater than three stories including any basement levels.

2.1.1 Pipe Joint Materials

Grooved pipe and hubless cast-iron soil pipe shall not be used underground. Solder containing lead shall not be used with copper pipe. Cast iron soil pipe and fittings shall be marked with the collective trademark of the Cast Iron Soil Institute. Joints and gasket materials shall conform to the following:

- a. Coupling for Cast-Iron Pipe: For hubless type: CISPI 310
- b. Brazing Material: Brazing material shall conform to AWS A5.8/A5.8M, BCuP-5.
- c. Brazing Flux: Flux shall be in paste or liquid form appropriate for use with brazing material. Flux shall be as follows: lead-free; have a 100 percent flushable residue; contain slightly acidic reagents; contain potassium borides; and contain fluorides.
- d. Solder Material: Solder metal shall conform to ASTM B32.
- e. Solder Flux: Flux shall be liquid form, non-corrosive, and conform to

ASTM B813, Standard Test 1.

- f. PTFE Tape: PTFE Tape, for use with Threaded Metal or Plastic Pipe.
- g. Rubber Gaskets for Cast-Iron Soil-Pipe and Fittings (hub and spigot type and hubless type): ASTM C564.
- h. Rubber Gaskets for Grooved Pipe: ASTM D2000, maximum temperature 230 degrees F.
- i. Flexible Elastomeric Seals: ASTM D3139, ASTM D3212 or ASTM F477.
- j. Bolts and Nuts for Grooved Pipe Couplings: Heat-treated carbon steel, ASTM A183.
- k. Solvent Cement for Transition Joints between ABS and PVC Nonpressure Piping Components: ASTM D3138.
- l. Plastic Solvent Cement for ABS Plastic Pipe: ASTM D2235.
- m. Plastic Solvent Cement for PVC Plastic Pipe: ASTM D2564 and ASTM D2855.
- n. Plastic Solvent Cement for CPVC Plastic Pipe: ASTM F493.
- o. Flanged fittings including, but not limited to, flanges, bolts, nuts and bolt patterns shall be in accordance with ASME B16.5 class 150 and shall have the manufacturer's trademark affixed in accordance with MSS SP-25. Flange material shall conform to ASTM A105/A105M. Blind flange material shall conform to ASTM A516/A516M cold service and ASTM A515/A515M for hot service. Bolts shall be high strength or intermediate strength with material conforming to ASTM A193/A193M.
- p. Press fittings for Copper Pipe and Tube: Copper press fittings shall conform to the material and sizing requirements of ASME B16.51 and performance criteria of IAPMO PS 117. Sealing elements for copper press fittings shall be EPDM, FKM or HNBR. Sealing elements shall be factory installed or an alternative supplied fitting manufacturer. Sealing element shall be selected based on manufacturer's approved application guidelines.
- q. Copper tubing shall conform to ASTM B88, Type K, L or M.

2.1.2 Miscellaneous Materials

Miscellaneous materials shall conform to the following:

- a. Copper, Sheet and Strip for Building Construction: ASTM B370.
- b. Asphalt Roof Cement: ASTM D2822/D2822M.
- c. Hose Clamps: SAE J1508.
- d. Supports for Off-The-Floor Plumbing Fixtures: ASME A112.6.1M.
- e. Metallic Cleanouts: ASME A112.36.2M.
- f. Plumbing Fixture Setting Compound: A preformed flexible ring seal

molded from hydrocarbon wax material. The seal material shall be nonvolatile nonasphaltic and contain germicide and provide watertight, gastight, odorproof and verminproof properties.

- g. Coal-Tar Protective Coatings and Linings for Steel Water Pipelines: AWWA C203.
- h. Hypochlorites: AWWA B300.
- i. Liquid Chlorine: AWWA B301.
- j. Gauges - Pressure and Vacuum Indicating Dial Type - Elastic Element: ASME B40.100.
- k. Thermometers: ASTM E1. Mercury shall not be used in thermometers.

2.1.3 Pipe Insulation Material

Insulation shall be as specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.2 PIPE HANGERS, INSERTS, AND SUPPORTS

Pipe hangers, inserts, and supports shall conform to MSS SP-58.

2.3 VALVES

Valves shall be provided on supplies to equipment and fixtures. Valves 2-1/2 inches and smaller shall be bronze with threaded bodies for pipe and solder-type connections for tubing. Valves 3 inches and larger shall have flanged iron bodies and bronze trim. Pressure ratings shall be based upon the application. Grooved end valves may be provided if the manufacturer certifies that the valves meet the performance requirements of applicable MSS standard. Valves shall conform to the following standards:

Description	Standard
Ball Valves with Flanged Butt-Welding Ends for General Service	MSS SP-72
Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends	MSS SP-110
Bronze Gate, Globe, Angle, and Check Valves	MSS SP-80
Steel Valves, Socket Welding and Threaded Ends	ASME B16.34
Cast-Iron Globe and Angle Valves, Flanged and Threaded Ends	MSS SP-85
Vacuum Relief Valves	ANSI Z21.22/CSA 4.4

Water Pressure Reducing Valves	ASSE 1003

2.4 FIXTURES

Water closet replacements in major renovations may have a flush valve of up to 1.28 GPF to accommodate existing plumbing capacity. Fixtures for use by the physically handicapped shall be in accordance with ICC A117.1 COMM. Vitreous China, nonabsorbent, hard-burned, and vitrified throughout the body shall be provided. Porcelain enameled ware shall have specially selected, clear white, acid-resisting enamel coating evenly applied on surfaces. No fixture will be accepted that shows cracks, crazes, blisters, thin spots, or other flaws. Fixtures shall be equipped with appurtenances such as traps, faucets, stop valves, and drain fittings. Each fixture and piece of equipment requiring connections to the drainage system shall be equipped with a trap. Brass expansion or toggle bolts capped with acorn nuts shall be provided for supports, and polished chromium-plated pipe, valves, and fittings shall be provided where exposed to view. Fixtures with the supply discharge below the rim shall be equipped with backflow preventers. Internal parts of flush valves and flushometer valves, shower mixing valves, shower head face plates, pop-up stoppers of lavatory waste drains, and pop-up stoppers and overflow tees and shoes of bathtub waste drains shall be copper alloy with all visible surfaces chrome plated.

2.4.1 Automatic Controls

Provide automatic, sensor operated faucets and flush valves to comply with ASSE 1037 and UL 1951 for lavatory faucets, urinals, and water closets. Flushing and faucet systems shall consist of solenoid-activated valves with light beam sensors. Flush valve for water closet shall include an override pushbutton. Flushing devices shall be provided as described in paragraph FIXTURES AND FIXTURE TRIMMINGS.

2.4.2 Flush Valve Water Closets

ASME A112.19.2/CSA B45.1, white vitreous china, siphon jet, elongated bowl, floor-mounted, floor outlet. Top of toilet seat height above floor shall be 14 to 15 inches, except 17 to 19 inches for wheelchair water closets. Provide wax bowl ring including plastic sleeve. Provide white solid plastic elongated open-front seat.

Water flushing volume of the water closet and flush valve combination shall not exceed 1.28 gallons per flush. Water closets must meet the EPA WaterSense product definition.

2.4.3 Flush Valve Urinals

ASME A112.19.2/CSA B45.1, white vitreous china, wall-mounted, wall outlet, siphon jet, integral trap, and extended side shields. Provide urinal with the rim 17 inches above the floor. Provide urinal with the rim 24 inches above the floor. Water flushing volume of the urinal and flush valve combination shall not exceed 0.5 gallons per flush.

2.4.4 Wall Hung Lavatories

ASME A112.19.2/CSA B45.1, white vitreous china, straight back type, minimum dimensions of 19 inches, wide by 17 inches front to rear, with

supply openings for use with top mounted centerset faucets, and openings for concealed arm carrier installation. Provide lavatory faucets and accessories meeting the flow rate and product requirements of the paragraph LAVATORIES.

2.4.5 Countertop Lavatories

ASME A112.19.2/CSA B45.1, white vitreous china, self-rimming, minimum dimensions of 19 inches wide by 17 inches front to rear, with supply openings for use with top mounted centerset faucets. Furnish template and mounting kit by lavatory manufacturer. Provide lavatory faucets and accessories meeting the flow rate and product requirements of the paragraph LAVATORIES.

2.4.6 Kitchen Sinks

ASME A112.19.3/CSA B45.4, 20 gage stainless steel with integral mounting rim for flush installation, minimum dimensions of 33 inches wide by 21 inches front to rear, two compartments, with undersides fully sound deadened, with supply openings for use with top mounted washerless sink faucets with hose spray, and with 3.5 inch drain outlet. Provide aerator with faucet. Water flow rate shall not exceed 2.2 gpm when measured at a flowing water pressure of 60 psi. Provide stainless steel drain outlets and stainless steel cup strainers. Provide separate 1.5 inch P-trap and drain piping to vertical vent piping from each compartment. Provide top mounted washerless sink faucets with hose spray.

2.4.7 Service Sinks

ASME A112.19.2/CSA B45.1, vitreous china ASME A112.19.3/CSA B45.4 302 stainless steel with integral back and wall hanger supports, minimum dimensions of 22 inches wide by 20 inches front to rear, with two supply openings in 10 inch high back. Provide floor supported wall outlet cast iron P-trap and stainless steel rim guards as recommended by service sink manufacturer. Provide back mounted washerless service sink faucets with vacuum breaker and 0.75 inch external hose threads.

2.5 BACKFLOW PREVENTERS

Backflow prevention devices must be approved by the State or local regulatory agencies. If there is no State or local regulatory agency requirements, the backflow prevention devices must be listed by the Foundation for Cross-Connection Control & Hydraulic Research, or any other approved testing laboratory having equivalent capabilities for both laboratory and field evaluation of backflow prevention devices and assemblies.

Reduced pressure principle assemblies, double check valve assemblies, atmospheric (nonpressure) type vacuum breakers, and pressure type vacuum breakers shall be meet the above requirements.

Backflow preventers with intermediate atmospheric vent shall conform to ASSE 1012. Reduced pressure principle backflow preventers shall conform to ASSE 1013. Hose connection vacuum breakers shall conform to ASSE 1011. Pipe applied atmospheric type vacuum breakers shall conform to ASSE 1001. Pressure vacuum breaker assembly shall conform to ASSE 1020. Air gaps in plumbing systems shall conform to ASME A112.1.2.

2.6 DRAINS

2.6.1 Floor Sinks

Floor sinks shall be square, with 12 inch nominal overall width or diameter and 10 inch nominal overall depth. Floor sink shall have an acid-resistant enamel interior finish with cast-iron body, ABS sediment bucket, and perforated grate of cast iron in industrial areas and stainless steel in finished areas. The outlet pipe size shall be as indicated or of the same size as the connecting pipe.

2.7 TRAPS

Unless otherwise specified, traps shall be copper-alloy adjustable tube type with slip joint inlet and swivel. Traps shall be without a cleanout.

Provide traps with removable access panels for easy clean-out at sinks and lavatories. Tubes shall be copper alloy with walls not less than 0.032 inch thick within commercial tolerances, except on the outside of bends where the thickness may be reduced slightly in manufacture by usual commercial methods. Inlets shall have rubber washer and copper alloy nuts for slip joints above the discharge level. Swivel joints shall be below the discharge level and shall be of metal-to-metal or metal-to-plastic type as required for the application. Nuts shall have flats for wrench grip. Outlets shall have internal pipe thread, except that when required for the application, the outlets shall have sockets for solder-joint connections. The depth of the water seal shall be not less than 2 inches. The interior diameter shall be not more than 1/8 inch over or under the nominal size, and interior surfaces shall be reasonably smooth throughout. A copper alloy "P" trap assembly consisting of an adjustable "P" trap and threaded trap wall nipple with cast brass wall flange shall be provided for lavatories. The assembly shall be a standard manufactured unit and may have a rubber-gasketed swivel joint.

2.8 MISCELLANEOUS PIPING ITEMS

2.8.1 Escutcheon Plates

Provide one piece or split hinge metal plates for piping entering floors, walls, and ceilings in exposed spaces. Provide chromium-plated on copper alloy plates or polished stainless steel finish in finished spaces. Provide paint finish on plates in unfinished spaces.

2.8.2 Pipe Sleeves

Provide where piping passes entirely through walls, ceilings, roofs, and floors. Sleeves are not required where drain, waste, and vent (DWV) piping passes through concrete floor slabs located on grade, except where penetrating a membrane waterproof floor.

2.8.2.1 Sleeves in Masonry and Concrete

Provide steel pipe sleeves or schedule 40 PVC plastic pipe sleeves. Sleeves are not required where drain, waste, and vent (DWV) piping passes through concrete floor slabs located on grade. Core drilling of masonry and concrete may be provided in lieu of pipe sleeves when cavities in the core-drilled hole are completely grouted smooth.

2.8.2.2 Sleeves Not in Masonry and Concrete

Provide 26 gage galvanized steel sheet or PVC plastic pipe sleeves.

2.8.3 Pipe Hangers (Supports)

Provide MSS SP-58 Type 1 with adjustable type steel support rods, except as specified or indicated otherwise. Attach to steel joists with Type 19 or 23 clamps and retaining straps. Attach to Steel W or S beams with Type 21, 28, 29, or 30 clamps. Attach to steel angles and vertical web steel channels with Type 20 clamp with beam clamp channel adapter. Attach to horizontal web steel channel and wood with drilled hole on centerline and double nut and washer. Attach to concrete with Type 18 insert or drilled expansion anchor. Provide Type 40 insulation protection shield for insulated piping.

2.8.4 Nameplates

Provide 0.125 inch thick melamine laminated plastic nameplates, black matte finish with white center core, for equipment, gages, thermometers, and valves; valves in supplies to faucets will not require nameplates. Accurately align lettering and engrave minimum of 0.25 inch high normal block lettering into the white core. Minimum size of nameplates shall be 1.0 by 2.5 inches. Key nameplates to a chart and schedule for each system. Frame charts and schedules under glass and place where directed near each system. Furnish two copies of each chart and schedule.

2.8.5 Labels

Provide labels for sensor operators at flush valves and faucets. Include the following information on each label:

- a. Identification of the sensor and its operation with written description.
- b. Range of the sensor.
- c. Battery replacement schedule.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Piping located in air plenums shall conform to NFPA 90A requirements. Piping located in shafts that constitute air ducts or that enclose air ducts shall be noncombustible in accordance with NFPA 90A. Installation of plastic pipe where in compliance with NFPA may be installed in accordance with PPFA Fire Man. The plumbing system shall be installed complete with necessary fixtures, fittings, traps, valves, and accessories. Water and drainage piping shall be extended 5 feet outside the building, unless otherwise indicated. A ball valve and drain shall be installed on the water service line inside the building approximately 6 inches above the floor from point of entry. Piping shall be connected to the exterior service lines or capped or plugged if the exterior service is not in place. Sewer and water pipes shall be laid in separate trenches, except when otherwise shown. Exterior underground utilities shall be at least 12 inches below the finish grade or as indicated on the drawings. If trenches are closed or the pipes are otherwise covered before being connected to the service lines, the location of the end of each plumbing

utility shall be marked with a stake or other acceptable means. Valves shall be installed with control no lower than the valve body.

3.1.1 Water Pipe, Fittings, and Connections

3.1.1.1 Utilities

The piping shall be extended to fixtures, outlets, and equipment. The hot-water and cold-water piping system shall be arranged and installed to permit draining. The supply line to each item of equipment or fixture, except faucets, flush valves, or other control valves which are supplied with integral stops, shall be equipped with a shutoff valve to enable isolation of the item for repair and maintenance without interfering with operation of other equipment or fixtures. Supply piping to fixtures, faucets, hydrants, shower heads, and flushing devices shall be anchored to prevent movement.

3.1.1.2 Cutting and Repairing

The work shall be carefully laid out in advance, and unnecessary cutting of construction shall be avoided. Damage to building, piping, wiring, or equipment as a result of cutting shall be repaired by mechanics skilled in the trade involved.

3.1.1.3 Protection of Fixtures, Materials, and Equipment

Pipe openings shall be closed with caps or plugs during installation. Fixtures and equipment shall be tightly covered and protected against dirt, water, chemicals, and mechanical injury. Upon completion of the work, the fixtures, materials, and equipment shall be thoroughly cleaned, adjusted, and operated. Safety guards shall be provided for exposed rotating equipment.

3.1.1.4 Mains, Branches, and Runouts

Piping shall be installed as indicated. Pipe shall be accurately cut and worked into place without springing or forcing. Structural portions of the building shall not be weakened. Aboveground piping shall run parallel with the lines of the building, unless otherwise indicated. Branch pipes from service lines may be taken from top, bottom, or side of main, using crossover fittings required by structural or installation conditions. Supply pipes, valves, and fittings shall be kept a sufficient distance from other work and other services to permit not less than 1/2 inch between finished covering on the different services. Bare and insulated water lines shall not bear directly against building structural elements so as to transmit sound to the structure or to prevent flexible movement of the lines. Water pipe shall not be buried in or under floors unless specifically indicated or approved. Changes in pipe sizes shall be made with reducing fittings. Use of bushings will not be permitted except for use in situations in which standard factory fabricated components are furnished to accommodate specific accepted installation practice. Change in direction shall be made with fittings, except that bending of pipe 4 inches and smaller will be permitted, provided a pipe bender is used and wide sweep bends are formed. The center-line radius of bends shall be not less than six diameters of the pipe. Bent pipe showing kinks, wrinkles, flattening, or other malformations will not be acceptable.

3.1.1.5 Pipe Drains

Pipe drains indicated shall consist of 3/4 inch hose bibb with renewable seat and ball valve ahead of hose bibb. At other low points, 3/4 inch brass plugs or caps shall be provided. Disconnection of the supply piping at the fixture is an acceptable drain.

3.1.1.6 Expansion and Contraction of Piping

Allowance shall be made throughout for expansion and contraction of water pipe. Each hot-water and hot-water circulation riser shall have expansion loops or other provisions such as offsets and changes in direction where indicated and required. Risers shall be securely anchored as required or where indicated to force expansion to loops. Branch connections from risers shall be made with ample swing or offset to avoid undue strain on fittings or short pipe lengths. Horizontal runs of pipe over 50 feet in length shall be anchored to the wall or the supporting construction about midway on the run to force expansion, evenly divided, toward the ends. Sufficient flexibility shall be provided on branch runouts from mains and risers to provide for expansion and contraction of piping. Flexibility shall be provided by installing one or more turns in the line so that piping will spring enough to allow for expansion without straining. If mechanical grooved pipe coupling systems are provided, the deviation from design requirements for expansion and contraction may be allowed pending approval of Contracting Officer.

3.1.1.7 Thrust Restraint

Plugs, caps, tees, valves and bends deflecting 11.25 degrees or more, either vertically or horizontally, in waterlines 4 inches in diameter or larger shall be provided with thrust blocks, where indicated, to prevent movement. Thrust blocking shall be concrete of a mix not leaner than: 1 cement, 2-1/2 sand, 5 gravel; and having a compressive strength of not less than 2000 psi after 28 days. Blocking shall be placed between solid ground and the fitting to be anchored. Unless otherwise indicated or directed, the base and thrust bearing sides of the thrust block shall be poured against undisturbed earth. The side of the thrust block not subject to thrust shall be poured against forms. The area of bearing will be as shown. Blocking shall be placed so that the joints of the fitting are accessible for repair. Steel rods and clamps, protected by galvanizing or by coating with bituminous paint, shall be used to anchor vertical down bends into gravity thrust blocks.

3.1.1.8 Commercial-Type Water Hammer Arresters

Commercial-type water hammer arresters shall be provided on hot- and cold-water supplies and shall be located as generally indicated, with precise location and sizing to be in accordance with PDI WH 201. Water hammer arresters, where concealed, shall be accessible by means of access doors or removable panels. Commercial-type water hammer arresters shall conform to ASSE 1010. Vertical capped pipe columns will not be permitted.

3.1.2 Joints

Installation of pipe and fittings shall be made in accordance with the manufacturer's recommendations. Mitering of joints for elbows and notching of straight runs of pipe for tees will not be permitted. Joints shall be made up with fittings of compatible material and made for the specific purpose intended.

3.1.2.1 Threaded

Threaded joints shall have American Standard taper pipe threads conforming to ASME B1.20.1. Only male pipe threads shall be coated with graphite or with an approved graphite compound, or with an inert filler and oil, or shall have a polytetrafluoroethylene tape applied.

3.1.2.2 Mechanical Couplings

Mechanical couplings may be used in conjunction with grooved pipe for aboveground, ferrous or non-ferrous, domestic hot and cold water systems, in lieu of unions, brazed, soldered, welded, flanged, or threaded joints.

Mechanical couplings are permitted in accessible locations including behind access plates. Flexible grooved joints will not be permitted, except as vibration isolators adjacent to mechanical equipment. Rigid grooved joints shall incorporate an angle bolt pad design which maintains metal-to-metal contact with equal amount of pad offset of housings upon installation to ensure positive rigid clamping of the pipe.

Designs which can only clamp on the bottom of the groove or which utilize gripping teeth or jaws, or which use misaligned housing bolt holes, or which require a torque wrench or torque specifications will not be permitted.

Grooved fittings and couplings, and grooving tools shall be provided from the same manufacturer. Segmentally welded elbows shall not be used. Grooves shall be prepared in accordance with the coupling manufacturer's latest published standards. Grooving shall be performed by qualified grooving operators having demonstrated proper grooving procedures in accordance with the tool manufacturer's recommendations.

The Contracting Officer shall be notified 24 hours in advance of test to demonstrate operator's capability, and the test shall be performed at the work site, if practical, or at a site agreed upon. The operator shall demonstrate the ability to properly adjust the grooving tool, groove the pipe, and to verify the groove dimensions in accordance with the coupling manufacturer's specifications.

3.1.2.3 Unions and Flanges

Unions, flanges and mechanical couplings shall not be concealed in walls, ceilings, or partitions. Unions shall be used on pipe sizes 2-1/2 inches and smaller; flanges shall be used on pipe sizes 3 inches and larger.

3.1.2.4 Grooved Mechanical Joints

Grooves shall be prepared according to the coupling manufacturer's instructions. Grooved fittings, couplings, and grooving tools shall be products of the same manufacturer. Pipe and groove dimensions shall comply with the tolerances specified by the coupling manufacturer. The diameter of grooves made in the field shall be measured using a "go/no-go" gauge, vernier or dial caliper, narrow-land micrometer, or other method specifically approved by the coupling manufacturer for the intended application. Groove width and dimension of groove from end of pipe shall be measured and recorded for each change in grooving tool setup to verify compliance with coupling manufacturer's tolerances. Grooved joints shall not be used in concealed locations.

3.1.2.5 Cast Iron Soil, Waste and Vent Pipe

Bell and spigot compression and hubless gasketed clamp joints for soil, waste and vent piping shall be installed per the manufacturer's recommendations.

3.1.2.6 Copper Tube and Pipe

- a. Brazed. Brazed joints shall be made in conformance with AWS B2.2/B2.2M, ASME B16.50, and CDA A4015 with flux and are acceptable for all pipe sizes. Copper to copper joints shall include the use of copper-phosphorus or copper-phosphorus-silver brazing metal without flux. Brazing of dissimilar metals (copper to bronze or brass) shall include the use of flux with either a copper-phosphorus, copper-phosphorus-silver or a silver brazing filler metal.
- b. Soldered. Soldered joints shall be made with flux and are only acceptable for piping 2 inches and smaller. Soldered joints shall conform to ASME B31.5 and CDA A4015. Soldered joints shall not be used in compressed air piping between the air compressor and the receiver.
- c. Copper Tube Extracted Joint. Mechanically extracted joints shall be made in accordance with ICC IPC.
- d. Press connection. Copper press connections shall be made in **strict** accordance with the manufacturer's installation instructions for manufactured rated size. The joints shall be pressed using the tool(s) approved by the manufacturer **of that joint**. Minimum distance between fittings shall be in accordance with the manufacturer's requirements.

3.1.2.7 Other Joint Methods

3.1.3 Dissimilar Pipe Materials

Connections between ferrous and non-ferrous copper water pipe shall be made with dielectric unions or flange waterways. Dielectric waterways shall have temperature and pressure rating equal to or greater than that specified for the connecting piping. Waterways shall have metal connections on both ends suited to match connecting piping. Dielectric waterways shall be internally lined with an insulator specifically designed to prevent current flow between dissimilar metals. Dielectric flanges shall meet the performance requirements described herein for dielectric waterways. Connecting joints between plastic and metallic pipe shall be made with transition fitting for the specific purpose.

3.1.4 Pipe Sleeves and Flashing

Pipe sleeves shall be furnished and set in their proper and permanent location.

3.1.4.1 Sleeve Requirements

Unless indicated otherwise, provide pipe sleeves meeting the following requirements:

Secure sleeves in position and location during construction. Provide

sleeves of sufficient length to pass through entire thickness of walls, ceilings, roofs, and floors.

A modular mechanical type sealing assembly may be installed in lieu of a waterproofing clamping flange and caulking and sealing of annular space between pipe and sleeve. The seals shall consist of interlocking synthetic rubber links shaped to continuously fill the annular space between the pipe and sleeve using galvanized steel bolts, nuts, and pressure plates. The links shall be loosely assembled with bolts to form a continuous rubber belt around the pipe with a pressure plate under each bolt head and each nut. After the seal assembly is properly positioned in the sleeve, tightening of the bolt shall cause the rubber sealing elements to expand and provide a watertight seal between the pipe and the sleeve. Each seal assembly shall be sized as recommended by the manufacturer to fit the pipe and sleeve involved.

Sleeves shall not be installed in structural members, except where indicated or approved. Rectangular and square openings shall be as detailed. Each sleeve shall extend through its respective floor, or roof, and shall be cut flush with each surface, except for special circumstances. Pipe sleeves passing through floors in wet areas such as mechanical equipment rooms, lavatories, kitchens, and other plumbing fixture areas shall extend a minimum of 4 inches above the finished floor.

Unless otherwise indicated, sleeves shall be of a size to provide a minimum of 1/4 inch clearance between bare pipe or insulation and inside of sleeve or between insulation and inside of sleeve. Sleeves in bearing walls and concrete slab on grade floors shall be steel pipe or cast-iron pipe. Sleeves in nonbearing walls or ceilings may be steel pipe, cast-iron pipe, galvanized sheet metal with lock-type longitudinal seam, or plastic.

Except as otherwise specified, the annular space between pipe and sleeve, or between jacket over insulation and sleeve, shall be sealed as indicated with sealants conforming to ASTM C920 and with a primer, backstop material and surface preparation as specified in Section 07 92 00 JOINT SEALANTS. The annular space between pipe and sleeve, between bare insulation and sleeve or between jacket over insulation and sleeve shall not be sealed for interior walls which are not designated as fire rated.

Sleeves through below-grade walls in contact with earth shall be recessed 1/2 inch from wall surfaces on both sides. Annular space between pipe and sleeve shall be filled with backing material and sealants in the joint between the pipe and masonry wall as specified above. Sealant selected for the earth side of the wall shall be compatible with dampproofing/waterproofing materials that are to be applied over the joint sealant. Pipe sleeves in fire-rated walls shall conform to the requirements in Section 07 84 00 FIRESTOPPING.

3.1.4.2 Flashing Requirements

Pipes passing through roof shall be installed through a 16 ounce copper flashing, each within an integral skirt or flange. Flashing shall be suitably formed, and the skirt or flange shall extend not less than 8 inches from the pipe and shall be set over the roof or floor membrane in a solid coating of bituminous cement. The flashing shall extend up the pipe a minimum of 10 inches. For cleanouts, the flashing shall be turned down into the hub and caulked after placing the ferrule. Pipes passing through pitched roofs shall be flashed, using lead or copper flashing, with an

adjustable integral flange of adequate size to extend not less than 8 inches from the pipe in all directions and lapped into the roofing to provide a watertight seal. The annular space between the flashing and the bare pipe or between the flashing and the metal-jacket-covered insulation shall be sealed as indicated. Flashing for dry vents shall be turned down into the pipe to form a waterproof joint. Pipes, up to and including 10 inches in diameter, passing through roof or floor waterproofing membrane may be installed through a cast-iron sleeve with caulking recess, anchor lugs, flashing-clamp device, and pressure ring with brass bolts. Flashing shield shall be fitted into the sleeve clamping device. Pipes passing through wall waterproofing membrane shall be sleeved as described above. A waterproofing clamping flange shall be installed.

3.1.4.3 Waterproofing

Waterproofing at floor-mounted water closets shall be accomplished by forming a flashing guard from soft-tempered sheet copper. The center of the sheet shall be perforated and turned down approximately 1-1/2 inches to fit between the outside diameter of the drainpipe and the inside diameter of the cast-iron or steel pipe sleeve. The turned-down portion of the flashing guard shall be embedded in sealant to a depth of approximately 1-1/2 inches; then the sealant shall be finished off flush to floor level between the flashing guard and drainpipe. The flashing guard of sheet copper shall extend not less than 8 inches from the drainpipe and shall be lapped between the floor membrane in a solid coating of bituminous cement. If cast-iron water closet floor flanges are used, the space between the pipe sleeve and drainpipe shall be sealed with sealant and the flashing guard shall be upturned approximately 1-1/2 inches to fit the outside diameter of the drainpipe and the inside diameter of the water closet floor flange. The upturned portion of the sheet fitted into the floor flange shall be sealed.

3.1.4.4 Optional Counterflashing

Instead of turning the flashing down into a dry vent pipe, or caulking and sealing the annular space between the pipe and flashing or metal-jacket-covered insulation and flashing, counterflashing may be accomplished by utilizing the following:

- a. A standard roof coupling for threaded pipe up to 6 inches in diameter.
- b. A tack-welded or banded-metal rain shield around the pipe.

3.1.4.5 Pipe Penetrations of Slab on Grade Floors

Where pipes, fixture drains, floor drains, cleanouts or similar items penetrate slab on grade floors, except at penetrations of floors with waterproofing membrane as specified in paragraphs FLASHING REQUIREMENTS and WATERPROOFING, a groove 1/4 to 1/2 inch wide by 1/4 to 3/8 inch deep shall be formed around the pipe, fitting or drain. The groove shall be filled with a sealant as specified in Section 07 92 00 JOINT SEALANTS.

3.1.4.6 Pipe Penetrations

Provide sealants for all pipe penetrations. All pipe penetrations shall be sealed to prevent infiltration of air, insects, and vermin.

3.1.5 Fire Seal

Where pipes pass through fire walls, fire-partitions, fire-rated pipe chase walls or floors above grade, a fire seal shall be provided as specified in Section 07 84 00 FIRESTOPPING.

3.1.6 Supports

3.1.6.1 General

Hangers used to support piping 2 inches and larger shall be fabricated to permit adequate adjustment after erection while still supporting the load. Pipe guides and anchors shall be installed to keep pipes in accurate alignment, to direct the expansion movement, and to prevent buckling, swaying, and undue strain. Piping subjected to vertical movement when operating temperatures exceed ambient temperatures shall be supported by variable spring hangers and supports or by constant support hangers. In the support of multiple pipe runs on a common base member, a clip or clamp shall be used where each pipe crosses the base support member. Spacing of the base support members shall not exceed the hanger and support spacing required for an individual pipe in the multiple pipe run. Threaded sections of rods shall not be formed or bent.

3.1.6.2 Pipe Hangers, Inserts, and Supports

Installation of pipe hangers, inserts and supports shall conform to MSS SP-58 except as modified herein.

- a. Types 5, 12, and 26 shall not be used.
- b. Type 3 shall not be used on insulated pipe.
- c. Type 18 inserts shall be secured to concrete forms before concrete is placed. Continuous inserts which allow more adjustment may be used if they otherwise meet the requirements for type 18 inserts.
- d. Type 19 and 23 C-clamps shall be torqued per MSS SP-58 and shall have both locknuts and retaining devices furnished by the manufacturer. Field-fabricated C-clamp bodies or retaining devices are not acceptable.
- e. Type 20 attachments used on angles and channels shall be furnished with an added malleable-iron heel plate or adapter.
- f. Type 24 may be used only on trapeze hanger systems or on fabricated frames.
- g. Type 39 saddles shall be used on insulated pipe 4 inches and larger when the temperature of the medium is 60 degrees F or higher. Type 39 saddles shall be welded to the pipe.
- h. Type 40 shields shall:
 - (1) Be used on insulated pipe less than 4 inches.
 - (2) Be used on insulated pipe 4 inches and larger when the temperature of the medium is 60 degrees F or less.
 - (3) Have a high density insert for all pipe sizes. High density

inserts shall have a density of 8 pcf or greater.

- i. Horizontal pipe supports shall be spaced as specified in MSS SP-58 and a support shall be installed not over 1 foot from the pipe fitting joint at each change in direction of the piping. Pipe supports shall be spaced not over 5 feet apart at valves. Operating temperatures in determining hanger spacing for PVC or CPVC pipe shall be 120 degrees F for PVC and 180 degrees F for CPVC. Horizontal pipe runs shall include allowances for expansion and contraction.
- j. Vertical pipe shall be supported at each floor, except at slab-on-grade, at intervals of not more than 15 feet nor more than 8 feet from end of risers, and at vent terminations. Vertical pipe risers shall include allowances for expansion and contraction.
- k. Type 35 guides using steel, reinforced polytetrafluoroethylene (PTFE) or graphite slides shall be provided to allow longitudinal pipe movement. Slide materials shall be suitable for the system operating temperatures, atmospheric conditions, and bearing loads encountered. Lateral restraints shall be provided as needed. Where steel slides do not require provisions for lateral restraint the following may be used:
 - (1) On pipe 4 inches and larger when the temperature of the medium is 60 degrees F or higher, a Type 39 saddle, welded to the pipe, may freely rest on a steel plate.
 - (2) On pipe less than 4 inches a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.
 - (3) On pipe 4 inches and larger carrying medium less than 60 degrees F a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.
- l. Pipe hangers on horizontal insulated pipe shall be the size of the outside diameter of the insulation. The insulation shall be continuous through the hanger on all pipe sizes and applications.
- m. Where there are high system temperatures and welding to piping is not desirable, the type 35 guide shall include a pipe cradle, welded to the guide structure and strapped securely to the pipe. The pipe shall be separated from the slide material by at least 4 inches or by an amount adequate for the insulation, whichever is greater.
- n. Hangers and supports for plastic pipe shall not compress, distort, cut or abrade the piping, and shall allow free movement of pipe except where otherwise required in the control of expansion/contraction.

3.1.6.3 Structural Attachments

Attachment to building structure concrete and masonry shall be by cast-in concrete inserts, built-in anchors, or masonry anchor devices. Inserts and anchors shall be applied with a safety factor not less than 5. Supports shall not be attached to metal decking. Supports shall not be attached to the underside of concrete filled floor or concrete roof decks unless approved by the Contracting Officer. Masonry anchors for overhead applications shall be constructed of ferrous materials only.

3.1.7 Welded Installation

Plumbing pipe weldments shall be as indicated. Changes in direction of piping shall be made with welding fittings only; mitering or notching pipe to form elbows and tees or other similar type construction will not be permitted. Branch connection may be made with either welding tees or forged branch outlet fittings. Branch outlet fittings shall be forged, flared for improvement of flow where attached to the run, and reinforced against external strains. Beveling, alignment, heat treatment, and inspection of weld shall conform to ASME B31.1. Weld defects shall be removed and repairs made to the weld, or the weld joints shall be entirely removed and rewelded. After filler metal has been removed from its original package, it shall be protected or stored so that its characteristics or welding properties are not affected. Electrodes that have been wetted or that have lost any of their coating shall not be used.

3.1.8 Pipe Cleanouts

Pipe cleanouts shall be the same size as the pipe except that cleanout plugs larger than 4 inches will not be required. A cleanout installed in connection with cast-iron soil pipe shall consist of a long-sweep 1/4 bend or one or two 1/8 bends extended to the place shown. An extra-heavy cast-brass or cast-iron ferrule with countersunk cast-brass head screw plug shall be caulked into the hub of the fitting and shall be flush with the floor. Cleanouts in connection with other pipe, where indicated, shall be T-pattern, 90-degree branch drainage fittings with cast-brass screw plugs, except plastic plugs shall be installed in plastic pipe. Plugs shall be the same size as the pipe up to and including 4 inches. Cleanout tee branches with screw plug shall be installed at the foot of soil and waste stacks, at the foot of interior downspouts, on each connection to building storm drain where interior downspouts are indicated, and on each building drain outside the building. Cleanout tee branches may be omitted on stacks in single story buildings with slab-on-grade construction or where less than 18 inches of crawl space is provided under the floor. Cleanouts on pipe concealed in partitions shall be provided with chromium plated bronze, nickel bronze, nickel brass or stainless steel flush type access cover plates. Round access covers shall be provided and secured to plugs with securing screw. Square access covers may be provided with matching frames, anchoring lugs and cover screws. Cleanouts in finished walls shall have access covers and frames installed flush with the finished wall. Cleanouts installed in finished floors subject to foot traffic shall be provided with a chrome-plated cast brass, nickel brass, or nickel bronze cover secured to the plug or cover frame and set flush with the finished floor. Heads of fastening screws shall not project above the cover surface. Where cleanouts are provided with adjustable heads, the heads shall be cast iron .

3.2 FIXTURES AND FIXTURE TRIMMINGS

Polished chromium-plated pipe, valves, and fittings shall be provided where exposed to view. Angle stops, straight stops, stops integral with the faucets, or concealed type of lock-shield, and loose-key pattern stops for supplies with threaded, sweat or solvent weld inlets shall be furnished and installed with fixtures. Where connections between copper tubing and faucets are made by rubber compression fittings, a beading tool shall be used to mechanically deform the tubing above the compression fitting. Exposed traps and supply pipes for fixtures and equipment shall be connected to the rough piping systems at the wall, unless otherwise specified under the item. Floor and wall escutcheons shall be as

specified. Drain lines and hot water lines of fixtures for handicapped personnel shall be insulated and do not require polished chrome finish. Plumbing fixtures and accessories shall be installed within the space shown.

3.2.1 Fixture Connections

Where space limitations prohibit standard fittings in conjunction with the cast-iron floor flange, special short-radius fittings shall be provided. Connections between earthenware fixtures and flanges on soil pipe shall be made gastight and watertight with a closet-setting compound or neoprene gasket and seal. Use of natural rubber gaskets or putty will not be permitted. Fixtures with outlet flanges shall be set the proper distance from floor or wall to make a first-class joint with the closet-setting compound or gasket and fixture used.

3.2.2 Height of Fixture Rims Above Floor

Lavatories shall be mounted with rim 31 inches above finished floor. Wall-hung drinking fountains and water coolers shall be installed with rim 42 inches above floor. Wall-hung service sinks shall be mounted with rim 28 inches above the floor. Installation of fixtures for use by the physically handicapped shall be in accordance with ICC A117.1 COMM.

3.2.3 Fixture Supports

Fixture supports for off-the-floor lavatories, urinals, water closets, and other fixtures of similar size, design, and use, shall be of the chair-carrier type. The carrier shall provide the necessary means of mounting the fixture, with a foot or feet to anchor the assembly to the floor slab. Adjustability shall be provided to locate the fixture at the desired height and in proper relation to the wall. Support plates, in lieu of chair carrier, shall be fastened to the wall structure only where it is not possible to anchor a floor-mounted chair carrier to the floor slab.

3.2.3.1 Support for Solid Masonry Construction

Chair carrier shall be anchored to the floor slab. Where a floor-anchored chair carrier cannot be used, a suitable wall plate shall be imbedded in the masonry wall.

3.2.3.2 Support for Concrete-Masonry Wall Construction

Chair carrier shall be anchored to floor slab. Where a floor-anchored chair carrier cannot be used, a suitable wall plate shall be fastened to the concrete wall using through bolts and a back-up plate.

3.2.3.3 Support for Steel Stud Frame Partitions

Chair carrier shall be used. The anchor feet and tubular uprights shall be of the heavy duty design; and feet (bases) shall be steel and welded to a square or rectangular steel tube upright. Wall plates, in lieu of floor-anchored chair carriers, shall be used only if adjoining steel partition studs are suitably reinforced to support a wall plate bolted to these studs.

3.2.3.4 Support for Wood Stud Construction

Where floor is a concrete slab, a floor-anchored chair carrier shall be used. Where entire construction is wood, wood crosspieces shall be installed. Fixture hanger plates, supports, brackets, or mounting lugs shall be fastened with not less than No. 10 wood screws, 1/4 inch thick minimum steel hanger, or toggle bolts with nut. The wood crosspieces shall extend the full width of the fixture and shall be securely supported.

3.2.4 Backflow Prevention Devices

Plumbing fixtures, equipment, and pipe connections shall not cross connect or interconnect between a potable water supply and any source of nonpotable water. Backflow preventers shall be installed where indicated and in accordance with ICC IPC at all other locations necessary to preclude a cross-connect or interconnect between a potable water supply and any nonpotable substance. In addition backflow preventers shall be installed at all locations where the potable water outlet is below the flood level of the equipment, or where the potable water outlet will be located below the level of the nonpotable substance. Backflow preventers shall be located so that no part of the device will be submerged. Backflow preventers shall be of sufficient size to allow unrestricted flow of water to the equipment, and preclude the backflow of any nonpotable substance into the potable water system. Bypass piping shall not be provided around backflow preventers. Access shall be provided for maintenance and testing. Each device shall be a standard commercial unit.

3.2.5 Access Panels

Access panels shall be provided for concealed valves and controls, or any item requiring inspection or maintenance. Access panels shall be of sufficient size and located so that the concealed items may be serviced, maintained, or replaced.

3.2.6 Traps

Each trap shall be placed as near the fixture as possible, and no fixture shall be double-trapped. Traps installed on cast-iron soil pipe shall be cast iron. Traps installed on steel pipe or copper tubing shall be recess-drainage pattern, or brass-tube type. Traps installed on plastic pipe may be plastic conforming to ASTM D3311. Traps for acid-resisting waste shall be of the same material as the pipe.

3.3 IDENTIFICATION SYSTEMS

3.3.1 Identification Tags

Identification tags made of brass, engraved laminated plastic, or engraved anodized aluminum, indicating service and valve number shall be installed on valves, except those valves installed on supplies at plumbing fixtures. Tags shall be 1-3/8 inch minimum diameter, and marking shall be stamped or engraved. Indentations shall be black, for reading clarity. Tags shall be attached to valves with No. 12 AWG, copper wire, chrome-plated beaded chain, or plastic straps designed for that purpose.

3.3.2 Pipe Color Code Marking

Color code marking of piping shall be as specified in Section 09 90 00 PAINTS AND COATINGS.

3.3.3 Color Coding Scheme for Locating Hidden Utility Components

Scheme shall be provided in buildings having suspended grid ceilings. The color coding scheme shall identify points of access for maintenance and operation of operable components which are not visible from the finished space and installed in the space directly above the suspended grid ceiling. The operable components shall include valves, dampers, switches, linkages and thermostats. The color coding scheme shall consist of a color code board and colored metal disks. Each colored metal disk shall be approximately 3/8 inch in diameter and secured to removable ceiling panels with fasteners. The fasteners shall be inserted into the ceiling panels so that the fasteners will be concealed from view. The fasteners shall be manually removable without tools and shall not separate from the ceiling panels when panels are dropped from ceiling height. Installation of colored metal disks shall follow completion of the finished surface on which the disks are to be fastened. The color code board shall have the approximate dimensions of 3 foot width, 30 inches height, and 1/2 inch thickness. The board shall be made of wood fiberboard and framed under glass or 1/16 inch transparent plastic cover. Unless otherwise directed, the color code symbols shall be approximately 3/4 inch in diameter and the related lettering in 1/2 inch high capital letters. The color code board shall be mounted and located in the mechanical or equipment room. The color code system shall be as indicated below:

Color	System	Item	Location

3.4 ESCUTCHEONS

Escutcheons shall be provided at finished surfaces where bare or insulated piping, exposed to view, passes through floors, walls, or ceilings, except in boiler, utility, or equipment rooms. Escutcheons shall be fastened securely to pipe or pipe covering and shall be satin-finish, corrosion-resisting steel, polished chromium-plated zinc alloy, or polished chromium-plated copper alloy. Escutcheons shall be either one-piece or split-pattern, held in place by internal spring tension or setscrew.

3.5 PAINTING

Painting of pipes, hangers, supports, and other iron work, either in concealed spaces or exposed spaces, is specified in Section 09 90 00 PAINTS AND COATINGS.

3.5.1 Painting of New Equipment

New equipment painting shall be factory applied or shop applied, and shall be as specified herein, and provided under each individual section.

3.5.1.1 Factory Painting Systems

Manufacturer's standard factory painting systems may be provided subject to certification that the factory painting system applied will withstand 125 hours in a salt-spray fog test, except that equipment located outdoors shall withstand 500 hours in a salt-spray fog test. Salt-spray fog test shall be in accordance with ASTM B117, and for that test the acceptance criteria shall be as follows: immediately after completion of the test,

the paint shall show no signs of blistering, wrinkling, or cracking, and no loss of adhesion; and the specimen shall show no signs of rust creepage beyond 0.125 inch on either side of the scratch mark.

The film thickness of the factory painting system applied on the equipment shall not be less than the film thickness used on the test specimen. If manufacturer's standard factory painting system is being proposed for use on surfaces subject to temperatures above 120 degrees F, the factory painting system shall be designed for the temperature service.

3.5.1.2 Shop Painting Systems for Metal Surfaces

Clean, pretreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and solvent degreasing prior to application of paint, except metal surfaces subject to temperatures in excess of 120 degrees F shall be cleaned to bare metal.

Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Color of finish coat shall be aluminum or light gray.

- a. Temperatures Less Than 120 Degrees F: Immediately after cleaning, the metal surfaces subject to temperatures less than 120 degrees F shall receive one coat of pretreatment primer applied to a minimum dry film thickness of 0.3 mil, one coat of primer applied to a minimum dry film thickness of one mil; and two coats of enamel applied to a minimum dry film thickness of one mil per coat.
- b. Temperatures Between 120 and 400 Degrees F: Metal surfaces subject to temperatures between 120 and 400 degrees F shall receive two coats of 400 degrees F heat-resisting enamel applied to a total minimum thickness of 2 mils.
- c. Temperatures Greater Than 400 Degrees F: Metal surfaces subject to temperatures greater than 400 degrees F shall receive two coats of 600 degrees F heat-resisting paint applied to a total minimum dry film thickness of 2 mils.

3.6 TESTS, FLUSHING AND DISINFECTION

3.6.1 Plumbing System

The following tests shall be performed on the plumbing system in accordance with ICC IPC, except that the drainage and vent system final test shall include the smoke test. The Contractor has the option to perform a peppermint test in lieu of the smoke test. If a peppermint test is chosen, the Contractor must submit a testing procedure and reasons for choosing this option in lieu of the smoke test to the Contracting Officer for approval.

- a. Drainage and Vent Systems Test. The final test shall include a smoke test.
- b. Building Sewers Tests.

c. Water Supply Systems Tests.

3.6.1.1 Test of Backflow Prevention Assemblies

Backflow prevention assembly shall be tested using gauges specifically designed for the testing of backflow prevention assemblies.

Backflow prevention assembly test gauges shall be tested annually for accuracy in accordance with the requirements of State or local regulatory agencies. If there is no State or local regulatory agency requirements, gauges shall be tested annually for accuracy in accordance with the requirements of University of Southern California's Foundation of Cross Connection Control and Hydraulic Research or the American Water Works Association Manual of Cross Connection (Manual M-14), or any other approved testing laboratory having equivalent capabilities for both laboratory and field evaluation of backflow prevention assembly test gauges. Report form for each assembly shall include, as a minimum, the following:

Data on Device	Data on Testing Firm
Type of Assembly	Name
Manufacturer	Address
Model Number	Certified Tester
Serial Number	Certified Tester No.
Size	Date of Test
Location	
Test Pressure Readings	Serial Number and Test Data of Gauges

If the unit fails to meet specified requirements, the unit shall be repaired and retested.

3.6.2 Defective Work

If inspection or test shows defects, such defective work or material shall be replaced or repaired as necessary and inspection and tests shall be repeated. Repairs to piping shall be made with new materials. Caulking of screwed joints or holes will not be acceptable.

3.6.3 System Flushing

3.6.3.1 During Flushing

Before operational tests or disinfection, potable water piping system shall be flushed with potable water. Sufficient water shall be used to produce a water velocity that is capable of entraining and removing debris in all portions of the piping system. This requires simultaneous operation of all fixtures on a common branch or main in order to produce a flushing velocity of approximately 4 fps through all portions of the piping system. In the event that this is impossible due to size of system, the Contracting Officer (or the designated representative) shall

specify the number of fixtures to be operated during flushing. Contractor shall provide adequate personnel to monitor the flushing operation and to ensure that drain lines are unobstructed in order to prevent flooding of the facility. Contractor shall be responsible for any flood damage resulting from flushing of the system. Flushing shall be continued until entrained dirt and other foreign materials have been removed and until discharge water shows no discoloration. All faucets and drinking water fountains, to include any device considered as an end point device by NSF/ANSI 61, Section 9, shall be flushed a minimum of 0.25 gallons per 24 hour period, ten times over a 14 day period.

3.6.3.2 After Flushing

System shall be drained at low points. Strainer screens shall be removed, cleaned, and replaced. After flushing and cleaning, systems shall be prepared for testing by immediately filling water piping with clean, fresh potable water. Any stoppage, discoloration, or other damage to the finish, furnishings, or parts of the building due to the Contractor's failure to properly clean the piping system shall be repaired by the Contractor. When the system flushing is complete, the hot-water system shall be adjusted for uniform circulation. Flushing devices and automatic control systems shall be adjusted for proper operation according to manufacturer's instructions. Flow rates on fixtures must not exceed those stated in PART 2 of this Section. Unless more stringent local requirements exist, lead levels shall not exceed limits established by 40 CFR 141.80 (c)(1). The water supply to the building shall be tested separately to ensure that any lead contamination found during potable water system testing is due to work being performed inside the building.

3.6.4 Operational Test

Upon completion of flushing and prior to disinfection procedures, the Contractor shall subject the plumbing system to operating tests to demonstrate satisfactory installation, connections, adjustments, and functional and operational efficiency. Such operating tests shall cover a period of not less than 8 hours for each system and shall include the following information in a report with conclusion as to the adequacy of the system:

- a. Time, date, and duration of test.
- b. Water pressures at the most remote and the highest fixtures.
- c. Operation of each fixture and fixture trim.
- d. Operation of each valve, hydrant, and faucet.
- e. Pump suction and discharge pressures.
- f. Temperature of each domestic hot-water supply.
- g. Operation of each floor and roof drain by flooding with water.
- h. Operation of each vacuum breaker and backflow preventer.
- i. Complete operation of each water pressure booster system, including pump start pressure and stop pressure.
- j. Compressed air readings at each compressor and at each outlet. Each

indicating instrument shall be read at 1/2 hour intervals. The report of the test shall be submitted in quadruplicate. The Contractor shall furnish instruments, equipment, and personnel required for the tests; the Government will furnish the necessary water and electricity.

3.6.5 Disinfection

After all system components are provided and operational tests are complete, the entire domestic hot- and cold-water distribution system shall be disinfected. Before introducing disinfecting chlorination material, entire system shall be flushed with potable water until any entrained dirt and other foreign materials have been removed.

Water chlorination procedure shall be in accordance with AWWA C651 and AWWA C652 as modified and supplemented by this specification. The chlorinating material shall be hypochlorites or liquid chlorine. The chlorinating material shall be fed into the water piping system at a constant rate at a concentration of at least 50 parts per million (ppm). Feed a properly adjusted hypochlorite solution injected into the system with a hypochlorinator, or inject liquid chlorine into the system through a solution-feed chlorinator and booster pump until the entire system is completely filled.

Test the chlorine residual level in the water at 6 hour intervals for a continuous period of 24 hours. If at the end of a 6 hour interval, the chlorine residual has dropped to less than 25 ppm, flush the piping including tanks with potable water, and repeat the above chlorination procedures. During the chlorination period, each valve and faucet shall be opened and closed several times.

After the second 24 hour period, verify that no less than 25 ppm chlorine residual remains in the treated system. The 24 hour chlorination procedure must be repeated until no less than 25 ppm chlorine residual remains in the treated system.

Upon the specified verification, the system including tanks shall then be flushed with potable water until the residual chlorine level is reduced to less than one part per million. During the flushing period, each valve and faucet shall be opened and closed several times.

Take additional samples of water in disinfected containers, for bacterial examination, at locations specified by the Contracting Officer

Test these samples for total coliform organisms (coliform bacteria, fecal coliform, streptococcal, and other bacteria) in accordance with AWWA 10084. The testing method used shall be EPA approved for drinking water systems and shall comply with applicable local and state requirements.

Disinfection shall be repeated until bacterial tests indicate the absence of coliform organisms (zero mean coliform density per 100 milliliters) in the samples for at least 2 full days. The system will not be accepted until satisfactory bacteriological results have been obtained.

3.7 POSTED INSTRUCTIONS

Framed instructions under glass or in laminated plastic, including wiring

and control diagrams showing the complete layout of the entire system, shall be posted where directed. Condensed operating instructions explaining preventive maintenance procedures, methods of checking the system for normal safe operation, and procedures for safely starting and stopping the system shall be prepared in typed form, framed as specified above for the wiring and control diagrams and posted beside the diagrams. The framed instructions shall be posted before acceptance testing of the systems.

3.8 PERFORMANCE OF WATER HEATING EQUIPMENT

Standard rating condition terms are as follows:

EF = Energy factor, minimum overall efficiency.

ET = Minimum thermal efficiency with 70 degrees F delta T.

SL = Standby loss is maximum (Btu/h) based on a 70 degrees F temperature difference between stored water and ambient requirements.

V = Rated volume in gallons

Q = Nameplate input rate in kW (Btu/h)

3.8.1 Storage Water Heaters

3.8.1.1 Electric

- a. Storage capacity of 60 gallons shall have a minimum energy factor (EF) of 0.93 or higher per FEMP requirements.
- b. Storage capacity of 60 gallons or more shall have a minimum energy factor (EF) of 0.91 or higher per FEMP requirements.

3.8.1.2 Gas

- a. Storage capacity of 50 gallons or less shall have a minimum energy factor (EF) of 0.67 or higher per FEMP requirements.
- b. Storage capacity of 20 gallons - or more and input rating of 75,000 Btu/h or less: minimum EF shall be 0.62 - 0.0019V per 10 CFR 430.
- c. Rating of less than 22980 W: (75,000 Btu/h) ET shall be 80 percent; maximum SL shall be $(Q/800+110x(V^{1/2}))$, per ANSI Z21.10.3/CSA 4.3

3.8.1.3 Oil

- a. Storage capacity of 20 gallons or more and input rating of 105,000 Btu/h or less: minimum EF shall be 0.59-0.0019V per 10 CFR 430.
- b. Rating of less than 4,000 Btu/h/gallon or input rating more than 105,000 Btu/h: ET shall be 78 percent; maximum SL shall be $(Q/800+100x(V^{1/2}))$, per ANSI Z21.10.3/CSA 4.3.

3.8.2 Unfired Hot Water Storage

All volumes and inputs: shall meet or exceed R-12.5.

3.8.3 Pool Heaters

- a. Gas/oil fuel, capacities and inputs: ET shall be 78 percent per ASHRAE 146.
- b. Heat Pump, All capacities and inputs shall meet a COP of 4.0 per ASHRAE 146

3.9 TABLES

TABLE I								
PIPE AND FITTING MATERIALS FOR DRAINAGE, WASTE, VENT AND CONDENSATE DRAIN PIPING SYSTEMS								
Item #	Pipe and Fitting Materials	SERVICE A	SERVICE B	SERVICE C	SERVICE D	SERVICE E	SERVICE F	SERVICE G
2	Cast iron soil pipe and fittings hubless, CISPI 301 and ASTM A888. Pipe and fittings shall be marked with the CISPI trademark.		X	X	X	X		
3	Cast iron drainage fittings, threaded, ASME B16.12 for use with Item 10	X		X	X			
4	Cast iron screwed fittings (threaded) ASME B16.4 for use with Item 10				X	X		
5	Grooved pipe couplings, ferrous and non-ferrous pipe ASTM A536 And ASTM A47/A47M	X	X		X	X		
7	Bronze sand casting grooved joint pressure fittings for non-ferrous pipe ASTM B584, for use with Item 5	X	X		X	X		
10	Steel pipe, seamless galvanized, ASTM A53/A53M, Type S, Grade B	X			X	X		

TABLE I								
PIPE AND FITTING MATERIALS FOR DRAINAGE, WASTE, VENT AND CONDENSATE DRAIN PIPING SYSTEMS								
Item #	Pipe and Fitting Materials	SERVICE A	SERVICE B	SERVICE C	SERVICE D	SERVICE E	SERVICE F	SERVICE G
12	Bronzed flanged fittings, ASME B16.24 for use with Items 11 and 14				X	X		X
13	Cast Copper alloy solder joint pressure fittings, ASME B16.18							
14	Seamless copper pipe, ASTM B42						X	X
16	Copper drainage tube, (DWV), ASTM B306	X*	X	X*	X	X		X
17	Wrought copper and wrought alloy solder-joint drainage fittings. ASME B16.29	X	X	X	X	X		X
18	Cast copper alloy solder joint drainage fittings, DWV, ASME B16.23	X	X	X	X	X		X
SERVICE: A - Underground Building Soil, Waste and Storm Drain B - Aboveground Soil, Waste, Drain In Buildings C - Underground Vent D - Aboveground Vent E - Interior Rainwater Conductors Aboveground F - Corrosive Waste And Vent Above And Belowground G - Condensate Drain Aboveground * - Hard Temper								

TABLE II					
PIPE AND FITTING MATERIALS FOR PRESSURE PIPING SYSTEMS					
Item #	Pipe and Fitting Materials	SERVICE A	SERVICE B	SERVICE C	SERVICE D
4	Steel pipe:				
	a. Seamless, galvanized, ASTM A53/A53M, Type S, Grade B	X	X	X	X
	b. Seamless, black, ASTM A53/A53M, Type S, Grade B			X	
7	Seamless copper pipe, ASTM B42	X	X		X
8	Seamless copper water tube, ASTM B88, ASTM B88M	X**	X**	X**	X***
32	Steel pipeline flanges, MSS SP-44	X	X		
33	Fittings: brass or bronze; ASME B16.15, and ASME B16.18 ASTM B828	X	X		
36	Nipples, pipe threaded ASTM A733	X	X	X	
38	Press Fittings	X	X		
	SERVICE: A - Cold Water Service Aboveground B - Hot and Cold Water Distribution 180 degrees F Maximum Aboveground C - Compressed Air Lubricated D - Cold Water Service Belowground Indicated types are minimum wall thicknesses. ** - Type L - Hard *** - Type K - Hard temper with brazed joints only or type K-soft temper without joints in or under floors **** - In or under slab floors only brazed joints				

-- End of Section --

SECTION 23 00 00

AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS
08/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING
ENGINEERS (ASHRAE)

- ASHRAE 52.2 (2012; Errata 1 2013; INT 1 2014; ADD A, B, AND D SUPP 2015; INT 3 2015; Errata 2 2015; ADD C 2015; ADD E, F 2016) Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size
- ASHRAE 62.1 (2013) Ventilation for Acceptable Indoor Air Quality
- ASHRAE 70 (2006; R 2011) Method of Testing for Rating the Performance of Air Outlets and Inlets

ASTM INTERNATIONAL (ASTM)

- ASTM A123/A123M (2017) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
- ASTM A53/A53M (2018) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
- ASTM A924/A924M (2018) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
- ASTM B117 (2016) Standard Practice for Operating Salt Spray (Fog) Apparatus
- ASTM B766 (1986; R 2015) Standard Specification for Electrodeposited Coatings of Cadmium
- ASTM C553 (2013) Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications
- ASTM D1654 (2008; R 2016; E 2017) Standard Test Method for Evaluation of Painted or Coated Specimens Subjected to Corrosive

Environments

ASTM D3359 (2009; E 2010; R 2010) Measuring Adhesion by Tape Test

ASTM D520 (2000; R 2011) Zinc Dust Pigment

ASTM E2016 (2015) Standard Specification for Industrial Woven Wire Cloth

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 90A (2021) Standard for the Installation of Air Conditioning and Ventilating Systems

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1966 (2005) HVAC Duct Construction Standards Metal and Flexible, 3rd Edition

SMACNA 1981 (2008) Seismic Restraint Manual Guidelines for Mechanical Systems, 3rd Edition

U.S. DEPARTMENT OF ENERGY (DOE)

Energy Star (1992; R 2006) Energy Star Energy Efficiency Labeling System (FEMP)

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

PL 109-58 Energy Policy Act of 2005 (EPAct05)

UNDERWRITERS LABORATORIES (UL)

UL 586 (2009; Reprint Sep 2014) Standard for High-Efficiency Particulate, Air Filter Units

UL 6 (2007; Reprint Nov 2014) Electrical Rigid Metal Conduit-Steel

UL 900 (2015) Standard for Air Filter Units

UL Bld Mat Dir (updated continuously online) Building Materials Directory

1.2 SYSTEM DESCRIPTION

Furnish ductwork, piping offsets, fittings, and accessories as required to provide a complete installation. Coordinate the work of the different trades to avoid interference between piping, equipment, structural, and electrical work. Provide complete, in place, all necessary offsets in piping and ductwork, and all fittings, and other components, required to install the work as indicated and specified.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation;

submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability Notebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Duct Connectors
Manual Balancing Dampers
Air Vents, Penthouses, and Goosenecks

SD-06 Test Reports

Performance Tests

SD-08 Manufacturer's Instructions

Manufacturer's Installation Instructions
Operation and Maintenance Training

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G

1.4 QUALITY ASSURANCE

Except as otherwise specified, approval of materials and equipment is based on manufacturer's published data.

- a. Where materials and equipment are specified to conform to the standards of the Underwriters Laboratories, the label of or listing with reexamination in UL Bld Mat Dir, and UL 6 is acceptable as sufficient evidence that the items conform to Underwriters Laboratories requirements. In lieu of such label or listing, submit a written certificate from any nationally recognized testing agency, adequately equipped and competent to perform such services, stating that the items have been tested and that the units conform to the specified requirements. Outline methods of testing used by the specified agencies.
- b. Where materials or equipment are specified to be constructed or tested, or both, in accordance with the standards of the ASTM International (ASTM), the ASME International (ASME), or other standards, a manufacturer's certificate of compliance of each item is acceptable as proof of compliance.
- c. Conformance to such agency requirements does not relieve the item from compliance with other requirements of these specifications.
- d. Where products are specified to meet or exceed the specified energy efficiency requirement of FEMP-designated or Energy Star certified product categories, equipment selected shall have as a minimum the efficiency rating identified under "Energy-Efficient Products" at <http://www1.eere.energy.gov/femp/procurement>.

These specifications conform to the efficiency requirements as defined in Public Law PL 109-58, "Energy Policy Act of 2005" for federal procurement of energy-efficient products. Equipment having a lower efficiency than Energy Star or FEMP requirements may be specified if the designer determines the equipment to be more life-cycle cost effective using the life-cycle cost analysis methodology and procedure in 10 CFR 436.

1.4.1 Prevention of Corrosion

Protect metallic materials against corrosion. Manufacturer shall provide rust-inhibiting treatment and standard finish for the equipment enclosures. Do not use aluminum in contact with earth, and where connected to dissimilar metal. Protect aluminum by approved fittings, barrier material, or treatment. Ferrous parts such as anchors, bolts, braces, boxes, bodies, clamps, fittings, guards, nuts, pins, rods, shims, thimbles, washers, and miscellaneous parts not of corrosion-resistant steel or nonferrous materials shall be hot-dip galvanized in accordance with ASTM A123/A123M for exterior locations and cadmium-plated in conformance with ASTM B766 for interior locations.

1.4.2 Asbestos Prohibition

Do not use asbestos and asbestos-containing products.

1.4.3 Test Procedures for duct leakage testing

Submit proposed test procedures and test schedules for the ductwork leak test, and performance tests of systems, at least 2 weeks prior to the start of related testing.

1.5 DELIVERY, STORAGE, AND HANDLING

Protect stored equipment at the jobsite from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Additionally, cap or plug all pipes until installed.

PART 2 PRODUCTS

2.1 PRODUCT SUSTAINABILITY CRITERIA

For products in this section, where applicable and to extent allowed by performance criteria, provide and document the following:

2.1.1 Reduce Volatile Organic Compounds (VOC) for sealants, coatings or adhesives

Low or no VOC's and no added urea formaldehyde for duct sealants, coatings or adhesives, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING paragraph REDUCE VOLATILE ORGANIC COMPOUNDS (VOC).

2.2 ANCHOR BOLTS

Provide anchor bolts for equipment placed on concrete equipment pads or on concrete slabs. Bolts to be of the size and number recommended by the equipment manufacturer and located by means of suitable templates. Installation of anchor bolts shall not degrade the surrounding concrete.

2.3 SEISMIC ANCHORAGE

Anchor equipment in accordance with applicable seismic criteria for the area and as defined in SMACNA 1981

2.4 PAINTING

Paint equipment units in accordance with approved equipment manufacturer's

standards unless specified otherwise. Field retouch only if approved. Otherwise, return equipment to the factory for refinishing.

2.5 INDOOR AIR QUALITY

Provide equipment and components that comply with the requirements of ASHRAE 62.1 unless more stringent requirements are specified herein.

2.6 DUCT SYSTEMS

2.6.1 Metal Ductwork

Provide metal ductwork construction, including all fittings and components, that complies with SMACNA 1966, as supplemented and modified by this specification .

- b. Provide radius type elbows with a centerline radius of 1.5 times the width or diameter of the duct where space permits. Otherwise, elbows having a minimum radius equal to the width or diameter of the duct or square elbows with factory fabricated turning vanes are allowed.
- d. Provide sealants that are suitable for the range of air distribution and ambient temperatures to which it is exposed. Do not use pressure sensitive tape as a sealant.
- e. Make spiral lock seam duct, and flat oval with approved methods indicated in SMACNA 1966.

2.6.1.1 General Service Duct Connectors

Provide a flexible duct connector approximately 6 inches in width where sheet metal connections are made to fans or where ducts of dissimilar metals are connected.

2.6.2 Diffusers, Registers, and Grilles

Provide factory-fabricated units of steel that distribute the specified quantity of air evenly over space intended without causing noticeable drafts, air movement faster than 50 fpm in occupied zone, or dead spots anywhere in the conditioned area. Provide outlets for diffusion, spread, throw, and noise level as required for specified performance. Certify performance according to ASHRAE 70. Provide sound rated and certified inlets and outlets according to ASHRAE 70. Provide sound power level as indicated. Provide diffusers and registers with volume damper with accessible operator, unless otherwise indicated; or if standard with the manufacturer, an automatically controlled device is acceptable. Provide opposed blade type volume dampers for all diffusers and registers, except linear slot diffusers. Provide linear slot diffusers with round or elliptical balancing dampers. Where the inlet and outlet openings are located less than 7 feet above the floor, protect them by a grille or screen according to NFPA 90A.

2.6.3 Air Vents, Penthouses, and Goosenecks

Fabricate air vents, penthouses, and goosenecks from galvanized steel sheets with galvanized structural shapes. Provide sheet metal thickness,

reinforcement, and fabrication that conform to SMACNA 1966. Accurately fit and secure louver blades to frames. Fold or bead edges of louver blades for rigidity and baffle these edges to exclude driving rain. Provide air vents, penthouses, and goosenecks with bird screen.

2.6.4 Bird Screens and Frames

Provide bird screens that conform to ASTM E2016, No. 2 mesh, aluminum or stainless steel. Provide "medium-light" rated aluminum screens. Provide "light" rated stainless steel screens. Provide removable type frames fabricated from either stainless steel or extruded aluminum.

2.7 AIR SYSTEMS EQUIPMENT

2.7.1 Air Filters

List air filters according to requirements of UL 900, except list high efficiency particulate air filters of 99.97 percent efficiency by the DOP Test method under the Label Service to meet the requirements of UL 586.

2.7.1.1 Extended Surface Pleated Panel Filters

Provide 2 inch depth, sectional, disposable type filters of the size indicated with a MERV of 8 when tested according to ASHRAE 52.2. Provide initial resistance at 500 fpm that does not exceed 0.36 inches water gauge. Provide UL Class 2 filters, and nonwoven cotton and synthetic fiber mat media. Attach a wire support grid bonded to the media to a moisture resistant fiberboard frame. Bond all four edges of the filter media to the inside of the frame to prevent air bypass and increase rigidity.

2.8 FACTORY PAINTING

Factory paint new equipment, which are not of galvanized construction. Paint with a corrosion resisting paint finish according to ASTM A123/A123M or ASTM A924/A924M. Clean, phosphatize and coat internal and external ferrous metal surfaces with a paint finish which has been tested according to ASTM B117, ASTM D1654, and ASTM D3359. Submit evidence of satisfactory paint performance for a minimum of 125 hours for units to be installed indoors and 500 hours for units to be installed outdoors. Provide rating of failure at the scribe mark that is not less than 6, average creepage not greater than 1/8 inch. Provide rating of the inscribed area that is not less than 10, no failure. On units constructed of galvanized steel that have been welded, provide a final shop docket of zinc-rich protective paint on exterior surfaces of welds or welds that have burned through from the interior according to ASTM D520 Type I.

Factory painting that has been damaged prior to acceptance by the Contracting Officer shall be field painted in compliance with the requirements of paragraph FIELD PAINTING OF MECHANICAL EQUIPMENT.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing the work.

3.2 INSTALLATION

- a. Install materials and equipment in accordance with the requirements of the contract drawings and approved manufacturer's installation instructions. Accomplish installation by workers skilled in this type of work. Perform installation so that there is no degradation of the designed fire ratings of walls, partitions, ceilings, and floors.
- b. No installation is permitted to block or otherwise impede access to any existing machine or system. Install all hinged doors to swing open a minimum of 120 degrees. Provide an area in front of all access doors that clears a minimum of 3 feet. In front of all access doors to electrical circuits, clear the area the minimum distance to energized circuits as specified in OSHA Standards, part 1910.333 (Electrical-Safety Related work practices) and an additional 3 feet.
- c. Except as otherwise indicated, install emergency switches and alarms in conspicuous locations. Mount all indicators, to include gauges, meters, and alarms in order to be easily visible by people in the area.

3.2.1 Flexible Duct

Install pre-insulated flexible duct in accordance with the latest printed instructions of the manufacturer to ensure a vapor tight joint. Provide hangers, when required to suspend the duct, of the type recommended by the duct manufacturer and set at the intervals recommended.

3.2.2 Duct Test Holes

Provide holes with closures or threaded holes with plugs in ducts and plenums as indicated or where necessary for the use of pitot tube in balancing the air system. Plug insulated duct at the duct surface, patched over with insulation and then marked to indicate location of test hole if needed for future use.

3.3 CLEANING

Thoroughly clean surfaces of piping and equipment that have become covered with dirt, plaster, or other material during handling and construction before such surfaces are prepared for final finish painting or are enclosed within the building structure. Before final acceptance, clean mechanical equipment, including piping, ducting, and fixtures, and free from dirt, grease, and finger marks. When the work area is in an occupied space, protect all furniture and equipment from dirt and debris. Incorporate housekeeping for field construction work which leaves all furniture and equipment in the affected area free of construction generated dust and debris; and, all floor surfaces vacuum-swept clean.

3.4 PENETRATIONS

Provide sleeves and prepared openings for duct mains, branches, and other penetrating items, and install during the construction of the surface to be penetrated. Cut sleeves flush with each surface. Place sleeves for round duct 15 inches and smaller. Build framed, prepared openings for round duct larger than 15 inches and square, rectangular or oval ducts. Sleeves and framed openings are also required where grilles, registers, and diffusers are installed at the openings. Provide one inch clearance between penetrating and penetrated surfaces except at grilles, registers, and diffusers. Pack spaces between sleeve or opening and duct or duct

insulation with mineral fiber conforming with ASTM C553, Type 1, Class B-2.

3.4.1 Sleeves

Fabricate sleeves, except as otherwise specified or indicated, from 20 gauge thick mill galvanized sheet metal. Where sleeves are installed in bearing walls or partitions, provide black steel pipe conforming with ASTM A53/A53M, Schedule 20.

3.4.2 Closure Collars

Provide closure collars of a minimum 4 inches wide, unless otherwise indicated, for exposed ducts and items on each side of penetrated surface, except where equipment is installed. Install collar tight against the surface and fit snugly around the duct or insulation. Grind sharp edges smooth to prevent damage to penetrating surface. Fabricate collars for round ducts 15 inches in diameter or less from 20 gauge galvanized steel. Fabricate collars for square and rectangular ducts, or round ducts with minimum dimension over 15 inches from 18 gauge galvanized steel. Fabricate collars for square and rectangular ducts with a maximum side of 15 inches or less from 20 gauge galvanized steel. Install collars with fasteners a maximum of 6 inches on center. Attach to collars a minimum of 4 fasteners where the opening is 12 inches in diameter or less, and a minimum of 8 fasteners where the opening is 20 inches in diameter or less.

3.4.3 Firestopping

Where ducts pass through fire-rated walls, fire partitions, and fire rated chase walls, seal the penetration with fire stopping materials as specified in Section 07 84 00 FIRESTOPPING.

3.5 FIELD PAINTING OF MECHANICAL EQUIPMENT

Clean, pretreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and solvent degreasing prior to application of paint, except clean to bare metal on metal surfaces subject to temperatures in excess of 120 degrees F. Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Provide aluminum or light gray finish coat.

3.5.1 Temperatures less than 120 degrees F

Immediately after cleaning, apply one coat of pretreatment primer applied to a minimum dry film thickness of 0.3 mil, one coat of primer applied to a minimum dry film thickness of one mil; and two coats of enamel applied to a minimum dry film thickness of one mil per coat to metal surfaces subject to temperatures less than 120 degrees F.

3.6 TESTING, ADJUSTING, AND BALANCING

The requirements for testing, adjusting, and balancing are specified in Section 23 05 93 TESTING, ADJUSTING AND BALANCING FOR HVAC. Begin testing, adjusting, and balancing only when the air supply and distribution, including controls, has been completed, with the exception of performance tests.

3.7 PERFORMANCE TESTS

After testing, adjusting, and balancing is complete as specified, test each system as a whole to see that all items perform as integral parts of the system and temperatures and conditions are evenly controlled throughout the building. Record the testing during the applicable season. Make corrections and adjustments as necessary to produce the conditions indicated or specified.

Submit test reports for the ductwork leak test, and performance tests in booklet form, upon completion of testing. Document phases of tests performed including initial test summary, repairs/adjustments made, and final test results in the reports.

3.8 OPERATION AND MAINTENANCE

3.8.1 Operation and Maintenance Manuals

Submit six manuals at least 2 weeks prior to field training. Submit data complying with the requirements specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA. Submit Data Package 3 for the items/units listed under SD-10 Operation and Maintenance Data

3.8.2 Operation And Maintenance Training

Conduct a training course for the members of the operating staff as designated by the Contracting Officer. Make the training period consist of a total of 8 hours of normal working time and start it after all work specified herein is functionally completed and the Performance Tests have been approved. Conduct field instruction that covers all of the items contained in the Operation and Maintenance Manuals as well as demonstrations of routine maintenance operations. Submit the proposed On-site Training schedule concurrently with the Operation and Maintenance Manuals and at least 14 days prior to conducting the training course.

-- End of Section --

SECTION 23 05 93

TESTING, ADJUSTING, AND BALANCING FOR HVAC
11/15

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASSOCIATED AIR BALANCE COUNCIL (AABC)

AABC MN-1 (2002; 6th ed) National Standards for
Total System Balance

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)

NEBB MASV (2006) Procedural Standards for
Measurements and Assessment of Sound and
Vibration

NEBB PROCEDURAL STANDARDS (2005) Procedural Standards for TAB
(Testing, Adjusting and Balancing)
Environmental Systems

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION
(SMACNA)

SMACNA 1780 (2002) HVAC Systems - Testing, Adjusting
and Balancing, 3rd Edition

SMACNA 1858 (2004) HVAC Sound And Vibration Manual -
First Edition

SMACNA 1972 CD (2012) HVAC Air Duct Leakage Test Manual -
2nd Edition

1.2 DEFINITIONS

- a. AABC: Associated Air Balance Council
- b. COTR: Contracting Officer's Technical Representative
- c. DALT: Duct air leakage test
- d. DALT'd: Duct air leakage tested
- e. HVAC: Heating, ventilating, and air conditioning; or heating, ventilating, and cooling
- f. NEBB: National Environmental Balancing Bureau
- g. Out-of-tolerance data: Pertains only to field acceptance testing of Final DALT or TAB report. When applied to DALT work, this phase means When applied to TAB work this phase means "a measurement taken

during TAB field acceptance testing which does not fall within the range of plus 5 to minus 5 percent of the original measurement reported on the TAB Report for a specific parameter."

- h. Season of maximum heating load: The time of year when the outdoor temperature at the project site remains within plus or minus 30 degrees Fahrenheit of the project site's winter outdoor design temperature, throughout the period of TAB data recording.
- i. Season of maximum cooling load: The time of year when the outdoor temperature at the project site remains within plus or minus 5 degrees Fahrenheit of the project site's summer outdoor design temperature, throughout the period of TAB data recording.
- j. Sound measurements terminology: Defined in AABC MN-1, NEBB MASV, or SMACNA 1858 (TABB).
- k. TAB: Testing, adjusting, and balancing (of HVAC systems)
- l. TAB'd: HVAC Testing/Adjusting/Balancing procedures performed
- m. TAB Agency: TAB Firm
- q. TABB: Testing Adjusting and Balancing Bureau

1.2.1 Similar Terms

In some instances, terminology differs between the Contract and the TAB Standard primarily because the intent of this Section is to use the industry standards specified, along with additional requirements listed herein to produce optimal results.

The following table of similar terms is provided for clarification only. Contract requirements take precedent over the corresponding AABC, NEBB, or TABB requirements where differences exist.

SIMILAR TERMS			
Contract Term	AABC Term	NEBB Term	TABB Term
TAB Standard	National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems	Procedural Standards for Testing, Adjusting and Balancing of Environmental Systems	International Standards for Environmental Systems Balance
TAB Specialist	TAB Engineer	TAB Supervisor	TAB Supervisor
Systems Readiness Check	Construction Phase Inspection	Field Readiness Check & Preliminary Field Procedures	Field Readiness Check & Prelim. Field Procedures

1.3 WORK DESCRIPTION

The work includes duct air leakage testing (DALT) and testing, adjusting,

and balancing (TAB) of new and existing heating, ventilating, and cooling (HVAC) air and water distribution systems including equipment and performance data, ducts, and piping which are located within, on, under, between, and adjacent to buildings.

Perform TAB in accordance with the requirements of the TAB procedural standard recommended by the TAB trade association that approved the TAB Firm's qualifications. Comply with requirements of AABC MN-1, NEBB PROCEDURAL STANDARDS, or SMACNA 1780 (TABB) as supplemented and modified by this specification section. All recommendations and suggested practices contained in the TAB procedural standards are considered mandatory.

Conduct DALT and TAB of the indicated existing systems and equipment and submit the specified DALT and TAB reports for approval. Conduct DALT testing in compliance with the requirements specified in SMACNA 1972 CD, except as supplemented and modified by this section. Conduct DALT and TAB work in accordance with the requirements of this section.

1.3.1 Air Distribution Systems

Test, adjust, and balance systems (TAB) in compliance with this section.

1.3.2 TAB SCHEMATIC DRAWINGS

Show the following information on TAB Schematic Drawings:

1. A unique number or mark for each piece of equipment or terminal.
2. Air quantities at air terminals.
3. Air quantities and temperatures in air handling unit schedules.
4. Ductwork Construction and Leakage Testing Table that defines the DALT test requirements, including each applicable HVAC duct system ID or mark, duct pressure class, duct seal class, and duct leakage test pressure. This table is included in the file for Graphics for Unified Facilities Guide Specifications:
<http://www.wbdg.org/FFC/NAVGRAPH/graphdoc.pdf>

Submit three copies of the TAB Schematic Drawings and Report Forms to the Contracting Officer, no later than 21 days prior to the start of TAB field measurements.

1.3.3 Related Requirements

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability Notebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Records of Existing Conditions

SD-02 Shop Drawings

TAB Schematic Drawings and Report Forms;

SD-03 Product Data

Equipment and Performance Data;

TAB Related HVAC Submittals;

A list of the TAB Related HVAC Submittals, no later than 7 days after the approval of the TAB team engineer.

SD-06 Test Reports

Completed Pre-Final DALT Report;

Certified Final DALT Report; G

SD-07 Certificates

Independent TAB Agency and Personnel Qualifications; G

DALT and TAB Submittal and Work Schedule;

TAB Pre-Field Engineering Report;

1.5 QUALITY ASSURANCE

1.5.1 Independent TAB Agency and Personnel Qualifications

To secure approval for the proposed agency, submit information certifying that the TAB agency is a first tier subcontractor who is not affiliated with any other company participating in work on this contract, including design, furnishing equipment, or construction. Further, submit the following, for the agency, to Contracting Officer for approval:

a. Independent AABC or NEBB TAB agency:

TAB agency: AABC registration number and expiration date of current certification; or NEBB certification number and expiration date of current certification; and expiration date of current certification.

TAB team supervisor: Name and copy of AABC or NEBB TAB supervisor certificate and expiration date of current certification.

TAB team field leader: Name and documented evidence that the team field leader has satisfactorily performed full-time supervision of TAB work in the field for not less than 3 years immediately preceding this contract's bid opening date.

TAB team field technicians: Names and documented evidence that each field technician has satisfactorily assisted a TAB team field leader in performance of TAB work in the field for not less than one year immediately preceding this contract's bid opening date.

Current certificates: Registrations and certifications are current, and valid for the duration of this contract. Renew Certifications which expire prior to completion of the TAB work, in a timely manner so that there is no lapse in registration or certification. TAB agency or TAB team personnel without a current registration or current certification are not to perform TAB work on this contract.

- b. TAB Team Members: TAB team approved to accomplish work on this contract are full-time employees of the TAB agency. No other personnel is allowed to do TAB work on this contract.
- c. Replacement of TAB team members: Replacement of members may occur if each new member complies with the applicable personnel qualifications and each is approved by the Contracting Officer.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 WORK DESCRIPTIONS OF PARTICIPANTS

Comply with requirements of this section.

3.2 PRE-DALT/TAB MEETING

Meet with the Contracting Officer's technical representative (COTR) to develop a mutual understanding relative to the details of the DALT work and TAB work requirements. Ensure that the TAB supervisor is present at this meeting. Requirements to be discussed include required submittals, work schedule, and field quality control.

3.3 DALT PROCEDURES

3.3.1 Instruments, Consumables and Personnel

Provide instruments, consumables and personnel required to accomplish the DALT field work. Follow the same basic procedure specified below for TAB Field Work, including maintenance and calibration of instruments, accuracy of measurements, preliminary procedures, field work, workmanship and treatment of deficiencies. Calibrate and maintain instruments in accordance with manufacturer's written procedures.

3.3.2

On completion of the installation of each duct system indicated to be DALT'd, notify the Contracting Officer in writing prior to the COTR's duct selection field visit.

3.3.3 Ductwork To Be DALT'd

From each duct system indicated as subject to DALT, the COTR will randomly select sections of each completed duct system for testing by the Contractor's TAB Firm. The sections selected will not exceed 20 percent of the total measured linear footage of duct systems indicated as subject to DALT. Sections of duct systems subject to DALT will include 20 percent

of main ducts, branch main ducts, branch ducts and plenums for supply, return, exhaust, and plenum ductwork.

It is acceptable for an entire duct system to be DALT'd instead of disassembling that system in order to DALT only the 20 percent portion specified above.

3.3.4 DALT Testing

Perform DALT on the HVAC duct sections of each system as selected by the COTR. Use the duct class, seal class, leakage class and the leak test pressure data indicated on the drawings, to comply with the procedures specified in SMACNA 1972 CD.

In spite of specifications of SMACNA 1972 CD to the contrary, DALT ductwork of construction class of 3-inch water gauge static pressure and below if indicated to be DALT'd. Complete DALT work on the COTR selected ductwork within 48 hours after the particular ductwork was selected for DALT. Separately conduct DALT work for large duct systems to enable the DALT work to be completed in 48 hours.

3.3.5 Completed Pre-Final DALT Report

3.3.6 Quality Assurance - COTR DALT Field Acceptance Testing

In the presence of the COTR and TAB team field leader, verify for accuracy Pre-final DALT Report data selected by the COTR. For each duct system, this acceptance testing shall be conducted on a maximum of 50 percent of the duct sections DALT'd.

Further, if any data on the Pre-final DALT report form for a given duct section is out-of-tolerance, then field acceptance testing shall be conducted on data for one additional duct section, preferably in the same duct system, in the presence of the COTR.

3.3.7 Additional COTR Field Acceptance Testing

If any of the duct sections checked for a given system are determined to have a leakage rate measured that exceeds the leakage rate allowed by SMACNA Leak Test Manual for an indicated duct construction class and sealant class, terminate data checking for that section. The associated Pre-final DALT Report data for the given duct system will be disapproved. Make the necessary corrections and prepare a revised Pre-final DALT Report. Reschedule a field check of the revised report data with the COTR.

3.3.8 Certified Final DALT Report

3.3.9 Prerequisite for TAB Field Work

Do not commence TAB field work prior to the completion and approval, for all systems, of the Final DALT Report.

3.4 TAB PROCEDURES

3.4.1 TAB Field Work

Test, adjust, and balance the HVAC systems until measured flow rates (air and water flow) are within plus or minus 5 percent of the design flow rates as specified or indicated on the contract documents.

That is, comply with the the requirements of AABC MN-1 or SMACNA 1780 (TABB) and SMACNA 1858 (TABB), except as supplemented and modified by this section.

Provide instruments and consumables required to accomplish the TAB work. Calibrate and maintain instruments in accordance with manufacturer's written procedures.

Test, adjust, and balance the HVAC systems until measured flow rates (air and water flow) are within plus or minus 5 percent of the design flow rates as specified or indicated on the contract documents. Conduct TAB work, including measurement accuracy, and sound measurement work in conformance with the AABC MN-1 and AABC MN-4, or NEBB TABES and NEBB MASV, or SMACNA 1780 (used by TABB) and SMACNA 1858 sound measurement procedures, except as supplemented and modified by this section.

3.4.2 Preliminary Procedures

Use the approved pre-field engineering report as instructions and procedures for accomplishing TAB field work. TAB engineer is to locate, in the field, test ports required for testing. It is the responsibility of the sheet metal contractor to provide and install test ports as required by the TAB engineer.

3.4.3 TAB Air Distribution Systems

3.4.3.1 Fan Coils

Fan coil unit systems including fans, coils, ducts, plenums, and air distribution devices for supply air, return air, and outside air.

3.4.3.2 Exhaust Fans

Exhaust fan systems including fans, ducts, plenums, grilles, and hoods for exhaust air.

3.4.4 TAB Work on Performance Tests Without Seasonal Limitations

3.4.4.1 Performance Tests

In addition to the TAB proportionate balancing work on the air distribution systems and the water distribution systems, accomplish TAB work on the HVAC systems which directly transfer thermal energy. TAB the operational performance of the heating systems and cooling systems.

3.4.4.2 Ambient Temperatures

On each tab report form used for recording data, record the outdoor and indoor ambient dry bulb temperature range and the outdoor and indoor ambient wet bulb temperature range within which the report form's data was recorded. Record these temperatures at beginning and at the end of data

taking.

3.4.5 Workmanship

Conduct TAB work on the HVAC systems until measured flow rates are within plus or minus 5 percent of the design flow rates as specified or indicated on the contract documents. This TAB work includes adjustment of balancing valves, balancing dampers, and sheaves. Further, this TAB work includes changing out fan sheaves and pump impellers if required to obtain air and water flow rates specified or indicated. If, with these adjustments and equipment changes, the specified or indicated design flow rates cannot be attained, contact the Contracting Officer for direction.

3.4.6 Deficiencies

Strive to meet the intent of this section to maximize the performance of the equipment as designed and installed. However, if deficiencies in equipment design or installation prevent TAB work from being accomplished within the range of design values specified in the paragraph WORKMANSHIP, provide written notice as soon as possible to the Contractor and the Contracting Officer describing the deficiency and recommended correction.

Responsibility for correction of installation deficiencies is the Contractor's. If a deficiency is in equipment design, call the TAB team supervisor for technical assistance. Responsibility for reporting design deficiencies to Contractor is the TAB team supervisor's.

3.4.7 TAB Reports

3.4.8 Quality Assurance - COTR TAB Field Acceptance Testing

3.4.8.1 TAB Field Acceptance Testing

During the field acceptance testing, verify, in the presence of the COTR, random selections of data (water, air quantities, air motion,) recorded in the TAB Report. Points and areas for field acceptance testing are to be selected by the COTR. Measurement and test procedures are the same as approved for TAB work for the TAB Report.

Field acceptance testing includes verification of TAB Report data recorded for the following equipment groups:

Group 5: All exhaust fans.

Further, if any data on the TAB Report for Groups 2 through 5 is found not to fall within the range of plus 5 to minus 5 percent of the TAB Report data, additional group data verification is required in the presence of the COTR. Verify TAB Report data for one additional piece of equipment in that group. Continue this additional group data verification until out-of-tolerance data ceases to be found.

3.4.8.2 Additional COTR TAB Field Acceptance Testing

If any of the acceptance testing measurements for a given equipment group is found not to fall within the range of plus 5 to minus 5 percent of the TAB Report data, terminate data verification for all affected data for that group. The affected data for the given group will be disapproved. Make the necessary corrections and prepare a revised TAB Report. Reschedule acceptance testing of the revised report data with the COTR.

3.4.8.3 Prerequisite for Approval

Compliance with the field acceptance testing requirements of this section is a prerequisite for the final Contracting Officer approval of the TAB Report submitted.

3.5 MARKING OF SETTINGS

Upon the final TAB work approval, permanently mark the settings of HVAC adjustment devices including valves, gauges, splitters, and dampers so that adjustment can be restored if disturbed at any time. Provide permanent markings clearly indicating the settings on the adjustment devices which result in the data reported on the submitted TAB report.

3.6 MARKING OF TEST PORTS

The TAB team is to permanently and legibly mark and identify the location points of the duct test ports. If the ducts have exterior insulation, make these markings on the exterior side of the duct insulation. Show the location of test ports on the as-built mechanical drawings with dimensions given where the test port is covered by exterior insulation.

-- End of Section --

SECTION 23 07 00

THERMAL INSULATION FOR MECHANICAL SYSTEMS
02/13, CHG 7: 05/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. At the discretion of the Government, the manufacturer of any material supplied will be required to furnish test reports pertaining to any of the tests necessary to assure compliance with the standard or standards referenced in this specification.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING
ENGINEERS (ASHRAE)

ASHRAE 90.2 (2018) Energy-Efficient Design of Low-Rise Residential Buildings

ASTM INTERNATIONAL (ASTM)

ASTM A167 (2011) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip

ASTM A240/A240M (2020) Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications

ASTM A580/A580M (2018) Standard Specification for Stainless Steel Wire

ASTM B209 (2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate

ASTM C195 (2007; R 2013) Standard Specification for Mineral Fiber Thermal Insulating Cement

ASTM C450 (2008) Standard Practice for Fabrication of Thermal Insulating Fitting Covers for NPS Piping, and Vessel Lagging

ASTM C534/C534M (2020a) Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form

ASTM C552 (2017; E 2018) Standard Specification for Cellular Glass Thermal Insulation

ASTM C647 (2008; R 2013) Properties and Tests of Mastics and Coating Finishes for Thermal

Insulation

ASTM C755	(2019b) Standard Practice for Selection of Water Vapor Retarders for Thermal Insulation
ASTM C795	(2008; R 2018) Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel
ASTM C916	(2020) Standard Specification for Adhesives for Duct Thermal Insulation
ASTM C920	(2018) Standard Specification for Elastomeric Joint Sealants
ASTM C921	(2010) Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation
ASTM C1136	(2017a) Standard Specification for Flexible, Low Permeance Vapor Retarders for Thermal Insulation
ASTM C1710	(2011) Standard Guide for Installation of Flexible Closed Cell Preformed Insulation in Tube and Sheet Form
ASTM D882	(2012) Tensile Properties of Thin Plastic Sheeting
ASTM D2863	(2019) Standard Test Method for Measuring the Minimum Oxygen Concentration to Support Candle-Like Combustion of Plastics (Oxygen Index)
ASTM D5590	(2000; R 2010; E 2012) Standard Test Method for Determining the Resistance of Paint Films and Related Coatings to Fungal Defacement by Accelerated Four-Week Agar Plate Assay
ASTM E84	(2020) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E96/E96M	(2016) Standard Test Methods for Water Vapor Transmission of Materials
ASTM E2231	(2019) Standard Practice for Specimen Preparation and Mounting of Pipe and Duct Insulation Materials to Assess Surface Burning Characteristics

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor

Sources using Environmental Chambers

FM GLOBAL (FM)

FM APP GUIDE

(updated on-line) Approval Guide
<http://www.approvalguide.com/>

GREEN SEAL (GS)

GS-36

(2013) Adhesives for Commercial Use

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)

ISO 2758

(2014) Paper - Determination of Bursting Strength

MIDWEST INSULATION CONTRACTORS ASSOCIATION (MICA)

MICA Insulation Stds

(8th Ed) National Commercial & Industrial Insulation Standards

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 90A

(2021) Standard for the Installation of Air Conditioning and Ventilating Systems

NFPA 90B

(2021) Standard for the Installation of Warm Air Heating and Air Conditioning Systems

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS

SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168

(2017) Adhesive and Sealant Applications

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-A-3316

(1987; Rev C; Am 2 1990) Adhesives, Fire-Resistant, Thermal Insulation

MIL-A-24179

(1969; Rev A; Am 2 1980; Notice 1 1987; Notice 2 2020) Adhesive, Flexible Unicellular-Plastic Thermal Insulation

MIL-PRF-19565

(1988; Rev C) Coating Compounds, Thermal Insulation, Fire- and Water-Resistant, Vapor-Barrier

UNDERWRITERS LABORATORIES (UL)

UL 94

(2013; Reprint May 2021) UL Standard for Safety Tests for Flammability of Plastic Materials for Parts in Devices and Appliances

UL 723

(2018) UL Standard for Safety Test for

Surface Burning Characteristics of
Building Materials

UL 2818

(2013) GREENGUARD Certification Program
For Chemical Emissions For Building
Materials, Finishes And Furnishings

1.2 SYSTEM DESCRIPTION

1.2.1 General

Provide field-applied insulation and accessories on mechanical systems as specified herein; factory-applied insulation is specified under the piping, duct or equipment to be insulated. Insulation of heat distribution systems and chilled water systems outside of buildings shall be as specified in Section 33 61 13 PRE-ENGINEERED UNDERGROUND HEAT DISTRIBUTION SYSTEM, Section 33 63 13.19 CONCRETE TRENCH HYDRONIC AND STEAM ENERGY DISTRIBUTION, Section 33 60 02 ABOVEGROUND HEAT DISTRIBUTION SYSTEM, and Section 33 61 13.13 PREFABRICATED UNDERGROUND HYDRONIC ENERGY DISTRIBUTION. Field applied insulation materials required for use on Government-furnished items as listed in the SPECIAL CONTRACT REQUIREMENTS shall be furnished and installed by the Contractor.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Submit the three SD types, SD-02 Shop Drawings, SD-03 Product Data, and SD-08 Manufacturer's Instructions at the same time for each system.

SD-02 Shop Drawings

MICA Plates; G

Pipe Insulation Systems and Associated Accessories

Duct Insulation Systems and Associated Accessories

Equipment Insulation Systems and Associated Accessories

Recycled content for insulation materials; S

SD-03 Product Data

Pipe Insulation Systems; G

Duct Insulation Systems; G

Equipment Insulation Systems

SD-04 Samples

Thermal Insulation; G

Display Samples; G

SD-07 Certificates

Indoor air quality for adhesives; S

SD-08 Manufacturer's Instructions

Pipe Insulation Systems; G

Duct Insulation Systems; G

Equipment Insulation Systems; G

1.4 CERTIFICATIONS

1.4.1 Adhesives and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.5 QUALITY ASSURANCE

1.5.1 Installer Qualification

Qualified installers shall have successfully completed three or more similar type jobs within the last 5 years.

1.6 DELIVERY, STORAGE, AND HANDLING

Materials shall be delivered in the manufacturer's unopened containers. Materials delivered and placed in storage shall be provided with protection from weather, humidity, dirt, dust and other contaminants. The Contracting Officer may reject insulation material and supplies that become dirty, dusty, wet, or contaminated by some other means. Packages or standard containers of insulation, jacket material, cements, adhesives, and coatings delivered for use, and samples required for approval shall have manufacturer's stamp or label attached giving the name of the manufacturer and brand, and a description of the material, date codes, and approximate shelf life (if applicable). Insulation packages and containers shall be asbestos free.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Provide materials which are the standard products of manufacturers regularly engaged in the manufacture of such products and that essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening. Submit a complete list of materials, including manufacturer's descriptive technical literature, performance data, catalog cuts, and installation instructions. The product number, k-value, thickness and furnished accessories including adhesives, sealants and jackets for each mechanical system requiring insulation shall be included. The product data must be copyrighted, have an identifying or

publication number, and shall have been published prior to the issuance date of this solicitation. Materials furnished under this section shall be submitted together in a booklet.

2.1.1 Insulation System

Provide insulation systems in accordance with the approved MICA National Insulation Standards plates as supplemented by this specification. Provide field-applied insulation for heating, ventilating, and cooling (HVAC) air distribution systems and piping systems that are located within, on, under, and adjacent to buildings; and for plumbing systems. Provide CFC and HCFC free insulation.

2.1.2 Surface Burning Characteristics

Unless otherwise specified, insulation must have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Flame spread, and smoke developed indexes, shall be determined by ASTM E84 or UL 723. Test insulation in the same density and installed thickness as the material to be used in the actual construction. Prepare and mount test specimens according to ASTM E2231.

2.2 MATERIALS

Provide insulation that meets or exceeds the requirements of ASHRAE 90.2. Insulation exterior shall be cleanable, grease resistant, non-flaking and non-peeling. Materials shall be compatible and shall not contribute to corrosion, soften, or otherwise attack surfaces to which applied in either wet or dry state. Materials to be used on stainless steel surfaces shall meet ASTM C795 requirements. Calcium silicate shall not be used on chilled or cold water systems. Materials shall be asbestos free. Provide product recognized under UL 94 (if containing plastic) and listed in FM APP GUIDE.

2.2.1 Adhesives

Provide non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) that meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168 (HVAC duct sealants must meet limit requirements of "Other" category within SCAQMD Rule 1168 sealants table). Provide aerosol adhesives used on the interior of the building that meet either emissions requirements of CDPH SECTION 01350 (use the office or classroom requirements, regardless of space type) or VOC content requirements of GS-36. Provide certification or validation of indoor air quality for adhesives.

2.2.1.1 Acoustical Lining Insulation Adhesive

Adhesive shall be a nonflammable, fire-resistant adhesive conforming to ASTM C916, Type I.

2.2.1.2 Mineral Fiber Insulation Cement

Cement shall be in accordance with ASTM C195.

2.2.1.3 Lagging Adhesive

Lagging is the material used for thermal insulation, especially around a cylindrical object. This may include the insulation as well as the cloth/material covering the insulation. To resist mold/mildew, lagging adhesive shall meet ASTM D5590 with 0 growth rating. Lagging adhesives shall be nonflammable and fire-resistant and shall have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Adhesive shall be MIL-A-3316, Class 1, pigmented white and be suitable for bonding fibrous glass cloth to faced and unfaced fibrous glass insulation board; for bonding cotton brattice cloth to faced and unfaced fibrous glass insulation board; for sealing edges of and bonding glass tape to joints of fibrous glass board; for bonding lagging cloth to thermal insulation; or Class 2 for attaching fibrous glass insulation to metal surfaces. Lagging adhesives shall be applied in strict accordance with the manufacturer's recommendations for pipe and duct insulation.

2.2.1.4 Contact Adhesive

Adhesives may be any of, but not limited to, the neoprene based, rubber based, or elastomeric type that have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. The adhesive shall not adversely affect, initially or in service, the insulation to which it is applied, nor shall it cause any corrosive effect on metal to which it is applied. Any solvent dispersing medium or volatile component of the adhesive shall have no objectionable odor and shall not contain any benzene or carbon tetrachloride. The dried adhesive shall not emit nauseous, irritating, or toxic volatile matters or aerosols when the adhesive is heated to any temperature up to 212 degrees F. The dried adhesive shall be nonflammable and fire resistant. Flexible Elastomeric Adhesive: Comply with MIL-A-24179, Type II, Class I. Provide product listed in FM APP GUIDE.

2.2.2 Caulking

ASTM C920, Type S, Grade NS, Class 25, Use A.

2.2.3 Corner Angles

Nominal 0.016 inch aluminum 1 by 1 inch with factory applied kraft backing. Aluminum shall be ASTM B209, Alloy 3003, 3105, or 5005.

2.2.4 Fittings

Fabricated Fittings are the prefabricated fittings for flexible elastomeric pipe insulation systems in accordance with ASTM C1710. Together with the flexible elastomeric tubes, they provide complete system integrity for retarding heat gain and controlling condensation drip from chilled-water and refrigeration systems. Flexible elastomeric, fabricated fittings provide thermal protection (0.25 k) and condensation resistance (0.05 Water Vapor Transmission factor). For satisfactory performance, properly installed protective vapor retarder/barriers and vapor stops shall be used on high relative humidity and below ambient temperature applications to reduce movement of moisture through or around the insulation to the colder interior surface.

2.2.5 Finishing Cement

ASTM C450: Mineral fiber hydraulic-setting thermal insulating and finishing cement. All cements that may come in contact with Austenitic stainless steel must comply with ASTM C795.

2.2.6 Fibrous Glass Cloth and Glass Tape

Fibrous glass cloth, with 20X20 maximum mesh size, and glass tape shall have maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Tape shall be 4 inch wide rolls. Class 3 tape shall be 4.5 ounces/square yard. Elastomeric Foam Tape: Black vapor-retarder foam tape with acrylic adhesive containing an anti-microbial additive.

2.2.7 Staples

Outward clinching type ASTM A167, Type 304 or 316 stainless steel.

2.2.8 Jackets

2.2.8.1 Aluminum Jackets

Aluminum jackets shall be corrugated, embossed or smooth sheet, 0.016 inch nominal thickness; ASTM B209, Temper H14, Temper H16, Alloy 3003, 5005, or 3105. Corrugated aluminum jacket shall not be used outdoors. Aluminum jacket securing bands shall be Type 304 stainless steel, 0.015 inch thick, 1/2 inch wide for pipe under 12 inch diameter and 3/4 inch wide for pipe over 12 inch and larger diameter. Aluminum jacket circumferential seam bands shall be 2 by 0.016 inch aluminum matching jacket material. Bands for insulation below ground shall be 3/4 by 0.020 inch thick stainless steel, or fiberglass reinforced tape. The jacket may, at the option of the Contractor, be provided with a factory fabricated Pittsburgh or "Z" type longitudinal joint. When the "Z" joint is used, the bands at the circumferential joints shall be designed by the manufacturer to seal the joints and hold the jacket in place.

2.2.8.2 Polyvinyl Chloride (PVC) Jackets

Polyvinyl chloride (PVC) jacket and fitting covers shall have high impact strength, ultraviolet (UV) resistant rating or treatment and moderate chemical resistance with minimum thickness 0.030 inch.

2.2.8.3 Vapor Barrier/Weatherproofing Jacket

Vapor barrier/weatherproofing jacket shall be laminated self-adhesive, greater than 3 plies standard grade, silver, white, black and embossed or greater than 8 ply (minimum 2.9 mils adhesive); with 0.0000 permeability when tested in accordance with ASTM E96/E96M, using the water transmission rate test method; heavy duty, white or natural; and UV resistant. Flexible Elastomeric exterior foam with factory applied, UV Jacket made with a cold weather acrylic adhesive. Construction of laminate designed to provide UV resistance, high puncture, tear resistance and excellent Water Vapor Transmission (WVT) rate.

2.2.8.4 Vapor Barrier/Vapor Retarder

Apply the following criteria to determine which system is required.

- a. On ducts, piping and equipment operating below 70 degrees F or located outside shall be equipped with a vapor barrier.
- b. Ducts, pipes and equipment that are located inside and that always operate above 70 degrees F shall be installed with a vapor retarder where required as stated in paragraph VAPOR RETARDER REQUIRED.

2.2.9 Vapor Retarder Required

ASTM C921, Type I, minimum puncture resistance 50 Beach units on all surfaces except concealed ductwork, where a minimum puncture resistance of 25 Beach units is acceptable. Minimum tensile strength, 35 pounds/inch width. ASTM C921, Type II, minimum puncture resistance 25 Beach units, tensile strength minimum 20 pounds/inch width. Jackets used on insulation exposed in finished areas shall have white finish suitable for painting without sizing. Based on the application, insulation materials that require manufacturer or fabricator applied pipe insulation jackets are cellular glass, when all joints are sealed with a vapor barrier mastic, and mineral fiber. All non-metallic jackets shall have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Flexible elastomerics require (in addition to vapor barrier skin) vapor retarder jacketing for high relative humidity and below ambient temperature applications.

2.2.9.1 White Vapor Retarder All Service Jacket (ASJ)

ASJ is for use on hot/cold pipes, ducts, or equipment indoors or outdoors if covered by a suitable protective jacket. The product shall meet all physical property and performance requirements of ASTM C1136, Type I, except the burst strength shall be a minimum of 85 psi. ASTM D2863 Limited Oxygen Index (LOI) shall be a minimum of 31.

In addition, neither the outer exposed surface nor the inner-most surface contacting the insulation shall be paper or other moisture-sensitive material. The outer exposed surface shall be white and have an emittance of not less than 0.80. The outer exposed surface shall be paintable.

2.2.9.2 Vapor Retarder/Vapor Barrier Mastic Coatings

2.2.9.2.1 Vapor Barrier

The vapor barrier shall be self adhesive (minimum 2 mils adhesive, 3 mils embossed) greater than 3 plies standard grade, silver, white, black and embossed white jacket for use on hot/cold pipes. Permeability shall be less than 0.02 when tested in accordance with ASTM E96/E96M. Products shall meet UL 723 or ASTM E84 flame and smoke requirements and shall be UV resistant.

2.2.9.2.2 Vapor Retarder

The vapor retarder coating shall be fire and water resistant and appropriately selected for either outdoor or indoor service. Color shall be white. The water vapor permeance of the compound shall be in accordance with ASTM C755, Section 7.2.2, Table 2, for insulation type and service conditions. The coating shall be nonflammable, fire resistant type. To resist mold/mildew, coating shall meet ASTM D5590 with 0 growth rating. Coating shall meet MIL-PRF-19565 Type II (if selected for indoor service) and be Qualified Products Database listed. All other application and service properties shall be determined pursuant to ASTM C647.

2.2.9.3 Laminated Film Vapor Retarder

ASTM C1136, Type I, maximum moisture vapor transmission 0.02 perms, minimum puncture resistance 50 Beach units on all surfaces except concealed ductwork; where Type II, maximum moisture vapor transmission 0.02 perms, a minimum puncture resistance of 25 Beach units is acceptable. Vapor retarder shall have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Flexible Elastomeric exterior foam with factory applied UV Jacket. Construction of laminate designed to provide UV resistance, high puncture, tear resistance and an excellent WVT rate.

2.2.9.4 Polyvinylidene Chloride (PVDC) Film Vapor Retarder

The PVDC film vapor retarder shall have a maximum moisture vapor transmission of 0.02 perms, minimum puncture resistance of 150 Beach units, a minimum tensile strength in any direction of 30 lb/inch when tested in accordance with ASTM D882, and a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84.

2.2.9.5 Polyvinylidene Chloride Vapor Retarder Adhesive Tape

Requirements must meet the same as specified for Laminated Film Vapor Retarder above.

2.2.9.6 Vapor Barrier/Weather Barrier

The vapor barrier shall be greater than 3 ply self adhesive laminate -white vapor barrier jacket- superior performance (less than 0.0000 permeability when tested in accordance with ASTM E96/E96M). Vapor barrier shall meet UL 723 or ASTM E84 25 flame and 50 smoke requirements; and UV resistant. Minimum burst strength 185 psi in accordance with ISO 2758. Tensile strength 68 lb/inch width (PSTC-1000). Tape shall be as specified for laminated film vapor barrier above.

2.2.10 Vapor Retarder Not Required

ASTM C921, Type II, Class D, minimum puncture resistance 50 Beach units on all surfaces except ductwork, where Type IV, maximum moisture vapor transmission 0.10, a minimum puncture resistance of 25 Beach units is acceptable. Jacket shall have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84.

2.2.11 Wire

Soft annealed ASTM A580/A580M Type 302, 304 or 316 stainless steel, 16 or 18 gauge.

2.2.12 Insulation Bands

Insulation bands shall be 1/2 inch wide; 26 gauge stainless steel.

2.2.13 Sealants

Sealants shall be chosen from the butyl polymer type, the styrene-butadiene rubber type, or the butyl type of sealants. Sealants shall have a maximum permeance of 0.02 perms based on Procedure B for

ASTM E96/E96M, and a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84.

2.3 DUCT INSULATION SYSTEMS

2.3.1 Factory Applied Insulation

Provide factory-applied ASTM C552, cellular glass thermal insulation according to manufacturer's recommendations for insulation with insulation manufacturer's standard reinforced fire-retardant vapor barrier, with identification of installed thermal resistance (R) value and out-of-package R value.

2.3.1.1 Rigid Insulation

Calculate the minimum thickness in accordance with ASHRAE 90.2.

2.3.1.2 Blanket Insulation

Calculate minimum thickness in accordance with ASHRAE 90.2.

2.3.2 Acoustical Duct Lining

2.3.2.1 General

For ductwork indicated or specified in Section 23 30 00 HVAC AIR DISTRIBUTION to be acoustically lined, provide external insulation in accordance with this specification section and in addition to the acoustical duct lining. Do not use acoustical lining in place of duct wrap or rigid board insulation (insulation on the exterior of the duct).

2.3.2.2 Duct Liner

Flexible Elastomeric Acoustical and Conformable Duct Liner Materials: Flexible Elastomeric Thermal, Acoustical and Conformable Insulation Compliance with ASTM C534/C534M Grade 1, Type II; and NFPA 90A or NFPA 90B as applicable.

2.3.3 Duct Insulation Jackets

2.3.3.1 All-Purpose Jacket

Provide insulation with insulation manufacturer's standard reinforced fire-retardant jacket with or without integral vapor barrier as required by the service. In exposed locations, provide jacket with a white surface suitable for field painting.

2.3.3.2 Metal Jackets

2.3.3.2.1 Aluminum Jackets

ASTM B209, Temper H14, minimum thickness of 27 gauge (0.016 inch), with factory-applied polyethylene and kraft paper moisture barrier on inside surface. Provide smooth surface jackets for jacket outside dimension 8 inches and larger. Provide corrugated surface jackets for jacket outside dimension 8 inches and larger. Provide stainless steel bands, minimum width of 1/2 inch.

2.3.3.2.2 Stainless Steel Jackets

ASTM A167 or ASTM A240/A240M; Type 304, minimum thickness of 33 gauge (0.010 inch), smooth surface with factory-applied polyethylene and kraft paper moisture barrier on inside surface. Provide stainless steel bands, minimum width of 1/2 inch.

2.3.3.3 Vapor Barrier/Weatherproofing Jacket

Vapor barrier/weatherproofing jacket shall be laminated self-adhesive (minimum 2 mils adhesive, 3 mils embossed) less than 0.0000 permeability, (greater than 3 ply, standard grade, silver, white, black and embossed or greater than 8 ply (minimum 2.9 mils adhesive), heavy duty white or natural).

2.3.4 Weatherproof Duct Insulation

Provide ASTM C552, cellular glass thermal insulation, and weatherproofing as specified in manufacturer's instruction. Multi-ply, Polymeric Blend Laminate Jacketing: Construction of laminate designed to provide UV resistance, high puncture, tear resistance and an excellent WVT rate.

2.4 EQUIPMENT INSULATION SYSTEMS

Insulate equipment and accessories as specified in Tables 5 and 6. In outside locations, provide insulation 1/2 inch thicker than specified. Increase the specified insulation thickness for equipment where necessary to equal the thickness of angles or other structural members to make a smooth, exterior surface. Submit a booklet containing manufacturer's published installation instructions for the insulation systems. The instructions must be copyrighted, have an identifying or publication number, and shall have been published prior to the issuance date of this solicitation. A booklet is also required by paragraphs titled: Pipe Insulation Systems and Duct Insulation Systems.

PART 3 EXECUTION

3.1 APPLICATION - GENERAL

Insulation shall only be applied to unheated and uncooled piping and equipment. Flexible elastomeric cellular insulation shall not be compressed at joists, studs, columns, ducts, hangers, etc. The insulation shall not pull apart after a one hour period; any insulation found to pull apart after one hour, shall be replaced.

3.1.1 Display Samples

Submit and display, after approval of materials, actual sections of installed systems, properly insulated in accordance with the specification requirements. Such actual sections must remain accessible to inspection throughout the job and will be reviewed from time to time for controlling the quality of the work throughout the construction site. Each material used shall be identified, by indicating on an attached sheet the specification requirement for the material and the material by each manufacturer intended to meet the requirement. The Contracting Officer will inspect display sample sections at the jobsite. Approved display sample sections shall remain on display at the jobsite during the construction period. Upon completion of construction, the display sample sections will be closed and sealed.

3.1.1.1 Pipe Insulation Display Sections

Display sample sections shall include as a minimum an elbow or tee, a valve, dielectric waterways and flanges, a hanger with protection shield and insulation insert, or dowel as required, at support point, method of fastening and sealing insulation at longitudinal lap, circumferential lap, butt joints at fittings and on pipe runs, and terminating points for each type of pipe insulation used on the job, and for hot pipelines and cold pipelines, both interior and exterior, even when the same type of insulation is used for these services.

3.1.1.2 Duct Insulation Display Sections

Display sample sections for rigid and flexible duct insulation used on the job. Use a temporary covering to enclose and protect display sections for duct insulation exposed to weather

3.1.2 Installation

Except as otherwise specified, material shall be installed in accordance with the manufacturer's written instructions. Insulation materials shall not be applied until tests specified in other sections of this specification are completed. Material such as rust, scale, dirt and moisture shall be removed from surfaces to receive insulation. Insulation shall be kept clean and dry. Insulation shall not be removed from its shipping containers until the day it is ready to use and shall be returned to like containers or equally protected from dirt and moisture at the end of each workday. Insulation that becomes dirty shall be thoroughly cleaned prior to use. If insulation becomes wet or if cleaning does not restore the surfaces to like new condition, the insulation will be rejected, and shall be immediately removed from the jobsite. Joints shall be staggered on multi layer insulation. Mineral fiber thermal insulating cement shall be mixed with demineralized water when used on stainless steel surfaces. Insulation, jacketing and accessories shall be installed in accordance with MICA Insulation Stds plates except where modified herein or on the drawings.

3.1.3 Firestopping

Where pipes and ducts pass through fire walls, fire partitions, above grade floors, and fire rated chase walls, the penetration shall be sealed with fire stopping materials as specified in Section 07 84 00 FIRESTOPPING. The protection of ducts at point of passage through firewalls must be in accordance with NFPA 90A and/or NFPA 90B. All other penetrations, such as piping, conduit, and wiring, through firewalls must be protected with a material or system of the same hourly rating that is listed by UL, FM, or a NRTL.

3.1.4 Painting and Finishing

Painting shall be as specified in Section 09 90 00 PAINTS AND COATINGS.

3.1.5 Installation of Flexible Elastomeric Cellular Insulation

Install flexible elastomeric cellular insulation with seams and joints sealed with rubberized contact adhesive. Flexible elastomeric cellular insulation shall not be used on surfaces greater than 220 degrees F. Stagger seams when applying multiple layers of insulation. Protect

insulation exposed to weather and not shown to have vapor barrier weatherproof jacketing with two coats of UV resistant finish or PVC or metal jacketing as recommended by the manufacturer after the adhesive is dry and cured.

3.1.5.1 Adhesive Application

Apply a brush coating of adhesive to both butt ends to be joined and to both slit surfaces to be sealed. Allow the adhesive to set until dry to touch but tacky under slight pressure before joining the surfaces. Insulation seals at seams and joints shall not be capable of being pulled apart one hour after application. Insulation that can be pulled apart one hour after installation shall be replaced.

3.1.5.2 Adhesive Safety Precautions

Use natural cross-ventilation, local (mechanical) pickup, and/or general area (mechanical) ventilation to prevent an accumulation of solvent vapors, keeping in mind the ventilation pattern must remove any heavier-than-air solvent vapors from lower levels of the workspaces. Gloves and spectacle-type safety glasses are recommended in accordance with safe installation practices.

3.1.6 Pipes/Ducts/Equipment That Require Insulation

Insulation is required on all pipes, ducts, or equipment, except for omitted items as specified.

3.2 DUCT INSULATION SYSTEMS INSTALLATION

Except for oven hood exhaust duct insulation, corner angles shall be installed on external corners of insulation on ductwork in exposed finished spaces before covering with jacket. Air conditioned spaces shall be defined as those spaces directly supplied with cooled conditioned air (or provided with a cooling device such as a fan-coil unit) and heated conditioned air (or provided with a heating device such as a unit heater, radiator or convector).

3.2.1 Duct Insulation Minimum Thickness

Duct insulation minimum thickness in accordance with Table 4.

Table 4 - Minimum Duct Insulation (inches)	
Cold Air Ducts	2.0
Relief Ducts	1.5
Fresh Air Intake Ducts	1.5
Warm Air Ducts	2.0
Relief Ducts	1.5
Fresh Air Intake Ducts	1.5

3.2.2 Insulation and Vapor Retarder/Vapor Barrier for Cold Air Duct

Insulation and vapor retarder/vapor barrier shall be provided for the following cold air ducts and associated equipment.

- a. Supply ducts.
- b. Return air ducts.
- c. Relief ducts.
- d. Flexible run-outs (field-insulated).
- e. Plenums.
- f. Duct-mounted coil casings.
- g. Coil headers and return bends.
- h. Coil casings.
- i. Fresh air intake ducts.
- j. Site-erected air conditioner casings.
- k. Ducts exposed to weather.

Insulation for rectangular ducts shall be flexible type where concealed, minimum density 3/4 pcf, and rigid type where exposed, minimum density 3 pcf. Insulation for both concealed or exposed round/oval ducts shall be flexible type, minimum density 3/4 pcf or a semi rigid board, minimum density 3 pcf, formed or fabricated to a tight fit, edges beveled and joints tightly butted and staggered. Insulation for all exposed ducts shall be provided with either a white, paint-able, factory-applied Type I jacket or a field applied vapor retarder/vapor barrier jacket coating finish as specified, the total field applied dry film thickness shall be approximately 1/16 inch. Insulation on all concealed duct shall be provided with a factory-applied Type I or II vapor retarder/vapor barrier jacket. Duct insulation shall be continuous through sleeves and prepared openings except firewall penetrations. Duct insulation terminating at fire dampers, shall be continuous over the damper collar and retaining angle of fire dampers, which are exposed to unconditioned air and which may be prone to condensate formation. Duct insulation and vapor retarder/vapor barrier shall cover the collar, neck, and any un-insulated surfaces of diffusers, registers and grills. Vapor retarder/vapor barrier materials shall be applied to form a complete unbroken vapor seal over the insulation. Sheet Metal Duct shall be sealed in accordance with Section 23 30 00 HVAC AIR DISTRIBUTION.

3.2.2.1 Installation on Concealed Duct

- a. For rectangular, oval or round ducts, flexible insulation shall be attached by applying adhesive around the entire perimeter of the duct in 6 inch wide strips on 12 inch centers.
- b. For rectangular and round ducts, 24 and larger insulation shall be additionally secured to bottom of ducts by the use of mechanical fasteners. Fasteners shall be spaced on 16 inch centers and not more than 16 inches from duct corners.
- c. For rectangular, oval and round ducts, mechanical fasteners shall be provided on sides of duct risers for all duct sizes. Fasteners shall be spaced on 16 inch centers and not more than 16 inches from duct

corners.

- d. Insulation shall be impaled on the mechanical fasteners (self stick pins) where used and shall be pressed thoroughly into the adhesive. Care shall be taken to ensure vapor retarder/vapor barrier jacket joints overlap 2 inches. The insulation shall not be compressed to a thickness less than that specified. Insulation shall be carried over standing seams and trapeze-type duct hangers.
- e. Where mechanical fasteners are used, self-locking washers shall be installed and the pin trimmed and bent over.
- f. Jacket overlaps shall be secured with staples and tape as necessary to ensure a secure seal. Staples, tape and seams shall be coated with a brush coat of vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate (minimum 2 mils adhesive, 3 mils embossed) - less than 0.0000 perm adhesive tape.
- g. Breaks in the jacket material shall be covered with patches of the same material as the vapor retarder jacket. The patches shall extend not less than 2 inches beyond the break or penetration in all directions and shall be secured with tape and staples. Staples and tape joints shall be sealed with a brush coat of vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate (minimum 2 mils adhesive, 3 mils embossed) - less than 0.0000 perm adhesive tape.
- h. At jacket penetrations such as hangers, thermometers, and damper operating rods, voids in the insulation shall be filled and the penetration sealed with a brush coat of vapor retarder coating or PVDC adhesive tape greater than 3 ply laminate (minimum 2 mils adhesive, 3 mils embossed) - less than 0.0000 perm adhesive tape.
- i. Insulation terminations and pin punctures shall be sealed and flashed with a reinforced vapor retarder coating finish or tape with a brush coat of vapor retarder coating.. The coating shall overlap the adjoining insulation and un-insulated surface 2 inches. Pin puncture coatings shall extend 2 inches from the puncture in all directions.
- j. Where insulation standoff brackets occur, insulation shall be extended under the bracket and the jacket terminated at the bracket.

3.2.2.2 Installation on Exposed Duct Work

- a. For rectangular ducts, rigid insulation shall be secured to the duct by mechanical fasteners on all four sides of the duct, spaced not more than 12 inches apart and not more than 3 inches from the edges of the insulation joints. A minimum of two rows of fasteners shall be provided for each side of duct 12 inches and larger. One row shall be provided for each side of duct less than 12 inches. Mechanical fasteners shall be as corrosion resistant as G60 coated galvanized steel, and shall indefinitely sustain a 50 lb tensile dead load test perpendicular to the duct wall.
- b. Form duct insulation with minimum jacket seams. Fasten each piece of rigid insulation to the duct using mechanical fasteners. When the height of projections is less than the insulation thickness, insulation shall be brought up to standing seams, reinforcing, and other vertical projections and shall not be carried over. Vapor

retarder/barrier jacket shall be continuous across seams, reinforcing, and projections. When height of projections is greater than the insulation thickness, insulation and jacket shall be carried over. Apply insulation with joints tightly butted. Neatly bevel insulation around name plates and access plates and doors.

- c. Impale insulation on the fasteners; self-locking washers shall be installed and the pin trimmed and bent over.
- d. Seal joints in the insulation jacket with a 4 inch wide strip of tape. Seal taped seams with a brush coat of vapor retarder coating.
- e. Breaks and ribs or standing seam penetrations in the jacket material shall be covered with a patch of the same material as the jacket. Patches shall extend not less than 2 inches beyond the break or penetration and shall be secured with tape and stapled. Staples and joints shall be sealed with a brush coat of vapor retarder coating.
- f. At jacket penetrations such as hangers, thermometers, and damper operating rods, the voids in the insulation shall be filled and the penetrations sealed with a flashing sealant.
- g. Insulation terminations and pin punctures shall be sealed and flashed with a reinforced vapor retarder coating finish. The coating shall overlap the adjoining insulation and un-insulated surface 2 inches. Pin puncture coatings shall extend 2 inches from the puncture in all directions.
- h. Oval and round ducts, flexible type, shall be insulated with factory Type I jacket insulation with minimum density of 3/4 pcf, attached as in accordance with MICA standards.

3.2.3 Insulation for Warm Air Duct

Insulation and vapor barrier shall be provided for the following warm air ducts and associated equipment:.

- a. Supply ducts.
- b. Return air ducts.
- c. Relief air ducts
- d. Flexible run-outs (field insulated).
- e. Plenums.
- f. Duct-mounted coil casings.
- g. Coil-headers and return bends.
- h. Coil casings.
- i. Fresh air intake ducts.
- j. Supply fans.
- k. Site-erected air conditioner casings.

- l. Ducts exposed to weather.
- m. Exhaust ducts passing through concealed spaces exhausting conditioned air.

Insulation for rectangular ducts shall be flexible type where concealed, and rigid type where exposed. Insulation on exposed ducts shall be provided with a white, paint-able, factory-applied Type II jacket, or finished with adhesive finish. Flexible type insulation shall be used for round ducts, with a factory-applied Type II jacket. Insulation on concealed duct shall be provided with a factory-applied Type II jacket. Adhesive finish where indicated to be used shall be accomplished by applying two coats of adhesive with a layer of glass cloth embedded between the coats. The total dry film thickness shall be approximately 1/16 inch. Duct insulation shall be continuous through sleeves and prepared openings. Duct insulation shall terminate at fire dampers and flexible connections.

3.2.3.1 Installation on Concealed Duct

- a. For rectangular, oval and round ducts, insulation shall be attached by applying adhesive around the entire perimeter of the duct in 6 inch wide strips on 12 inch centers.
- b. For rectangular and oval ducts 24 inches and larger, insulation shall be secured to the bottom of ducts by the use of mechanical fasteners. Fasteners shall be spaced on 18 inch centers and not more than 18 inches from duct corner.
- c. For rectangular, oval and round ducts, mechanical fasteners shall be provided on sides of duct risers for all duct sizes. Fasteners shall be spaced on 18 inch centers and not more than 18 inches from duct corners.
- d. The insulation shall be impaled on the mechanical fasteners where used. The insulation shall not be compressed to a thickness less than that specified. Insulation shall be carried over standing seams and trapeze-type hangers.
- e. Self-locking washers shall be installed where mechanical fasteners are used and the pin trimmed and bent over.
- f. Insulation jacket shall overlap not less than 2 inches at joints and the lap shall be secured and stapled on 4 inch centers.

3.2.3.2 Installation on Exposed Duct

- a. For rectangular ducts, the rigid insulation shall be secured to the duct by the use of mechanical fasteners on all four sides of the duct, spaced not more than 16 inches apart and not more than 6 inches from the edges of the insulation joints. A minimum of two rows of fasteners shall be provided for each side of duct 12 inches and larger and a minimum of one row for each side of duct less than 12 inches.
- b. Duct insulation with factory-applied jacket shall be formed with minimum jacket seams, and each piece of rigid insulation shall be fastened to the duct using mechanical fasteners. When the height of projection is less than the insulation thickness, insulation shall be brought up to standing seams, reinforcing, and other vertical

projections and shall not be carried over the projection. Jacket shall be continuous across seams, reinforcing, and projections. Where the height of projections is greater than the insulation thickness, insulation and jacket shall be carried over the projection.

- c. Insulation shall be impaled on the fasteners; self-locking washers shall be installed and pin trimmed and bent over.
- d. Joints on jacketed insulation shall be sealed with a 4 inch wide strip of tape and brushed with vapor retarder coating.
- e. Breaks and penetrations in the jacket material shall be covered with a patch of the same material as the jacket. Patches shall extend not less than 2 inches beyond the break or penetration and shall be secured with adhesive and stapled.
- f. Insulation terminations and pin punctures shall be sealed with tape and brushed with vapor retarder coating.
- g. Oval and round ducts, flexible type, shall be insulated with factory Type I jacket insulation, minimum density of 3/4 pcf attached by staples spaced not more than 16 inches and not more than 6 inches from the degrees of joints. Joints shall be sealed in accordance with item "d." above.

3.2.4 Ducts Handling Air for Dual Purpose

For air handling ducts for dual purpose below and above 60 degrees F, ducts shall be insulated as specified for cold air duct.

3.2.5 Insulation for Evaporative Cooling Duct

Evaporative cooling supply duct located in spaces not evaporatively cooled, shall be insulated. Material and installation requirements shall be as specified for duct insulation for warm air duct.

3.2.6 Duct Test Holes

After duct systems have been tested, adjusted, and balanced, breaks in the insulation and jacket shall be repaired in accordance with the applicable section of this specification for the type of duct insulation to be repaired.

3.2.7 Duct Exposed to Weather

3.2.7.1 Installation

Ducts exposed to weather shall be insulated and finished as specified for the applicable service for exposed duct inside the building. After the above is accomplished, the insulation shall then be further finished as detailed in the following subparagraphs.

3.2.7.2 Round Duct

Laminated self-adhesive (minimum 2 mils adhesive, 3 mils embossed) vapor barrier/weatherproofing jacket - Less than 0.0000 permeability, (greater than 3 ply, standard grade, silver, white, black and embossed or greater than 8 ply, heavy duty, white and natural) membrane shall be applied overlapping material by 3 inches no bands or caulking needed - see

manufacturer's recommended installation instructions. Aluminum jacket with factory applied moisture retarder shall be applied with the joints lapped not less than 3 inches and secured with bands located at circumferential laps and at not more than 12 inch intervals throughout. Horizontal joints shall lap down to shed water and located at 4 or 8 o'clock position. Joints shall be sealed with metal jacketing sealant to prevent moisture penetration. Where jacketing abuts an un-insulated surface, joints shall be sealed with metal jacketing sealant.

3.2.7.3 Fittings

Fittings and other irregular shapes shall be finished as specified for rectangular ducts.

3.2.7.4 Rectangular Ducts

Two coats of weather barrier mastic reinforced with fabric or mesh for outdoor application shall be applied to the entire surface. Each coat of weatherproof mastic shall be 1/16 inch minimum thickness. The exterior shall be a metal jacketing applied for mechanical abuse and weather protection, and secured with screws or vapor barrier/weatherproofing jacket less than 0.0000 permeability greater than 3 ply, standard grade, silver, white, black, and embossed or greater than 8 ply, heavy duty white and natural. Membrane shall be applied overlapping material by 3 inches. No bands or caulking needed-see manufacturing recommend installation instructions.

3.3 EQUIPMENT INSULATION SYSTEMS INSTALLATION

3.3.1 General

Removable insulation sections shall be provided to cover parts of equipment that must be opened periodically for maintenance including vessel covers, fasteners, flanges and accessories. Equipment insulation shall be omitted on the following:

- a. Hand-holes.
- b. Cleanouts.
- c. ASME stamps.
- d. Manufacturer's nameplates.
- e. Duct Test/Balance Test Holes.

3.3.2 Insulation for Cold Equipment

3.3.2.1 Other Equipment

- a. Insulation shall be formed or fabricated to fit the equipment. To ensure a tight fit on round equipment, edges shall be beveled and joints shall be tightly butted and staggered.
- b. Insulation shall be secured in place with bands or wires at intervals as recommended by the manufacturer but not more than 12 inch centers except flexible elastomeric cellular which shall be adhered with contact adhesive. Insulation corners shall be protected under wires and bands with suitable corner angles.

- c. Cellular glass shall be installed in accordance with manufacturer's instructions. Joints and ends shall be sealed with joint sealant, and sealed with a vapor retarder coating.
- d. Insulation on heads of heat exchangers shall be removable. Removable section joints shall be fabricated using a male-female shiplap type joint. The entire surface of the removable section shall be finished by applying two coats of vapor retarder coating with a layer of glass cloth embedded between the coats. The total dry thickness of the finish shall be 1/16 inch.
- e. Exposed insulation corners shall be protected with corner angles.
- f. Insulation on equipment with ribs shall be applied over 6 by 6 inches by 12 gauge welded wire fabric which has been cinched in place, or if approved by the Contracting Officer, spot welded to the equipment over the ribs. Insulation shall be secured to the fabric with J-hooks and 2 by 2 inches washers or shall be securely banded or wired in place on 12 inch centers.

3.3.2.2 Vapor Retarder/Vapor Barrier

Upon completion of installation of insulation, penetrations shall be caulked. Two coats of vapor retarder coating or vapor barrier jacket shall be applied over insulation, including removable sections, with a layer of open mesh synthetic fabric embedded between the coats. The total dry thickness of the finish shall be 1/16 inch. Flashing sealant or vapor barrier tape shall be applied to parting line between equipment and removable section insulation.

3.3.3 Insulation for Hot Equipment

3.3.3.1 Other Equipment

- a. Insulation shall be formed or fabricated to fit the equipment. To ensure a tight fit on round equipment, edges shall be beveled and joints shall be tightly butted and staggered.
- b. Insulation shall be secured in place with bands or wires at intervals as recommended by the manufacturer but not greater than 12 inch centers except flexible elastomeric cellular which shall be adhered. Insulation corners shall be protected under wires and bands with suitable corner angles.
- c. On high vibration equipment, cellular glass insulation shall be set in a coating of bedding compound as recommended by the manufacturer, and joints shall be sealed with bedding compound. Mineral fiber joints shall be filled with finishing cement.
- d. Insulation on heads of heat exchangers shall be removable. The removable section joint shall be fabricated using a male-female shiplap type joint. Entire surface of the removable section shall be finished as specified.
- e. Exposed insulation corners shall be protected with corner angles.
- f. On equipment with ribs, such as boiler flue gas connection, draft fans, and fly ash or soot collectors, insulation shall be applied over

6 by 6 inch by 12 gauge welded wire fabric which has been cinched in place, or if approved by the Contracting Officer, spot welded to the equipment over the ribs. Insulation shall be secured to the fabric with J-hooks and 2 by 2 inch washers or shall be securely banded or wired in place on 12 inch (maximum) centers.

- g. On equipment handling media above 600 degrees F, insulation shall be applied in two or more layers with joints staggered.
- h. Upon completion of installation of insulation, penetrations shall be caulked. Two coats of adhesive shall be applied over insulation, including removable sections, with a layer of glass cloth embedded between the coats. The total dry thickness of the finish shall be 1/16 inch. Caulking shall be applied to parting line between equipment and removable section insulation.

3.3.4 Equipment Handling Dual Temperature Media

Below and above 60 degrees F: equipment handling dual temperature media shall be insulated as specified for cold equipment.

3.3.5 Equipment Exposed to Weather

3.3.5.1 Installation

Equipment exposed to weather shall be insulated and finished in accordance with the requirements for ducts exposed to weather in paragraph DUCT INSULATION INSTALLATION.

3.3.5.2 Optional Panels

At the option of the Contractor, prefabricated metal insulation panels may be used in lieu of the insulation and finish previously specified. Thermal performance shall be equal to or better than that specified for field applied insulation. Panels shall be the standard catalog product of a manufacturer of metal insulation panels. Fastenings, flashing, and support system shall conform to published recommendations of the manufacturer for weatherproof installation and shall prevent moisture from entering the insulation. Panels shall be designed to accommodate thermal expansion and to support a 250 pound walking load without permanent deformation or permanent damage to the insulation. Exterior metal cover sheet shall be aluminum and exposed fastenings shall be stainless steel or aluminum.

-- End of Section --

SECTION 23 11 25

FACILITY GAS PIPING
11/08

PART 1 GENERAL

1.1 SUMMARY

This specification section applies to gas piping installed within buildings incidental underground piping under building, above ground steel piping and corrugated stainless steel tubing (CSST) both outside (up to 5 feet beyond exterior walls) and within buildings in compliance with NFPA 54 /AGA Z223.1, "National Fuel Gas Code" NFPA 58, "Fuel Gas Piping".

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN GAS ASSOCIATION (AGA)

AGA XR0603 (2006; 8th Ed) AGA Plastic Pipe Manual for Gas Service

AGA Z223.1 (2012) National Fuel Gas Code

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z21.15/CSA 9.1 (2009; Addenda A 2012, Addenda B 2013; R 2019) Manually Operated Gas Valves for Appliances, Appliance Connector Valves and Hose End Valves

ANSI Z21.18/CSA 6.3 (2007; R 2017) Gas Appliance Pressure Regulators

ANSI Z21.21/CSA 6.5 (2015) Automatic Valves for Gas Appliances

ANSI Z21.24/CSA 6.10 (2015; Errata 2017) Connectors for Gas Appliances

ANSI Z21.41/CSA 6.9 (2014; R 2019) Quick-Disconnect Devices for Use with Gas Fuel Appliances

ANSI Z21.69/CSA 6.16 (2009; Addenda A 2012; R 2014) Connectors for Movable Gas Appliances

ANSI Z21.80/CSA 6.22 (2019) Line Pressure Regulators

AMERICAN PETROLEUM INSTITUTE (API)

API RP 1110 (2013; R 2018) Recommended Practice for the Pressure Testing of Steel Pipelines for the Transportation of Gas, Petroleum Gas, Hazardous Liquids, Highly Volatile

Liquids, or Carbon Dioxide

API RP 2009	(2002; R 2007; 7th Ed) Safe Welding, Cutting, and Hot Work Practices in Refineries, Gasoline Plants, and Petrochemical Plants
API Spec 6D	(June 2018, 4th Ed; Errata 1 July 2018; Errata 2 August 2018) Specification for Pipeline and Piping Valves
API Std 598	(2009) Valve Inspecting and Testing
API Std 607	(2016) Fire Test for Quarter-turn Valves and Valves Equipped with Non-metallic Seats

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME A13.1	(2015) Scheme for the Identification of Piping Systems
ASME B1.1	(2003; R 2018) Unified Inch Screw Threads (UN and UNR Thread Form)
ASME B1.20.1	(2013; R 2018) Pipe Threads, General Purpose (Inch)
ASME B16.21	(2016) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B16.33	(2012; R 2017) Manually Operated Metallic Gas Valves for Use in Gas Piping Systems Up to 125 psi, (Sizes NPS 1/2 - NPS 2)
ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(2015) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B31.9	(2017) Building Services Piping
ASME BPVC SEC IX	(2017; Errata 2018) BPVC Section IX-Welding, Brazing and Fusing Qualifications

ASTM INTERNATIONAL (ASTM)

ASTM A193/A193M	(2019) Standard Specification for Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service and Other Special Purpose Applications
ASTM A194/A194M	(2018) Standard Specification for Carbon Steel, Alloy Steel, and Stainless Steel Nuts for Bolts for High-Pressure or High-Temperature Service, or Both

CSA GROUP (CSA)

ANSI LC 1/CSA 6.26 (2018) Fuel Gas Piping Systems Using
Corrugated Stainless Steel Tubing (CSST)

CGA 9.2-M88 (1988; R 2009) Manually Operated Shut-Off
Valves for Gas Piping Systems

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS
INDUSTRY (MSS)

MSS SP-25 (2018) Standard Marking System for Valves,
Fittings, Flanges and Unions

MSS SP-58 (2018) Pipe Hangers and Supports -
Materials, Design and Manufacture,
Selection, Application, and Installation

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 54 (2018) National Fuel Gas Code

NFPA 58 (2020) Liquefied Petroleum Gas Code

NFPA 70 (2020; ERTA 20-1 2020; ERTA 20-2 2020; TIA
20-1; TIA 20-2; TIA 20-3; TIA 20-4)
National Electrical Code

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC SP 6/NACE No.3 (2007) Commercial Blast Cleaning

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-STD-101 (2014; Rev C) Color Code for Pipelines and
for Compressed Gas Cylinders

UNDERWRITERS LABORATORIES (UL)

UL FLAMMABLE & COMBUSTIBLE (2012) Flammable and Combustible Liquids
and Gases Equipment Directory

1.3 SYSTEM DESCRIPTION

The gas piping system includes natural gas piping and appurtenances from point of connection with supply system, as indicated, to gas operated equipment within the facility. Submit operation and maintenance data in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA, in three separate packages.

1.3.1 Gas Facility System and Equipment Operation

Include shop drawings showing piping layout, locations of system valves, gas line markers; step-by-step procedures for system start up, operation and shutdown (index system components and equipment to the system drawings); isolation procedures including valve operation to shutdown or isolate each section of the system (index valves to the system maps and provide separate procedures for normal operation and emergency shutdown if required to be different). Submit Data package No. 4.

1.3.2 Gas Facility System Maintenance

Include maintenance procedures and frequency for system and equipment; identification of pipe materials and manufacturer by locations, pipe repair procedures, and jointing procedures at transitions to other piping material or material from a different manufacturer. Submit Data Package No.4.

1.3.3 Gas Facility Equipment Maintenance

Include identification of valves, shut-offs, disconnects, and other equipment by materials, manufacturer, vendor identification and location; maintenance procedures and recommended tool kits for valves and equipment; recommended repair methods (i.e., field repair, factory repair, or replacement) for each valve and piece of equipment; and preventive maintenance procedures, possible failure modes and troubleshooting guide. Submit Data Package No. 3.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Gas Piping System; G

SD-03 Product Data

Pipe and Fittings; G

Gas Equipment Connectors; G

Gas Piping System; G

Pipe Coating Materials; G

Pressure Regulators; G

Risers; G

Transition Fittings; G

Valves; G

Warning and Identification Tape; G

SD-06 Test Reports

Testing; G

Pressure Tests; G

Test with Gas; G

SD-07 Certificates

Welders Procedures and Qualifications; G

Assigned Number, Letter, or Symbol; G

SD-08 Manufacturer's Instructions

PE Pipe and Fittings; G

Pipe Coating Materials; G

SD-10 Operation and Maintenance Data

Gas Facility System and Equipment Operation; G

Gas Facility System Maintenance; G

Gas Facility Equipment Maintenance; G

1.5 QUALITY ASSURANCE

Submit manufacturer's descriptive data and installation instructions for approval for compression-type mechanical joints used in joining dissimilar materials and for insulating joints. Mark all valves, flanges and fittings in accordance with MSS SP-25.

1.5.1 Welding Qualifications

- a. Weld piping in accordance with qualified procedures using performance qualified welders and welding operators in accordance with API RP 2009, ASME BPVC SEC IX, and ASME B31.9. Welding procedures qualified by others, and welders and welding operators qualified by another employer may be accepted as permitted by ASME B31.9. Notify the Contracting Officer at least 24 hours in advance of tests, and perform at the work site if practicable.
- b. Submit a certified copy of welders procedures and qualifications metal and PE in conformance with ASME B31.9 for each welder and welding operator. Submit the assigned number, letter, or symbol that will be used in identifying the work of each welder to the Contracting Officer.

1.5.2 Jointing Thermoplastic and Fiberglass Piping

Perform all jointing of piping using qualified joiners and qualified procedures in accordance with AGA XR0603. Furnish the Contracting Officer with a copy of qualified procedures and list of and identification symbols of qualified joiners. Submit manufacturer's installation instructions and manufacturer's visual joint appearance chart, including all PE pipe and fittings.

1.5.3 Shop Drawings

Submit drawings for complete Gas Piping System, within 30 days of contract award, showing location, size and all branches of pipeline; location of all required shutoff valves; and instructions necessary for the installation of gas equipment connectors and supports. Include LP storage tank, pad, and mounting details.

1.6 DELIVERY, STORAGE, AND HANDLING

1.6.1 Plastic Pipe

Handle, transport, and store plastic pipe and fittings carefully. Plug or cap pipe and fittings ends during transportation or storage to minimize dirt and moisture entry. Do not subject piping to abrasion or concentrated external loads. Discard PE pipe sections and fittings that have been damaged.

1.6.2 CSST Tubing

Handle, transport and store CSST tubing on the wooden spool or shipping container provided by the manufacturer. Insure tubing ends are capped during transportation and storage to minimize dirt and moisture entry. Discard any tubing segment and fitting that has been damaged.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

Provide materials and equipment which are the standard products of a manufacturer regularly engaged in the manufacture of the products and that essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening. Asbestos or products containing asbestos are not allowed. Submit catalog data and installation instructions for pipe, valves, all related system components, pipe coating materials and application procedures. Conform to NFPA 54NFPA 58 and with requirements specified herein. Provide supply piping to appliances or equipment at least as large as the inlets thereof.

2.2 GAS PIPING SYSTEM AND FITTINGS

2.2.1 Sealants for Steel Pipe Threaded Joints

Provide joint sealing compound as listed in UL FLAMMABLE & COMBUSTIBLE, Class 20 or less. For taping, use tetrafluoroethylene tape conforming to UL FLAMMABLE & COMBUSTIBLE.

2.2.2 Warning and Identification

Provide pipe flow markings, warning and identification tape, and metal tags as required.

2.2.3 Flange Gaskets

Provide gaskets of nonasbestos compressed material in accordance with ASME B16.21, 1/16 inch thickness, full face or self-centering flat ring type, containing aramid fibers bonded with styrene butadiene rubber (SBR) or nitrile butadiene rubber (NBR) suitable for a maximum 600 degree F service, to be used for hydrocarbon service.

2.2.4 Pipe Threads

Provide pipe threads conforming to ASME B1.20.1.

2.2.5 Escutcheons

Provide chromium-plated steel or chromium-plated brass escutcheons, either one piece or split pattern, held in place by internal spring tension or set screw.

2.2.6 Gas Transition Fittings

- a. Provide steel to plastic (PE) designed for steel-to-plastic with tapping tee or sleeve conforming to AGA XR0603 requirements for transitions fittings.. Coat or wrap exposed steel pipe with heavy plastic coating.
- c. Provide manually operated shut-off valve conforming to CGA 9.2-M88

2.2.7 Insulating Pipe Joints

2.2.7.1 Insulating Joint Material

Provide insulating joint material between flanged or threaded metallic pipe systems where shown to control galvanic or electrical action.

2.2.7.2 Threaded Pipe Joints

Provide threaded pipe joints of steel body nut type dielectric unions with insulating gaskets.

2.2.7.3 Flanged Pipe Joints

Provide joints for flanged pipe consisting of full face sandwich-type flange insulating gasket of the dielectric type, insulating sleeves for flange bolts, and insulating washers for flange nuts.

2.2.8 Flexible Connectors

- a. Provide flexible connectors for connecting gas utilization equipment to building gas piping conforming to ANSI Z21.24/CSA 6.10 or ANSI Z21.41/CSA 6.9 for quick disconnect devices, and flexible connectors for movable food service equipment conforming to ANSI Z21.69/CSA 6.16.
- b. Do not install the flexible connector through the appliance cabinet face. Provide rigid metallic pipe and fittings to extend the final connection beyond the cabinet, except when appliance is provided with an external connection point.

2.3 VALVES

Provide lockable shutoff or service isolation valves as indicated in the drawings conforming to the following:

2.3.1 Valves 2 Inches and Smaller

Provide valves 2 inches and smaller conforming to ASME B16.33 of materials and manufacture compatible with system materials used.

2.3.2 Valves 2-1/2 Inches and Larger

Provide valves 2-1/2 inches and larger of carbon steel conforming to

API Spec 6D, Class 150.

2.4 RISERS

Provide manufacturer's standard riser, transition from plastic to steel pipe with 7 to 12 mil thick epoxy coating. Use swaged gas-tight construction with O-ring seals, metal insert, and protective sleeve. Provide remote bolt-on or bracket or wall-mounted riser supports .

2.5 PIPE HANGERS AND SUPPORTS

Provide pipe hangers and supports conforming to MSS SP-58.

2.6 LINE AND APPLIANCE REGULATORS AND SHUTOFF VALVES

Provide regulators conforming to ANSI Z21.18/CSA 6.3 for appliances , and ANSI Z21.80/CSA 6.22 for line pressure regulators. Provide shutoff valves conforming to ANSI Z21.15/CSA 9.1 for manually controlled gas shutoff valves and ANSI Z21.21/CSA 6.5 for automatic shutoff valves for gas appliances.

2.7 BOLTING (BOLTS AND NUTS)

Stainless steel bolting; ASTM A193/A193M, Grade B8M or B8MA, Type 316, for bolts; and ASTM A194/A194M, Grade 8M, Type 316, for nuts. Dimensions of bolts, studs, and nuts must conform with ASME B18.2.1 and ASME B18.2.2 with coarse threads conforming to ASME B1.1, with Class 2A fit for bolts and studs and Class 2B fit for nuts. Bolts or bolt-studs must extend through the nuts and may have reduced shanks of a diameter not less than the diameter at root of threads. Bolts must have American Standard regular square or heavy hexagon heads; nuts must be American Standard heavy semifinished hexagonal.

2.8 GASKETS

Fluorinated elastomer, compatible with flange faces.

2.9 IDENTIFICATION FOR ABOVEGROUND PIPING

MIL-STD-101 for legends and type and size of characters. For pipes 3/4 inch od and larger, provide printed legends to identify contents of pipes and arrows to show direction of flow. Color code label backgrounds to signify levels of hazard. Make labels of plastic sheet with pressure-sensitive adhesive suitable for the intended application. For pipes smaller than 3/4 inch od, provide brass identification tags 1 1/2 inches in diameter with legends in depressed black-filled characters.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy or areas of conflict before performing the work.

3.2 EXCAVATION AND BACKFILLING

Provide required excavation, backfilling, and compaction as specified in Section 31 00 00 EARTHWORK.

3.3 GAS PIPING SYSTEM

Provide a gas piping system from the point of delivery, defined as the outlet of the meter set assembly, to the connections to each gas utilization device that is in compliance with NFPA 54.

3.3.1 Protection and Cleaning of Materials and Components

Protect equipment, pipe, and tube openings by closing with caps or plugs during installation. At the completion of all work, thoroughly clean the entire system.

3.3.2 Workmanship and Defects

Piping, tubing and fittings must be clear and free of cutting burrs and defects in structure or threading and must be thoroughly brushed and chip-and scale-blown. Repair of defects in piping, tubing or fittings is not allowed; replace defective items when found.

3.4 PROTECTIVE COVERING

3.4.1 Aboveground Metallic Piping Systems

3.4.1.1 Ferrous Surfaces

Touch up shop primed surfaces with ferrous metal primer. Solvent clean surfaces that have not been shop primed. Mechanically clean surfaces that contain loose rust, loose mill scale and other foreign substances by power wire brushing or commercial sand blasted conforming to SSPC SP 6/NACE No.3 and prime with ferrous metal primer or vinyl type wash coat. Finish primed surfaces with two coats of exterior oil paint or vinyl paint.

3.5 INSTALLATION

Install the gas system in conformance with the manufacturer's recommendations and applicable provisions of NFPA 54, NFPA 58 and AGA XR0603, and as indicated. Perform all pipe cutting without damage to the pipe, with an approved type of mechanical cutter, unless otherwise authorized. Use wheel cutters where practicable. On steel pipe 6 inches and larger, an approved gas cutting and beveling machine may be used. Cut thermoplastic and fiberglass pipe in accordance with AGA XR0603.

3.5.1 Metallic Piping Installation

Bury underground piping a minimum of 18 inches below grade. Make changes in direction of piping with fittings only; mitering or notching pipe to form elbows and tees or other similar type construction is not permitted. Branch connection may be made with either tees or forged branch outlet fittings. Provide branch outlet fittings which are forged, flared for improvement of flow where attached to the run, and reinforced against external strains. Do not use aluminum alloy pipe in exterior locations or underground.

3.5.2 Metallic Tubing Installation

Install metallic tubing using gas tubing fittings approved by the tubing manufacturer. CSST gas piping systems must be installed by contractors

who have completed the manufacturer's training program as indicated on a certification card. Make branch connections with tees. Prepare all tubing ends with tools designed for that purpose. Do not use aluminum alloy tubing in exterior locations or underground. Maintain electrical continuity of gas piping system in accordance with NFPA 54 , paragraph entitled 'Electrical Bonding and Grounding'.

3.5.3 Concealed Piping in Buildings

Do not use combinations of fittings (unions, tubing fittings, running threads, right- and left-hand couplings, bushings, and swing joints) to conceal piping within buildings.

3.5.3.1 Piping and Tubing in Partitions

Locate concealed piping and tubing in hollow, rather than solid, partitions. Protect tubing passing through walls or partitions against physical damage both during and after construction, and provide appropriate safety markings and labels. Provide protection of concealed pipe and tubing in accordance with ANSI LC 1/CSA 6.26.

3.5.4 Aboveground Piping

Run aboveground piping as straight as practicable along the alignment and elevation indicated, with a minimum of joints, and separately supported from other piping system and equipment. Install exposed horizontal piping no farther than 6 inches from nearest parallel wall and at an elevation which prevents standing, sitting, or placement of objects on the piping.

3.5.5 Final Gas Connections

Flexible connectors may be used for final connections to gas utilization equipment. In addition to cautions listed in instructions required by ANSI standards for flexible connectors, insure that flexible connectors do not pass through equipment cabinet. Provide accessible gas shutoff valve and coupling for each gas equipment item.

3.6 PIPE JOINTS

Design and install pipe joints to effectively sustain the longitudinal pull-out forces caused by contraction of the piping or superimposed loads.

3.6.1 Threaded Metallic Joints

Provide threaded joints in metallic pipe with tapered threads evenly cut and made with UL approved graphite joint sealing compound for gas service or tetrafluoroethylene tape applied to the male threads only. Threaded joints up to 1-1/2 inches in diameter may be made with approved tetrafluoroethylene tape. Threaded joints up to 2 inches in diameter may be made with approved joint sealing compound. After cutting and before threading, ream pipe and remove all burrs. Caulking of threaded joints to stop or prevent leaks is not permitted.

3.6.2 Welded Metallic Joints

Conform beveling, alignment, heat treatment, and inspection of welds to NFPA 54. Remove weld defects and make repairs to the weld, or remove the weld joints entirely and reweld. After filler metal has been removed from its original package, protect and store so that its characteristics or

welding properties are not affected adversely. Do not use electrodes that have been wetted or have lost any of their coating.

3.7 PIPE SLEEVES

Provide pipes passing through concrete or masonry walls or concrete floors or roofs with pipe sleeves fitted into place at the time of construction. Do not install sleeves in structural members except where indicated or approved. Make all rectangular and square openings as detailed. Extend each sleeve through its respective wall, floor or roof, and cut flush with each surface, except in mechanical room floors not located on grade where clamping flanges or riser pipe clamps are used. Extend sleeves in mechanical room floors above grade at least 4 inches above finish floor. Unless otherwise indicated, use sleeves large enough to provide a minimum clearance of 1/4 inch all around the pipe. Provide steel pipe for sleeves in bearing walls, waterproofing membrane floors, and wet areas. Provide sleeves in nonbearing walls, floors, or ceilings of steel pipe, galvanized sheet metal with lock-type longitudinal seam, or moisture-resistant fiber or plastic. For penetrations of fire walls, fire partitions and floors which are not on grade, seal the annular space between the pipe and sleeve with fire-stopping material and sealant that meet the requirement of Section 07 84 00 FIRESTOPPING.

3.8 PIPES PENETRATING WATERPROOFING MEMBRANES

Install pipes penetrating waterproofing membranes as specified in Section 22 00 00 PLUMBING, GENERAL PURPOSE.

3.9 FIRE SEAL

Fire seal all penetrations of fire rated partitions, walls and floors in accordance with Section 07 84 00 FIRESTOPPING.

3.10 ESCUTCHEONS

Provide escutcheons for all finished surfaces where gas piping passes through floors, walls, or ceilings except in boiler, utility, or equipment rooms.

3.11 SPECIAL REQUIREMENTS

Provide drips, grading of the lines, freeze protection, and branch outlet locations as shown and conforming to the requirements of NFPA 54NFPA 58.

3.12 BUILDING STRUCTURE

Do not weaken any building structure by the installation of any gas piping. Do not cut or notch beams, joists or columns. Attach piping supports to metal decking. Do not attach supports to the underside of concrete filled floors or concrete roof decks unless approved by the Contracting Officer.

3.13 PIPING SYSTEM SUPPORTS

Support gas piping systems in buildings with pipe hooks, metal pipe straps, bands or hangers suitable for the size of piping or tubing. Do not support any gas piping system by other piping. Conform spacing of supports in gas piping and tubing installations to the requirements of NFPA 54NFPA 58. Conform the selection and application of supports in gas

piping and tubing installations to the requirements of MSS SP-58. In the support of multiple pipe runs on a common base member, use a clip or clamp where each pipe crosses the base support member. Spacing of the base support members is not to exceed the hanger and support spacing required for any of the individual pipes in the multiple pipe run. Rigidly connect the clips or clamps to the common base member. Provide a clearance of 1/8 inch between the pipe and clip or clamp for all piping which may be subjected to thermal expansion.

3.14 ELECTRICAL BONDING AND GROUNDING

Provide a gas piping system within the building that is electrically continuous and bonded to a grounding electrode as required by NFPA 54, NFPA 58, and NFPA 70.

3.15 LINE AND APPLIANCE PRESSURE REGULATORS

Install line pressure regulators and appliance regulators in accordance with the manufacturer's requirements and in accordance with NFPA 54. Install each regulator in an accessible location and install shutoff valves ahead of each line and appliance regulator to allow for maintenance. Where vent limiting devices are not included in the regulators, install a vent pipe to the exterior of the building. Terminate all service regulator vents and relief vents in the outside air in rain and insect resistant fittings. Locate the open end of the vent where gas can escape freely into the atmosphere, away from any openings into the building and above areas subject to flooding.

3.16 TESTING

Submit test procedures and reports in booklet form tabulating test and measurements performed; dated after award of this contract, and stating the Contractor's name and address, the project name and location, and a list of the specific requirements which are being certified. Test entire gas piping system to ensure that it is gastight prior to putting into service. Prior to testing, purge the system, clean, and clear all foreign material. Test each joint with an approved gas detector, soap and water, or an equivalent nonflammable solution. Inspect and test each valve in conformance with API Std 598 and API Std 607. Complete testing before any work is covered, enclosed, or concealed, and perform with due regard for the safety of employees and the public during the test. Install bulkheads, anchorage and bracing suitably designed to resist test pressures if necessary, and as directed and or approved by the Contracting Officer. Do not use oxygen as a testing medium.

3.16.1 Pressure Tests

Submit test procedures and reports in booklet form tabulating test and measurements performed; dated after award of this contract, and stating the Contractor's name and address, the project name and location, and a list of the specific requirements which are being certified. Before appliances are connected, test by filling the piping systems with air or an inert gas to withstand a minimum pressure of 3 pounds gauge for a period of not less than 10 minutes as specified in NFPA 54 as specified in NFPA 58 without showing any drop in pressure. Do not use Oxygen for test. Measure pressure with a mercury manometer, slope gauge, or an equivalent device calibrated to be read in increments of not greater than 0.1 pound. Isolate the source of pressure before the pressure tests are made.

3.16.2 Test With Gas

Before turning on gas under pressure into any piping, close all openings from which gas can escape. Immediately after turning on the gas, check the piping system for leakage by using a laboratory-certified gas meter, an appliance orifice, a manometer, or equivalent device. Conform all testing to the requirements of NFPA 54NFPA 58. If leakage is recorded, shut off the gas supply, repair the leak , and repeat the tests until all leaks have been stopped.

3.16.3 Purging

After testing is completed, and before connecting any appliances, fully purge all gas piping. LPG piping tested using fuel gas with appliances connected does not require purging. Conform testing procedures to API RP 1110. Do not purge piping into the combustion chamber of an appliance. Do not purge the open end of piping systems into confined spaces or areas where there are ignition sources unless the safety precautions recommended in NFPA 54NFPA 58 are followed.

3.16.4 Labor, Materials and Equipment

Furnish all labor, materials and equipment necessary for conducting the testing and purging.

3.17 PIPE COLOR CODE MARKING

Provide color code marking of piping as specified in Section 09 90 00 PAINTS AND COATINGS, conforming to ASME A13.1.

-- End of Section --

SECTION 26 20 00

INTERIOR DISTRIBUTION SYSTEM

08/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B1	(2013) Standard Specification for Hard-Drawn Copper Wire
ASTM B8	(2011; R 2017) Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
ASTM D709	(2017) Standard Specification for Laminated Thermosetting Materials

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 81	(2012) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System
IEEE 100	(2000; Archived) The Authoritative Dictionary of IEEE Standards Terms
IEEE C2	(2017; Errata 1-2 2017; INT 1 2017) National Electrical Safety Code

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2017; Errata 2017) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI C80.1	(2005) American National Standard for Electrical Rigid Steel Conduit (ERSC)
ANSI C80.3	(2015) American National Standard for Electrical Metallic Tubing (EMT)
ANSI C80.5	(2015) American National Standard for Electrical Rigid Aluminum Conduit
NEMA 250	(2020) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA FU 1	(2012) Low Voltage Cartridge Fuses

NEMA ICS 1	(2000; R 2015) Standard for Industrial Control and Systems: General Requirements
NEMA ICS 2	(2000; R 2005; Errata 2008) Industrial Control and Systems Controllers, Contactors, and Overload Relays Rated 600 V
NEMA ICS 4	(2015) Application Guideline for Terminal Blocks
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems; Enclosures
NEMA KS 1	(2013) Enclosed and Miscellaneous Distribution Equipment Switches (600 V Maximum)
NEMA RN 1	(2005; R 2013) Polyvinyl-Chloride (PVC) Externally Coated Galvanized Rigid Steel Conduit and Intermediate Metal Conduit
NEMA ST 20	(1992; R 19972014) Standard for Dry-Type Transformers for General Applications
NEMA TC 2	(2013) Standard for Electrical Polyvinyl Chloride (PVC) Conduit
NEMA TC 3	(2016) Polyvinyl Chloride (PVC) Fittings for Use With Rigid PVC Conduit and Tubing
NEMA WD 1	(1999; R 2020) Standard for General Color Requirements for Wiring Devices
NEMA WD 6	(2016) Wiring Devices Dimensions Specifications
NEMA Z535.4	(2011; R 2017) Product Safety Signs and Labels

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2020; ERTA 20-1 2020; ERTA 20-2 2020; TIA 20-1; TIA 20-2; TIA 20-3; TIA 20-4) National Electrical Code
NFPA 70E	(2018; TIA 18-1; TIA 81-2) Standard for Electrical Safety in the Workplace
NFPA 780	(2017) Standard for the Installation of Lightning Protection Systems

TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA)

TIA-607	(2015c; Addendum 1 2017) Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

- 10 CFR 431 Energy Efficiency Program for Certain Commercial and Industrial Equipment
- 29 CFR 1910.147 The Control of Hazardous Energy (Lock Out/Tag Out)
- 29 CFR 1910.303 Electrical, General

UNDERWRITERS LABORATORIES (UL)

- UL 1 (2005; Reprint Aug 2017) UL Standard for Safety Flexible Metal Conduit
- UL 5 (2016) UL Standard for Safety Surface Metal Raceways and Fittings
- UL 6 (2007; Reprint Nov 2014) Electrical Rigid Metal Conduit-Steel
- UL 6A (2008; Reprint Nov 2014) Electrical Rigid Metal Conduit - Aluminum, Red Brass, and Stainless Steel
- UL 20 (2018; Reprint Jan 2021) UL Standard for Safety General-Use Snap Switches
- UL 44 (2018) UL Standard for Safety Thermoset-Insulated Wires and Cables
- UL 50 (2015) UL Standard for Safety Enclosures for Electrical Equipment, Non-Environmental Considerations
- UL 67 (2018; Reprint Mar 2019) UL Standard for Safety Panelboards
- UL 83 (2017) UL Standard for Safety Thermoplastic-Insulated Wires and Cables
- UL 198M (2018) UL Standard for Mine-Duty Fuses
- UL 360 (2013; Reprint Nov 2018) UL Standard for Safety Liquid-Tight Flexible Metal Conduit
- UL 467 (2013; Reprint Jun 2017) UL Standard for Safety Grounding and Bonding Equipment
- UL 486A-486B (2018) UL Standard for Safety Wire Connectors
- UL 486C (2018) UL Standard for Safety Splicing Wire Connectors
- UL 489 (2016) UL Standard for Safety Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures

UL 498	(2017; Reprint Dec 2018) UL Standard for Safety Attachment Plugs and Receptacles
UL 506	(2017) UL Standard for Safety Specialty Transformers
UL 508	(2018; Reprint Jul 2021) UL Standard for Safety Industrial Control Equipment
UL 510	(2017) UL Standard for Safety Polyvinyl Chloride, Polyethylene and Rubber Insulating Tape
UL 514A	(2013; Reprint Aug 2017) UL Standard for Safety Metallic Outlet Boxes
UL 514B	(2012; Reprint Nov 2014) Conduit, Tubing and Cable Fittings
UL 514C	(2014; Reprint Nov 2018) UL Standard for Safety Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers
UL 651	(2011; Reprint Nov 2018) UL Standard for Safety Schedule 40, 80, Type EB and A Rigid PVC Conduit and Fittings
UL 797	(2007; Reprint Mar 2017) UL Standard for Safety Electrical Metallic Tubing -- Steel
UL 817	(2015; Reprint May 2017) UL Standard for Safety Cord Sets and Power-Supply Cords
UL 869A	(2006) Reference Standard for Service Equipment
UL 870	(2016; Reprint Mar 2019) UL Standard for Safety Wireways, Auxiliary Gutters, and Associated Fittings
UL 943	(2016; Reprint Feb 2018) UL Standard for Safety Ground-Fault Circuit-Interrupters
UL 1063	(2017) UL Standard for Safety Machine-Tool Wires and Cables
UL 1242	(2006; Reprint Mar 2014) Standard for Electrical Intermediate Metal Conduit -- Steel
UL 1449	(2014; Reprint Jul 2017) UL Standard for Safety Surge Protective Devices
UL 1561	(2011; Reprint Jun 2015) Dry-Type General Purpose and Power Transformers
UL 1660	(2019) Liquid-Tight Flexible Nonmetallic Conduit

UL 4248-1 (2017) UL Standard for Safety Fuseholders
- Part 1: General Requirements

UL 4248-12 (2018) UL Standard for Safety Fuseholders
- Part 12: Class R

1.2 DEFINITIONS

Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, are as defined in IEEE 100.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval.

SD-03 Product Data

Receptacles

Circuit Breakers

Switches

Transformers

Enclosed Circuit Breakers

Motor Controllers

Manual Motor Starters

Fuses

Panelboards

Wireways

Marking Strips

Surge Protective Devices; G

SD-06 Test Reports

600-volt Wiring Test

Grounding System Test

Transformer Tests

Ground-Fault Receptacle Test

SD-09 Manufacturer's Field Reports

Transformer Factory Tests

SD-10 Operation and Maintenance Data

Electrical Systems, Data Package 5

1.4 QUALITY ASSURANCE

1.4.1 Fuses

Submit coordination data as specified in paragraph, FUSES of this section.

1.4.2 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" or "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Provide equipment, materials, installation, and workmanship in accordance with NFPA 70 unless more stringent requirements are specified or indicated.

1.4.3 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship and:

- a. Have been in satisfactory commercial or industrial use for 2 years prior to bid opening including applications of equipment and materials under similar circumstances and of similar size.
- b. Have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period.
- c. Where two or more items of the same class of equipment are required, provide products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.4.3.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.4.3.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site are not acceptable.

1.5 MAINTENANCE

1.5.1 Electrical Systems

Submit operation and maintenance manuals for electrical systems that provide basic data relating to the design, operation, and maintenance of the electrical distribution system for the building. Include the following:

- a. Single line diagram of the "as-built" building electrical system.

- b. Schematic diagram of electrical control system (other than HVAC, covered elsewhere).
- c. Manufacturers' operating and maintenance manuals on active electrical equipment.

1.6 WARRANTY

Provide equipment items supported by service organizations that are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

As a minimum, meet requirements of UL, where UL standards are established for those items, and requirements of NFPA 70 for all materials, equipment, and devices.

2.2 CONDUIT AND FITTINGS

Conform to the following:

2.2.1 Rigid Metallic Conduit

2.2.1.1 Rigid, Threaded Zinc-Coated Steel Conduit

ANSI C80.1, UL 6.

2.2.1.2 Rigid Aluminum Conduit

ANSI C80.5, UL 6A.

2.2.2 Rigid Nonmetallic Conduit

PVC Type EPC-40, and EPC-80 in accordance with NEMA TC 2, UL 651.

2.2.3 Intermediate Metal Conduit (IMC)

UL 1242, zinc-coated steel only.

2.2.4 Electrical, Zinc-Coated Steel Metallic Tubing (EMT)

UL 797, ANSI C80.3.

2.2.5 Plastic-Coated Rigid Steel and IMC Conduit

NEMA RN 1, Type 40(40 mils thick).

2.2.6 Flexible Metal Conduit

UL 1.

2.2.6.1 Liquid-Tight Flexible Metal Conduit, Steel

UL 360.

2.2.7 Fittings for Metal Conduit, EMT, and Flexible Metal Conduit

UL 514B. Ferrous fittings: cadmium- or zinc-coated in accordance with UL 514B.

2.2.7.1 Fittings for Rigid Metal Conduit and IMC

Threaded-type. Split couplings unacceptable.

2.2.7.2 Fittings for EMT

Steel compression type.

2.2.8 Fittings for Rigid Nonmetallic Conduit

NEMA TC 3 for PVC, and UL 514B.

2.2.9 Liquid-Tight Flexible Nonmetallic Conduit

UL 1660.

2.3 SURFACE RACEWAY

2.3.1 Surface Metal Raceway

UL 5, two-piece painted aluminum, totally enclosed, snap-cover type.

2.4 OUTLET BOXES AND COVERS

UL 514A, cadmium- or zinc-coated, if ferrous metal. UL 514C, if nonmetallic.

2.5 CABINETS, JUNCTION BOXES, AND PULL BOXES

UL 50; volume greater than 100 cubic inches, NEMA Type 1 enclosure; sheet steel, hot-dip, zinc-coated. Where exposed to wet, damp, or corrosive environments, NEMA Type 3R or as indicated.

2.6 WIRES AND CABLES

Provide wires and cables in accordance applicable requirements of NFPA 70 and UL for type of insulation, jacket, and conductor specified or indicated. Do not use wires and cables manufactured more than 12 months prior to date of delivery to site.

2.6.1 Conductors

Provide the following:

- a. Conductor sizes and capacities shown are based on copper, unless indicated otherwise.
- b. Conductors No. 8 AWG and larger diameter: stranded.
- c. Conductors No. 10 AWG and smaller diameter: solid.
- d. Conductors for remote control, alarm, and signal circuits, classes 1, 2, and 3: stranded unless specifically indicated otherwise.

- e. All conductors: copper.

2.6.1.1 Minimum Conductor Sizes

Provide minimum conductor size in accordance with the following:

- a. Branch circuits: No. 12 AWG.
- b. Class 1 remote-control and signal circuits: No. 14 AWG.
- c. Class 2 low-energy, remote-control and signal circuits: No. 16 AWG.
- d. Class 3 low-energy, remote-control, alarm and signal circuits: No. 22 AWG.

2.6.2 Color Coding

Provide color coding for service, feeder, branch, control, and signaling circuit conductors.

2.6.2.1 Ground and Neutral Conductors

Provide color coding of ground and neutral conductors as follows:

- a. Grounding conductors: Green.
- b. Neutral conductors: White.
- c. Exception, where neutrals of more than one system are installed in same raceway or box, other neutrals color coding: white with a different colored (not green) stripe for each.

2.6.2.2 Ungrounded Conductors

Provide color coding of ungrounded conductors in different voltage systems as follows:

- a. 208/120 volt, three-phase
 - (1) Phase A - black
 - (2) Phase B - red
 - (3) Phase C - blue
- b. 480/277 volt, three-phase
 - (1) Phase A - brown
 - (2) Phase B - orange
 - (3) Phase C - yellow
- c. 120/240 volt, single phase: Black and red

2.6.3 Insulation

Unless specified or indicated otherwise or required by NFPA 70, provide

power and lighting wires rated for 600-volts, Type THWN/THHN conforming to UL 83 or Type XHHW or RHW conforming to UL 44, except that grounding wire may be type TW conforming to UL 83; remote-control and signal circuits: Type TW or TF, conforming to UL 83. Where lighting fixtures require 90-degree Centigrade (C) conductors, provide only conductors with 90-degree C insulation or better.

2.6.4 Bonding Conductors

ASTM B1, solid bare copper wire for sizes No. 8 AWG and smaller diameter; ASTM B8, Class B, stranded bare copper wire for sizes No. 6 AWG and larger diameter.

2.6.4.1 Telecommunications Bonding Backbone (TBB)

Provide a copper conductor TBB in accordance with TIA-607 with No. 6 AWG minimum size, and sized at 2 kcmil per linear foot of conductor length up to a maximum size of 3/0 AWG. Provide insulated TBB with insulation as specified in the paragraph INSULATION and meeting the fire ratings of its pathway.

2.6.4.2 Bonding Conductor for Telecommunications

Provide a copper conductor Bonding Conductor for Telecommunications between the telecommunications main grounding busbar (TMGB) and the electrical service ground in accordance with TIA-607. Size the bonding conductor for telecommunications the same as the TBB.

2.6.5 Cord Sets and Power-Supply Cords

UL 817.

2.7 SPLICES AND TERMINATION COMPONENTS

UL 486A-486B for wire connectors and UL 510 for insulating tapes. Connectors for No. 10 AWG and smaller diameter wires: insulated, pressure-type in accordance with UL 486A-486B or UL 486C (twist-on splicing connector). Provide solderless terminal lugs on stranded conductors.

2.8 DEVICE PLATES

Provide the following:

- a. UL listed, one-piece device plates for outlets to suit the devices installed.
- b. For metal outlet boxes, plates on unfinished walls: zinc-coated sheet steel or cast metal having round or beveled edges.
- c. For nonmetallic boxes and fittings, other suitable plates may be provided.
- d. Plates on finished walls: nylon or lexan, minimum 0.03 inch wall thickness and same color as receptacle or toggle switch with which they are mounted.
- e. Screws: machine-type with countersunk heads in color to match finish of plate.

- f. Sectional type device plates are not be permitted.
- g. Plates installed in wet locations: gasketed and UL listed for "wet locations."

2.9 SWITCHES

2.9.1 Toggle Switches

NEMA WD 1, UL 20, single pole, double pole, three-way, and four-way, totally enclosed with bodies of thermoplastic or thermoset plastic and mounting strap with grounding screw. Include the following:

- a. Handles: per Architect thermoplastic.
- b. Wiring terminals: screw-type, side-wired.
- c. Contacts: silver-cadmium and contact arm - one-piece copper alloy.
- d. Switches: rated quiet-type ac only, 120/277 volts, with current rating and number of poles indicated.

2.9.2 Switch with Red Pilot Handle

NEMA WD 1. Provide the following:

- a. Pilot lights that are integrally constructed as a part of the switch's handle.
- b. Pilot light color: red and illuminate whenever the switch is closed or "on".
- c. Pilot lighted switch: rated 20 amps and 120 volts or 277 volts as indicated.
- d. The circuit's neutral conductor to each switch with a pilot light.

2.9.3 Disconnect Switches

NEMA KS 1. Provide heavy duty-type switches where indicated, where switches are rated higher than 240 volts, and for double-throw switches. Utilize Class R fuseholders and fuses for fused switches, unless indicated otherwise. Provide horsepower rated for switches serving as the motor-disconnect means. Provide switches in NEMA 1 or 3R, enclosure as indicated per NEMA ICS 6.

2.10 FUSES

NEMA FU 1. Provide complete set of fuses for each fusible switch. Coordinate time-current characteristics curves of fuses serving motors or connected in series with circuit breakers for proper operation. Submit coordination data for approval. Provide fuses with a voltage rating not less than circuit voltage.

2.10.1 Fuseholders

Provide in accordance with UL 4248-1.

2.10.2 Cartridge Fuses, Current Limiting Type (Class R)

UL 198M, Class RK-1 or RK-5 time-delay type. Provide only Class R associated fuseholders in accordance with UL 4248-12.

2.10.3 Cartridge Fuses, High-Interrupting Capacity, Current Limiting Type (Classes J, L, and CC)

UL 198M, Class J for zero to 600 amperes, Class L for 601 to 6,000 amperes, and Class CC for zero to 30 amperes.

2.10.4 Cartridge Fuses, Current Limiting Type (Class T)

UL 198M, Class T for zero to 1,200 amperes, 300 volts; and zero to 800 amperes, 600 volts.

2.11 RECEPTACLES

Provide the following:

- a. UL 498, general purpose specification grade, grounding-type. Residential grade receptacles are not acceptable.
- b. Ratings and configurations: as indicated.
- c. Bodies: Per Architect as per NEMA WD 1.
- d. Face and body: thermoplastic supported on a metal mounting strap.
- e. Dimensional requirements: per NEMA WD 6.
- f. Screw-type, side-wired wiring terminals or of the solderless pressure type having suitable conductor-release arrangement.
- g. Grounding pole connected to mounting strap.
- h. The receptacle: containing triple-wipe power contacts and double or triple-wipe ground contacts.

2.11.1 Split Duplex Receptacles

Provide separate terminals for each ungrounded pole. One receptacle must be controlled separately.

2.11.2 Weatherproof Receptacles

Provide receptacles, UL listed for use in "wet locations". Include cast metal box with gasketed, hinged, lockable and weatherproof while-in-use, die-cast metal/aluminum cover plate.

2.11.3 Ground-Fault Circuit Interrupter Receptacles

UL 943, duplex type for mounting in standard outlet box. Provide device capable of detecting current leak when the current to ground is 6 milliamperes or higher, and tripping per requirements of UL 943 for Class A ground-fault circuit interrupter devices. Provide screw-type, side-wired wiring terminals or pre-wired (pigtail) leads.

2.12 PANELBOARDS

Provide panelboards in accordance with the following:

- a. UL 67 and UL 50 having a short-circuit current rating as indicated of 10,000 amperes symmetrical minimum for voltages 240 V and below of 14,000 amperes symmetrical minimum for 480 V.
- b. Panelboards for use as service disconnecting means: additionally conform to UL 869A.
- c. Panelboards: circuit breaker-equipped.
- d. Designed such that individual breakers can be removed without disturbing adjacent units or without loosening or removing supplemental insulation supplied as means of obtaining clearances as required by UL.
- e. "Specific breaker placement" is required in panelboards to match the breaker placement indicated in the panelboard schedule on the drawings.
- f. Use of "Subfeed Breakers" is not acceptable.
- g. Main breaker: "separately" mounted "above" or "below" branch breakers.
- h. Where "space only" is indicated, make provisions for future installation of breakers.
- i. Directories: indicate load served by each circuit in panelboard.
- j. Directories: indicate source of service to panelboard (e.g., Panel PA served from Panel MDP).
- k. Provide new directories for existing panels modified by this project as indicated.
- l. Type directories and mount in holder behind transparent protective covering.
- m. Panelboards: listed and labeled for their intended use.
- n. Panelboard nameplates: provided in accordance with paragraph FIELD FABRICATED NAMEPLATES.

2.12.1 Enclosure

Provide panelboard enclosure in accordance with the following:

- a. UL 50.
- b. Cabinets mounted outdoors or flush-mounted: hot-dipped galvanized after fabrication.
- c. Cabinets: painted in accordance with paragraph PAINTING.
- d. Outdoor cabinets: NEMA 3R raintight with conduit hubs welded to the cabinet.
- e. Front edges of cabinets: form-flanged or fitted with structural

shapes welded or riveted to the sheet steel, for supporting the panelboard front.

- f. All cabinets: fabricated such that no part of any surface on the finished cabinet deviates from a true plane by more than 1/8 inch.
- g. Holes: provided in the back of indoor surface-mounted cabinets, with outside spacers and inside stiffeners, for mounting the cabinets with a 1/2 inch clear space between the back of the cabinet and the wall surface.
- h. Flush doors: mounted on hinges that expose only the hinge roll to view when the door is closed.
- i. Each door: fitted with a combined catch and lock latch.
- j. Keys: two provided with each lock, with all locks keyed alike.
- k. Finished-head cap screws: provided for mounting the panelboard fronts on the cabinets.

2.12.2 Panelboard Buses

Support bus bars on bases independent of circuit breakers. Design main buses and back pans so that breakers may be changed without machining, drilling, or tapping. Provide isolated neutral bus in each panel for connection of circuit neutral conductors. Provide separate ground bus identified as equipment grounding bus per UL 67 for connecting grounding conductors; bond to steel cabinet. In addition to equipment grounding bus, provide second "isolated" ground bus, where indicated.

2.12.2.1 Panelboard Neutrals for Non-Linear Loads

Provide in accordance with the following:.

- a. UL listed, with panelboard type specifically UL heat rise tested for use on non-linear loads.
- b. Panelboard: heat rise tested in accordance with UL 67, except with the neutral assembly installed and carrying 200 percent of the phase bus current during testing.
- c. Verification of the testing procedure: provided upon request.
- d. Two neutral assemblies paralleled together with cable is not acceptable.
- e. Nameplates for panelboard rated for use on non-linear loads: marked "SUITABLE FOR NON-LINEAR LOADS" and in accordance with paragraph FIELD FABRICATED NAMEPLATES.
- f. Provide a neutral label with instructions for wiring the neutral of panelboards rated for use on non-linear loads.

2.12.3 Circuit Breakers

UL 489, thermal magnetic-type having a minimum short-circuit current rating equal to the short-circuit current rating of the panelboard in which the circuit breaker will be mounted. Breaker terminals: UL listed

as suitable for type of conductor provided. Where indicated on the drawings, provide circuit breakers with shunt trip devices. Series rated circuit breakers and plug-in circuit breakers are unacceptable.

2.12.3.1 Multipole Breakers

Provide common trip-type with single operating handle. Design breaker such that overload in one pole automatically causes all poles to open. Maintain phase sequence throughout each panel so that any three adjacent breaker poles are connected to Phases A, B, and C, respectively.

2.12.3.2 Circuit Breaker With Ground-Fault Circuit Interrupter

UL 943 and NFPA 70. Provide with auto-monitoring (self-test) and lockout features, "push-to-test" button, visible indication of tripped condition, and ability to detect and trip when current imbalance is 6 milliamperes or higher per requirements of UL 943 for Class A ground-fault circuit interrupter devices.

2.13 ENCLOSED CIRCUIT BREAKERS

UL 489. Individual molded case circuit breakers with voltage and continuous current ratings, number of poles, overload trip setting, and short circuit current interrupting rating as indicated. Enclosure type as indicated.

2.14 TRANSFORMERS

Provide transformers in accordance with the following:

- a. NEMA ST 20, general purpose, dry-type, self-cooled, ventilated.
- b. Provide transformers in NEMA 1 enclosure.
- c. Taps for transformers 15 kVA and larger: Two 2.5 percent taps Full Capacity Above Nominal (FCAN) and four 2.5 percent taps Full Capacity Below Nominal (FCBN) .
- d. Transformer insulation system:
 - (1) 220 degrees C insulation system for transformers 15 kVA and greater, with temperature rise not exceeding 115 degrees C under full-rated load in maximum ambient of 40 degrees C.
 - (2) 180 degrees C insulation for transformers rated 10 kVA and less, with temperature rise not exceeding 80 degrees C under full-rated load in maximum ambient of 40 degrees C.
- e. Transformer of 150 degrees C temperature rise is not acceptable.
- f. Transformer of 115 degrees C temperature rise: capable of carrying continuously 115 percent of nameplate kVA without exceeding insulation rating.
- g. Transformers: quiet type with maximum sound level at least 3 decibels less than NEMA standard level for transformer ratings indicated.

2.14.1 Specified Transformer Efficiency

Transformers, indicated and specified with: 480V primary, 80 degrees C or 115 degrees C temperature rise, kVA ratings of 37.5 to 100 for single phase or 30 to 500 for three phase, energy efficient type. The transformer is not acceptable if the calculated transformer efficiency is less than the efficiency indicated in 10 CFR 431, Subpart K.

2.14.2 Transformers With Non-Linear Loads

Provide transformers for non-linear loads in accordance with the following:

- a. Transformer insulation: UL recognized 220 degrees C system. Neither the primary nor the secondary temperature is allowed to exceed 220 degrees C at any point in the coils while carrying their full rating of non-sinusoidal load.
- b. Transformers are to be UL listed and labeled for K-Factor rating as indicated in accordance with UL 1561.
- c. Transformers evaluated by the UL K-Factor evaluation: listed for 115 degrees C average temperature rise only.
- d. Transformers with K-Factor ratings with temperature rise of 150 degrees C rise are not acceptable.
- e. K-Factor rated transformers impedance: allowed range of 3 percent to 5 percent, with a minimum reactance of 2 percent to prevent excessive neutral current when supplying loads with large amounts of third harmonic.

2.15 MOTOR CONTROLLERS

Provide motor controllers in accordance with the following:

- a. UL 508, NEMA ICS 1, and NEMA ICS 2.
- b. Provide controllers with thermal overload protection in each phase, and one spare normally open auxiliary contact, and one spare normally closed auxiliary contact.
- c. Provide controllers for motors rated 1-hp and above with electronic phase-voltage monitors designed to protect motors from phase-loss, undervoltage, and overvoltage.
- d. Provide protection for motors from immediate restart by a time adjustable restart relay.
- e. When used with pressure, float, or similar automatic-type or maintained-contact switch, provide a hand/off/automatic selector switch with the controller.
- f. Connections to selector switch: wired such that only normal automatic regulatory control devices are bypassed when switch is in "hand" position.
- g. Safety control devices, such as low and high pressure cutouts, high temperature cutouts, and motor overload protective devices: connected in motor control circuit in "hand" and "automatic" positions.

- h. Control circuit connections to hand/off/automatic selector switch or to more than one automatic regulatory control device: made in accordance with indicated or manufacturer's approved wiring diagram.
- i. Provide a disconnecting means, capable of being locked in the open position, for the motor that is located in sight from the motor location and the driven machinery location. As an alternative, provide a motor controller disconnect, capable of being locked in the open position, to serve as the disconnecting means for the motor if it is in sight from the motor location and the driven machinery location.
- j. Overload protective devices: provide adequate protection to motor windings; be thermal inverse-time-limit type; and include manual reset-type pushbutton on outside of motor controller case.
- k. Cover of combination motor controller and manual switch or circuit breaker: interlocked with operating handle of switch or circuit breaker so that cover cannot be opened unless handle of switch or circuit breaker is in "off" position.

2.15.1 Control Wiring

Provide control wiring in accordance with the following:

- a. All control wire: stranded tinned copper switchboard wire with 600-volt flame-retardant insulation Type SIS meeting UL 44, or Type MTW meeting UL 1063, and passing the VW-1 flame tests included in those standards.
- b. Hinge wire: Class K stranding.
- c. Current transformer secondary leads: not smaller than No. 10 AWG.
- d. Control wire minimum size: No. 14 AWG.
- e. Power wiring for 480-volt circuits and below: the same type as control wiring with No. 12 AWG minimum size.
- f. Provide wiring and terminal arrangement on the terminal blocks to permit the individual conductors of each external cable to be terminated on adjacent terminal points.

2.15.2 Control Circuit Terminal Blocks

Provide control circuit terminal blocks in accordance with the following:

- a. NEMA ICS 4.
- b. Control circuit terminal blocks for control wiring: molded or fabricated type with barriers, rated not less than 600 volts.
- c. Provide terminals with removable binding, fillister or washer head screw type, or of the stud type with contact and locking nuts.
- d. Terminals: not less than No. 10 in size with sufficient length and space for connecting at least two indented terminals for 10 AWG conductors to each terminal.

- e. Terminal arrangement: subject to the approval of the Contracting Officer with not less than four spare terminals or 10 percent, whichever is greater, provided on each block or group of blocks.
- f. Modular, pull apart, terminal blocks are acceptable provided they are of the channel or rail-mounted type.
- g. Submit data showing that any proposed alternate will accommodate the specified number of wires, are of adequate current-carrying capacity, and are constructed to assure positive contact between current-carrying parts.

2.15.2.1 Types of Terminal Blocks

- a. Short-Circuiting Type: Short-circuiting type terminal blocks: furnished for all current transformer secondary leads with provision for shorting together all leads from each current transformer without first opening any circuit. Terminal blocks: comply with the requirements of paragraph CONTROL CIRCUIT TERMINAL BLOCKS above.
- b. Load Type: Load terminal blocks rated not less than 600 volts and of adequate capacity: provided for the conductors for NEMA Size 3 and smaller motor controllers and for other power circuits, except those for feeder tap units. Provide terminals of either the stud type with contact nuts and locking nuts or of the removable screw type, having length and space for at least two indented terminals of the size required on the conductors to be terminated. For conductors rated more than 50 amperes, provide screws with hexagonal heads. Conducting parts between connected terminals must have adequate contact surface and cross-section to operate without overheating. Provide each connected terminal with the circuit designation or wire number placed on or near the terminal in permanent contrasting color.

2.15.3 Control Circuits

Control circuits: maximum voltage of 120 volts derived from control transformer in same enclosure. Transformers: conform to UL 506, as applicable. Transformers, other than transformers in bridge circuits: provide primaries wound for voltage available and secondaries wound for correct control circuit voltage. Size transformers so that 80 percent of rated capacity equals connected load. Provide disconnect switch on primary side. Provide fuses in each ungrounded primary feeder. Provide one fused secondary lead with the other lead grounded.

2.15.4 Enclosures for Motor Controllers

NEMA ICS 6.

2.15.5 Pushbutton Stations

Provide with "start/stop" momentary contacts having one normally open and one normally closed set of contacts, and red lights to indicate when motor is running. Stations: heavy duty, oil-tight design.

2.15.6 Pilot and Indicating Lights

Provide LED cluster lamps.

2.16 MANUAL MOTOR STARTERS (MOTOR RATED SWITCHES)

SingleDoubleThree pole designed for surface mounting with overload protection and pilot lights.

2.16.1 Pilot Lights

Provide yoke-mounted, seven element LED cluster light module. Color: in accordance with NEMA ICS 2.

2.17 LOCKOUT REQUIREMENTS

Provide circuit breakers, disconnecting means, and other devices that are electrical energy-isolating capable of being locked out for machines and other equipment to prevent unexpected startup or release of stored energy in accordance with 29 CFR 1910.147, NFPA 70E and 29 CFR 1910.303. Comply with requirements of Division 23, "Mechanical" for mechanical isolation of machines and other equipment.

2.18 GROUNDING AND BONDING EQUIPMENT

2.18.1 Ground Rods

UL 467. Ground rods: cone pointed copper-clad steel, with minimum diameter of 3/4 inch and minimum length 10 feet. Sectional ground rods are permitted.

2.18.2 Ground Bus

Copper ground bus: provided in the electrical equipment rooms as indicated.

2.19 MANUFACTURER'S NAMEPLATE

Provide on each item of equipment a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.20 FIELD FABRICATED NAMEPLATES

Provide field fabricated nameplates in accordance with the following:

- a. ASTM D709.
- b. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device; as specified or as indicated on the drawings.
- c. Each nameplate inscription: identify the function and, when applicable, the position.
- d. Nameplates: melamine plastic, 0.125 inch thick, black with white center core.
- e. Surface: matte finish. Corners: square. Accurately align lettering and engrave into the core.
- f. Minimum size of nameplates: one by 2.5 inches.

- g. Lettering size and style: a minimum of 0.25 inch high normal block style.

2.21 WARNING SIGNS

Provide warning signs for flash protection in accordance with NFPA 70E and NEMA Z535.4 for switchboards, panelboards, industrial control panels, and motor control centers that are in other than dwelling occupancies and are likely to require examination, adjustment, servicing, or maintenance while energized. Provide field installed signs to warn qualified persons of potential electric arc flash hazards when warning signs are not provided by the manufacturer. Provide marking that is clearly visible to qualified persons before examination, adjustment, servicing, or maintenance of the equipment.

2.22 FIRESTOPPING MATERIALS

Provide firestopping around electrical penetrations .

2.23 WIREWAYS

UL 870. Material: steel galvanized 16 gauge for heights and depths up to 6 by 6 inches, and 14 gauge for heights and depths up to 12 by 12 inches. Provide in length indicated required for the application with screw- cover NEMA 1 enclosure per NEMA ICS 6.

2.24 SURGE PROTECTIVE DEVICES

Provide parallel type surge protective devices (SPD) which comply with UL 1449 at the service entrance. Provide surge protectors in a NEMA 1 enclosure per NEMA ICS 6. SPD must have the same short-circuit current rating as the protected equipment and shall not be installed at a point of system where the available fault current is in excess of that rating. Use Type 1 or Type 2 SPD and connect on the load side of a dedicated circuit breaker. Submit performance and characteristic curves. Provide the following modes of protection:

FOR SINGLE PHASE AND THREE PHASE WYE CONNECTED SYSTEMS-

- Phase to phase (L-L)
- Each phase to neutral (L-N)
- Neutral to ground (N-G)
- Phase to ground (L-G)

FOR DELTA CONNECTIONS-

- Phase to phase (L-L)
- Phase to ground (L-G)

SPDs at the service entrance: provide with a minimum surge current rating of 80,000 amperes for L-L mode minimum and 40,000 amperes for other modes (L-N, L-G, and N-G).

Provide SPDs. Maximum L-N, L-G, and N-G Voltage Protection Rating:

700V for 208Y/120V, three phase system

Maximum L-L Voltage Protection Rating:

1,200V for 208Y/120V, three phase system

The minimum MCOV (Maximum Continuous Operating Voltage) rating for L-N and L-G modes of operation: 120 percent of nominal voltage for 240 volts and below.

2.25 FACTORY APPLIED FINISH

Provide factory-applied finish on electrical equipment in accordance with the following:

- a. NEMA 250 corrosion-resistance test and the additional requirements as specified herein.
- b. Interior and exterior steel surfaces of equipment enclosures: thoroughly cleaned followed by a rust-inhibitive phosphatizing or equivalent treatment prior to painting.
- c. Exterior surfaces: free from holes, seams, dents, weld marks, loose scale or other imperfections.
- d. Interior surfaces: receive not less than one coat of corrosion-resisting paint in accordance with the manufacturer's standard practice.
- e. Exterior surfaces: primed, filled where necessary, and given not less than two coats baked enamel with semigloss finish.
- f. Equipment located indoors: ANSI Light Gray, and equipment located outdoors: ANSI Light Gray.
- g. Provide manufacturer's coatings for touch-up work and as specified in paragraph FIELD APPLIED PAINTING.

2.26 SOURCE QUALITY CONTROL

2.26.1 Transformer Factory Tests

Submittal: include routine NEMA ST 20 transformer test results on each transformer and also provide the results of NEMA "design" and "prototype" tests that were made on transformers electrically and mechanically equal to those specified.

PART 3 EXECUTION

3.1 INSTALLATION

Electrical installations, including weatherproof and hazardous locations and ducts, plenums and other air-handling spaces: conform to requirements of NFPA 70 and IEEE C2 and to requirements specified herein.

3.1.1 Underground Service

Underground service conductors and associated conduit: continuous from service entrance equipment to outdoor power system connection.

3.1.2 Labels

Wherever work results in service entrance disconnect devices in more than one enclosure, as permitted by NFPA 70, label each enclosure, new and

existing, as one of several enclosures containing service entrance disconnect devices. Label, at minimum: indicate number of service disconnect devices housed by enclosure and indicate total number of enclosures that contain service disconnect devices. Provide laminated plastic labels conforming to paragraph FIELD FABRICATED NAMEPLATES. Use lettering of at least 0.25 inch in height, and engrave on black-on-white matte finish. Service entrance disconnect devices in more than one enclosure: provided only as permitted by NFPA 70.

3.1.3 Wiring Methods

Provide insulated conductors installed in rigid steel conduit, IMC, rigid nonmetallic conduit, or EMT, except where specifically indicated or specified otherwise or required by NFPA 70 to be installed otherwise. Grounding conductor: separate from electrical system neutral conductor. Provide insulated green equipment grounding conductor for circuit(s) installed in conduit and raceways. Minimum conduit size: 1/2 inch in diameter for low voltage lighting and power circuits. Vertical distribution in multiple story buildings: made with metal conduit in fire-rated shafts, with metal conduit extending through shafts for minimum distance of 6 inches. Firestop conduit which penetrates fire-rated walls, fire-rated partitions, or fire-rated floors .

3.1.3.1 Pull Wire

Install pull wires in empty conduits. Pull wire: plastic having minimum 200-pound force tensile strength. Leave minimum 36 inches of slack at each end of pull wire.

3.1.4 Conduit Installation

Unless indicated otherwise, conceal conduit under floor slabs and within finished walls, ceilings, and floors. Keep conduit minimum 6 inches away from parallel runs of flues and steam or hot water pipes. Install conduit parallel with or at right angles to ceilings, walls, and structural members where located above accessible ceilings and where conduit will be visible after completion of project.

3.1.4.1 Restrictions Applicable to Aluminum Conduit

- a. Do not install underground or encase in concrete or masonry.
- b. Do not use brass or bronze fittings.
- c. Do not use when the enclosed conductors must be shielded from the effects of High-altitude Electromagnetic Pulse (HEMP).

3.1.4.2 Restrictions Applicable to EMT

- a. Do not install underground.
- b. Do not encase in concrete, mortar, grout, or other cementitious materials.
- c. Do not use in areas subject to physical damage including but not limited to equipment rooms where moving or replacing equipment could physically damage the EMT.
- d. Do not use in hazardous areas.

- e. Do not use outdoors.
- f. Do not use in fire pump rooms.
- g. Do not use when the enclosed conductors must be shielded from the effects of High-altitude Electromagnetic Pulse (HEMP).

3.1.4.3 Restrictions Applicable to Flexible Conduit

Use only as specified in paragraph FLEXIBLE CONNECTIONS. Do not use when the enclosed conductors must be shielded from the effects of High-altitude Electromagnetic Pulse (HEMP).

3.1.4.4 Underground Conduit

Plastic-coated rigid steel; plastic-coated steel IMC; PVC, Type EPC-40 Convert nonmetallic conduit, other than PVC Schedule 40 or 80, to plastic-coated rigid, or IMC, steel conduit before rising through floor slab. Plastic coating: extend minimum 6 inches above floor.

3.1.4.5 Conduit Installed Under Floor Slabs

Conduit run under floor slab: located a minimum of 12 inches below the vapor barrier. Seal around conduits at penetrations thru vapor barrier.

3.1.4.6 Conduit Through Floor Slabs

Where conduits rise through floor slabs, do not allow curved portion of bends to be visible above finished slab. Where conduit rises through slab-on grade, seal all electrical penetrations to address radon mitigation and prevent infiltration of air, insects, and vermin.

3.1.4.7 Stub-Ups

Provide conduits stubbed up through concrete floor for connection to free-standing equipment with adjustable top or coupling threaded inside for plugs, set flush with finished floor. Extend conductors to equipment in rigid steel conduit, except that flexible metal conduit may be used 6 inches above floor. Where no equipment connections are made, install screwdriver-operated threaded flush plugs in conduit end.

3.1.4.8 Conduit Support

Support conduit by pipe straps, wall brackets, threaded rod conduit hangers, or ceiling trapeze. Fasten by wood screws to wood; by toggle bolts on hollow masonry units; by concrete inserts or expansion bolts on concrete or brick; and by machine screws, welded threaded studs, or spring-tension clamps on steel work. Threaded C-clamps may be used on rigid steel conduit only. Do not weld conduits or pipe straps to steel structures. Do not exceed one-fourth proof test load for load applied to fasteners. Provide vibration resistant and shock-resistant fasteners attached to concrete ceiling. Do not cut main reinforcing bars for any holes cut to depth of more than 1 1/2 inches in reinforced concrete beams or to depth of more than 3/4 inch in concrete joints. Fill unused holes. In partitions of light steel construction, use sheet metal screws. In suspended-ceiling construction, run conduit above ceiling. Do not support conduit by ceiling support system. Conduit and box systems: supported independently of both (a) tie wires supporting ceiling grid system, and

(b) ceiling grid system into which ceiling panels are placed. Do not share supporting means between electrical raceways and mechanical piping or ducts. Coordinate installation with above-ceiling mechanical systems to assure maximum accessibility to all systems. Spring-steel fasteners may be used for lighting branch circuit conduit supports in suspended ceilings in dry locations. Where conduit crosses building expansion joints, provide suitable expansion fitting that maintains conduit electrical continuity by bonding jumpers or other means. For conduits greater than 2 1/2 inches inside diameter, provide supports to resist forces of 0.5 times the equipment weight in any direction and 1.5 times the equipment weight in the downward direction.

3.1.4.9 Directional Changes in Conduit Runs

Make changes in direction of runs with symmetrical bends or cast-metal fittings. Make field-made bends and offsets with hickey or conduit-bending machine. Do not install crushed or deformed conduits. Avoid trapped conduits. Prevent plaster, dirt, or trash from lodging in conduits, boxes, fittings, and equipment during construction. Free clogged conduits of obstructions.

3.1.4.10 Locknuts and Bushings

Fasten conduits to sheet metal boxes and cabinets with two locknuts where required by NFPA 70, where insulated bushings are used, and where bushings cannot be brought into firm contact with the box; otherwise, use at least minimum single locknut and bushing. Provide locknuts with sharp edges for digging into wall of metal enclosures. Install bushings on ends of conduits, and provide insulating type where required by NFPA 70.

3.1.4.11 Flexible Connections

Provide flexible steel conduit between 3 and 6 feet in length for recessed and semirecessed lighting fixtures; for equipment subject to vibration, noise transmission, or movement; and for motors. Install flexible conduit to allow 20 percent slack. Minimum flexible steel conduit size: 1/2 inch diameter. Provide liquidtight flexible conduit in wet and damp locations for equipment subject to vibration, noise transmission, movement or motors. Provide separate ground conductor across flexible connections.

3.1.5 Boxes, Outlets, and Supports

Provide boxes in wiring and raceway systems wherever required for pulling of wires, making connections, and mounting of devices or fixtures. Boxes for metallic raceways: cast-metal, hub-type when located in wet locations, when surface mounted on outside of exterior surfaces, and when specifically indicated. Provide each box with volume required by NFPA 70 for number of conductors enclosed in box. Boxes for mounting lighting fixtures: minimum 4 inches square, or octagonal, except that smaller boxes may be installed as required by fixture configurations, as approved. Boxes for use in masonry-block or tile walls: square-cornered, tile-type, or standard boxes having square-cornered, tile-type covers. Provide gaskets for cast-metal boxes installed in wet locations and boxes installed flush with outside of exterior surfaces. Provide separate boxes for flush or recessed fixtures when required by fixture terminal operating temperature; provide readily removable fixtures for access to boxes unless ceiling access panels are provided. Support boxes and pendants for surface-mounted fixtures on suspended ceilings independently of ceiling supports. Fasten boxes and supports with wood screws on wood, with bolts

and expansion shields on concrete or brick, with toggle bolts on hollow masonry units, and with machine screws or welded studs on steel. In open overhead spaces, cast boxes threaded to raceways need not be separately supported except where used for fixture support; support sheet metal boxes directly from building structure or by bar hangers. Where bar hangers are used, attach bar to raceways on opposite sides of box, and support raceway with approved-type fastener maximum 24 inches from box. When penetrating reinforced concrete members, avoid cutting reinforcing steel.

3.1.5.1 Boxes

Boxes for use with raceway systems: minimum 1 1/2 inches deep, except where shallower boxes required by structural conditions are approved. Boxes for other than lighting fixture outlets: minimum 4 inches square. Telecommunications outlets: a minimum of 4 inches square by 2 1/8 inches deep. Mount outlet boxes flush in finished walls.

3.1.5.2 Pull Boxes

Construct of at least minimum size required by NFPA 70 of code-gauge galvanized sheet steel, except where cast-metal boxes are required in locations specified herein. Provide boxes with screw-fastened covers. Where several feeders pass through common pull box, tag feeders to indicate clearly electrical characteristics, circuit number, and panel designation.

3.1.5.3 Extension Rings

Extension rings are not permitted for new construction. Use only on existing boxes in concealed conduit systems where wall is furred out for new finish.

3.1.6 Mounting Heights

Mount panelboards, enclosed circuit breakers, motor controller and disconnecting switches so height of operating handle at its highest position is maximum 78 inches above floor. Mount lighting switches 48 inches above finished floor. Mount receptacles and telecommunications outlets 18 inches above finished floor, unless otherwise indicated. Wall-mounted telecommunications outlets: mounted at height indicated. Mount other devices as indicated. Measure mounting heights of wiring devices and outlets in non-hazardous areas to center of device or outlet.

3.1.7 Conductor Identification

Provide conductor identification within each enclosure where tap, splice, or termination is made. For conductors No. 6 AWG and smaller diameter, provide color coding by factory-applied, color-impregnated insulation. For conductors No. 4 AWG and larger diameter, provide color coding by plastic-coated, self-sticking markers; colored nylon cable ties and plates; or heat shrink-type sleeves.

3.1.7.1 Marking Strips

Provide marking strips for identification of power distribution, control, data, and communications cables in accordance with the following:

- a. Provide white or other light-colored plastic marking strips, fastened by screws to each terminal block, for wire designations.

- b. Use permanent ink for the wire numbers
- c. Provide reversible marking strips to permit marking both sides, or provide two marking strips with each block.
- d. Size marking strips to accommodate the two sets of wire numbers.
- e. Assign a device designation in accordance with NEMA ICS 1 to each device to which a connection is made. Mark each device terminal to which a connection is made with a distinct terminal marking corresponding to the wire designation used on the Contractor's schematic and connection diagrams.
- f. The wire (terminal point) designations used on the Contractor's wiring diagrams and printed on terminal block marking strips may be according to the Contractor's standard practice; however, provide additional wire and cable designations for identification of remote (external) circuits for the Government's wire designations.
- g. Prints of the marking strips drawings submitted for approval will be so marked and returned to the Contractor for addition of the designations to the terminal strips and tracings, along with any rearrangement of points required.

3.1.8 Splices

Make splices in accessible locations. Make splices in conductors No. 10 AWG and smaller diameter with insulated, pressure-type connector. Make splices in conductors No. 8 AWG and larger diameter with solderless connector, and cover with insulation material equivalent to conductor insulation.

3.1.9 Covers and Device Plates

Install with edges in continuous contact with finished wall surfaces without use of mats or similar devices. Plaster fillings are not permitted. Install plates with alignment tolerance of 1/16 inch. Use of sectional-type device plates are not permitted. Provide gasket for plates installed in wet locations.

3.1.10 Electrical Penetrations

Seal openings around electrical penetrations through fire resistance-rated walls, partitions, floors, or ceilings .

3.1.11 Grounding and Bonding

Provide in accordance with NFPA 70 and NFPA 780. Ground exposed, non-current-carrying metallic parts of electrical equipment, metallic raceway systems, grounding conductor in metallic and nonmetallic raceways, telecommunications system grounds, and neutral conductor of wiring systems.

Make ground connection at main service equipment, and extend grounding conductor to point of entrance of metallic water service. Make connection to water pipe by suitable ground clamp or lug connection to plugged tee. Supplement metallic water service grounding system with additional made electrode in compliance with NFPA 70. Make ground connection to driven ground rods on exterior of building. Bond additional driven rods together with a minimum of 4 AWG soft bare copper wire buried to a depth of at least

12 inches. Interconnect all grounding media in or on the structure to provide a common ground potential. This includes electrical service, telecommunications system grounds, as well as underground metallic piping systems. In addition to the requirements specified herein, provide telecommunications grounding in accordance with TIA-607. Where ground fault protection is employed, ensure that connection of ground and neutral does not interfere with correct operation of fault protection.

3.1.11.1 Ground Rods

Provide ground rods and measure the resistance to ground using the fall-of-potential method described in IEEE 81. Do not exceed 25 ohms under normally dry conditions for the maximum resistance of a driven ground. If this resistance cannot be obtained with a single rod, provide additional rods, spaced on center. Spacing for additional rods must be a minimum of 10 feet. In high-ground-resistance, UL listed chemically charged ground rods may be used. If the resultant resistance exceeds 25 ohms measured not less than 48 hours after rainfall, notify the Contracting Officer who will decide on the number of ground rods to add.

3.1.11.2 Grounding Connections

Make grounding connections which are buried or otherwise normally inaccessible, excepting specifically those connections for which access for periodic testing is required, by exothermic weld or high compression connector.

- a. Make exothermic welds strictly in accordance with the weld manufacturer's written recommendations. Welds which are "puffed up" or which show convex surfaces indicating improper cleaning are not acceptable. Mechanical connectors are not required at exothermic welds.
- b. Make high compression connections using a hydraulic or electric compression tool to provide the correct circumferential pressure. Provide tools and dies as recommended by the manufacturer. Use an embossing die code or other standard method to provide visible indication that a connector has been adequately compressed on the ground wire.

3.1.11.3 Ground Bus

Provide a copper ground bus in the electrical equipment rooms as indicated. Noncurrent-carrying metal parts of transformer neutrals and other electrical equipment: effectively grounded by bonding to the ground bus. Bond the ground bus to both the entrance ground, and to a ground rod or rods as specified above having the upper ends terminating approximately 4 inches above the floor. Make connections and splices of the brazed, welded, bolted, or pressure-connector type, except use pressure connectors or bolted connections for connections to removable equipment.

3.1.11.4 Resistance

Maximum resistance-to-ground of grounding system: do not exceed 5 ohms under dry conditions. Where resistance obtained exceeds 5 ohms, contact Contracting Officer for further instructions.

3.1.12 Equipment Connections

Provide power wiring for the connection of motors and control equipment under this section of the specification. Except as otherwise specifically noted or specified, automatic control wiring, control devices, and protective devices within the control circuitry are not included in this section of the specifications and are provided under the section specifying the associated equipment.

3.1.13 Government-Furnished Equipment

Contractor rough-in for Government-furnished equipment to make equipment operate as intended, including providing miscellaneous items such as plugs, receptacles, wire, cable, conduit, flexible conduit, and outlet boxes or fittings.

3.1.14 Repair of Existing Work

Perform repair of existing work, demolition, and modification of existing electrical distribution systems as needed.

3.1.14.1 Workmanship

Lay out work in advance. Exercise care where cutting, channeling, chasing, or drilling of floors, walls, partitions, ceilings, or other surfaces is necessary for proper installation, support, or anchorage of conduit, raceways, or other electrical work. Repair damage to buildings, piping, and equipment using skilled craftsmen of trades involved.

3.1.14.2 Existing Concealed Wiring to be Removed

Disconnect existing concealed wiring to be removed from its source. Remove conductors; cut conduit flush with floor, underside of floor, and through walls; and seal openings.

3.2 FIELD FABRICATED NAMEPLATE MOUNTING

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.3 WARNING SIGN MOUNTING

Provide the number of signs required to be readable from each accessible side. Space the signs in accordance with NFPA 70E.

3.4 FIELD APPLIED PAINTING

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria.

3.5 FIELD QUALITY CONTROL

Furnish test equipment and personnel and submit written copies of test results. Give Contracting Officer 5 working days notice prior to each test.

3.5.1 Devices Subject to Manual Operation

Operate each device subject to manual operation at least five times, demonstrating satisfactory operation each time.

3.5.2 600-Volt Wiring Test

Test wiring rated 600 volt and less to verify that no short circuits or accidental grounds exist. Perform insulation resistance tests on wiring No. 6 AWG and larger diameter using instrument which applies voltage of 1,000 volts DC for 600 volt rated wiring and 500 volts DC for 300 volt rated wiring per NETA ATS to provide direct reading of resistance. All existing wiring to be reused shall also be tested.

3.5.3 Transformer Tests

Perform the standard, not optional, tests in accordance with the Inspection and Test Procedures for transformers, dry type, air-cooled, 600 volt and below; as specified in NETA ATS. Measure primary and secondary voltages for proper tap settings. Tests need not be performed by a recognized independent testing firm or independent electrical consulting firm.

3.5.4 Ground-Fault Receptacle Test

Test ground-fault receptacles with a "load" (such as a plug in light) to verify that the "line" and "load" leads are not reversed. Press the TEST button and then the RESET button to verify by LED status that the device is a self-test model as specified in UL 943.

3.5.5 Grounding System Test

Test grounding system to ensure continuity, and that resistance to ground is not excessive. Test each ground rod for resistance to ground before making connections to rod; tie grounding system together and test for resistance to ground. Make resistance measurements in dry weather, not earlier than 48 hours after rainfall. Submit written results of each test to Contracting Officer, and indicate location of rods as well as resistance and soil conditions at time measurements were made.

-- End of Section --

SECTION 26 51 00

INTERIOR LIGHTING
05/20, CHG 2: 11/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A580/A580M	(2018) Standard Specification for Stainless Steel Wire
ASTM A641/A641M	(2019) Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire
ASTM A653/A653M	(2020) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A1008/A1008M	(2021) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM B164	(2003; R 2014) Standard Specification for Nickel-Copper Alloy Rod, Bar, and Wire
ASTM B633	(2019) Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel
ASTM D4674 REV A	(2002; R 2010) Standard Practice for Accelerated Testing for Color Stability of Plastics Exposed to Indoor Office Environments

ILLUMINATING ENGINEERING SOCIETY (IES)

ANSI/IES LM-79	(2019) Approved Method: Electrical and Photometric Measurements of Solid State Lighting Products
ANSI/IES LM-80	(2020) Approved Method: Measuring Luminous Flux and Color Maintenance of LED Packages, Arrays and Modules
ANSI/IES LS-1	(2020) Lighting Science: Nomenclature and Definitions for Illuminating Engineering

ANSI/IES TM-15	(2020) Technical Memorandum: Luminaire Classification System for Outdoor Luminaires
ANSI/IES TM-21	(2019) Technical Memorandum: Projecting Long-Term Lumen, Photon, and Radiant Flux Maintenance of LED Light Sources
ANSI/IES TM-30	(2020) Technical Memorandum: IES Method for Evaluating Light Source Color Rendition
IES Lighting Library	IES Lighting Library

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 100	(2000; Archived) The Authoritative Dictionary of IEEE Standards Terms
IEEE C2	(2017; Errata 1-2 2017; INT 1 2017) National Electrical Safety Code
IEEE C62.41	(1991; R 1995) Recommended Practice on Surge Voltages in Low-Voltage AC Power Circuits

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 77	(2017) Temporal Light Artifacts: Test Methods and Guidance for Acceptance Criteria
NEMA 250	(2020) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA ANSLG C78.377	(2017) Electric Lamps— Specifications for the Chromaticity of Solid State Lighting Products
NEMA C82.77-10	(2020) Harmonic Emission Limits - Related Power Quality Requirements
NEMA SSL 1	(2016) Electronic Drivers for LED Devices, Arrays, or Systems
NEMA SSL 3	(2011) High-Power White LED Binning for General Illumination
NEMA SSL 7A	(2015) Phase-Cut Dimming for Solid State Lighting: Basic Compatibility
NEMA WD 1	(1999; R 2020) Standard for General Color Requirements for Wiring Devices
NEMA WD 7	(2011; R 2016) Occupancy Motion Sensors Standard

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2020; ERTA 20-1 2020; ERTA 20-2 2020; TIA 20-1; TIA 20-2; TIA 20-3; TIA 20-4)
National Electrical Code

NFPA 101 (2021) Life Safety Code

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

47 CFR 15 Radio Frequency Devices

UNDERWRITERS LABORATORIES (UL)

UL 20 (2018; Reprint Jan 2021) UL Standard for Safety General-Use Snap Switches

UL 94 (2013; Reprint May 2021) UL Standard for Safety Tests for Flammability of Plastic Materials for Parts in Devices and Appliances

UL 508 (2018; Reprint Jul 2021) UL Standard for Safety Industrial Control Equipment

UL 844 (2012; Reprint Jul 2020) UL Standard for Safety Luminaires for Use in Hazardous (Classified) Locations

UL 916 (2015) Standard for Energy Management Equipment

UL 924 (2016; Reprint May 2020) UL Standard for Safety Emergency Lighting and Power Equipment

UL 1472 (2015) UL Standard for Safety Solid-State Dimming Controls

UL 1598 (2021; Reprint Jun 2021) Luminaires

UL 1598C (2014) Standard for Light-Emitting Diode (LED) Retrofit Luminaire Conversion Kits

UL 2043 (2013) Fire Test for Heat and Visible Smoke Release for Discrete Products and Their Accessories Installed in Air-Handling Spaces

UL 8750 (2015; Reprint Jul 2021) UL Standard for Safety Light Emitting Diode (LED) Equipment for Use in Lighting Products

1.2 RELATED REQUIREMENTS

Materials not considered to be luminaires, luminaire accessories, or lighting equipment are specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

1.3 DEFINITIONS

- a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications and on the drawings, must be as defined in IEEE 100 and ANSI/IES LS-1.
- b. For LED luminaire light sources, "Useful Life" is the operating hours before reaching 70 percent of the initial rated lumen output (L70) with no catastrophic failures under normal operating conditions. This is also known as 70 percent "Rated Lumen Maintenance Life" as defined in ANSI/IES LM-80.
- c. For LED luminaires, "Luminaire Efficacy" (LE) is the appropriate measure of energy efficiency, measured in lumens/watt. This is gathered from LM-79 data for the luminaire, in which absolute photometry is used to measure the lumen output of the luminaire as one entity, not the source separately and then the source and housing together.
- d. Total harmonic distortion (THD) is the root mean square (RMS) of all the harmonic components divided by the total fundamental current.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following:

SD-02 Shop Drawings

Occupancy/Vacancy Sensor Coverage Layout; G

Lighting Control System One-Line Diagram; G

Sequence of Operation for Lighting Control System; G

SD-03 Product Data

Luminaire Drawings; G

Luminaires; G

Light Sources; G

LED Drivers; G

Luminaire Warranty; G

Lighting Controls Warranty; G

Local Area Controller; G

Switches; G

Wall Box Dimmers; G

Occupancy/Vacancy Sensors; G

Photosensors; G

Power Packs; G

Exit Signs; G

Emergency Drivers; G

SD-05 Design Data

Photometric Plan; G

SD-06 Test Reports

ANSI/IES LM-79 Test Report

ANSI/IES LM-80 Test Report

ANSI/IES TM-21 Test Report

ANSI/IES TM-30 Test Report

Occupancy/Vacancy Sensor Verification Test

Photosensor Verification Test

SD-07 Certificates

LED Driver and Dimming Switch Compatibility Certificate; G

SD-10 Operation and Maintenance Data

Lighting System, Data Package 5; G

Lighting Control System, Data Package 5; G

Maintenance Staff Training Plan; GEnd-User Training Plan; G

1.5 QUALITY ASSURANCE

Data, drawings, and reports must employ the terminology, classifications and methods prescribed by the IES Lighting Library as applicable, for the lighting system specified.

1.5.1 Luminaire Drawings

Include dimensions, accessories installation details, and construction details. Photometric data, including CRI, CCT, LED driver type, aiming diagram, zonal lumen data, and candlepower distribution data must accompany shop drawings.

1.5.2 ANSI/IES LM-79 Test Report

Submit test report on manufacturer's standard production model of specified luminaire. Testing must be performed at the same operating drive current as specified luminaire. Include all applicable and required data in IES format as outlined under "14.0 Test Report" in ANSI/IES LM-79.

1.5.3 ANSI/IES LM-80 Test Report

Submit report on manufacturer's standard production LED light source (package, array, or module) of specified luminaire. Testing must be performed at the same operating drive current as specified luminaire. Include all applicable and required data as outlined under "8.0 Test Report" in ANSI/IES LM-80.

1.5.4 ANSI/IES TM-21 Test Report

Submit test report on manufacturer's standard production LED light source (package, array, or module) of specified luminaire. Testing must be performed at the same operating drive current as specified luminaire. Include all applicable and required data, as well as required interpolation information as outlined under "7.0 Report" in ANSI/IES TM-21.

1.5.5 ANSI/IES TM-30 Test Report

Submit color vector graphic in accordance with ANSI/IES TM-30 on manufacturer's standard production LED light source (package, array, or module) of specified luminaire. Include spectral distribution of test LED light source.

1.5.6 LED Driver and Dimming Switch Compatibility Certificate

Submit certification from the luminaire, driver, or dimmer switch manufacturer that ensures compatibility and operability between devices without flickering and to specified dimming levels.

1.5.7 Photometric Plan

1.5.7.1 Computer-generated Photometric Plans

Computer-generated photometric plans for each space are required to verify proposed luminaires and locations meet the required performance criteria of the design using the applicable light loss factor (LLF).

Target illumination levels are provided for each Interior Application. Depending on the application and the recommendations provided by the IES, values are given as one of the following:

- a. Minimum: No values anywhere on the calculation grid may be less than this value, within a 10 percent margin of error.
- b. Minimum Average: An average, taken over the entire task area for the application, may not be less than this value, within a 10 percent margin of error.
- c. Maximum: No values anywhere on the calculation grid may be greater than this value, within a 10 percent margin of error.
- d. Maximum Average: An average, taken over the entire task area for the application, may not be greater than this value, within a 10 percent margin of error.
- e. Uniformity: Unless otherwise noted, uniformity is calculated as a ratio of the average calculated illuminance over the minimum calculated illuminance of the calculation grid.

1.5.7.2 Schematic Photometric Plan Calculations

Schematic photometric plan calculations must include:

- a. Horizontal illuminance measurements at workplane or other designated height above finished floor, taken at a maximum of every one foot across the task area.
- b. Average maintained illuminance level.
- c. Minimum and maximum maintained illuminance levels.
- d. Lighting power density (Watts per square foot).
- e. LLF. Recommended LLF is 0.81 for LED luminaires but LLF varies based on environment and application.

1.5.7.3 Final Photometric Plan Calculations

Final photometric plan calculations must include:

- a. Horizontal illuminance measurements at workplane or other designated height above finished floor, taken at a maximum of every one foot across the task area.
- b. Where applicable, vertical illuminance measurements at designated surface, taken at a maximum of every one foot across task area.
- c. Minimum and maximum maintained illuminance levels.
- d. Average maintained illuminance level.
- e. Average to minimum and maximum to minimum ratios for horizontal illuminance.
- f. Lighting power density (Watts per square foot).
- g. LLF. Recommended LLF is 0.81 for LED luminaires but LLF varies based on environment and application.

1.5.8 Occupancy/Vacancy Sensor Coverage Layout

Provide floor plans showing coverage layouts of all devices using manufacturer's product information.

1.5.9 Test Laboratories

Test laboratories for the ANSI/IES LM-79 and ANSI/IES LM-80 test reports must be one of the following:

- a. National Voluntary Laboratory Accreditation Program (NVLAP) accredited for solid-state lighting testing as part of the Energy-Efficient Lighting Products laboratory accreditation program for both LM-79 and LM-80 testing.
- b. One of the qualified labs listed on the Department of Energy - LED Lighting Facts Approved Testing Laboratories List for LM-79 testing.
- c. One of the EPA-Recognized Laboratories listed for LM-80 testing.

1.5.10 Regulatory Requirements

Equipment, materials, installation, and workmanship must be in accordance with the mandatory and advisory provisions of NFPA 70, unless more stringent requirements are specified or indicated. Provide luminaires and assembled components that are approved by and bear the label of UL for the applicable location and conditions unless otherwise specified.

1.5.11 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design, and workmanship. Products must have been in satisfactory commercial or industrial use for six months prior to bid opening. The six-month period must include applications of equipment and materials under similar circumstances and of similar size. The product must have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the six-month period. Where two or more items of the same class of equipment are required, these items must be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.5.11.1 Alternative Qualifications

Products having less than a six-month field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.11.2 Material and Equipment Manufacturing Date

Do not use products manufactured more than six months prior to date of delivery to site, unless specified otherwise.

1.6 WARRANTY

Support all equipment items by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.6.1 Luminaire Warranty

Provide and transfer to the government the original LED luminaire manufacturers standard commercial warranty for each different luminaire manufacturer used in the project.

- a. Provide a written five year minimum replacement warranty for material, luminaire finish, and workmanship. Provide written warranty document that contains all warranty processing information needed, including customer service point of contact, whether or not a return authorization number is required, return shipping information, and closest return location to the luminaire location.

- (1) Finish warranty must include failure and substantial deterioration such as blistering, cracking, peeling, chalking, or fading.

(2) Material warranty must include:

- (a) All LED drivers and integral control equipment.
 - (b) Replacement when more than 15 percent of LED sources in any lightbar or subassembly(s) are defective, non-starting, or operating below 70 percent of specified lumen output.
 - (c) Replacement when more than 15 percent of LED sources in any lightbar or subassembly(s) show a color shift greater than 0.003 delta u'v' from the zero hour measurement stated in the ANSI/IES LM-79 Test Report.
- b. Warranty period must begin in accordance with the manufacturer's standard warranty starting date.
- c. Provide replacements that are promptly shipped, without charge, to the using Government facility point of contact and that are identical to or an improvement upon the original equipment. All replacements must include testing of new components and assembly.

1.6.2 Lighting Controls Warranty

Provide and transfer to the government the original lighting controls manufacturers standard commercial warranty for each different lighting controls manufacturer used in the project. Warranty coverage must begin from date of final system commissioning or three months from date of delivery, whichever is the earliest. Warranty service must be performed by a factory-trained engineer or technician.

- a. Unless otherwise noted, provide a written five year minimum warranty on the complete system for all systems with factory commissioning. Provide warranty that covers 100 percent of the cost of any replacement parts and services required over the five years which are directly attributable to the product failure. Failures include, but are not limited to, the following:
- (1) Software: Failure of input/output to execute switching or dimming commands.
 - (2) Damage of electronic components due to transient voltage surges.
 - (3) Failure of control devices, including but not limited to occupancy sensors, photosensors, and manual wall station control devices.
- b. Provide a written five year minimum warranty on all input devices against defect in workmanship or materials provided by device manufacturer.
- c. Provide a written five year minimum warranty on all control components attached to luminaires against defect in workmanship or materials.

1.7 OPERATION AND MAINTENANCE MANUALS

1.7.1 Lighting System

Provide operation and maintenance manuals for the lighting system that provide basic data relating to the design, operation, and maintenance of the lighting system for the building. Include the following:

- a. Manufacturers' operating and maintenance manuals.
- b. Luminaire shop drawings for modified and custom luminaires.
- c. Luminaire Manufacturers' standard commercial warranty information as specified in paragraph LUMINAIRE WARRANTY.

1.7.2 Lighting Control System

Provide operation and maintenance manuals for the lighting control system that provide basic data relating to the design, operation, and maintenance of the lighting control system for the building. Include the following:

- a. Lighting control system layout and wiring plan.
- b. Lighting control system one-line diagram.
- c. Product data for all devices, including installation and programming instructions.
- d. Occupancy/vacancy sensor coverage layout.
- e. Training materials, such as videos or in-depth manuals, that cover basic operation of the lighting control system and instructions on modifying the lighting control system. Training materials must include calibration, adjustment, troubleshooting, maintenance, repair, and replacement.
- f. Sequence of operation descriptions for each typical room type, including final programming, schedules, and calibration settings.
- g. "As-built" lighting control panel schedules.

PART 2 PRODUCTS

2.1 PRODUCT COORDINATION

2.2 LUMINAIRES

UL 1598, NEMA C82.77-10. Provide luminaires as indicated in the luminaire schedule and NL plates or details on project plans, complete with light source, wattage, and lumen output indicated. All luminaires of the same type must be provided by the same manufacturer. Luminaires must be specifically designed for use with the driver and light source provided.

2.2.1 Luminaires

UL 8750, ANSI/IES LM-79, ANSI/IES LM-80. For all luminaires, provide:

- a. Complete system with LED drivers and light sources.
- b. Housings constructed of non-corrosive materials. All new aluminum housings must be anodized or powder-coated. All new steel housings must be treated to be corrosion resistant.
- c. ANSI/IES TM-21, ANSI/IES LM-80. Minimum L70 lumen maintenance value of 50,000 hours unless otherwise indicated in the luminaire schedule. Luminaire drive current value must be identical to that provided by

test data for luminaire in question.

- d. Minimum efficacy as specified in the luminaire schedule. Theoretical models of initial lamp lumens per watt are not acceptable. If efficacy values are not listed in the luminaire schedule, provide luminaires that meet the following minimum values:

Luminaire Style	Minimum Luminaire Efficacy
Recessed 1 by 4, 2 by 4, and 2 by 2	100 LPW
Recessed Downlight (fixed, adjustable, wallwash)	80 LPW
Linear, Accent (undercabinet, cove)	45 LPW
Linear, Ambient (indirect wall mount, linear pendent)	100 LPW
High Bay, Low Bay, and Industrial Locations	100 LPW
Food Service and Hazardous Locations	60 LPW
Other (track, residential diffusers)	50 LPW
Exterior Wall Sconce	50 LPW
Steplight	30 LPW
Parking Garage Luminaire	100 LPW

- e. UL listed for dry or damp location typical of interior installations. Any luminaire mounted on the exterior of the building must be UL listed for wet location typical of exterior installations.
- f. LED driver and light source package, array, or module are accessible for service or replacement without removal or destruction of luminaire.
- g. Provide polycarbonate vandal-resistant lenses as indicated. Sandblasting, etching and polishing must be performed as indicated in the luminaire description.
- h. ANSI/IES TM-15. Provide exterior building-mounted luminaires that do not exceed the BUG ratings as listed in the luminaire schedule. If BUG ratings are not listed in the luminaire schedule, provide luminaires that meet the following minimum values for each application and mounting conditions:

Lighting Application	Mounting Conditions	BUG Rating
Exterior Wall Sconce	Above 1.2 meters 4 feet AFF	B1-U0-G2
Exterior Wall Sconce	Below or at 1.2 meters 4 feet AFF	B4-U0-G4

Lighting Application	Mounting Conditions	BUG Rating
Steplight	Above 1.2 meters 4 feet AFF	B1-U1-G2
Steplight	Below or at 1.2 meters 4 feet AFF	B4-U1-G4
Parking Garage Luminaire	Ceiling mounted	B4-U4-G3

- i. For all recessed luminaires that are identified to be in contact with insulation, provide luminaires that are IC-rated.

2.2.1.1 Luminaire Conversion Kits

Provide luminaire conversion kits that meet UL 1598C Standard for Light-Emitting Diode (LED) Retrofit Luminaire Conversion Kits.

2.2.2 Luminaires for Hazardous Locations

In addition to requirements stated herein, provide LED luminaires for hazardous locations which conform to UL 844 or which have Factory Mutual certification for the class and division indicated.

2.3 LIGHT SOURCES

NEMA ANSLG C78.377, NEMA SSL 3. Provide type, delivered lumen output, and wattage as indicated in the luminaire schedule on project plans.

2.3.1 LED Light Sources

Provide LED light sources that meet the following requirements:

- a. NEMA ANSLG C78.377. Emit white light and have a nominal CCT of 4000 Kelvin.
- b. Minimum Color Rendering Index (CRI) of 80.
- c. Light source color consistency by utilizing a binning tolerance within a 3-step McAdam ellipse.

2.4 LED DRIVERS

NEMA SSL 1, UL 8750. Provide LED drivers that are electronic, UL Class 1 or Class 2, constant-current type and that comply with the following requirements:

- a. The combined driver and LED light source system does not exceed the minimum luminaire efficacy values as listed in the luminaire schedule provided.
- b. Operates at a voltage of 120 volts at 50/60 hertz, with input voltage fluctuations of plus/minus 10 percent.
- c. Power Factor (PF) greater than or equal to 0.90 at full input power and across specified dimming range.
- d. Maximum Total Harmonic Distortion (THD) less than 20 percent at full input power and across specified dimming range.

- e. Operates for at least 50,000 hours at maximum case temperature and 90 percent non-condensing relative humidity.
- f. Withstands Category A surges of 2 kV without impairment of performance. Provide surge protection that is integral to the driver.
- g. Integral thermal protection that reduces the output power to protect the driver and light source from damage if the case temperature approaches or exceeds the driver's maximum operating temperature.
- h. 47 CFR 15. Complies with the requirements of the Federal Communications Commission (FCC) rules and regulations, Non-Consumer (Class A) for EMI/RFI (conducted and radiated).
- i. Class A sound rating.
- j. Provide dimming capability as indicated in the luminaire schedule on project plans. Dimmable drivers must dim down to 10 percent. Dimmable drivers must be controlled by a Class 2 low voltage 0-10VDC controller dimming signal protocol unless otherwise specified. LED drivers of the same family/series must track evenly across multiple luminaires at all light levels.

2.4.1 Remote LED Drivers

Provide remote LED Drivers that are UL listed for dry locations typical of interior installations. Provide LED driver in junction box or housing with mounting plate. Housing must allow for field connections to occur inside the housing or must contain mechanical connections.

2.5 LIGHTING CONTROLS

Provide network certification for all networked lighting control systems and devices. Provide lighting control systems that do not switch off battery-operated or emergency backup luminaires or exit signs in path of egress. Provide system with override of lighting control devices controlling luminaires in path of egress with activation of fire alarm system.

2.5.1 System

Provide lighting control system that operates the lighting system as described in the lighting control strategies in the project plans. Submit Sequence of Operation for Lighting Control System describing the operation of the proposed lighting control system and devices. Sequence of Operation must provide the strategies identified in the lighting control strategies.

2.5.1.1 Localized Control Systems

Provide room or area-wide lighting control system capable of manual control, time-based control, and receiving input from photosensors and occupancy/vacancy sensors.

2.5.1.1.1 Local Area Controller

Provide controller designed for single area or room with the following requirements:

- a. Operates at a voltage of 120 volts at 50/60 hertz.
- b. Provide inputs for occupancy/vacancy sensors, photosensors, and low-voltage wall switches.
- c. Provide daylight harvesting capability with full-range dimming control with input from photosensor.
- d. Capable of 0-10V dimming.

2.5.1.2 Centralized Control Systems

Provide a centralized lighting control system capable of manual control, time-based control, receiving input from photosensors and occupancy/vacancy sensors, with the capabilities of controlling, monitoring, and programming changes from one centralized on-site location, and integration with other building systems.

2.5.2 Devices

2.5.2.1 Switches

Provide line-voltage toggle switches as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. When used for non-digital loads, devices must be rated at 20 Amps inductive load, and be compatible with the lighting control systems.

2.5.2.2 Wall Box Dimmers

UL 1472, UL 20, IEEE C62.41, NEMA 77, NEMA SSL 7A. Dimmers must provide flicker-free, continuously variable light output throughout the dimming range of 10 percent to 100 percent. Devices must be capable of operating at their full rated capacity regardless of being single or ganged-mounted, and be compatible with three-way and four-way switching scenarios.

Provide wall-box dimmers that meet the following requirements:

- a. Device operates as an independent control device.
- b. Device operates with the use of a vertical slider, paddle, rotary, button, or toggle with adjacent vertical slider.
- c. Finish of device matches switches and outlets in the same area.
- d. Back box in wall has sufficient depth to accommodate body of switch and wiring.
- e. Dimmer is capable of controlling 0-10 volt LED drivers. Dimmers and the drivers they control must be provided from the same manufacturer or tested and certified as compatible for use together.
- f. Radio frequency interference suppression is integral to device.

2.5.2.3 Occupancy/Vacancy Sensors

IEEE C62.41, NEMA WD 1, UL 94, UL 916, UL 508, ASTM D4674 REV A, NEMA WD 7. Provide occupancy/vacancy sensors with coverage patterns as indicated on manufacturer shop drawings. Provide no less quantity of sensors as shown on plans, but add additional sensors when required to fulfill coverage

requirement for the specific model of sensor provided. Provide occupancy sensor operation that requires movement to activate luminaires controlled and turns luminaires off after a set time of inactivity. Provide vacancy sensor operation that requires manual control to activate luminaires and turns luminaires off after a set time of inactivity. Provide ceiling or wall-mounted occupancy/vacancy sensors that meet the following requirements:

- a. Operating voltage of 120 volts.
- b. Time delay of 30 seconds to 30 minutes with at least four intermediate time delay settings.
- c. Sensors are ceiling mounted or wall mounted.
- d. Shielded or controlled by internal logic to adjust sensitivity to avoid false triggering due to ambient temperature, air temperature variations or HVAC air movement.
- e. Sensor is equipped to automatically energize the connected load upon loss of normal power when located in a means of egress.
- f. Occupancy and vacancy operation is field-adjustable and programmable with push-button or dip switch on the sensor device.
- g. No leakage current to load when in the off mode.
- h. Utilize zero-crossing circuitry to prevent damage from high inrush current and to promote long life operation.
- i. Allow the adding or deleting of specific luminaires or zones to the assigned sensor without the use of ladders.
- j. Provide an isolated relay for integrating control of HVAC or other automated systems.

2.5.2.3.1 Dual Technology Sensors

Provide dual technology sensors that meet the requirements for PIR sensors and ultrasonic sensors indicated above. If either the PIR or ultrasonic sensing registers occupancy, the luminaires must remain on.

2.5.2.3.2 High Bay Sensors

Provide occupancy/vacancy sensors specifically designed for high-bay mounting applications for all ceiling-mounted sensors mounted above 35 feet using PIR technology. Provide high-bay sensors with interchangeable lenses for 360 degree open area coverage or narrow rectangular warehouse aisle coverage.

2.5.2.3.3 Power Packs

UL 2043. Provide power packs to provide power to lighting control sensors as required in accordance with the manufacturer's specifications. Provide power packs that meet the following requirements:

- a. Operate at an input voltage of 120 VAC, with an output voltage 12-24 VDC at 225 mA.
- b. Constructed of plenum-rated, high-impact thermoplastic enclosure.

- c. Utilizes zero-crossing circuitry to prevent damage from inrush current.
- d. Maximum load rating of 16 amps for electronic lighting loads.

2.5.2.4 Photosensors

Provide photosensors that meet the following requirements:

- a. Detect changes in ambient lighting level and enable dimming as required by sequence of operation by operating in an open-loop system.
- b. Contain a detection cone, where the base of the cone may be circular or an elongated shape, and where the smallest angle between the edge and the axis of the cone is between 20 and 50 degrees. The cone axis may be tilted to the vertical when installed to give the sensor preferred directionality.
- c. Sensors are ceiling-mounted with sensitivity, filtering, range and viewing angle to meet requirements of sequence of operation, scope of work and construction documents.
- d. Time delay that is adjustable from 1 to 30 seconds ON delay, and 1 to 30 minutes OFF delay to prevent cycling, with deadband adjustment of 25 percent to 100 percent above lower setpoint.
- e. Output dimming signal is linear to light level with less than 1 percent variation. Cadmium sulfide photo-resistors are not acceptable.
- f. Sensor is not combined in the same housing or location with occupancy or vacancy sensors if the proper location for one function compromises the successful operation of the other function, or in any way reduces the system's ability to meet the design intent.

2.6 EXIT AND EMERGENCY LIGHTING EQUIPMENT

2.6.1 Exit Signs

UL 924, NFPA 101. Provide wattage as indicated in the luminaire schedule on project plans. Provide LED Exit Signs that meet the following criteria:

- a. Housing constructed of UV-stable, thermo-plastic white finish.
- b. UL listed for damp location.
- c. Configured for universal mounting.
- d. 6 inch high, 3/4 inch stroke green lettering on face of sign with chevrons on either side of lettering to indicate direction.
- e. Single or double face as indicated in project plans and luminaire schedule.

2.6.1.1 Exit Signs with Battery Backup

Equip with automatic power failure device, test switch, and pilot light, and fully automatic high/low trickle charger in a self-contained power pack. Battery must be sealed, maintenance free nickel-cadmium type, and must operate unattended for a period of not less than five years. Emergency run time must be a minimum of 1-1/2 hours. LEDs must have a

minimum rated life of 10 years. Provide self-diagnostic circuitry integral to emergency LED driver.

2.6.2 LED Emergency Drivers

UL 924, NFPA 101. Provide LED emergency driver with automatic power failure detection, test switch and LED indicator (or combination switch/indicator) located on luminaire exterior, and fully-automatic solid-state charger, battery and inverter integral to a self-contained housing. Integral nickel-cadmium battery is required to supply a minimum of 90 minutes of emergency power at 10 watts, 10-50 VDC, constant output. Driver must be RoHS compliant, rated for installation in plenum-rated spaces and damp locations, and be warranted for a minimum of five years.

2.7 LUMINAIRE MOUNTING ACCESSORIES

2.7.1 Suspended Luminaires

- a. Provide hangers capable of supporting twice the combined weight of luminaires supported by hangers.
- b. Hangers must allow luminaires to swing within an angle of 45 degrees. Brace pendants 4 feet or longer to limit swinging. Provide with swivel hangers to ensure a plumb installation for rigid stem pendants. Provide cadmium-plated steel with a swivel-ball tapped for the conduit size indicated.
- c. Single-unit suspended luminaires must have cable hangers. Multiple-unit or continuous row luminaires with a separate power supply cord must have a tubing or stem for wiring at one point and a tubing or rod suspension provided for each unit length of chassis, including one at each end.

2.7.2 Recess and Surface Mounted Luminaires

Provide access to light source and LED driver from bottom of luminaire. Provide trim and lenses for the exposed surface of flush-mounted luminaires as indicated on project drawings and specifications. Luminaires recessed in ceilings which have a fire resistive rating of one hour or more must be enclosed in a box which has a fire resistive rating equal to that of the ceiling. For surface mounted luminaires with brackets, provide flanged metal stem attached to outlet box, with threaded end suitable for supporting the luminaire rigidly in design position. Flanged part of luminaire stud must be of broad base type, secured to outlet box at not fewer than three points.

2.7.3 Luminaire Support Hardware

2.7.3.1 Wire

ASTM A641/A641M. Galvanized, soft tempered steel, minimum 0.11 inches in diameter, or galvanized, braided steel, minimum 0.08 inches in diameter.

2.7.3.2 Wire for Humid Spaces

ASTM A580/A580M. Composition 302 or 304, annealed stainless steel, minimum 0.11 inches in diameter.

ASTM B164. UNS N04400, annealed nickel-copper alloy, minimum 0.11 inches

in diameter.

2.7.3.3 Threaded Rods

Threaded steel rods, 3/16 inch diameter, zinc or cadmium coated.

2.7.3.4 Straps

Galvanized steel, one by 3/16 inch, conforming to ASTM A653/A653M, with a light commercial zinc coating or ASTM A1008/A1008M with an electrodeposited zinc coating conforming to ASTM B633, Type RS.

2.8 EQUIPMENT IDENTIFICATION

2.8.1 Manufacturer's Nameplate

Each item of equipment must have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.8.2 Labels

UL 1598. All luminaires must be clearly marked for operation of specific light sources and LED drivers. The labels must be easy to read when standing next to the equipment, and durable to match the life of the equipment to which they are attached. Note the following light source characteristics in the format "Use Only _____":

- a. Correlated Color Temperature (CCT) and Color Rendering Index (CRI) for all luminaires.
- b. Driver and dimming protocol.

All markings related to light source type must be clear and located to be readily visible to service personnel, but unseen from normal viewing angles when light sources are in place. LED drivers must have clear markings indicating dimming type and indicate proper terminals for the various outputs.

2.9 FACTORY APPLIED FINISH

NEMA 250. Provide all luminaires and lighting equipment with factory-applied painting system that as a minimum, meets requirements of corrosion-resistance testing.

PART 3 EXECUTION

3.1 INSTALLATION

IEEE C2, NFPA 70.

3.1.1 Light Sources

When light sources are not provided as an integral part of the luminaire, deliver light sources of the type, wattage, lumen output, color temperature (CCT), color rendering index (CRI), and voltage rating indicated to the project site and install just prior to project completion, if not already installed in the luminaires from the factory.

3.1.2 Luminaires

Set luminaires plumb, square, and level with ceiling and walls, in alignment with adjacent luminaires and secure in accordance with manufacturers' directions and approved drawings. Provide accessories as required for ceiling construction type indicated on Finish Schedule. Luminaire catalog numbers do not necessarily denote specific mounting accessories for type of ceiling in which a luminaire may be installed. Provide wires, straps, or rods for luminaire support in this section. Install luminaires with vent holes free of air blocking obstacles.

3.1.2.1 Suspended Luminaires

Measure mounting heights from the bottom of the luminaire for ceiling-mounted luminaires and to center of luminaire for wall-mounted luminaires. Obtain architect approval of the exact mounting height on the job before commencing installation and, where applicable, after coordinating with the type, style, and pattern of the ceiling being installed. Support suspended luminaires from structural framework of ceiling or from inserts cast into slab.

- a. Provide suspended luminaires with 45 degree swivel hangers so that they hang plumb and level.
- b. Locate so that there are no obstructions within the 45 degree range in all directions.
- c. The stem, canopy and luminaire must be capable of 45 degree swing.
- d. Rigid pendent stem, aircraft cable, rods, or chains 4 feet or longer excluding luminaire must be braced to prevent swaying using three cables at 120 degree separation.
- e. Suspended luminaires in continuous rows must have internal wireway systems for end to end wiring and must be properly aligned to provide a straight and continuous row without bends, gaps, light leaks or filler pieces.
- f. Utilize aligning splines on extruded aluminum luminaires to assure minimal hairline joints.
- g. Support steel luminaires to prevent "oil-canning" effects.
- h. Match supporting pendants with supported luminaire. Aircraft cable must be stainless steel.
- i. Match finish of canopies to match the ceiling, and provide low profile canopies unless otherwise shown.
- j. Maximum distance between suspension points must be 10 feet or as recommended by the manufacturer, whichever is less.

3.1.2.2 Recessed and Semi-Recessed Luminaires

- a. Support recessed and semi-recessed luminaires independently from the building structure by a minimum of two wires, straps or rods per luminaire and located near opposite corners of the luminaire. Secure horizontal movement with clips provided by manufacturer. Ceiling grid

clips are not allowed as an alternative to independently supported luminaires.

- b. Support round luminaires or luminaires smaller in size than the ceiling grid independently from the building structure by a minimum of four wires, straps or rods per luminaire, spaced approximately equidistant around.
- c. Do not support luminaires by acoustical tile ceiling panels.
- d. Where luminaires of sizes less than the ceiling grid are indicated to be centered in the acoustical panel, support each independently and provide at least two 3/4 inch metal channels spanning, and secured to, the ceiling tees for centering and aligning the luminaire.
- e. Adjust aperture rings on all applicable ceiling recessed luminaires to accommodate various ceiling material thickness. Coordinate cut-out size in ceiling to ensure aperture covers cut-out entirely. Install aperture rings such that the bottom of the ring is flush with finished ceiling or not more than 1/16 inch above. Do not install luminaires such that the aperture ring extends below the finished ceiling surface.
- f. For luminaire recessed in plaster ceilings, provide plaster frames for setting. Install setting such that the bottom of the frame is flush with finished ceiling. Support luminaires with plaster frames utilizing yokes or leveling lugs. Do not mount luminaires or support elements to ducts or pipes. Yokes must support a luminaire by no fewer than two bolts each.

3.1.3 LED Drivers

Provide LED drivers integral to luminaire as constructed by the manufacturer.

3.1.4 Exit Signs

NFPA 101. Wire exit signs and emergency lighting units ahead of the local switch, to the normal lighting circuit located in the same room or area.

3.1.5 Lightings Controls

3.1.5.1 Occupancy/Vacancy Sensors

- a. Provide quantity of sensor units indicated as a minimum. Provide additional units to give full coverage over controlled area. Full coverage must provide hand and arm motion detection for office and administration type areas and walking motion for industrial areas, warehouses, storage rooms and hallways.
- b. Locate ceiling-mounted sensors no closer than 6 feet from the nearest HVAC supply or return diffuser.
- c. Locate the sensor(s) as indicated and in accordance with the manufacturer's recommendations.

3.1.5.2 Photosensors

Locate and aim sensor as indicated and in accordance with the manufacturer's recommendations. Adjust sensor set-point in accordance

with the manufacturer's recommendations and for the indicated light level of the area of coverage, measured at the work plane.

3.2 FIELD QUALITY CONTROL

3.2.1 Tests

3.2.1.1 Lighting Control Verification Tests

Verify lighting control system and devices operate according to approved sequence of operations. Verification tests are to be completed after commissioning.

- a. Verify occupancy/vacancy sensors operate as described in sequence of operations. Provide testing of sensor coverage, sensitivity, and time-out settings in all spaces where sensors are placed. This is to be completed only after all furnishings have been installed. Submit occupancy/vacancy sensor verification test.
- b. Verify photosensors operate as described in sequence of operations. Provide testing of sensor coverage, aiming, and calibration in all spaces where sensors are placed. This is to be completed only after all furnishings have been installed. Submit photosensor verification test.
- c. Verify wall box dimmers and scene wallstations operate as described in sequence of operations.

3.2.1.2 Emergency Lighting Test

Interrupt power supply to demonstrate proper operation of emergency lighting. If adjustments are made to the lighting system, re-test system to show compliance with standards.

3.3 CLOSEOUT ACTIVITIES

3.3.1 Commissioning

NFPA 101. Factory Trained Field Service Technician is responsible for calibration and programming sequences for input devices and systems in accordance with the requirements described in the sequence of operation.

3.3.2 Training

3.3.2.1 Maintenance Staff Training

Submit a Maintenance Staff Training Plan at least 30 calendar days prior to training session that describes training procedures for Owner's personnel in the operation and maintenance of lighting and lighting control system. Provide on-site training which demonstrates full system functionality, assigning schedules, calibration adjustments for light levels and sensor sensitivity, integration procedures for connecting to third-party devices, and manual override including information on appropriate use. Provide protocols for troubleshooting, maintenance, repair, and replacement, and literature on available system updates and process for implementing updates.

3.3.2.2 End-User Training

Submit an End-User Training Plan at least 30 calendar days prior to training session that describes training procedures for end-users on the lighting control system. Provide users with a list of control devices located within user-occupied spaces, such as photosensors and occupancy and vacancy sensors, including information on the proper operation and schedule for each device. Provide demonstration for each type of interface. Provide users with the building schedule as currently commissioned, including conditional programming based on astronomic time clock functionality. Provide users with the correct contact information for maintenance personnel who will be available to address any lighting control issues.

Provide laminated instructions to the user at each scene wallstation. Provide only instructions relevant to the functionality of the specific scene wallstation. Provide a description of each labeled scene control button. If the room utilizes occupancy/vacancy sensors or photosensors, include a description of this functionality on the instruction sheet.

-- End of Section --

SECTION 27 10 00

BUILDING TELECOMMUNICATIONS CABLING SYSTEM

08/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D709 (2017) Standard Specification for
Laminated Thermosetting Materials

ELECTRONIC COMPONENTS INDUSTRY ASSOCIATION (ECIA)

ECIA EIA/ECA 310-E (2005) Cabinets, Racks, Panels, and
Associated Equipment

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 100 (2000; Archived) The Authoritative
Dictionary of IEEE Standards Terms

INSULATED CABLE ENGINEERS ASSOCIATION (ICEA)

ICEA S-90-661 (2021) Category 3 and 5E Individually
Unshielded Twisted Pairs, Indoor Cables
(With or Without an Overall Shield) for
Use in General Purpose and LAN
Communications Wiring Systems

NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA)

NECA/BICSI 568 (2006) Standard for Installing Building
Telecommunications Cabling

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI/NEMA WC 66 (2019) Performance Standard for Category 6
and Category 7 100 Ohm Shielded and
Unshielded Twisted Pairs

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2020; ERTA 20-1 2020; ERTA 20-2 2020; TIA
20-1; TIA 20-2; TIA 20-3; TIA 20-4)
National Electrical Code

TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA)

TIA-568.0 (2020e) Generic Telecommunications Cabling
for Customer Premises

TIA-568.1	(2020e) Commercial Building Telecommunications Infrastructure Standard
TIA-568.2	(2018d) Balanced Twisted-Pair Telecommunications Cabling and Components Standards
TIA-568.3	(2016d; Add 1 2019) Optical Fiber Cabling Components Standard
TIA-569	(2019e) Telecommunications Pathways and Spaces
TIA-606	(2021d) Administration Standard for Telecommunications Infrastructure
TIA-607	(2019d) Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises
TIA-1152	(2016; R 2021) Requirements for Field Test Instruments and Measurements for Balanced Twisted-Pair Cabling

U.S. FEDERAL COMMUNICATIONS COMMISSION (FCC)

FCC Part 68	Connection of Terminal Equipment to the Telephone Network (47 CFR 68)

UNDERWRITERS LABORATORIES (UL)

UL 444	(2017; Reprint Jun 2021) UL Standard for Safety Communications Cables
UL 467	(2013; Reprint Jun 2017) UL Standard for Safety Grounding and Bonding Equipment
UL 514C	(2014; Reprint Feb 2020) UL Standard for Safety Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers
UL 723	(2018) UL Standard for Safety Test for Surface Burning Characteristics of Building Materials
UL 969	(2017; Reprint Mar 2018) UL Standard for Safety Marking and Labeling Systems
UL 1286	(2008; Reprint Apr 2021) UL Standard for Safety Office Furnishings
UL 1863	(2004; Reprint Oct 2019) UL Standard for Safety Communication Circuit Accessories

1.2 RELATED REQUIREMENTS

Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM and Section 33 82 00 TELECOMMUNICATIONS, OUTSIDE PLANT (OSP), apply to this section with additions and modifications specified herein.

1.3 DEFINITIONS

Unless otherwise specified or indicated, electrical and electronics terms used in this specification shall be as defined in TIA-568.1, TIA-568.2, TIA-568.3, TIA-569, TIA-606 and IEEE 100 and herein.

1.3.1 Campus Distributor (CD)

A distributor from which the campus backbone cabling emanates. (International expression for main cross-connect (MC).)

1.3.2 Building Distributor (BD)

A distributor in which the building backbone cables terminate and at which connections to the campus backbone cables may be made. (International expression for intermediate cross-connect (IC).)

1.3.3 Floor Distributor (FD)

A distributor used to connect horizontal cable and cabling subsystems or equipment. (International expression for horizontal cross-connect (HC).)

1.3.4 Telecommunications Room (TR)

An enclosed space for housing telecommunications equipment, cable, terminations, and cross-connects. The room is the recognized cross-connect between the backbone cable and the horizontal cabling.

1.3.5 Entrance Facility (EF) (Telecommunications)

An entrance to the building for both private and public network service cables (including wireless) including the entrance point at the building wall and continuing to the equipment room.

1.3.6 Equipment Room (ER) (Telecommunications)

An environmentally controlled centralized space for telecommunications equipment that serves the occupants of a building. Equipment housed therein is considered distinct from a telecommunications room because of the nature of its complexity. Equipment Rooms (ERs) are defined in TIA/EIA-568-B.1, chapter 8. The primary ER for the typical facility is the service entrance for the building's distribution and communications systems. It is the primary location for C4I switching and transmission equipment, main distribution frame(s), and other equipment needed for the termination of the building's interior wiring systems and to interface them with the exterior (outside plant) cable system. The ER also provides the primary distribution point for communications cables and wiring within the building and associated cross-connect cable/wiring. The location of the ER should ensure the horizontal cable distance to a user outlet is no more than 90 meters (295 feet) per ANSI/TIA/EIA-568-B.1, paragraph 4.3, Horizontal Distances.

1.3.7 Open Cable

Cabling that is not run in a raceway as defined by NFPA 70. This refers to cabling that is "open" to the space in which the cable has been installed and is therefore exposed to the environmental conditions associated with that space.

1.3.8 Open Office

A floor space division provided by furniture, moveable partitions, or other means instead of by building walls.

1.3.9 Pathway

A physical infrastructure utilized for the placement and routing of telecommunications cable.

1.4 SYSTEM DESCRIPTION

The building telecommunications cabling and pathway system shall include permanently installed backbone and horizontal cabling, horizontal and backbone pathways, service entrance facilities, work area pathways, telecommunications outlet assemblies, conduit, raceway, and hardware for splicing, terminating, and interconnecting cabling necessary to transport telephone and data (including LAN) between equipment items in a building. The horizontal system shall be wired in a star topology from the telecommunications work area to the floor distributor or campus distributor at the center or hub of the star. The backbone cabling and pathway system includes intrabuilding and interbuilding interconnecting cabling, pathway, and terminal hardware. The intrabuilding backbone provides connectivity from the floor distributors to the building distributors or to the campus distributor and from the building distributors to the campus distributor as required. The backbone system shall be wired in a star topology with the campus distributor at the center or hub of the star. Provide telecommunications pathway systems referenced herein as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. The telecommunications contractor must coordinate with the NMCI/COSC/NGEN contractor concerning access to and configuration of telecommunications spaces. The telecommunications contractor may be required to coordinate work effort within the telecommunications spaces with the NMCI/COSC/NGEN contractor.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Telecommunications Drawings; G

Telecommunications Space Drawings; G

In addition to Section 01 33 00 SUBMITTAL PROCEDURES, provide shop drawings in accordance with paragraph SHOP DRAWINGS.

SD-03 Product Data

Telecommunications Cabling (backbone and horizontal); G

Patch Panels; G

Telecommunications Outlet/Connector Assemblies; G

Equipment Support Frame; G

Connector Blocks; G

Spare Parts; G

Submittals shall include the manufacturer's name, trade name, place of manufacture, and catalog model or number. Include performance and characteristic curves. Submittals shall also include applicable federal, military, industry, and technical society publication references. Should manufacturer's data require supplemental information for clarification, the supplemental information shall be submitted as specified in paragraph REGULATORY REQUIREMENTS and as required in Section 01 33 00 SUBMITTAL PROCEDURES.

SD-06 Test Reports

Telecommunications Cabling Testing; G

SD-07 Certificates

Telecommunications Contractor Qualifications; G

Key Personnel Qualifications; G

Manufacturer Qualifications; G

Test Plan; G

SD-09 Manufacturer's Field Reports

Factory Reel Tests; G

SD-10 Operation and Maintenance Data

Telecommunications Cabling and Pathway System Data Package 5; G

SD-11 Closeout Submittals

Record Documentation; G

1.6 QUALITY ASSURANCE

1.6.1 Shop Drawings

In exception to Section 01 33 00 SUBMITTAL PROCEDURES, submitted plan drawings shall be a minimum of 11 by 17 inches in size using a minimum scale of 1/8 inch per foot, except as specified otherwise. Include wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, piping, ductwork, and other items that must be shown to ensure a coordinated installation. Wiring diagrams shall identify circuit terminals and indicate the internal wiring for each item of equipment and the interconnection between each item of equipment. Drawings shall indicate adequate clearance for operation, maintenance, and replacement of operating equipment devices. Submittals shall include the nameplate data,

size, and capacity. Submittals shall also include applicable federal, military, industry, and technical society publication references.

1.6.1.1 Telecommunications Drawings

Provided registered communications distribution designer (RCDD) approved, drawings in accordance with TIA-606. The identifier for each termination and cable shall appear on the drawings. Drawings shall depict final telecommunications installed wiring system infrastructure in accordance with TIA-606. The drawings should provide details required to prove that the distribution system shall properly support connectivity from the EF telecommunications and ER telecommunications, CD's, BD's, and FD's to the telecommunications work area outlets. Provide a plastic laminated schematic of the as-installed telecommunications cable system showing cabling, CD's, BD's, FD's, and the EF and ER for telecommunications keyed to floor plans by room number. Mount the laminated schematic in the EF telecommunications space as directed by the Contracting Officer. The following drawings shall be provided as a minimum:

- a. T1 - Layout of complete building per floor - Building Area/Serving Zone Boundaries, Backbone Systems, and Horizontal Pathways. Layout of complete building per floor. The drawing indicates location of building areas, serving zones, vertical backbone diagrams, telecommunications rooms, access points, pathways, grounding system, and other systems that need to be viewed from the complete building perspective.
- b. T2 - Serving Zones/Building Area Drawings - Drop Locations and Cable Identification (ID'S). Shows a building area or serving zone. These drawings show drop locations, telecommunications rooms, access points and detail call outs for common equipment rooms and other congested areas.
- c. T4 - Typical Detail Drawings - Faceplate Labeling, Firestopping, Americans with Disabilities Act (ADA), Safety, Department of Transportation (DOT). Detailed drawings of symbols and typicals such as faceplate labeling, faceplate types, faceplate population installation procedures, detail racking, and raceways.
- d. T5 - Drawings shall include schedules to show information for cut-over and cable plant management, patch panel layouts and cover plate assignments, cross connect information, and connecting terminal layout as a minimum. T5 drawings shall be provided in hard copy format on electronic media using Windows based computer cable management software, all drawings will be provided in an AutoCAD and Adobe Acrobat format.

1.6.1.2 Telecommunications Space Drawings

Provide T3 drawings in accordance with TIA-606 that include telecommunications rooms plan views, pathway layout (cable tray, racks, ladder-racks, etc.), mechanical/electrical layout, and , rack, backboard and wall elevations. Drawings shall show layout of applicable equipment including incoming cable stub or connector blocks, building protector assembly, outgoing cable connector blocks, patch panels and equipment spaces and cabinet/racks. Drawings shall include a complete list of equipment and material, equipment rack details, proposed layout and anchorage of equipment and appurtenances, and equipment relationship to other parts of the work including clearance for maintenance and operation. Drawings may also be an enlargement of a congested area of T1

or T2 drawings.

1.6.2 Telecommunications Qualifications

Work under this section shall be performed by and the equipment shall be provided by the approved telecommunications contractor and key personnel. Qualifications shall be provided for: the telecommunications system contractor, the telecommunications system installer, and the supervisor (if different from the installer). A minimum of 30 days prior to installation, submit documentation of the experience of the telecommunications contractor and of the key personnel.

1.6.2.1 Telecommunications Contractor

The telecommunications contractor shall be a firm which is regularly and professionally engaged in the business of the applications, installation, and testing of the specified telecommunications systems and equipment. The telecommunications contractor shall demonstrate experience in providing successful telecommunications systems within the past 3 years of similar scope and size. Submit documentation for a minimum of three and a maximum of five successful telecommunication system installations for the telecommunications contractor.

1.6.2.2 Key Personnel

Provide key personnel who are regularly and professionally engaged in the business of the application, installation and testing of the specified telecommunications systems and equipment. There may be one key person or more key persons proposed for this solicitation depending upon how many of the key roles each has successfully provided. Each of the key personnel shall demonstrate experience in providing successful telecommunications systems within the past 3 years.

Supervisors and installers assigned to the installation of this system or any of its components shall be Building Industry Consulting Services International (BICSI) Registered Cabling Installers, Technician Level. Submit documentation of current BICSI certification for each of the key personnel.

In lieu of BICSI certification, supervisors and installers assigned to the installation of this system or any of its components shall have a minimum of 3 years experience in the installation of the specified copper and fiber optic cable and components. They shall have factory or factory approved certification from each equipment manufacturer indicating that they are qualified to install and test the provided products. Submit documentation for a minimum of three and a maximum of five successful telecommunication system installations for each of the key personnel. Documentation for each key person shall include at least two successful system installations provided that are equivalent in system size and in construction complexity to the telecommunications system proposed for this solicitation. Include specific experience in installing and testing telecommunications systems and provide the names and locations of at least two project installations successfully completed using copper telecommunications cabling systems. All of the existing telecommunications system installations offered by the key persons as successful experience shall have been in successful full-time service for at least 18 months prior to the issuance date for this solicitation. Provide the name and role of the key person, the title, location, and completed installation date of the referenced project, the referenced project owner point of contact information

including name, organization, title, and telephone number, and generally, the referenced project description including system size and construction complexity.

Indicate that all key persons are currently employed by the telecommunications contractor, or have a commitment to the telecommunications contractor to work on this project. All key persons shall be employed by the telecommunications contractor at the date of issuance of this solicitation, or if not, have a commitment to the telecommunications contractor to work on this project by the date that the bid was due to the Contracting Officer.

Note that only the key personnel approved by the Contracting Officer in the successful proposal shall do work on this solicitation's telecommunications system. Key personnel shall function in the same roles in this contract, as they functioned in the offered successful experience. Any substitutions for the telecommunications contractor's key personnel requires approval from The Contracting Officer.

1.6.2.3 Minimum Manufacturer Qualifications

Cabling, equipment and hardware manufacturers shall have a minimum of 3 years experience in the manufacturing, assembly, and factory testing of components which comply with TIA-568.1, TIA-568.2 and TIA-568.3.

1.6.3 Test Plan

Provide a complete and detailed test plan for the telecommunications cabling system including a complete list of test equipment for the components and accessories for each cable type specified, 60 days prior to the proposed test date. Include procedures for certification, validation, and testing.

1.6.4 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.6.5 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items shall be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.6.5.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.6.5.2 Material and Equipment Manufacturing Date

Products manufactured more than 1 year prior to date of delivery to site shall not be used, unless specified otherwise.

1.7 DELIVERY AND STORAGE

Provide protection from weather, moisture, extreme heat and cold, dirt, dust, and other contaminants for telecommunications cabling and equipment placed in storage.

1.8 ENVIRONMENTAL REQUIREMENTS

Connecting hardware shall be rated for operation under ambient conditions of 32 to 140 degrees F and in the range of 0 to 95 percent relative humidity, noncondensing.

1.9 WARRANTY

The equipment items shall be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.10 MAINTENANCE

1.10.1 Operation and Maintenance Manuals

Commercial off the shelf manuals shall be furnished for operation, installation, configuration, and maintenance of products provided as a part of the telecommunications cabling and pathway system, Data Package 5. Submit operations and maintenance data in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA and as specified herein not later than 2 months prior to the date of beneficial occupancy. In addition to requirements of Data Package 5, include the requirements of paragraphs TELECOMMUNICATIONS DRAWINGS, TELECOMMUNICATIONS SPACE DRAWINGS, and RECORD DOCUMENTATION. Ensure that these drawings and documents depict the as-built configuration.

1.10.2 Record Documentation

Provide T5 drawings including documentation on cables and termination hardware in accordance with TIA-606. T5 drawings shall include schedules to show information for cut-overs and cable plant management, patch panel layouts and cover plate assignments, cross-connect information and connecting terminal layout as a minimum. T5 drawings shall be provided in hard copy format and on electronic media using Windows based computer cable management software. A licensed copy of the cable management software including documentation, shall be provided. Provide the following T5 drawing documentation as a minimum:

- a. Cables - A record of installed cable shall be provided in accordance

with TIA-606. The cable records shall include the required data fields for each cable and complete end-to-end circuit report for each complete circuit from the assigned outlet to the entry facility in accordance with TIA-606. Include manufacture date of cable with submittal.

- b. Termination Hardware - A record of installed patch panels, cross-connect points, distribution frames, terminating block arrangements and type, and outlets shall be provided in accordance with TIA-606. Documentation shall include the required data fields as a minimum in accordance with TIA-606.

1.10.3 Spare Parts

In addition to the requirements of Section 01 78 23 OPERATION AND MAINTENANCE DATA, provide a complete list of parts and supplies, with current unit prices and source of supply, and a list of spare parts recommended for stocking.

PART 2 PRODUCTS

2.1 COMPONENTS

Components shall be UL or third party certified. Where equipment or materials are specified to conform to industry and technical society reference standards of the organizations, submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. The certificate shall state that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard. Provide a complete system of telecommunications cabling and pathway components using star topology. Provide support structures and pathways, complete with outlets, cables, connecting hardware and telecommunications cabinets/racks. Cabling and interconnecting hardware and components for telecommunications systems shall be UL listed or third party independent testing laboratory certified, and shall comply with NFPA 70 and conform to the requirements specified herein.

2.2 TELECOMMUNICATIONS PATHWAY

Provide telecommunications pathways in accordance with TIA-569 and as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide system furniture pathways in accordance with UL 1286.

2.3 TELECOMMUNICATIONS CABLING

Cabling shall be UL listed for the application and shall comply with TIA-568.0, TIA-568.1, TIA-568.2, and NFPA 70. Provide a labeling system for cabling as required by TIA-606 and UL 969. Ship cable on reels or in boxes bearing manufacture date for for unshielded twisted pair (UTP) in accordance with ICEA S-90-661 for all cable used on this project. Cabling manufactured more than 12 months prior to date of installation shall not be used.

2.3.1 Horizontal Cabling

Provide horizontal cable in compliance with NFPA 70 and performance characteristics in accordance with TIA-568.1.

2.3.1.1 Horizontal Copper

Provide horizontal copper cable, UTP, 100 ohm in accordance with TIA-568.2, UL 444, ANSI/NEMA WC 66, ICEA S-90-661 . Provide four each individually twisted pair, minimum size 24 AWG conductors, Category 6, with a blue thermoplastic jacket. Cable shall be imprinted with manufacturers name or identifier, flammability rating, gauge of conductor, transmission performance rating (category designation) and length marking at regular intervals in accordance with ICEA S-90-661. Provide plenum (CMP), riser (CMR), or general purpose (CM or CMG) communications rated cabling in accordance with NFPA 70. Substitution of a higher rated cable shall be permitted in accordance with NFPA 70. Cables installed in conduit within and under slabs shall be UL listed and labeled for wet locations in accordance with NFPA 70.

2.4 TELECOMMUNICATIONS SPACES

Provide connecting hardware and termination equipment in the telecommunications entrance facility to facilitate installation as shown on design drawings for terminating and cross-connecting permanent cabling. Provide telecommunications interconnecting hardware color coding in accordance with TIA-606.

2.4.1 Backboards

Provide void-free, interior grade A-C plywood 3/4 inch thick 4 by 8 feet as indicated. Backboards shall be fire rated by manufacturing process. Fire stamp shall be clearly visible. Paint applied over fire retardant backboard shall be UL 723 fire retardant paint. Provide label including paint manufacturer, date painted, UL listing and name of Installer. When painted, paint label and fire stamp shall be clearly visible. Backboards shall be provided on a minimum of two adjacent walls in the telecommunication spaces.

2.4.2 Connector Blocks

Provide insulation displacement connector (IDC) Type 110 for Category 6 systems. Provide blocks for the number of horizontal and backbone cables terminated on the block plus 25 percent spare.

2.4.3 Cable Guides

Provide cable guides specifically manufactured for the purpose of routing cables, wires and patch cords horizontally and vertically on 19 inches equipment cabinets and telecommunications backboards. Cable guides of ring or bracket type devices mounted on cabinet panels for horizontal cable management and individually mounted for vertical cable management. Mount cable guides with screws, and or nuts and lock washers.

2.4.4 Patch Panels

Provide ports for the number of horizontal and backbone cables terminated on the panel plus 25 percent spare. Provide pre-connectorized copper

patch cords for patch panels. Provide patch cords, as complete assemblies, with matching connectors as specified. Patch cords shall meet minimum performance requirements specified in TIA-568.1, TIA-568.2 for cables, cable length and hardware specified.

2.4.4.1 Modular to 110 Block Patch Panel

Provide in accordance with TIA-568.1 and TIA-568.2. Panels shall be third party verified and shall comply with EIA/TIA Category 6 requirements. Panel shall be constructed of 0.09 inches minimum aluminum and shall be rackmounted and compatible with an EIA/ECA 310-E 19 inches equipment rack. Panel shall provide 48 non-keyed, 8-pin modular ports, wired to T568B. Patch panels shall terminate the building cabling on Type 110 IDCs and shall utilize a printed circuit board interface. The rear of each panel shall have incoming cable strain-relief and routing guides. Panels shall have each port factory numbered and be equipped with laminated plastic nameplates above each port.

2.5 TELECOMMUNICATIONS OUTLET/CONNECTOR ASSEMBLIES

2.5.1 Outlet/Connector Copper

Outlet/connectors shall comply with FCC Part 68, TIA-568.1, and TIA-568.2. UTP outlet/connectors shall be UL 1863 listed, non-keyed, 8-pin modular, constructed of high impact rated thermoplastic housing and shall be third party verified and shall comply with TIA-568.2 Category 6 requirements. Outlet/connectors provided for UTP cabling shall meet or exceed the requirements for the cable provided. Outlet/connectors shall be terminated using a Type 110 IDC PC board connector, color-coded for both T568A and T568B wiring. Each outlet/connector shall be wired T568B as indicated. UTP outlet/connectors shall comply with TIA-568.2 for 200 mating cycles.

2.5.2 Cover Plates

Telecommunications cover plates shall comply with UL 514C, and TIA-568.1, TIA-568.2, ; flush oversized design constructed of high impact thermoplastic material white in color to match color of receptacle/switch cover plates specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM 302 stainless material brass material. Provide labeling in accordance with the paragraph LABELING in this section.

2.6 GROUNDING AND BONDING PRODUCTS

Provide in accordance with UL 467, TIA-607, and NFPA 70. Components shall be identified as required by TIA-606. Provide ground rods, bonding conductors, and grounding busbars as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

2.7 FIRESTOPPING MATERIAL

Provide as specified in Section 07 84 00 FIRESTOPPING.

2.8 MANUFACTURER'S NAMEPLATE

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.9 FIELD FABRICATED NAMEPLATES

ASTM D709. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device; as specified or as indicated on the drawings. Each nameplate inscription shall identify the function and, when applicable, the position. Nameplates shall be melamine plastic, 0.125 inches thick, white with center core. Surface shall be matte finish. Corners shall be square. Accurately align lettering and engrave into the core. Minimum size of nameplates shall be one by 2.5 inches. Lettering shall be a minimum of 0.25 inches high normal block style.

2.10 TESTS, INSPECTIONS, AND VERIFICATIONS

2.10.1 Factory Reel Tests

Provide documentation of the testing and verification actions taken by manufacturer to confirm compliance with TIA-568.1, TIA-568.2,

PART 3 EXECUTION

3.1 INSTALLATION

Install telecommunications cabling and pathway systems, including the horizontal and backbone cable, pathway systems, telecommunications outlet/connector assemblies, and associated hardware in accordance with NECA/BICSI 568, TIA-568.1, TIA-568.2, TIA-569, NFPA 70, and UL standards as applicable. Provide cabling in a star topology network. Pathways and outlet boxes shall be installed as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Install telecommunications cabling with copper media in accordance with the following criteria to avoid potential electromagnetic interference between power and telecommunications equipment. The interference ceiling shall not exceed 3.0 volts per meter measured over the usable bandwidth of the telecommunications cabling. Cabling shall be run with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.

3.1.1 Cabling

Install UTP, telecommunications cabling system as detailed in TIA-568.1, TIA-568.2,. Screw terminals shall not be used except where specifically indicated on plans. Use an approved insulation displacement connection (IDC) tool kit for copper cable terminations. Do not exceed manufacturers' cable pull tensions for copper cables. Provide a device to monitor cable pull tensions. Do not exceed 25 pounds pull tension for four pair copper cables. Do not chafe or damage outer jacket materials. Use only lubricants approved by cable manufacturer. Do not over cinch cables, or crush cables with staples. For UTP cable, bend radii shall not be less than four times the cable diameter. Cables shall be terminated; no cable shall contain unterminated elements. Cables shall not be spliced. Label cabling in accordance with paragraph LABELING in this section.

3.1.1.1 Open Cable

Use only where specifically indicated on plans for use in cable trays, or below raised floors. Install in accordance with TIA-568.1, TIA-568.2. Do not exceed cable pull tensions recommended by the manufacturer. Copper

cable not in a wireway or pathway shall be suspended a minimum of 8 inches above ceilings by cable supports no greater than 60 inches apart. Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items. Placement of cable parallel to power conductors shall be avoided, if possible; a minimum separation of 12 inches shall be maintained when such placement cannot be avoided.

Plenum cable shall be used where open cables are routed through plenum areas. Cable routed exposed under raised floors shall be plenum rated. Plenum cables shall comply with flammability plenum requirements of NFPA 70. Install cabling after the flooring system has been installed in raised floor areas. Cable 6 feet long shall be neatly coiled not less than 12 inches in diameter below each feed point in raised floor areas.

3.1.1.2 Horizontal Cabling

Install horizontal cabling as indicated on drawings. Do not untwist Category 6 UTP cables more than one half inch from the point of termination to maintain cable geometry. Provide slack cable in the form of a figure eight (not a service loop) on each end of the cable, 10 feet in the telecommunications room, and 12 inches in the work area outlet.

3.1.2 Pathway Installations

Provide in accordance with TIA-569 and NFPA 70. Provide building pathway as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

3.1.3 Cable Tray Installation

Install cable tray as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Only CMP type cable shall be installed in a plenum.

3.1.4 Work Area Outlets

3.1.4.1 Terminations

Terminate UTP cable in accordance with TIA-568.1, TIA-568.2 and wiring configuration as specified.

3.1.4.2 Cover Plates

As a minimum, each outlet/connector shall be labeled as to its function and a unique number to identify cable link in accordance with the paragraph LABELING in this section.

3.1.4.3 Cables

Unshielded twisted pair and fiber optic cables shall have a minimum of 12 inches of slack cable loosely coiled into the telecommunications outlet boxes. Minimum manufacturer's bend radius for each type of cable shall not be exceeded.

3.1.4.4 Pull Cords

Pull cords shall be installed in conduit serving telecommunications outlets that do not have cable installed.

3.1.5 Telecommunications Space Termination

Install termination hardware required for Category 6 system. An insulation displacement tool shall be used for terminating copper cable to insulation displacement connectors.

3.1.5.1 Connector Blocks

Connector blocks shall be rack mounted in orderly rows and columns. Adequate vertical and horizontal wire routing areas shall be provided between groups of blocks. Install in accordance with industry standard wire routing guides in accordance with TIA-569.

3.1.5.2 Patch Panels

Patch panels shall be mounted in existing equipment rack with sufficient ports to accommodate the installed cable plant plus 25 percent spares.

- a. Copper Patch Panel. Copper cable entering a patch panel shall be secured to the panels recommended by the manufacturer to prevent movement of the cable.

3.1.5.3 Equipment Support Frames

Install in accordance with TIA-569:

- a. Contractor shall provide an alternate price for a wall mounted 19" wall mounted equipment rack in the event that the existing rack is not able to accommodate the additional CAT6 patch panel/s. The alternate wall mounted rack shall adhere to all applicable specifications listed within this specification.

3.1.6 Electrical Penetrations

Seal openings around electrical penetrations through fire resistance-rated wall, partitions, floors, or ceilings as specified in Section 07 84 00 FIRESTOPPING.

3.1.7 Grounding and Bonding

Provide in accordance with TIA-607, NFPA 70 and as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

3.2 LABELING

3.2.1 Labels

Provide labeling in accordance with TIA-606. Handwritten labeling is unacceptable. Stenciled lettering for voice and data circuits shall be provided using thermal ink transfer process.

3.2.2 Cable

Cables shall be labeled using color labels on both ends with identifiers in accordance with TIA-606.

3.2.3 Termination Hardware

Workstation outlets and patch panel connections shall be labeled using color coded labels with identifiers in accordance with TIA-606.

3.3 FIELD APPLIED PAINTING

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria. Painting shall be as specified in Section 09 90 00 PAINTS AND COATINGS.

3.3.1 Painting Backboards

If backboards are required to be painted, then the manufactured fire retardant backboard must be painted with fire retardant paint, so as not to increase flame spread and smoke density and must be appropriately labeled. Label and fire rating stamp must be unpainted.

3.4 FIELD FABRICATED NAMEPLATE MOUNTING

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.5 TESTING

3.5.1 Telecommunications Cabling Testing

Perform telecommunications cabling inspection, verification, and performance tests in accordance with TIA-568.1, TIA-568.2,. Test equipment shall conform to TIA-1152. Remove failed cable reels from project site upon attenuation test failure.

3.5.1.1 Inspection

Visually inspect UTP jacket materials for UL or third party certification markings. Inspect cabling terminations in telecommunications rooms and at workstations to confirm color code for T568A or T568B pin assignments, and inspect cabling connections to confirm compliance with TIA-568.1, TIA-568.2. Visually confirm Category 6, marking of outlets, cover plates, outlet/connectors, and patch panels.

3.5.1.2 Verification Tests

UTP backbone copper cabling shall be tested for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors, and between conductors and shield, if cable has overall shield. Test operation of shorting bars in connection blocks. Test cables after termination but prior to being cross-connected.

Perform verification acceptance tests.

3.5.1.3 Final Verification Tests

Perform verification tests for UTP systems after the complete telecommunications cabling and workstation outlet/connectors are installed.

a. Voice Tests. These tests assume that dial tone service has been

installed. Connect to the network interface device at the demarcation point. Go off-hook and listen and receive a dial tone. If a test number is available, make and receive a local, long distance, and DSN telephone call.

- b. Data Tests. These tests assume the Information Technology Staff has a network installed and are available to assist with testing. Connect to the network interface device at the demarcation point. Log onto the network to ensure proper connection to the network.

-- End of Section --

SECTION 28 31 70

INTERIOR FIRE ALARM SYSTEM, ADDRESSABLE
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

FM GLOBAL (FM)

FM APP GUIDE (updated on-line) Approval Guide
<http://www.approvalguide.com/>

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C62.41.1 (2002; R 2008) Guide on the Surges
Environment in Low-Voltage (1000 V and
Less) AC Power Circuits

IEEE C62.41.2 (2002) Recommended Practice on
Characterization of Surges in Low-Voltage
(1000 V and Less) AC Power Circuits

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 4 (2018) Standard for Integrated Fire
Protection and Life Safety System Testing

NFPA 70 (2020; ERTA 20-1 2020; ERTA 20-2 2020; TIA
20-1; TIA 20-2; TIA 20-3; TIA 20-4)
National Electrical Code

NFPA 72 (2022) National Fire Alarm and Signaling
Code

NFPA 90A (2021) Standard for the Installation of
Air Conditioning and Ventilating Systems

NFPA 170 (2021) Standard for Fire Safety and
Emergency Symbols

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-601-02 (2010) Operations and Maintenance:
Inspection, Testing, and Maintenance of
Fire Protection Systems

UFC 4-010-06 (2016; with Change 1, 2017) Cybersecurity
of Facility-Related Control Systems

UNDERWRITERS LABORATORIES (UL)

UL 268	(2016; Reprint Nov 2021) UL Standard for Safety Smoke Detectors for Fire Alarm Systems
UL 268A	(2008; Reprint Oct 2014) Smoke Detectors for Duct Application
UL 464	(2016; Reprint Sep 2017) UL Standard for Safety Audible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories
UL 497A	(2001; Bul. 2019) UL Standard for Safety Secondary Protectors for Communications Circuits
UL 497B	(2004; Reprint Dec 2012) Protectors for Data Communication Circuits
UL 521	(1999; Reprint Mar 2021) UL Standard for Safety Heat Detectors for Fire Protective Signaling Systems
UL 864	(2014; Reprint May 2020) UL Standard for Safety Control Units and Accessories for Fire Alarm Systems
UL 1283	(2017) UL Standard for Safety Electromagnetic Interference Filters
UL 1449	(2021) UL Standard for Safety Surge Protective Devices
UL 1638	(2016; Reprint Sep 2017) UL Standard for Safety Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories
UL 1971	(2002; Reprint Oct 2008) Signaling Devices for the Hearing Impaired
UL Fire Prot Dir	(2012) Fire Protection Equipment Directory

1.2 RELATED SECTIONS

Section 25 05 11Cybersecurity for Facility-Related Control Systems, applies to this section, with the additions and modifications specified herein. In addition, refer to the following sections for related work and coordination:

Section 21 13 13 WET PIPE SPRINKLER SYSTEM, FIRE PROTECTION

Section 07 84 00 FIRESTOPPING for additional work related to firestopping.

1.3 SUMMARY

1.3.1 Scope

- a. This work includes designing and modifying the existing fire alarm system as described herein and on the contract drawings. Include system wiring, raceways, pull boxes, terminal cabinets, outlet and mounting boxes, control equipment, initiating devices, notification appliances, supervising station fire alarm transmitters, and other accessories and miscellaneous items required for a complete operational system even though each item is not specifically mentioned or described. Provide system complete and ready for operation. Design and installation must comply with UFGS 25 05 11, UFC 4-010-06 and AFGM 2019-320-02.
- b. Provide equipment, materials, installation, workmanship, inspection, and testing in strict accordance with NFPA 72, except as modified herein.
- f. The fire alarm system must be independent of the building security, building management, and energy/utility monitoring systems other than for control functions.

1.4 DEFINITIONS

Wherever mentioned in this specification or on the drawings, the equipment, devices, and functions must be defined as follows:

1.4.1 Interface Device

An addressable device that interconnects hard wired systems or devices to an analog/addressable system.

1.4.2 Fire Alarm Control Unit (FACU)

A master control unit having the features of a fire alarm control unit (FACU).

1.4.3 Remote Fire Alarm Control Unit

A control unit, physically remote from the fire alarm control unit, that receives inputs from automatic and manual fire alarm devices; may supply power to detection devices and interface devices; may provide transfer of power to the notification appliances; may provide transfer of condition to relays or devices connected to the control unit; and reports to and receives signals from the fire alarm and mass notification control unit.

1.4.4 Terminal Cabinet

A steel cabinet with locking, hinge-mounted door where terminal strips are securely mounted inside the cabinet.

1.4.5 Control Module and Relay Module

Terms utilized to describe emergency control function interface devices as

defined by NFPA 72.

1.4.6 Designated Fire Protection Engineer (DFPE)

The DoD fire protection engineer that oversees that Area of Responsibility for that project. This is sometimes referred to as the "cognizant" fire protection engineer. Interpret reference to "authority having jurisdiction" and/or AHJ in referenced standards to mean the Designated Fire Protection Engineer (DFPE). The DFPE may be responsible for review of the contractor submittals having a "G" designation, and for witnessing final inspection and testing.

1.4.7 Qualified Fire Protection Engineer (QFPE)

A QFPE is an individual who is a licensed professional engineer (P.E.), who has passed the fire protection engineering written examination administered by the National Council of Examiners for Engineering and Surveying (NCEES) and has relevant fire protection engineering experience.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government.

Shop drawings (SD-02), product data (SD-03) and calculations (SD-05) must be prepared by the fire alarm designer and combined and submitted as one complete package. The QFPE must review the SD-02/SD-03/SD-05 submittal package for completeness and compliance with the Contract provisions prior to submission to the Government. The QFPE must provide a Letter of Confirmation that they have reviewed the submittal package for compliance with the contract provisions. This letter must include their registered professional engineer stamp and signature. Partial submittals and submittals not reviewed by the QFPE will be returned by the Government disapproved without review.

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualified Fire Protection Engineer (QFPE); G

Fire alarm system designer; G

Supervisor; G

Technician; G

Installer; G

Test Technician; G

Fire Alarm System Site-Specific Software Acknowledgement; G

SD-02 Shop Drawings

Nameplates; G

Instructions; G
Wiring Diagrams; G
System Layout; G
Notification Appliances; G
Initiating devices; G
Battery Power; G
Voltage Drop Calculations; G

SD-03 Product Data

Fire Alarm Control Unit (FACU); G
LCD Annunciator; G
Manual Stations; G
Smoke Detectors; G
Duct Smoke Detectors; G
Heat Detectors; G
Multi-Criteria Detectors; G

Addressable Interface Devices; G
Addressable Control Modules; G
Isolation Modules; G
Notification Appliances; G
Batteries; G
Battery Chargers; G
Surge Protective Devices; G
Alarm Wiring; G
Back Boxes and Conduit; G
Ceiling Bridges for Ceiling-Mounted Appliances; G
Terminal Cabinets; G
Digital Alarm Communicator Transmitter (DACT); G
Electromagnetic Door Holders; G

Environmental Enclosures or Guards; G

Document Storage Cabinet; G

SD-05 Design Data

SD-06 Test Reports

Test Procedures; G

SD-07 Certificates

Verification of Compliant Installation; G

Request for Government Final Test; G

SD-10 Operation and Maintenance Data

Operation and Maintenance (O&M) Instructions; G

Instruction of Government Employees; G

SD-11 Closeout Submittals

As-Built Drawings

Spare Parts

1.6 SYSTEM OPERATION

Fire alarm system components requiring power, except for the FACU(s) power supply, must operate on 24 volts DC unless noted otherwise in this section.

The interior fire alarm system must be a complete, supervised, noncoded, analog/addressable fire alarm system conforming to NFPA 72, and UL 864. Systems meeting UL 2017 only are not acceptable. The system must be activated into the alarm mode by actuation of an alarm initiating device. The system must remain in the alarm mode until the initiating device is reset and the control unit is reset and restored to normal.

1.6.1 Alarm Initiating Devices and Notification Appliances (Visual, Audible)

- a. Connect alarm initiating devices to initiating device circuits (IDC) , or to signaling line circuits (SLC) Class and installed in accordance with NFPA 72.
- b. Connect notification appliances to notification appliance circuits (NAC) .

1.6.2 Functions and Operating Features

The system must provide the following functions and operating features:

- a. Power, annunciation, supervision, and control for the system. Addressable systems must be microcomputer (microprocessor or microcontroller) based with a minimum word size of eight bits with sufficient memory to perform as specified.

- b. Visual alarm notification appliances must be synchronized as required by NFPA 72.
- c. Electrical supervision of the primary power (AC) supply, presence of the battery, battery voltage, and placement of system modules within the control unit.
- d. An audible and visual trouble signal to activate upon a single break or open condition, or ground fault. The trouble signal must also operate upon loss of primary power (AC) supply, absence of a battery supply, low battery voltage, or removal of alarm or supervisory control unit modules. After the system returns to normal operating conditions, the trouble signal must again sound until the trouble is acknowledged. A smoke detector in the process of being verified for the actual presence of smoke must not initiate a trouble condition.
- e. A trouble signal silence feature that must silence the audible trouble signal, without affecting the visual indicator.
- f. Program capability via switches in a locked portion of the FACU to bypass the automatic notification appliance circuits, features. Operation of this programmed action must indicate on the FACU display as a supervisory or trouble condition.
- g. Alarm functions must override trouble or supervisory functions. Supervisory functions must override trouble functions.
- h. The system must be capable of being programmed from the control unit keyboard. Programmed information must be stored in non-volatile memory.
- i. The system must be capable of operating, supervising, and/or monitoring non-addressable alarm and supervisory devices.
- j. There must be no limit, other than maximum system capacity, as to the number of addressable devices that may be in alarm simultaneously.
- k. Where the fire alarm system is responsible for initiating an action in another emergency control device or system, such as the addressable fire alarm relay must be located in the vicinity of the emergency control device.
- l. An alarm signal must automatically initiate the following functions:
 - (1) Transmission of an alarm signal to a remote supervising station.
 - (2) Visual indication of the device operated on the FACU, and on the remote annunciator.
 - (3) Record the event on the system printer.
 - (4) Actuation of alarm notification appliances.
 - (5) Recording of the event electronically in the history log of the FACU.
- m. A supervisory signal must automatically initiate the following

functions:

- (1) Visual indication of the device operated on the FACU, and on the remote annunciator.
- (2) Record the event on the system printer.
- (3) Transmission of a supervisory signal to a remote supervising station.
- (4) Operation of a duct smoke detector must shut down the appropriate air handler in accordance with NFPA 90A in addition to other requirements of this paragraph and as allowed by NFPA 72.
- (5) Recording of the event electronically in the history log of the FACU.

n. A trouble condition must automatically initiate the following functions:

- (1) Visual indication of the device operated on the FACU, and on the remote annunciator.
- (2) Record the event on the system printer.
- (3) Transmission of a trouble signal to a remote supervising station.
- (4) Recording of the event electronically in the history log of the FACU.

p. System control equipment must be programmed to provide a 60-minute to 180-minute delay in transmission of trouble signals resulting from primary power failure.

1.7 TECHNICAL DATA AND SITE-SPECIFIC SOFTWARE

Technical data and site-specific software (meaning technical data that relates to computer software) that are specifically identified in this project, and may be required in other specifications, must be delivered, strictly in accordance with the CONTRACT CLAUSES. The fire alarm system manufacturer must submit written confirmation of this contract provision as "Fire Alarm System Site-Specific Software Acknowledgement". Identify data delivered by reference to the specification paragraph against which it is furnished. Data to be submitted must include complete system, equipment, and software descriptions. Descriptions must show how the equipment will operate as a system to meet the performance requirements of this contract. The site-specific software data package must also include the following:

- a. Items identified in NFPA 72, titled "Site-Specific Software".
- b. Identification of programmable portions of the system equipment and capabilities.
- c. Description of system revision and expansion capabilities and methods of implementation detailing both equipment and software requirements.
- d. Provision of operational software data on all modes of programmable portions for fire alarm .

- e. Description of Fire Alarm Control Unit equipment operation.
- f. Description of auxiliary and remote equipment operations.
- g. Library of application software.
- h. Operation and maintenance manuals.

1.8 EXISTING EQUIPMENT

- a. Equipment and devices must be compatible and operable with the existing fire alarm mass notification system and must not impair reliability or operational functions of existing supervising station fire alarm system..
- b. Equipment and devices must be compatible and operable with the existing building fire alarm system. Equipment must not impair reliability or operational functions of the existing system. The existing building system control unit is unknown.

1.9 QUALITY ASSURANCE

1.9.1 Submittal Documents

1.9.1.1 Preconstruction Submittals

Within 36 days of contract award but not less than 14 days prior to commencing any work on site, the Contractor must submit the following for review and approval. SD-02, SD-03 and SD-05 submittals received prior to the review and approval of the qualifications of the fire alarm subcontractor and QFPE must be returned disapproved without review. All resultant delays must be the sole responsibility of the Contractor.

1.9.1.2 Shop Drawings

Shop drawings must not be smaller than the Contract Drawings. Drawings must comply with the requirements of NFPA 72 and NFPA 170. Minimum scale for floor plans must be 1/8"=1'.

1.9.1.3 Nameplates

Nameplate illustrations and data to obtain approval by the Contracting Officer before installation.

1.9.1.4 Wiring Diagrams

3 copies of point-to-point wiring diagrams showing the points of connection and terminals used for electrical field connections in the system, including interconnections between the equipment or systems that are supervised or controlled by the system. Diagrams must show connections from field devices to the FACU and remote FACU, initiating circuits, switches, relays and terminals, including pathway diagrams between the control unit and shared communications equipment within the protected premises. Point-to-point wiring diagrams must be job specific and must not indicate connections or circuits not being utilized. Provide complete riser diagrams indicating the wiring sequence of all devices and their connections to the control equipment. Include a color-code schedule for the wiring.

1.9.1.5 System Layout

3 copies of plan view drawing showing device locations, terminal cabinet locations, junction boxes, other related equipment, conduit routing, conduit sizes, wire counts, conduit fill calculations, wire color-coding, circuit identification in each conduit, and circuit layouts for all floors. Indicate candela rating of each visual notification appliance. Clearly identify the locations of isolation modules. Indicate the addresses of all devices, modules, relays, and similar. Indicate if the environment for the FACU is within its environmental listing (e.g. temperature/humidity).

Provide a complete description of the system operation in matrix format similar to the "Typical Input/Output Matrix" included in the Annex of NFPA 72.

1.9.1.6 Notification Appliances

Calculations and supporting data on each circuit to indicate that there is at least 25 percent spare capacity for notification appliances. Annotate data for each circuit on the drawings.

1.9.1.7 Initiating Devices

Calculations and supporting data on each circuit to indicate that there is at least 25 percent spare capacity for initiating devices. Annotate data for each circuit on the drawings.

1.9.1.8 Battery Power

Calculations and supporting data as required in paragraph Battery Power Calculations for alarm, alert, and supervisory power requirements. Calculations including ampere-hour requirements for each system component and each control unit component, and the battery recharging period, must be included on the drawings.

1.9.1.9 Voltage Drop Calculations

Voltage drop calculations for each notification circuit indicating that sufficient voltage is available for proper operation of the system and all components, at a minimum rated voltage of the system operating on batteries. Include the calculations on the system layout drawings.

1.9.1.10 Product Data

3 copies of annotated descriptive data to show the specific model, type, and size of each item. Catalog cuts must also indicate the NRTL listing. The data must be highlighted to show model, size, and options that are intended for consideration. Data must be adequate to demonstrate compliance with all contract requirements. Product data for all equipment must be combined into a single submittal.

Provide an equipment list identifying the type, quantity, make, and model number of each piece of equipment to be provided under this submittal. The equipment list must include the type, quantity, make and model of spare equipment. Types and quantities of equipment submitted must coincide with the types and quantities of equipment used in the battery calculations and

those shown on the shop drawings.

1.9.1.11 Operation and Maintenance (O&M) Instructions

Six copies of the Operation and Maintenance Instructions. The O&M Instructions must be prepared in a single volume or in multiple volumes, with each volume indexed, and may be submitted as a Technical Data Package. Manuals must be approved prior to training. The Interior Fire Alarm System Operation and Maintenance Instructions must include the following:

- a. "Manufacturer Data Package five" as specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA.
- b. Operating manual outlining step-by-step procedures required for system startup, operation, and shutdown. The manual must include the manufacturer's name, model number, service manual, parts list, and preliminary equipment list complete with description of equipment and their basic operating features.
- c. Maintenance manual listing routine maintenance procedures, possible breakdowns and repairs, and troubleshooting guide. The manuals must include conduit layout, equipment layout and simplified wiring, and control diagrams of the system as installed.
- d. Complete procedures for system revision and expansion, detailing both equipment and software requirements.
- e. Software submitted for this project on CD/DVD media utilized.
- f. Printouts of configuration settings for all devices.
- g. Routine maintenance checklist. The routine maintenance checklist must be arranged in a columnar format. The first column must list all installed devices, the second column must state the maintenance activity or state no maintenance required, the third column must state the frequency of the maintenance activity, and the fourth column provided for additional comments or reference. All data (devices, testing frequencies, and similar) must comply with UFC 3-601-02.
- h. A final Equipment List must be submitted with the Operating and Maintenance (O&M) manual.

1.9.1.12 As-Built Drawings

The drawings must show the system as installed, including deviations from both the project drawings and the approved shop drawings. These drawings must be submitted within two weeks after the final Government test of the system. At least one set of the as-built (marked-up) drawings must be provided at the time of, or prior to the final Government test.

1.9.2 Qualifications

1.9.2.1 Fire Alarm System Designer

The fire alarm system designer must be certified as a Level IIIIV (minimum) Technician by National Institute for Certification in Engineering Technologies (NICET) in the Fire Alarm Systems subfield of Fire Protection Engineering Technology or meet the qualifications for a QFPE.

1.9.2.2 Supervisor

A NICET Level III or IV fire alarm technician must supervise the installation of the fire alarm system. The fire alarm technicians supervising the installation of equipment must be factory trained in the installation, adjustment, testing, and operation of the equipment specified herein and on the drawings.

1.9.2.3 Technician

Fire alarm technicians with a minimum of four years of experience must be utilized to install and terminate fire alarm devices, cabinets and control units. The fire alarm technicians installing the equipment must be factory trained in the installation, adjustment, testing, and operation of the equipment specified herein and on the drawings.

1.9.2.4 Installer

Fire alarm installer with a minimum of two years of experience utilized to assist in the installation of fire alarm devices, cabinets and control units. A licensed electrician must be allowed to install wire, cable, conduit and backboxes for the fire alarm system system. The fire alarm installer must be factory trained in the installation, adjustment, testing, and operation of the equipment specified herein and on the drawings.

1.9.2.5 Test Technician

Fire alarm technicians with a minimum of eight years of experience and NICET Level III or IV utilized in testing and certification of the installation of the fire alarm devices, cabinets and control units. The fire alarm technicians testing the equipment must be factory trained in the installation, adjustment, testing, and operation of the equipment installed as part of this project.

1.9.2.6 Manufacturer

Components must be of current design and must be in regular and recurrent production at the time of installation. Provide design, materials, and devices for a protected premises fire alarm system, complete, conforming to NFPA 72, except as specified herein.

1.9.3 Regulatory Requirements

Equipment and material must be listed or approved. Listed or approved, as used in this Section, means listed, labeled or approved by a Nationally Recognized Testing Laboratory (NRTL) such as UL Fire Prot Dir or FM APP GUIDE. The omission of these terms under the description of any item of equipment described must not be construed as waiving this requirement. All listings or approvals by testing laboratories must be from an existing ANSI or UL published standard. The recommended practices stated in the manufacturer's literature or documentation must be considered as mandatory requirements.

1.10 DELIVERY, STORAGE, AND HANDLING

Protect equipment delivered and placed in storage from the weather, humidity, and temperature variation, dirt and dust, and other contaminants.

1.11 MAINTENANCE

1.11.1 Spare Parts

Furnish the following spare parts in the manufacturers original unopened containers:

- a. Five complete sets of system keys.
- b. Two of each type of fuse required by the system.
- c. One manual stations.
- d. Two of each type of detector installed.
- e. Two of each type of detector base and head installed.
- i. Two of each type of audible and visual alarm device installed.
- j. Two of each type of addressable monitor module installed.
- k. Two of each type of addressable control module installed.
- l. Two low voltage, one , and one 120 VAC surge protective device.
- n. Two spare printer ribbons.

1.11.2 Special Tools

Software, connecting cables and proprietary equipment, necessary for the maintenance, testing, and reprogramming of the equipment must be furnished to the Contracting Officer, prior to the instruction of Government employees.

PART 2 PRODUCTS

2.1 GENERAL PRODUCT REQUIREMENT

All fire alarm equipment must be listed for use under the applicable reference standards.

2.2 MATERIALS AND EQUIPMENT

2.2.1 Standard Products

Provide materials, equipment, and devices that have been tested by a nationally recognized testing laboratory and listed for fire protection service when so required by NFPA 72 or this specification. Select material from one manufacturer, where possible, and not a combination of manufacturers, for any particular classification of materials. Material and equipment must be the standard products of a manufacturer regularly engaged in the manufacture of the products for at least 2 years prior to bid opening.

2.2.2 Nameplates

Major components of equipment must have the manufacturer's name, address, type or style, model or serial number, catalog number, date of

installation, installing Contractor's name and address, and the contract number provided on a new name plate permanently affixed to the item or equipment. Major components include, but are not limited to, the following:

a. FACU

Nameplates must be etched metal or plastic, permanently attached by screws to control units or adjacent walls.

2.2.3 Keys

Keys and locks for equipment, control units and devices must be identical. Master all keys and locks to a single key as required by the Installation Fire Department. Keys must match existing.

2.2.4 Instructions

Provide a typeset printed or typewritten instruction card mounted behind a Lexan plastic or glass cover in a stainless steel or aluminum frame. Install the instructions on the interior of the FACU. The card must show those steps to be taken by an operator when a signal is received as well as the functional operation of the system under all conditions, normal, alarm, supervisory, and trouble. The instructions and their mounting location must be approved by the Contracting Officer before being posted.

2.3 FIRE ALARM CONTROL UNIT

Provide a complete fire alarm control unit (FACU) fully enclosed in a lockable steel cabinet as specified herein. Operations required for testing or for normal care, maintenance, and use of the system must be performed from the front of the enclosure. If more than a single unit is required at a location to form a complete control unit, the unit cabinets must match exactly. If more than a single unit is required, and is located in the lobby/entrance, notify the Contracting Officer's Designated Representative (COR), prior to installing the equipment. The system must be capable of defining any module as an alarm module and report alarm trouble, loss of polling, or as a supervisory module, and reporting supervisory short, supervisory open or loss of polling such as waterflow switches, valve supervisory switches, fire pump monitoring, independent smoke detection systems, relays for output function actuation.

- a. Each control unit must provide power, supervision, control, and logic for the entire system, utilizing solid state, modular components, internally mounted and arranged for easy access. Each control unit must be suitable for operation on a 120 volt, 60 hertz, normal building power supply. Provide each control unit with supervisory functions for power failure, internal component placement, and operation.
- b. Visual indication of alarm, supervisory, or trouble initiation on the FACU must be by liquid crystal display or similar means with a minimum of 80 characters.

2.3.1 Cabinet

Install control unit components in cabinets large enough to accommodate all components and also to allow ample gutter space for interconnection of control units as well as field wiring. The cabinet must be a sturdy steel housing, complete with back box, hinged steel door with cylinder lock, and existing mounting provisions. The enclosure must be identified by an

engraved phenolic resin nameplate. Lettering on the nameplate must say "Fire Alarm control unit" and must not be less than 1-inch high. Provide prominent rigid plastic or metal identification plates for lamps, circuits, meters, fuses, and switches.

2.3.2 Silencing Switches

2.3.2.1 Alarm Silencing Switch

Provide an alarm silencing switch at the FACU that must silence the audible and visual notification appliances. Subsequent activation of initiating devices must cause the notification appliances to re-activate.

2.3.2.2 Supervisory/Trouble Silencing Switch

Provide supervisory and trouble silencing switch(es) that must silence the audible trouble and supervisory signal(s), but not extinguish the visual indicator. This switch must be overridden upon activation of a subsequent supervisory or trouble condition. Audible trouble indication must resound automatically every 24 hours after the silencing feature has been operated if the supervisory or trouble condition still exists.

2.3.3 Non-Interfering

Power and supervise each circuit such that a signal from one device does not prevent the receipt of signals from any other device. Initiating devices must be manually reset by switch from the FACU after the initiating device or devices have been restored to normal.

2.3.4 Memory

Provide each control unit with non-volatile memory and logic for all functions. The use of long life batteries, capacitors, or other age-dependent devices must not be considered as equal to non-volatile processors, PROMS, or EPROMS.

2.3.5 Field Programmability

Provide control units and control units that are fully field programmable for both input and output of control, initiation, notification, supervisory, and trouble functions. The system program configuration must be menu driven. System changes must be password protected. Any proprietary equipment and proprietary software needed by qualified technicians to implement future changes to the fire alarm system must be provided as part of this contract.

2.3.6 Input/Output Modifications

The FACU must contain features that allow the bypassing of input devices from the system or the modification of system outputs. These control features must consist of a control unit mounted keypad. Any bypass or modification to the system must indicate a trouble condition on the FACU.

2.3.7 Resetting

Provide the necessary controls to prevent the resetting of any alarm, supervisory, or trouble signal while the alarm, supervisory or trouble condition on the system still exists.

2.3.8 Walk Test

The FACU must have a walk test feature. When using this feature, operation of initiating devices must result in limited system outputs, so that the notification appliances operate for only a few seconds and the event is indicated in the history log and on the system printer, but no other outputs occur.

2.3.9 History Logging

The control unit must have the ability to store a minimum of 400 events in a log. These events must be stored in a battery-protected memory and must remain in the memory until the memory is downloaded or cleared manually. Resetting of the control unit must not clear the memory.

2.3.10 Manual Access

An operator at the control unit, having a proper access level, must have the capability to manually access the following information for each initiating device.

- a. Primary status.
- b. Device type.
- c. Present average value.
- d. Present sensitivity selected.
- e. Detector range (normal, dirty).

2.4 REMOTE ANNUNCIATOR

2.5 MANUAL STATIONS

Provide metal or plastic, mounted, double-action, addressable manual stations, that are not subject to operation by jarring or vibration. Stations must be equipped with screw terminals for each conductor. Stations that require the replacement of any portion of the device after activation are not permitted. Stations must be finished in red with molded raised lettering operating instructions of contrasting color. The use of a key must be required to reset the station.

2.6 SMOKE DETECTORS

2.6.1 Spot Type Detectors

Provide addressable photoelectric smoke detectors as follows:

- a. Provide analog/addressable photoelectric smoke detectors utilizing the photoelectric light scattering principle for operation in accordance with UL 268. Smoke detectors must be listed for use with the FACU.
- b. Provide self-restoring type detectors that do not require any readjustment after actuation at the FACU to restore them to normal operation. The detector must have a visual indicator to show actuation.
- c. Vibration must have no effect on the detector's operation. Protect the detection chamber with a fine mesh metallic screen that prevents the

entrance of insects or airborne materials. The screen must not inhibit the movement of smoke particles into the chamber.

- d. Provide twist lock bases with screw terminals for each conductor. The detectors must maintain contact with their bases without the use of springs.
- e. The detector address must identify the particular unit, its location within the system. Detectors must be of the low voltage type rated for use on a 24 VDC system.

2.6.2 Duct Smoke Detectors

Duct-mounted addressable photoelectric smoke detectors must consist of a smoke detector, as specified in paragraph Spot Type Detectors, mounted in a special housing fitted with duct sampling tubes. Detector circuitry must be mounted in a metallic or plastic enclosure exterior to the duct. Detectors must be listed for operation over the complete range of air velocities, temperature and humidity expected at the detector when the air-handling system is operating. Detectors must be powered from the FACU.

- a. Sampling tubes must run the full width of the duct. The duct detector package must conform to the requirements of NFPA 90A, UL 268A, and must be listed for use in air-handling systems. The control functions, operation, reset, and bypass must be controlled from the FACU.
- b. Lights to indicate the operation and alarm condition must be visible and accessible with the unit installed and the cover in place. Remote indicators must be provided where required by NFPA 72. Remote indicators as well as the affected fan units must be properly identified in etched plastic placards.
- c. Detectors must provide for control of auxiliary contacts that provide control, interlock, and shutdown functions specified in Section 23 09 00 to INSTRUMENTATION AND CONTROL FOR HVAC. Auxiliary contacts provide for this function must be located within 3 feet of the controlled circuit or appliance. The auxiliary contacts must be supplied by the fire alarm system manufacturer to ensure complete system compatibility.

2.7 HEAT DETECTORS

2.7.1 Heat Detectors

Heat detectors must be analog/addressable and designed for detection of fire by combination fixed temperature and rate-of-rise principle in accordance with UL 521. The alarm condition must be determined by comparing detector value with the stored values.. Detectors located in areas subject to moisture, exterior atmospheric conditions, or hazardous locations as defined by NFPA 70, must be types approved for such locations.

2.7.1.1 Combination Fixed-Temperature and Rate-of-Rise Detectors

Detectors must be surface mounted in the horizontal orientation and supported independently of wiring connections. Detectors must be self-resetting. Detector must operate at 135 degrees F. Detector must feature rate compensation. Detectors rated to operate at 135 degrees F must not respond to momentary temperature fluctuations less than 30 degrees F per minute between 60 and 100 degrees F.

2.8 MULTI-CRITERIA DETECTORS

Multi-criteria detectors must contain , rate-of-rise heat sensor, photoelectric smoke detector, elements in a single housing.

2.9 ADDRESSABLE INTERFACE DEVICES

The initiating device being monitored must be configured as a existing initiating device circuits. The module must be listed as compatible with the control unit. The module must provide address setting means compatible with the control unit's SLC supervision and store an internal identifying code. Monitor module must contain an integral LED that flashes each time the monitor module is polled and is visible through the device cover plate. Pull stations with a monitor module in a common backbox are not required to have an LED. Existing fire alarm system initiating device circuits must be connected to a single module to supervise the circuit. Modules must be listed for the environmental conditions in which they will be installed.

2.10 ADDRESSABLE CONTROL MODULES

The control module must be capable of operating as a relay (dry contact form C) for interfacing the control unit with other systems, and to control door holders or initiate elevator fire service. The module must be listed as compatible with the control unit. The indicating device or the external load being controlled must be configured as existing notification appliance circuits. The system must be capable of supervising, audible, visual and dry contact circuits. The control module must have both an input and output address. The supervision must detect a short on the supervised circuit and must prevent power from being applied to the circuit. The control model must provide address setting means compatible with the control unit's SLC supervision and store an internal identifying code. The control module must contain an integral LED that flashes each time the control module is polled and is visible through the device cover plate. Control Modules must be listed for the environmental conditions in which they will be installed.

2.11 NOTIFICATION APPLIANCES

2.11.1 Audible Notification Appliances

Audible appliances must conform to the applicable requirements of UL 464. Appliances must be connected into notification appliance circuits. Surface mounted audible appliances must be painted red. Recessed audible appliances must be installed with a grill that is painted red.

2.11.1.1 Horns

Horns must be surface-mounted, with the matching mounting backbox surface mounted vibrating type suitable for use in an electrically supervised circuit. Horns must produce a sound rating of at least 85 dBA at 10 feet. Horns used in exterior locations must be specifically listed or approved for outdoor use and be provided with metal housing and protective grilles.

2.11.2 Visual Notification Appliances

Visual notification appliances must conform to the applicable requirements of UL 1638, UL 1971 and conform to the Architectural Barriers Act (ABA). Visual Notification Appliances must have clear high intensity optic lens,

xenon flash tubes, or light emitting diode (LED) and be marked "Alert" in letters of contrasting color. The light pattern must be disbursed so that it is visible above and below the strobe and from a 90 degree angle on both sides of the strobe. Strobe flash rate must be 1 flash per second and a minimum of 153075 candela based on the UL 1971 test. Strobe must be surface mounted.

2.12 ELECTRIC POWER

2.12.1 Primary Power

Power must be 120 VAC 60 Hz service for the FACU from the AC service to the building in accordance with NFPA 72.

2.13 SECONDARY POWER SUPPLY

Provide for system operation in the event of primary power source failure. Transfer from normal to auxiliary (secondary) power or restoration from auxiliary to normal power must be automatic and must not cause transmission of a false alarm.

2.13.1 Batteries

Provide sealed, maintenance-free, sealed lead acid/lead-calcium/gel cell batteries as the source for emergency power to the FACU. Batteries must contain suspended electrolyte. The battery system must be maintained in a fully charged condition by means of a solid state battery charger. Provide an automatic transfer switch to transfer the load to the batteries in the event of the failure of primary power.

2.13.1.1 Capacity

Battery size must be the following capacity. This capacity applies to every control unit associated with this system, including supplemental notification appliance circuit panels, auxiliary power supply panels, and fire alarm transmitters.

- a. Sufficient capacity to operate the fire alarm system under supervisory and trouble conditions, including audible trouble signal devices for 48 hours and audible and visual signal devices under alarm conditions for an additional 15 minutes.

2.13.1.2 Battery Power Calculations

- a. Verify that battery capacity exceeds supervisory and alarm power requirements for the criteria noted in the paragraph "Capacity" above.
 - (1) Substantiate the battery calculations for alarm and supervisory power requirements. Include ampere-hour requirements for each system component and each control unit component, and compliance with UL 864.
 - (2) Provide complete battery calculations for both the alarm and supervisory power requirements. Submit ampere-hour requirements for each system component with the calculations.
 - (3) Provide voltage drop calculations to indicate that sufficient voltage is available for proper operation of the system and all components. Calculations must be performed using the minimum

rated voltage of each component.

- b. For battery calculations assume a starting voltage of 24 VDC for starting the calculations to size the batteries. Calculate the required Amp-Hours for the specified standby time, and then calculate the required Amp-Hours for the specified alarm time. Using 20.4 VDC as starting voltage, perform a voltage drop calculation for circuits containing device and/or appliances remote from the power sources.

2.13.2 Battery Chargers

Provide a solid state, fully automatic, variable charging rate battery charger. The charger must be capable of providing 120 percent of the connected system load and must maintain the batteries at full charge. In the event the batteries are fully discharged (20.4 Volts dc), the charger must recharge the batteries back to 95 percent of full charge within 48 hours after a single discharge cycle as described in paragraph CAPACITY above. Provide pilot light to indicate when batteries are manually placed on a high rate of charge as part of the unit assembly if a high rate switch is provided.

2.14 SURGE PROTECTIVE DEVICES

Surge protective devices must be provided to suppress all voltage transients which might damage fire alarm control unit components. Systems having circuits located outdoors, communications equipment must be protected against surges induced on any signaling line circuit. Cables and conductors, that serve as communications links, must have surge protection circuits installed at each end. The surge protective device must wire in series to the power supply of the protected equipment with screw terminations. Line voltage surge arrestor must be installed directly adjacent to the power panel where the FACU breaker is located.

- a. Surge protective devices for nominal 120 VAC must be UL 1449 listed with a maximum 500 volt suppression level and have a maximum response time of 5 nanoseconds. The surge protective device must also meet IEEE C62.41.1 and IEEE C62.41.2 category B tests for surge capacity. The surge protective device must feature multi-stage construction and be provided with a long-life indicator lamp (either light emitting diode or neon) which extinguishes upon failure of protected components. Any unit fusing must be externally accessible.
- b. Surge protective devices for nominal 24 VAC, fire alarm telephone dialer, or ethernet connection must be UL 497B listed, meet IEEE C62.41.1 and have a maximum response time of 1-nanosecond. The surge protective device must feature multi-stage construction and be self-resetting. The surge protective device must be a base and plug style. The base assembly must have screw terminals for fire alarm wiring. The base assembly must accept "plug-in" surge protective module.
- c. All surge protective devices (SPD) must be the standard product of a single manufacturer and be equal or better than the following:
 - (1) For 120 VAC nominal line voltage: UL 1449 and UL 1283 listed, series connected 120 VAC, 20A rated, surge protective device in a NEMA 4x enclosure. Minimum 50,000 amp surge current rating with EMI/RFI filtering and a dry contact circuit for remote monitoring of surge protection status.

- (2) For 24-volt nominal line voltage: UL 497B listed, series connected low voltage, 24-volt, 5A rated, loop circuit protector, base and replaceable module.
- (3) For alarm telephone dialers: UL 497A listed, series connected, 130-volt, 150 mA rated with self-resetting fuse, dialer circuit protector with modular plug and play.
- (4) For IP-DACTS: UL 497B listed, series connected, 6.4-volt, 1.5A rated with 20 kA/pair surge current, data network protector with modular plug and play.

2.15 WIRING

Provide wiring materials under this section as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM with the additions and modifications specified herein.

2.15.1 Alarm Wiring

IDC and SLC wiring must be fiber optic or solid copper cable in accordance with the manufacturers requirements. Copper signaling line circuits and initiating device circuit field wiring must be No. 14 AWG size conductors at a minimum. Visual notification appliance circuit conductors, that contain audible alarm appliances, must be copper No. 14 AWG size conductors at a minimum. Wire size must be sufficient to prevent voltage drop problems. Circuits operating at 24 VDC must not operate at less than the listed voltages for the detectors and/or appliances. Power wiring, operating at 120 VAC minimum, must be a minimum No. 12 AWG solid copper having similar insulation. Acceptable power-limited cables are FPL, FPLR or FPLP as appropriate with red colored covering. Nonpower-limited cables must comply with NFPA 70.

2.16 AUTOMATIC FIRE ALARM TRANSMITTERS

2.16.1 Signals to Be Transmitted to the Base Receiving Station

The following signals must be sent to the base receiving station:

- a. Sprinkler waterflow
- b. Manual pull stations
- c. Smoke detectors
- d. Duct smoke detectors
- g. Heat detectors
- h. Fire extinguishing system
- i. Sprinkler valve supervision

2.17 SYSTEM MONITORING

2.17.1 Valves

Each valve affecting the proper operation of a fire protection system, including automatic sprinkler control valves, sprinkler service entrance valve, isolating valves for pressure type waterflow or supervision switches, and valves at backflow preventers, whether supplied under this contract or existing, must be electrically monitored to ensure its proper position. Provide each tamper switch with a separate address, unless they are within the same room, then a maximum of five can use the same address.

2.18 ENVIRONMENTAL ENCLOSURES OR GUARDS

Environmental enclosures must be provided to permit fire alarm components to be used in areas that exceed the environmental limits of the listing. The enclosure must be listed for the device or appliance as either a manufactured part number or as a listed compatible accessory for the component is currently listed. Guards required to deter mechanical damage must be either a listed manufactured part or a listed accessory for the category of the initiating device or notification appliance.

PART 3 EXECUTION

3.1 VERIFYING ACTUAL FIELD CONDITIONS

Before commencing work, examine all adjoining work on which the contractor's work is in any way dependent for perfect workmanship according to the intent of this specification section, and report to the Contracting Officer's Representative any condition which prevents performance of first class work. No "waiver of responsibility" for incomplete, inadequate or defective adjoining work will be considered unless notice has been filed before submittal of a proposal.

3.2 INSTALLATION

3.2.1 Fire Alarm Control Unit (FACU)

Locate the FACU as existing.. Existing the enclosure with the top of the cabinet 6 feet above the finished floor or center the cabinet at 5 feet, whichever is lower. Conductor terminations must be labeled and a drawing containing conductors, their labels, their circuits, and their interconnection must be permanently mounted in the FACU. Locate the document storage cabinet adjacent to the FACU unless the Contracting Officer directs otherwise.

3.2.2 Battery Cabinets

When batteries will not fit in the FACU, locate battery cabinets below or adjacent to the FACU. Battery cabinets must be installed at an accessible location when standing at floor level. Battery cabinets must not be installed lower than 12 inches above finished floor, measured to the bottom of the cabinet, nor higher than 36 inches above the floor, measured to the top of the cabinet. Installing batteries above drop ceilings or in inaccessible locations is prohibited. Battery cabinets must be large enough to accommodate batteries and also to allow ample gutter space for interconnection of control units as well as field wiring. The cabinet must be provided in a sturdy steel housing, complete with back box, hinged steel door with cylinder lock, and surface mounting provisions. The cabinet must

be identified by an engraved phenolic resin nameplate. Lettering on the nameplate must indicate the control unit(s) the batteries power and must not be less than 1-inch high.

3.2.3 Manual Stations

Locate manual stations as required by NFPA 72. Mount stations so they are located no farther than 5 feet from the exit door they serve, measured horizontally. Manual stations must be mounted at 44 inches measured to the operating handle.

3.2.4 Notification Appliances

- a. Locate notification appliance devices as required by NFPA 72 Where more than two visual notification appliances are located in the same room or corridor or field of view, provide synchronized operation. Devices must use screw terminals for all field wiring. Audible and visual notification appliances mounted in acoustical ceiling tiles must be centered in the tiles plus or minus 2 inches..
- b. Audible and visual notification appliances mounted on the exterior of the building, within unconditioned spaces, or in the vicinity of showers must be listed weatherproof appliances installed on weatherproof backboxes.
- c. Speakers must not be located in close proximity to the FACU or LOC so as to cause feedback when the microphone is in use.

3.2.5 Smoke and Heat Detectors

Locate detectors as required by NFPA 72 and their listing on a 4-inch mounting box. Install heat detectors not less than 4 inches from a side wall to the near edge. Heat detectors located on the wall must have the top of the detector at least 4 inches below the ceiling, but not more than 12 inches below the ceiling. Smoke detectors are permitted to be on the wall no lower than 12 inches from the ceiling with no minimum distance from the ceiling. Install smoke detectors no closer than 3 feet from air handling supply diffusers. Detectors installed in acoustical ceiling tiles must be centered in the tiles plus or minus 2 inches.

3.2.6 LCD REMOTE Annunciator

Locate the LCD annunciator as shown on the drawings. Mount the annunciator, with the top 6 feet above the finished floor or center the annunciator at existing. feet, whichever is lower.

3.2.7 Ceiling Bridges

Provide ceiling bridges for ceiling-mounted appliances. Ceiling bridges must be as recommended/required by the manufacturer of the ceiling-mounted notification appliance.

3.3 SYSTEM FIELD WIRING

3.3.1 Wiring within Cabinets, Enclosures, and Boxes

Provide wiring installed in a neat and workmanlike manner and installed parallel with or at right angles to the sides and back of any box, enclosure, or cabinet. Conductors that are terminated, spliced, or

otherwise interrupted in any enclosure, cabinet, mounting, or junction box must be connected to screw-type terminal blocks. Mark each terminal in accordance with the wiring diagrams of the system. The use of wire nuts or similar devices is prohibited. Wiring to conform with NFPA 70.

Indicate the following in the wiring diagrams:

- a. Point-to-point wiring diagrams showing the points of connection and terminals used for electrical field connections in the system, including interconnections between the equipment or systems that are supervised or controlled by the system. Diagrams must show connections from field devices to the FACU and remote fire alarm control units, initiating circuits, switches, relays and terminals.
- b. Complete riser diagrams indicating the wiring sequence of devices and their connections to the control equipment. Include a color code schedule for the wiring. Include floor plans showing the locations of devices and equipment.

3.3.2 Terminal Cabinets

Provide a terminal cabinet at the base of any circuit riser, on each floor at each riser, and where indicated on the drawings. Terminal size must be appropriate for the size of the wiring to be connected. Conductor terminations must be labeled and a drawing containing conductors, their labels, their circuits, and their interconnection must be permanently mounted in the terminal cabinet. Minimum size is 8 inches by 8 inches. Only screw-type terminals are permitted. Provide an identification label, that displays "FIRE ALARM TERMINAL CABINET" with 2-inch lettering, on the front of the terminal cabinet.

3.3.3 Alarm Wiring

- a. Voltages must not be mixed in any junction box, housing or device, except those containing power supplies and control relays.
- b. Utilize shielded wiring where recommended by the manufacturer. For shielded wiring, ground the shield at only one point, in or adjacent to the FACU.
- c. Pigtail or T-tap connections to signal line circuits, initiating device circuits, supervisory alarm circuits, and notification appliance circuits are prohibited.
- d. Color coding is required for circuits and must be maintained throughout the circuit. Conductors used for the same functions must be similarly color coded. Conform wiring to NFPA 70.
- e. Pull all conductors splice free. The use of wire nuts, crimped connectors, or twisting of conductors is prohibited. Where splices are unavoidable, the location of the junction box or pull box where they occur must be identified on the as-built drawings. The number and location of splices must be subject to approval by the Designated Fire Protection Engineer (DFPE).

3.3.4 Back Boxes and Conduit

In addition to the requirements of Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM, provide all wiring in rigid metal conduit or intermediate metal

conduit unless specifically indicated otherwise. Minimum conduit size must be 3/4-inch in diameter. Do not use electrical non-metallic tubing (ENT) or flexible non-metallic tubing and associated fittings.

- a. Galvanized rigid steel (GRS) conduit must be utilized where exposed to weather, where subject to physical damage, and where exposed on exterior of buildings. Intermediate metal conduit (IMC) may be used in lieu of GRS as allowed by NFPA 70.
- b. Electrical metallic tubing (EMT) is permitted above suspended ceilings or exposed where not subject to physical damage. Do not use EMT underground, encased in concrete, mortar, or grout, in hazardous locations, where exposed to physical damage, outdoors or in fire pump rooms. Use die-cast compression connectors.
- c. For rigid metallic conduit (RMC), only threaded type fitting are permitted for wet or damp locations.
- d. Flexible metal conduit is permitted for initiating device circuits 6 feet in length or less. Flexible metal conduit is prohibited for notification appliance circuits and signaling line circuits. Use liquid tight flexible metal conduit in damp and wet locations.
- e. Schedule 40 (minimum) polyvinyl chloride (PVC) is permitted where conduit is routed underground or underground below floor slabs. Convert non-metallic conduit, other than PVC Schedule 40 or 80, to plastic-coated rigid, or IMC, steel conduit before turning up through floor slab.
- f. Exterior wall penetrations must be weathertight. Conduit must be sealed to prevent the infiltration of moisture.

3.3.5 Conductor Terminations

Labeling of conductors at terminal blocks in terminal cabinets, FACU, and remote FACU must be provided at each conductor connection. Each conductor or cable must have a shrink-wrap label to provide a unique and specific designation. Each terminal cabinet, FACU, and remote FACU must contain a laminated drawing that indicates each conductor, its label, circuit, and terminal. The laminated drawing must be neat, using 12 point lettering minimum size, and mounted within each cabinet, control unit, or unit so that it does not interfere with the wiring or terminals. Maintain existing color code scheme where connecting to existing equipment.

3.4 FIRESTOPPING

Provide firestopping for holes at conduit penetrations through floor slabs, fire-rated walls, partitions with fire-rated doors, corridor walls, and vertical service shafts in accordance with Section 07 84 00 FIRESTOPPING.

3.5 PAINTING

- a. In unfinished areas (including areas above drop ceilings), paint all exposed electrical conduit (serving fire alarm equipment), fire alarm conduit, surface metal raceway, junction boxes and covers red. In lieu of painting conduit, the contractor may utilize red conduit with a factory applied finish.
- b. In finished areas, paint exposed electrical conduit (serving fire alarm

equipment), fire alarm conduit, surface metal raceways, junction boxes, and electrical boxes to match adjacent finishes. The inside cover of the junction box must be identified as "Fire Alarm" and the conduit must have painted red bands 3/4-inch wide at 10-foot centers and at each side of a floor, wall, or ceiling penetration.

- c. Painting must comply with Section 09 90 00 PAINTS AND COATINGS.

3.6 FIELD QUALITY CONTROL

3.6.1 Test Procedures

Submit detailed test procedures, prepared and signed by the NICET Level III or IV Fire Alarm Technician, and the representative of the installing company, 60 days prior to performing system tests. Detailed test procedures must list all components of the installed system such as initiating devices and circuits, notification appliances and circuits, signaling line devices and circuits, control devices/equipment, batteries, transmitting and receiving equipment, power sources/supply, annunciators, special hazard equipment, emergency communication equipment, interface equipment, and surge protective devices. Test procedures must include sequence of testing, time estimate for each test, and sample test data forms. The test data forms must be in a check-off format (pass/fail with space to add applicable test data; similar to the forms in NFPA 72 and NFPA 4.) The test procedures and accompanying test data forms must be used for the pre-Government testing and the Government testing. The test data forms must record the test results and must:

- a. Identify the NFPA Class of all Initiating Device Circuits (IDC), and Notification Appliance Circuits (NAC), and Signaling Line Circuits (SLC).
- b. Identify each test required by NFPA 72 Test Methods and required test herein to be performed on each component, and describe how these tests must be performed.
- c. Identify each component and circuit as to type, location within the facility, and unique identity within the installed system. Provide necessary floor plan sheets showing each component location, test location, and alphanumeric identity.
- d. Identify all test equipment and personnel required to perform each test (including equipment necessary for smoke detector testing. The use of magnets is not permitted.
- e. Provide space to identify the date and time of each test. Provide space to identify the names and signatures of the individuals conducting and witnessing each test.

3.6.2 Pre-Government Testing

3.6.2.1 Verification of Compliant Installation

Conduct inspections and tests to ensure that devices and circuits are functioning properly. Tests must meet the requirements of paragraph entitled "Minimum System Tests" as required by NFPA 72. The contractor and an authorized representative from each supplier of equipment must be in attendance at the pre-Government testing to make necessary adjustments. After inspection and testing is complete, provide a signed Verification of

Compliant Installation letter by the QFPE that the installation is complete, compliant with the specification and fully operable. The letter must include the names and titles of the witnesses to the pre-Government tests. Provide all completion documentation as required by NFPA 72 including all referenced annex sections and the test reports noted below.

- a. NFPA 72 Record of Completion.
- b. NFPA 72 Record of Inspection and Testing.
- c. Fire Alarm and Emergency Communication System Inspection and Testing Form.
- d. Audibility test results with marked-up test floor plans.
- e. Documentation that all tests identified in the paragraph "Minimum System Tests" are complete.

3.6.2.2 Request for Government Final Test

When the verification of compliant installation has been completed, submit a formal request for Government final test to the Contracting Officer's Representative (COR). Government final testing will not be scheduled until the DFPE has received copies of the request for Government final testing and Verification of Compliant Installation letter with all required reports. Government final testing will not be performed until after the connections to the installation-wide fire reporting system has been completed and tested to confirm communications are fully functional. Submit request for test at least 15 calendar days prior to the requested test date.

3.6.3 Correction of Deficiencies

If equipment was found to be defective or non-compliant with contract requirements, perform corrective actions and repeat the tests. Tests must be conducted and repeated if necessary until the system has been demonstrated to comply with all contract requirements.

3.6.4 Government Final Tests

The tests must be performed in accordance with the approved test procedures in the presence of the DFPE. Furnish instruments and personnel required for the tests. The following must be provided at the job site for Government Final Testing:

- a. The manufacturer's technical representative.
- c. Marked-up red line drawings of the system as actually installed.
- d. Loop resistance test results.
- e. Complete program printout including input/output addresses.
- f. Copy of pre-Government Test Certificate, test procedures and completed test data forms.
- g. Audibility test results with marked-up floor plans.

Government Final Tests will be witnessed by the , Contracting Officer's Representative (COR). At this time, any and all required tests noted in the paragraph "Minimum System Tests" must be repeated at their discretion.

3.7 MINIMUM SYSTEM TESTS

3.7.1 System Tests

Test the system in accordance with the procedures outlined in NFPA 72. The required tests are as follows:

- a. Loop Resistance Tests: Measure and record the resistance of each circuit with each pair of conductors in the circuit short-circuited at the farthest point from the circuit origin. The tests must be witnessed by the Contracting Officer and test results recorded for use at the final Government test.
- b. Verify the absence of unwanted voltages between circuit conductors and ground. The tests must be accomplished at the pre-Government test with results available at the final system test.
- c. Verify that the control unit is in the normal condition as detailed in the manufacturer's O&M manual.
- d. Test each initiating device and notification appliance and circuit for proper operation and response at the control unit. Smoke detectors must be tested in accordance with manufacturer's recommended calibrated test method. Use of magnets is prohibited. Testing of duct smoke detectors must comply with the requirements of NFPA 72 except disconnect at least 20 percent of devices. If there is a failure at these devices, then supervision must be tested at each device.
- f. Test the system for specified functions in accordance with the contract drawings and specifications and the manufacturer's O&M manual.
- g. Test both primary power and secondary power. Verify, by test, the secondary power system is capable of operating the system for the time period and in the manner specified.
- h. Determine that the system is operable under trouble conditions as specified.
- i. Visually inspect wiring.
- j. Test the battery charger and batteries.
- k. Verify that software control and data files have been entered or programmed into the FACU. Hard copy records of the software must be provided to the Contracting Officer.
- l. Verify that red-line drawings are accurate.
- m. Measure the current in circuits to ensure there is the calculated spare capacity for the circuits.
- n. Measure voltage readings for circuits to ensure that voltage drop is not excessive.
- o. Disconnect the verification feature for smoke detectors during tests to

minimize the amount of smoke needed to activate the sensor. Testing of smoke detectors must be conducted using real smoke or the use of canned smoke which is permitted.

- p. Measure the voltage drop at the most remote appliance (based on wire length) on each notification appliance circuit.
- q. Verify the documentation cabinet is installed and contains all as-built shop drawings, product data sheets, design calculations, site-specific software data package, and all documentation required by paragraph titled "Test Reports".

3.7.2 Audibility Tests

Sound pressure levels from audible notification appliances must be a minimum of 15 dBA over ambient with a maximum of 110 dBA in any occupiable area. The provisions for audible notification (audibility and intelligibility) must be met with doors, fire shutters, movable partitions, and similar devices closed.

3.8 SYSTEM ACCEPTANCE

Following acceptance of the system, as-built drawings and O&M manuals must be delivered to the Contracting Officer for review and acceptance. The drawings must show the system as installed, including deviations from both the project drawings and the approved shop drawings. These drawings must be submitted within two weeks after the final Government test of the system. At least one set of as-built (marked-up) drawings must be provided at the time of, or prior to the Final Government Test.

- a. The drawings must be prepared electronically and sized no less than the contract drawings.
- b. Include complete wiring diagrams showing connections between devices and equipment, both factory and field wired.
- c. Include a riser diagram and drawings showing the as-built location of devices and equipment.
- d. Provide Operation and Maintenance (O&M) Instructions.

3.9 INSTRUCTION OF GOVERNMENT EMPLOYEES

3.9.1 Instructor

Provide the services of an instructor, who has received specific training from the manufacturer for the training of other persons regarding the operation, inspection, testing, and maintenance of the system provided. The instructor must train the Government employees designated by the Contracting Officer, in the care, adjustment, maintenance, and operation of the fire alarm system. The instructor must be thoroughly familiar with all parts of this installation. The instructor must be trained in operating theory as well as in practical O&M work. Submit the instructors information and qualifications including the training history.

3.9.2 Required Instruction Time

Provide 8 hours of instruction after final acceptance of the system. The instruction must be given during regular working hours on such dates and

times selected by the Contracting Officer. The instruction may be divided into two or more periods at the discretion of the Contracting Officer. The training must allow for rescheduling for unforeseen maintenance and/or fire department responses.

3.9.2.1 Technical Training

Equipment manufacturer or a factory representative must provide 1 days of on site and 5 days of technical training to the Government at the manufacturing facility. Training must allow for classroom instruction as well as individual hands on programming, troubleshooting and diagnostics exercises. Factory training must occur within 12 months of system acceptance.

3.9.3 Technical Training Manual

Provide, in manual format, lesson plans, operating instructions, maintenance procedures, and training data for the training courses. The operations training must familiarize designated government personnel with proper operation of the installed system. The maintenance training course must provide the designated government personnel adequate knowledge required to diagnose, repair, maintain, and expand functions inherent to the system.

3.10 EXTRA MATERIALS

3.10.1 Repair Service/Replacement Parts

Repair services and replacement parts for the system must be available for a period of 10 years after the date of final acceptance of this work by the Contracting Officer. During the warranty period, the service technician must be on-site within 24 hours after notification. All repairs must be completed within 24 hours of arrival on-site.

During the warranty period, the installing fire alarm contractor is responsible for conducting all required testing and maintenance in accordance with the requirements and recommended practices of NFPA 72 and the system manufacturer. Installing fire alarm contractor is NOT responsible for any damage resulting from abuse, misuse, or neglect of equipment by the end user.

3.10.2 Spare Parts

Spare parts furnished must be directly interchangeable with the corresponding components of the installed system. Spare parts must be suitably packaged and identified by nameplate, tagging, or stamping. Spare parts must be delivered to the Contracting Officer at the time of the Government testing and must be accompanied by an inventory list.

3.10.3 Document Storage Cabinet

Upon completion of the project, but prior to project close-out, place in the document storage cabinet copies of the following record documentation:

- a. As-built shop drawings
- b. Product data sheets
- c. Design calculations

- d. Site-specific software data package
- e. All documentation required by SD-06.

-- End of Section --